



INDEX DATA	RPS INFORMATION
Scheme Title A 36 East of Bath to Beckington.	Details Woulkover survey.
Road Number A 36.	Date August 1993.
Contractor RPS.	
County Wiltshire.	
OS Reference ST 85	
Single sided <input checked="" type="checkbox"/> Double sided	
A3 7 Colour 8(7A3).	

A36 EAST OF BATH TO BECKINGTON

WALKOVER SURVEY

R1551

A36 East of
Bath To
Beckington.

Walkover
Survey

August 1993

RPS CLOUSTON
THE OLD BARN
DEANES CLOSE
STEVENTON
ABINGDON
OXON OX13 6SY

CONTENTS

	Page No
1. INTRODUCTION	1
2. METHODOLOGY	3
3. RESULTS	5
4. PUBLIC CONSULTATION ALTERNATIVES AND PUBLIC CONSULTATION ROUTE RESULTS	8
5. CONCLUSIONS	15
APPENDICES	
1. FIELD SUMMARY	
2. WALKOVER SURVEY RESULTS: IMPACT OF PCR AND PCA ROUTES	
3. SUPPLEMENTARY SITES	
4. PROFORMA WALKOVER RECORD SHEET	

A36 East of Bath to Beckington Walkover Survey

1 Introduction

- 1.1 The archaeological assessment of the A36 East of Bath to Beckington proposal has been carried out using a staged approach as set out in the Department of Transport (DoT) Design Manual for Roads and Bridges (vol 11). Stage 1 was sufficient to identify the constraints associated with broadly defined routes, and consisted of a review of known constraints, including the county's Sites and Monuments Records (SMRs), Scheduled Ancient Monuments (SAMs), listed buildings and designated constraints. These were the subject of the March 1992 Corridor Analysis Working Papers 4 (Listed Buildings) and 5 (Archaeology).
- 1.2 Following the Public Consultation in September 1992 a number of alternative routes to the Public Consultation Route (PCR) were put forward Public Consultation Alternatives (PCAs).
- 1.3 The objective of a Stage II archaeological study is to undertake sufficient assessment to identify the archaeological factors and the effects upon them which need to be taken into account in choosing alternative routes. The methods for achieving this are:
- a check with the county archaeologists that there are no additions or modifications since the original survey to the SMR and designated areas;

- a detailed desk-top study to identify all known sites and assess the likely impact of the possible routes;
- a preliminary walkover survey of areas where there are areas of pasture, woodland, or other gaps in the record which may be filled by the observation of surface features; and
- an in-confidence response from English Heritage on their view of the assessment.

1.4 To date the Stage II study has consisted of a review of the SMR entries on the PCA route and the PCR corridors, and has solicited EH's views on the assessment. The present paper is a report on the preliminary walkover survey undertaken in June 1993 as part of the study. Included is a consideration of the SMRs and SAMs in the PCA route and PCR corridors.

1.5 The preliminary walkover involved the recording of the presence and probable nature of earthworks and/or other significant visible features, but no excavation took place at this stage to confirm/disprove the assumptions made.

1.6 Fields were selected for walkover on the basis of the information already gathered. Most fields affected by the PCR were assessed. Fields on PCA routes were selected where appropriate on the basis of known archaeology.

2 Methodology

- 2.1 The aims of this survey were to identify and record the presence of visible archaeological sites in order to supplement the desk top study. This is necessary to enhance information in areas where few archaeological sites have been recorded or where known sites may require checking.
- 2.2 Apparent lack of sites could be due to a various factors, such as: little archaeology surviving; past and present land uses which mask archaeology; and lack of research or fieldwork in the area.
- 2.3 The survey took the form of walking over the proposed route where possible and taking note of any evidence of archaeology (especially in the form of earthworks) and factors that would effect the visibility of archaeology. Information recorded during the study included present land use, past land use, topography and aspect, the presence and location of any water courses, the geology and the soil type. A *pro-forma* was used (Appendix 4).
- 2.4 The presence or absence of earthworks was noted, the form and nature of any earthworks (if these could be defined) and the quality of their preservation. The quality of preservation was defined as follows:

poor;
intermediate; and
clear preservation.

and the earthwork categories were:

settlement earthwork;
field system earthwork;
other earthwork;
no earthworks visible;
survey not possible; and
no earthworks present.

- 2.5 Information solicited from landowners and tenants was also noted, with chance archaeological finds being identified and their find spots recorded. Field names were occasionally gathered, as these sometimes give information on the past land-use and characteristics.
- 2.6 Some information was also gleaned from present-day maps. The plan of fields and settlements can sometimes suggest a period for their layout, due to the different agricultural requirements and traditions of different periods.
- 2.7 Thorough survey was not possible at some points due to factors such as lack of permission for access, standing crops which could mask lesser earthworks, and woodland, where undergrowth at the time of the survey made earthworks difficult to identify. Timetabling pressures unfortunately demanded that this survey was carried out whilst undergrowth was at its height and some crops were still standing, making earthwork identification impossible in woods and some fields.

3 Results

- 3.1 Despite the constraints outlined above, it was possible to identify many earthworks which were not previously recorded on the county SMRs. These ranged from former field boundaries and trackways to possible settlement earthworks and other earthworks of an unknown nature.
- 3.2 Newly discovered sites included possible deserted settlement earthworks (most probably medieval) at Woolley Park Farm (field 33/1) and the reported presence of cropmarks/parchmarks at Church Farm, Wingfield (field 52/1).
- 3.3 At Farleigh Wick a large ditch and bank of unknown nature or purpose in field 27/8 was previously unrecorded.
- 3.4 Sites already recorded, such as the field system at Inwoods (Wilts SMR ST 86 SW 300), have been defined more accurately in terms of their present condition.
- 3.5 The Deserted Medieval Village at Arnolds Hill (Wilts SMR ST 85 NW 452), Wingfield, could only be surveyed from the roadside due to lack of access permission. Settlement earthworks were clearly visible, as were field system earthworks, but accurate plotting of these features could not be carried out. Some fields in this area where access was not permitted could not be surveyed, due to thick hedges preventing observation from public access points.

3.6 A full listing of all sites (previously known or unknown) is given for each field surveyed in Appendix 1, "Field Summary".

3.7 The priority of sites has been decided on the criteria used by the DoE in scheduling decisions. These include: rarity value, state of preservation and the implications of the find.

- Rarity Value: if a site is an extremely rare or unusual type, or combines a number of unusual features in unique way, a case may be made for its preservation. Some forms of historic field boundary are very common and would not usually require preservation, but an extensive field system of considerable antiquity is rare and constitutes a feature which may be worth avoiding.
- The state of preservation of a site or monument: if a site is well preserved it would provide much more archaeological information than a site that has been damaged by, for example, ploughing over a prolonged period.
- Implications of the find or site recorded: for example, building material or extensive earthworks suggest occupation in the area, whereas a coin hoard or a solitary find of a flint tool does not imply intensive activity.

3.8 In general the sites where there is surviving physical evidence of occupation, ritual or historic industrial activity have been given a higher priority than stray finds and isolated elements of extensive agricultural systems.

4 Public Consultation Alternatives (PCAs) and Public Consultation Route (PCR) Results

The following section considers the affect of each of the PCAs and the PCR and compares them. A series of papers on each section of the proposal has been produced and the following is organised in conformity with those papers.

4.1 **Paper 1 PCA routes 6, 8, 10/11 and PCR centred on Great Cumberwell**

PCA Route 6. The north end of this route is close to listed grade II buildings at Farleigh Wick (Monkton Farleigh nos 114 - 117). The route impinges on earthworks (also affected by PCR) east of Farleigh Wick (field 28/8). These may be part of the extensive prehistoric/Romano-British field system recorded to the south of the route. About 500m north west of Little Cumberwell there are reports of Romano-British pottery and building material finds (SMR ST 86 SW 313) now under the existing road, but it may be evidence of occupation which could spread south into the path of PCA route 6 (or north to affect PCR). There are references to a ploughed out medieval field system (SMR ST 86 SW 600) to the west of Little Cumberwell which is only affected by PCA route 6. At the south end this route passes close to Fairfield House, listed Grade II (Bradford on Avon 176).

PCA route 8. This is very similar in its effect to PCA route 6, although it passes a little further away from the listed Grade II Potticks House (South Wraxall 457).

PCA route 10/11. There are no known features on this route. It was not walked over as its distance from the field system to the south was judged to minimise its potential for new sites.

PCR centred on Great Cumberwell. Great Cumberwell is mentioned in Domesday, but the present buildings are of no great antiquity. Most of the land north of this line is a golf course, which revealed nothing to the walkover survey. The southern part of this line would pass between Fairfield House and Fairfield Farm, both listed Grade II buildings (Bradford on Avon 175 and 176).

The Wiltshire County Council designated Area of Special Archaeological Significance (ASAS 9) embraces much of the land to the south of the existing road between Dry Arch and Little Cumberwell and the earthwork features affected by the PCR and PCA 6 are part of the field system which contributes to this designation.

The PCR route and PCA route 10/11 are preferable to PCA route 6, but there is little to differentiate them as all these routes impinge on the ASAS in the area where earthworks are visible.

4.2 Paper No. 2 PCA route 13 and PCR between Home Wood and Monkton Farleigh

PCA route 13. The only known feature is north of Hays Wood Farm, where field bank earthworks were recorded in the walkover survey (Field 25/15).

PCR between Home Wood and Monkton Farleigh. At the north end of the route is an undated unidentified SMR reference (Avon 4872) and a Romano-British building recorded at Dry Arch (Avon SMR 1836). From the edge of Home Wood to Farleigh Wick the route passes through an area of ill-defined earthworks, probably part of the extensive Romano-British field system recorded to the south (Wilts SMR ST 86 SW 300). A well defined hollow way runs north south on the eastern boundary of Field 27/3. This is probably medieval or earlier. The route passes close to the listed Grade II buildings at Farleigh Wick (Monkton Farleigh nos. 114-117). East of Farleigh Wick there are pronounced earthworks forming a bank and ditch (Field 27/8), probably medieval agricultural traces.

The PCA route 13 is preferable as it passes too far north to be involved in the extensive earthworks south of the existing road. It also has less effect on listed buildings.

4.3 Paper No. 3 PCA 1B, 1C, 21 and PCR (including 1) PCA 1B

In Field 61/3 is a bank parallel to Green Park Lane, and undulations, date unknown. In the field to the east are earthworks which may represent a deserted medieval village (DMV) not on the county SMR (Site A). The southern extremity of the route east of Eastcote Farm impinges on a listed Grade II milestone (Beckington 53).

PCA 1C. This route passes through a field in which APs have reputedly indicated ring ditches (Sites D1 and D2). This has not been checked.

PCA 21. This route passes through a field north of the Devil's Bed and Bolster with old boundaries showing as earthworks (Field 60/10). The route is also the closest (150m) to the Devil's Bed and Bolster, a Scheduled Ancient Monument.

PCR. The PCR affects an undated earthwork platform south of Parsonage Farm (Field 60/3) as well as the same undated bank and poorly defined earthworks in Field 61/3 as PCA route 1B. PCR (1) passes through a field with reputed ring ditches seen by the tenant farmer on APs (Sites D1 and D2) north of the Devil's Bed and Bolster. The route is 200m from the SAM. It is also 300m away from Seymours Court, Listed Grade I.

The PCR (not including 1) is the route which has the least effect in this area.

4.4 Paper No 4 PCA 2 and PCR

PCA 2. This route affects no known sites, except undulations in Field 59/1. It passes close (100m) to a listed Grade II building (Rode no.358).

PCR Poplar Tree Lane to Green Park Pond. This route affects no known sites, except undulations in Field 59/1.

Neither of these routes has any advantage over the other, and both are relatively innocuous in their affect.

4.5 Paper No. 5 PCA 3C and PCR (including 3, 3A and 3B) from Westwood Road to Poplar Tree Lane

PCA 3C. This route crosses a complex of AP marks north and south of Arnolds Hill Farm (Wilts SMR ST 85 NW 607) which represent early agricultural features. Earthworks in roughly the same area are the remains of a deserted medieval village (SMR ST 85 NW 452). There are field banks south of the DMV complex in Field nos. 51/5, 52/7, 53/3, and 52.4 and medieval coins at the southern end north of Park Farm (SMR ST 85 NW 466).

PCR including 3, 3A and 3B. The PCR crosses a field of undefined earth east of Trowle Farm (Field no. 50/6) before passing west of the Arnolds Hill Farm DMV but it crosses another area of complex AP traces reported east of St Mary's Church, Wingfield (Site E, Field no. 52/1). Further south it crosses an area of AP field boundary traces (SMR ST 85 NW 605) in Field no. 52/6 as well as the field bank in 52/4. Routes 3 and 3B (route 3A is not on base map) are essentially the same in their impact as 3C, and in particular, both affect the Arnolds Hill Farm DMV.

The PCR is to be preferred in this section, although the affect on the complex APs at Site E requires to be determined more precisely. Routes 3 and 3B are similar to 3C and would have an impact on important known sites.

4.6 Paper No. 6 PCA 5B and PCR including 5 and 5C PCA 5B

This route has no impact on known sites until it affects fields with undefined earthworks north and east of Woolley Park Farm (Field nos. 33/2, 33/3, 33/4).

PCR including 5 and 5C. PCR E1 is close to a listed Grade II building at Widbrook Farm and crosses two linear earthwork features (probably field boundaries) east and north of Great Bradford Wood (Field nos. 36/11 and 35/2). It then crosses the same fields east and north of Woolley Park Farm. PCR E2 avoids these features but does impinge on possible DMV earthworks (Site F) between Woolley Barn Farm and Woolley Park Farm (Field no. 33/1) and passes close to the listed Grade II building at the canal near Widbrook. Route 5 is similar to 5B in its affects, as is 5C.

PCA 5, 5B and 5C are preferable to the PCR routes E1 and E2, particularly E2 which affects a possible DMV.

4.7 Paper No. 7 PCA 18 and PCR

PCA 18. There is one site on this route, a field of ridge and furrow between Southwick and Wingfield (Field 53/6). The route passes to the east of the Arnolds Hill DMV, and grazes a field of undefined earthworks north east of Beckington (no. 61/9).

PCR from Fairfield north of Bradford-on-Avon to Beckington. The E1 and E2 sections of this route are considered in Paper 6 and E2 affects a potentially major site. The Westwood Road to Poplar Tree Lane is discussed in Paper 5, where the affect on the AP complex E is considered the most significant impact. The Poplar Tree Lane to Green Park pond is discussed in Paper 3 with the conclusion that it has no significant affect. The stretch from Green Park pond to Beckington crosses a field with undefined earthworks and a linear earthwork, probably a field boundary (Field no. 61/3), but affects no other known sites.

The PCA 18 route is the preferred one, although the most significant constraint on the PCR is the reported AP complex east of Wingfield church, which requires verification.

4.8 Paper No. 8 PCA 14 (12 options) and PCR

PCA 14. This route is drawn as beginning at the railway line west of the River Avon and east of Bathampton Farm. Here it would be in the flood plain of the river and there is the potential for waterlogged prehistoric deposits sealed by the alluvium. On the east side of the Avon is the site of a Romano-British building the location of which is unclear, but may be in the path of the route (Avon SMR 1739).

PCR from Bathford Bridge to Warleigh Lane. The PCR commences at the existing (listed Grade II) railway bridge, then crosses the vicinity of Bathford Bridge which is a

Scheduled Ancient Monument. An undated embankment in the field west of the existing road would be affected (Field no.12/1) would be affected, and undefined earthworks further south would also be in the path (Field no. 12/3). The alluvium cover in the Bathford Bridge area would have the same potential for earlier waterlogged material as the Avon valley alluvium. The Romano-British building may be on the PCR, and this may be a more likely location for it, out of the flood plain, than the lower suggested location (SMR 1739). Both PCA 14 and the PCR cross the suggested line of a Roman road although there is no physical evidence for its existence.

PCA route 14 is preferable in that it does not have an affect on the Bathford Bridge SAM, the listed railway arch or the other features in the vicinity of the By Brook. Many of the fields in this stretch were visited but were under crops which would have obscured earthwork features.

5 Conclusions

- 5.1 It has been possible to identify and prioritize sites and therefore make recommendations as to route preferences. In order to complete the Stage II study, documentary research should be carried out. This should include tythe, estate and early OS maps for specific areas as the large area to be studied precludes this for the whole study corridor.

ARCHAEOLOGY

APPENDIX I

FIELD SUMMARY

A36 EAST OF BATH - WALKOVER SURVEY: FIELD SUMMARY

21 JULY 1993

MAP 1

Field No.	Owner	Survey Results	Other Information (including SMR)	Recommendations
12/1	Horler	Embankment c1.5m high, c4m wide in line with "Bathford Hill" road and also line of pylons	Adjacent to Bathford Bridge, Avon 1737	
12/2	Horler	Flood plain with no visible earthworks	One of three possible sites for SMR Avon 1739 - Romano British buildings	
12/3	Horler	Earthworks on eastern boundary, of unclear nature	Adjacent to one of three possible sites for Avon SMR 1739 - Romano British buildings	
12/4	Horler	Earthworks on eastern boundary, of unclear nature	One of three possible sites for Avon SMR 1739 - Romano British building	
13/1	Harris	Undulating slope. No earthworks visible from road (no access)	Conjectured line of Roman road passes through (Avon SMR 4560)	
13/2	Harris	Not visible from road (no access)		
13/3	Harris	Only partially visible from road, with no obvious undulations, but cereal crop and no access made through survey impossible	Avon SMR 6186, undated water mill. Conjectured line of Roman road (Avon SMR 4560) passes through this field	
13/4	Harris	Not clearly visible from road. No access	Conjectured line of Roman road (Avon SMR 4560) passes through this field	

13/5	Harris	No access - surveyed from road - no visible earthworks			
13/6	Harris	Not clearly visible from road - no access	Avon SMR 4433 earthwork boundary dividing 13/6 and 13/7		
13/7	Harris	No earthworks visible from road	Avon SMR 4433 earthwork boundary dividing 13/6 and 13/7. Well established hedgerow separating 13/7 and 13/8		
13/8	Harris	No earthworks visible from road	Avon SMR 4433 earthwork boundary dividing 13/6 and 13/7. Well established hedgerow separating 13/7 and 13/8		
13/9	Harris	No access			
13/10	Harris	Surveyed from road. Break in slope visible - former field boundary running north-south. Clear banked field boundary between 13/10 and 13/11, c.5m high and 1m high			
13/11	Harris	Surveyed from road. Break in slope visible - former field boundary running north-south. Clear banked field boundary between 13/10 and 13/11, c.5m high and 1m high			
13/12	Harris	Not possible to survey standing crop	SMR 605 earthworks well preserved field system U/D		Walkover survey

14/1	Keevil	Large undulations - field has been ploughed, no obvious earthworks	Steeply sloping. Established hedgerow on eastern boundary c.4-5m wide, with dry stone wall. Avon SMR 4585 (round barrow) in adjacent copse	
14/2	Keevil	Large undulations and steep slopes due to geology no obvious earthworks	Thick hedgerow borders	
14/3	Keevil	Steep slopes and undulations due to geology	Thick hedgerow and wooded borders	

MAP 2

Field No.	Owner	Survey Results	Other Information (including SMR)	Recommendations
15/1	Wharton	Deciduous woodland with occasional steep slopes/scarps	Avon SMR 4872 in southern section of this wood (Map 2). Also a Romano British building (Avon SMR 1836) in the vicinity of the Dry Arch	
16/1	Eker	Mixed woodland with steep scarps and slopes. Possible quarrying locations		
17/1	Hobhouse	High cereal crop would be masking any earthworks, none visible only undulations		
17/2	Hobhouse	High cereal crop would be masking any earthworks, none visible, only undulations		
18/1	Walsh	Steep slopes in mixed woodland. Undulating hill slope with possible stone quarries. Dry stone wall runs along County boundary	Avon SMR 1836 - Romano British building in vicinity of northern end of wood	
19/1	Llewellyn	Flat area of grass with no earthworks, but surrounded by dry stone wall		
19/2	Llewellyn	Sheep pasture on North facing slope with undulations, but no obvious earthworks	Avon SMR 1836 Romano British building in vicinity of eastern corner	
25/1	James	Golf course. Landscaping in progress. No remaining earthworks		

25/2	James	Golf course. Landscaping in progress. No remaining earthworks			
25/3	James	Golf course. Landscaping in progress. No remaining earthworks			
25/4	James	Golf course. Landscaping in progress. No remaining earthworks	Wiltshire SMR 313 on south-eastern boundary		
25/5	James	Pasture with no visible earthworks			
25/6	James	Standing crop, no visible earthworks	Adjacent to Great Cumberwell. SMR 456		
25/7	James	Disturbed ground with much dumped material			
25/8	James	Standing crop - no visible earthworks	Hedge between 25/8 and 25/9 grubbed out		
25/9	James	Standing crop - no visible earthworks	Hedge between 25/8 and 25/9 grubbed out		
25/10	James	Non existent - now part of 25/8 and 25/9			
25/11	James	Landscaping in progress			
25/12	James	Landscaping in progress			
25/13	James	Scrub and rough grass no earthworks visible			
25/14	James	Cereal crop prevents identification of any earthworks, but land is undulating and very bumpy			

25/15	James	Banks, probably former field boundaries		
25/16	James	Cereal crop prevents identification of earthworks		
25/17	James	Indistinct bump in SW corner		Dry stone walls surround field
25/18	James	Cereal crop prevents identification of earthworks		
26/1	McCubbin	No visible earthworks		Hollow way on northern boundary 1.5m below field level
26/2	McCubbin	Possible raised track undulating, but no identifiable earthworks		Thick hedgerow on northern boundary c5m thick probably marks the course of the old road
26/3	McCubbin	Undulating with dip in middle		Hollow way on southern boundary with thin hedgerow
26/4	McCubbin	No identifiable earthworks		Intermittent thick hedgerow and ditch on southern boundary
27/1	Dr Whitehead	Indeterminate earthworks, dry stone walls to north east and south		Wiltshire SMR 300 extant Romano British field system in woodland it is likely that this extended further north
27/2	Whitehead	General spread of earthworks with poor definition - probable field system. Dry stone wall to north east south and west		Wiltshire SMR 300 - extant Romano British field system in woodland. It is likely this extended further north

27/3	Whitehead	Undulating with undefined unclear earthworks. A broad hollow banked trackway runs north to south dividing field 27/3 from field 27/4 and 5. This way continues to the north of the present road and is likely to be at least medieval or older in date	Wiltshire SMR 300 - extant Romano British field system in woodland. It is likely this extended further north	
27/4} 27/5} 27/6}	Whitehead	These three fields now form one unit, with the former field boundaries visible. Undulations are also visible, but no earthworks identified due to long grass	Wiltshire SMR 300 - extant Romano British field system in woodland. It is likely this extended further north SMR 150 Bronze Age arrowheads	
27/7	Whitehead	No earthworks identified due to very long grass	Wiltshire SMR 300 - extant Romano British field system in woodland. It is likely this extended further north	
27/8	Whitehead	A bank and ditch c6-7m wide forms a rounded right angle in this field. A possible lynchet lies to the east. At the northern boundary a thick hedgerow marks where the land surface falls to the level of the road which is a hollow way (recently widened to the north)	Wiltshire SMR 300 - extant Romano British field system in woodland. It is likely this extended further north	
27/9	Whitehead	Standing crop prevents identification of any earthworks		
13/12	Harris	Cereal crop prevents identification of any earthworks		
28/1	Lock	Cereal crop prevents identification of any earthworks		

28/2	Lock	Landfill site			
28/3	Lock	Cereal crop prevents identification of any earthworks			
28/4	Lock	No earthworks			
28/5	Lock	No earthworks			
24/1	Hillier	Long grass and scrub prevents identification of any earthworks			

tc574/v3/1551

MAP 3

Field No.	Owner	Survey Results	Other Information (including SMR)	Recommendations
29/1	Compton	Cereal crop makes accurate survey impossible		
29/2	Compton	Cereal crop makes accurate survey impossible		
29/3	Compton	Grass - no earthworks		
29/4	Compton	Grass - no earthworks		
29/5	Compton	Grass - no earthworks		
30/1	Compton	Leaf crop - no earthworks visible		
32/5	Singer	Cereal crop - makes survey difficult		
32/6	Singer	Cereal crop - makes survey difficult		
33/7	Singer	No earthworks visible, but cereal crop makes survey difficult		
33/1	Candy	Denuded settlement earthworks		
33/2	Candy	Undefined unclear earthworks		
33/3	Candy	Undefined unclear earthworks		
33/4	Candy	Undefined unclear earthworks		
33/5	Candy	No earthworks visible		
34/1	Bayfield	Field system earthworks and poss settlement earthworks		

34/2	Bayfield	Undulations no identifiable earthworks			
35/1	Prentice	Very slight undulations - no earthworks			
35/2	Prentice	No earthworks			
36/1	Moulton	Bank visible running parallel to road. Probably former field boundary. <u>NB</u> there are big undulations in southern corner, but these are riverine erosion/ deposition features			
36/2	Moulton	Undulations close to stream - flood plain and river cliff. Not man made earthworks			
36/4	Moulton	Bradford Wood Lane, running between 36/2 and 36/4 is a shallow hollow way with thick banked hedgerows. Thick hedgerows with banks all round field			
36/5	Moulton	No visible earthworks			
36/6	Moulton	Scrub and trees make survey impossible			
36/7	Moulton	Eroded entrance by gateway and some mounding adjacent to the road			
36/8	Moulton	No visible earthworks			

36/10	Moulton	Small undulations. No visible earthworks	Close to Wiltshire SMR 604 - earthwork in Great Bradford Wood
36/11	Moulton	Earthworks - disused trackway running east-west through field. Possibly "missing portion" of Bradford Wood Lane.	Adjacent to Wiltshire SMR 604. Earthwork in Great Bradford Wood. Flood plain banks clearly visible c10-15m from streams present course
36/12	Moulton	No visible earthworks	Adjacent to edge of River Avon Flood plain. Boundary with 13 runs along flood plain banks
36/13	Moulton	No visible man made earthworks	Riverine erosion and deposition features in evidence
40/1	Gover	No earthworks	
41/1	Pope	Bank on parish boundary	

MAP 4

Field No.	Owner	Survey Results	Other Information (including SMR)	Recommendations
38/1	Griggs	Now a pub car park, and garden and a barge marina. No visible earthworks except canal		
38/2	Griggs	No earthworks		
38/3	Griggs	No earthworks		
39/1	Ross Poultry Ltd	No earthworks		
42/1	Dyke	No earthworks	Adjacent to Wilts SMR 463 - the Late Medieval settlement of Wiggebok (1279). Now built over	
46/1	Fry	No earthworks		
47/1	Lewerill	No earthworks		
47/2	Lewerill	No earthworks		
47/3	Lewerill	No earthworks		
47/4	Lewerill	No earthworks. Between 47/2 and 47/6 is very broad trackway with very thick hedgerows either side		
47/5	Lewerill	Undulations. No earthworks		
49/1	Archer	No earthworks	Adjacent Wilts SMR 463	
49/2	Archer	No earthworks		
50/4	Turner	No earthworks		

50/5	Turner	No identifiable earthworks		Broad ditch separating 50/5 and 50/8. Adjacent to Wilts SMR 304 Romano British Finds	
50/6	Turner	Joined with 50/7			
50/7	Turner	Possible banks and raised areas. Ditch around perimeter with hedgerow		Adjacent to Wilts SMR 304. Romano British finds. Also air photograph crop marks visible. SMR 452 - Deserted Medieval Village	Wilts
50/8	Turner	Undulations. No visible earthworks			

MAP 5

Field No.	Owner	Survey Results	Other Information (including SMR)	Recommendations
50/5	Turner	No identifiable earthworks	Broad ditch separating 50/5 and 50/8. Adjacent to Wilts SMR 304 Romano British Finds	
50/6	Turner	Joined with 50/7		
50/7	Turner	Possible banks and raised areas. Ditch around perimeter with hedgerow	Adjacent to Wilts SMR 304. Romano British finds. Also air photograph crop marks visible. Wilts SMR 452 - Deserted Medieval Village	
50/1	Turner	Not possible to survey		
50/2	Turner	No distinguishable earthworks		
50/3	Turner	No distinguishable earthworks		
51/1	Turner	Not visible from Road		
51/2	Fear	No distinguishable earthworks		
51/3	Fear	2 field boundaries surviving as substantial lynchets	Air photographs of possible medieval fields	
51/4	Fear	Not visible		
51/5	Fear	Linear earthwork running parallel to road	Air photo showing same earthwork	
51/6	Fear	Undulations unidentified earthwork		
51/7	Fear	Not visible from road		

51/8	Fear	Not visible from road		
51/9	Fear	No identifiable earthworks, but undulations		
51/10	Fear	Deserted Medieval Village earthworks		SMR 452 - DMV
51/11	Fear	Drop of c2m from 51/7 along hedgeline possible lynchet. Possible hollow way leaving field at southern boundary		
52/1	Fuller	Farmer field boundary bank running NW/SE		Find of a neolithic polished axe in this field. In 1976 parched patterns observed in squares, ovals, circles and lines. (Pers. comm Mr Fuller, the farmer)
52/2	Fuller	Undulations possibly undefined earthworks		
52/3	Fuller	Possible traces of terracing. Low bank. Possibly former boundary		Broad ditch separates 52/3 and 52/4 = SMR 606 c.
52/4	Fuller	Low bank dividing field. Visible at edge		
52/5	Fuller	North west end of field is platformed approx. 0.3m higher than rest of field. Probable former field boundary		Air photos = SMR 605 modern track and tractor marks 466 med? coins
52/6	Fuller	No earthworks		Air photos SMR 605 are modern track and tractor marks

52/7	Fuller	2 possible out	lynchets since ploughed		
53/1	Berrett	No visible	earthworks		
53/2	Berrett	No visible	earthworks		
53/3	Berrett	Undulations earthworks	- no visible		
53/4	Berrett	Undulating			
53/5	Berrett	Undulating			
53/6	Berrett	Possible ridge	and furrow		
54/1	Vigar	No earthworks			
54/2	Vigar	No earthworks			
55/1	Arney	No earthworks			
55/2	Arney	No earthworks			
55/3	Arney	No earthworks			

MAP 6

Field No.	Owner	Survey Results	Other Information (including SMR)	Recommendations
50/1	Turner	Not possible to survey		
54/1	Vigar	No earthworks		
54/2	Vigar	No earthworks		
55/1	Arney	No earthworks		
55/2	Arney	No earthworks		
55/3	Arney	No earthworks		
56/1	Farley	No earthworks		
57/1	Weeks	No earthworks		
58/1	Osbourne	58/1 and 58/3 are now the same field. No visible earthworks		
58/2	Osbourne	No visible earthworks		
58/3	Osbourne	No visible earthworks		
58/4	Osbourne	Standing crop, survey not possible		
58/5	Osbourne	No visible earthworks		
58/6	Osbourne	No visible earthworks		
58/7	Osbourne	No visible earthworks		
58/8	Osbourne	No visible earthworks		
58/9	Osbourne	No visible earthworks	SMR 24247 ring ditch	

58/10 58/11	Osbourne	58/10 and 58/11 are now joined, but a lynchet (partially ploughed out) remains on former boundary				
59/2	Fussel	High leaf crop, survey impossible				
61/3	Slay	Bank running parallel with road. Undulations. Possible crop marks				
61/4	Slay	No visible earthworks				
61/5	Slay	No visible earthworks				
61/6	Slay	Recent dumping of clay etc.	Adjacent to SMR Somerset 24252 sarunken village			
61/7	Slay	No visible earthworks				
61/8	Slay	No visible earthworks				
61/9	Slay	Possible earthworks	Adjacent to Somerset SMR 23139 prehistoric flint scatter			
61/10	Slay	No obvious earthworks				
61/11	Slay	Undulations, but no obvious earthworks				
61/12	Slay	Not possible to survey				
61/13	Slay	No visible earthworks				
59/1	Fussel	Undulations - no definite earthworks				
60/1	Ellis	No earthworks				
60/2	Ellis	No earthworks				

60/3	Ellis	Poorly defined earthworks forming a platform in south west corner			
60/4	Ellis	No earthworks			
60/5	Ellis	No earthworks			
60/6	Ellis	No earthworks			
60/7	Ellis	No earthworks			
60/8	Ellis	Undulations - no obvious earthworks	Adjacent to the Devils Bed and Bolster Long Barrow. (Scheduled Ancient Monument 428). Flint scatter around monument		
60/10	Ellis	Earthworks, probable former field systems			
61/1} 61/2}	Slay	Not possible to survey, but settlement earthworks in adjacent fields	Settlement earthworks in field to south		
61/13	Slay	No visible earthworks			

MAP 7

Field No.	Owner	Survey Results	Other Information (including SMR)	Recommendations
59/2	Fussel	High leaf crop survey impossible		
61/3	Slay	Bank running parallel with road undulations - possible crop marks		
61/4	Slay	No visible earthworks		
61/5	Slay	No visible earthworks		
61/6	Slay	Recent dumping of clay etc.	Adjacent to SMR Somerset 2452 shrunken village	
61/7	Slay	No visible earthworks		
61/8	Slay	No visible earthworks		
61/9	Slay	Possible earthworks	Adjacent to Somerset SMR 23/39 prehistoric flint scatter field called Peggate	
61/10	Slay	No obvious earthworks	Cottage, of unknown date called "Billingsgate" now demolished, was in southern corner (Pers. comm. Mr Slay). Path running through may have been a track as the place name element "gate" usually implies close to a road	
61/11	Slay	Undulations but no obvious earthworks		
61/12	Slay	Not possible to survey		
61/13	Slay	No visible earthworks		

62/4	Williams/ Millet	No earthworks			
62/5	Williams/ Millet	No earthworks			

ARCHAEOLOGY

APPENDIX II

**WALKOVERSURVEY RESULTS:
IMPACT OF PCR AND PCA ROUTES**

A36 EAST OF BATH: ARCHAEOLOGY

21 JULY 1993

WALKOVERSURVEY RESULTS: IMPACT OF PCR AND PCA ROUTES

PAPER 1

Routes 6, 10/11 & PCR

Route 6	10/11	PCR	Field description
27/8		27/8	Earthworks present
27/9		27/9	Survey not possible
13/2			Survey not possible
Unsurveyed field			
Unsurveyed field			
Unsurveyed field			
24/1		24/1	Survey not possible
28/3	28/3	28/3	Survey not possible
28/4		28/4	No earthworks recorded
Unsurveyed fields			
29/1	29/1	29/1	Survey not possible
29/2		29/2	Survey not possible
29/3		29/3	No earthworks recorded
29/5		29/5	No earthworks recorded
	25/1	25/1	No earthworks recorded
	25/2	25/2	No earthworks recorded
	25/3	25/3	No earthworks recorded

	25/4	25/4	No earthworks recorded SMR 313?
		25/5	No earthworks recorded
	Not surveyed		
		25/7	No earthworks recorded
		25/8	No earthworks recorded
		25/9	No earthworks recorded
		28/1	Survey not possible
		24/1	Survey not possible
	28/4	28/4	No earthworks recorded
	28/2	N/A	No earthworks recorded
	28/5	28/5	No earthworks recorded

PAPER 2

Route 13, & PCR Homewood - Monkton Farleigh

13	PCR	Field Descriptions
16/1	16/1	No earthworks recorded
	15/1	SMR 4872 SMR 1836 - Roman building in the vicinity of the dry arch
Bays Wood		Not assessed
17/2		No earthworks recorded
17/1		No earthworks recorded
Unsurveyed field		
25/18		No earthworks recorded
25/17		Platform earthwork in SW corner
25/16		No earthworks recorded
25/15		Field bank earthworks
25/14		No earthworks recorded
25/13		No earthworks recorded
	27/1	Roman building in vicinity of dry arch - undefined earthworks which are probably part of the Romano-British field system extant in the woods. The Romano-British settlement has not been located so further assessment may be necessary
	27/2	Undefined earthworks recommendations for 27/1 also apply here
	27/3	Undefined earthworks recommendations for 27/1 also apply here
	27/3	Ditched and banked trackway runs between 27/3 and 27/4 which continues to the north of the present road, likely to be at least medieval in date. Needs assessment

	27/4, 27/5, 27/6	Former field boundaries extant. SMR 300 - Romano- British field system probably extended to this area
	27/7	No earthworks visible
	27/8	A bank and ditch c6-7m wide forms a rounded right angle. This is of undetermined date or nature. Also a lynchet and adjacent to the road a steep slope down to the road surface
27/9	27/9	Survey not possible

PAPER 3
Rode PCA 1B, 1C 21, PCR

PCA 1B	PCA 1C	PCA 21	PCR	Field Description
61/3				Bank running parallel with road. Undulation possible cropmarks adjacent to possible DMV
61/4			61/4	No recorded earthworks
Unsurveyed fields	N/A	N/A		
N/A	N/A	N/A	55/2, 55/3, 56/1, 57/1, 58/6, 58/5, 59/1	Fields with no visible earthworks and of relatively recent layout
	58/4		58/4	Survey not possible
	58/3, 58/1, 60/1	58/3, 58/1, 60/1	58/3, 58/1, 60/1	No earthworks recorded, field shape medieval in character
	60/2	60/2	60/2	No earthworks
			60/3	Poorly defined earthworks forming platform in SE corner
		60/10		Linear earthworks former field boundaries
		60/8		No earthworks
		60/4	60/4	No earthworks field shape medieval in character
		60/5	60/5	No earthworks field shape medieval in character
			60/6	No earthworks field shape medieval in character

			60/6	No earthworks field shape medieval in character
		61/1	61/1	Survey not possible
61/3			61/3	Adjacent to conjectured DMV (to SE) Bank running parallel to road former field boundary. Undulations possible cropmarks
61/4			61/4	No earthworks recorded
Unassessed fields				
			61/5	No earthworks recorded
			62/4	No earthworks recorded
			62/5	No earthworks recorded
	Unassessed fields			Route passes through possible location of ring ditches shown on AP. Area of known prehistoric activity around SAM
	61/11			Survey not possible
	61/12			No earthworks visible
	61/13			No earthworks visible
	61/8			No earthworks visible
	61/7			No earthworks visible

PAPER 4
PCA 2 & PCR (NE of Rode)

PCA 2	PCR	Field Description
55/2 55/3	55/2 55/3	No earthworks - p.m/modern field layout
Unsurveyed fields	Unsurveyed field	With p.m/modern field layout
	56/1	No earthworks, p.m/modern field layout
57/1	57/1	No earthworks, p.m/modern field layout
Unsurveyed field		p.m/modern field layout
	58/6 58/5	No earthworks, p.m/modern field layout
59/1	59/1	Undulations, possible earthworks
Unsurveyed fields		-
	58/4	Standing crop, not possible to survey
	58/3 } same 58/1 } field	No visible earthworks, possible medieval layout. No visible earthworks
	58/2	No visible earthworks, medieval shape?
	60/1	No earthworks, medieval shape?
60/2	60/2	No earthworks

PAPER 5
PCA 3C & PCR (including 3, 3A and 3B)

PCR	PCA 3	PCA 3B	PCA 3C	Field Description
47/5	47/5	47/5	47/5	Undulations. No visible earthworks
50/4				No earthworks
50/5	50/5	50/5	50/5	Broad ditch separating 50/5 and 50/8, impacted by PCR. No identifiable earthworks in field itself, possible banks and raised areas. Ditch around perimeter. Close to SMR 304 - R-B finds, AP cropmarks and SMR 452 - Deserted Medieval Village. No direct impact on known sites
	51/1	51/1	51/1	AP cropmarks in SMR. Not surveyed from road (no access)
			Unsurveyed field	AP cropmarks
	51/10	51/10	51/10	SMR 452. Deserted Medieval Village. Earthworks visible direct impact with all three routes
51/2				No distinguishable earthworks
	51/5	51/5		Linear earthwork running parallel to road. AP shows same earthworks
			51/6	Two field boundaries surviving as substantial lynchets. APs of possible medieval fields

	51/4	51/4	51/4	Not visible. SMR 607 - APs possible medieval fields - earthworks
52/1	52/1			Linear bank visible. Find of neolithic polished axe. Extensive cropmark complex in 1976 reported
			52/7	Two possible lynchets now ploughed out
52/2	52/2			Undulations, possibly undefined earthworks
52/3	52/3		52/3	Possible traces of terracing. Low bank, probable former field boundary. SMR 606 - broad ditch separating from 52/4
52/4	52/4		52/4	Low bank dividing field. Medieval field shape
52/5	52/5			Former field boundaries in evidence. Find of medieval coins SMR 466

PAPER 6
PCA 4B and PCR (including 5 & 5C)

PCA 5B	PCA 5	PCA 5C	PCR E1	PCR E2	Field Descriptions
32/5			32/5	32/5	Not possible to survey
32/6				32/6	Not possible to survey
32/7				32/7	Not possible to survey
33/2	33/2		33/2		Undefined unclear earthworks
33/3			33/3		Undefined unclear earthworks
33/4			33/4		Undefined unclear earthworks
Unsurveyed field	Unsurveyed fields	Unsurveyed field			
47/6					No earthworks
47/5			47/5	47/5	No earthworks
50/4			50/4	50/4	No earthworks
	50/5				No earthworks
		49/2	49/2		No earthworks
		47/4	47/4	47/4	No earthworks
			33/5		No earthworks
			35/7		Linear earthwork
			36/8		No earthworks
			36/10		No earthworks

			36/11		Linear earthwork
			36/12		No earthworks
			36/13	36/13	No earthworks
			38/2		No earthworks
			38/3		No earthworks
			42/1		No earthworks
			39/1		No earthworks
			49/1		No earthworks
				41/1	Linear earthworks
				33/1	Denuded settlement earthworks - supplementary site F
				34/1	Field system earthworks and possible settlement earthworks
				35/1	No earthworks
				34/2	No earthworks
				40/1	No earthworks
				36/1	Linear earthwork
				36/2	No earthworks
				36/4	Field system earthworks
				38/1	No earthworks
				47/1	No earthworks
				47/2	No earthworks
				47/3	No earthworks

PAPER 7
PCA 18 & PCR

Most of 18 has not been surveyed, apart from East of Wingfield, but SMRs have been plotted.

PCA 18	PCR	Field Descriptions
Unsurveyed fields		<p>Close to SMR 610 ST 85 NW (AP enclosures)</p> <p>Close to SMR 608 medieval fields earthworks</p> <p>Some fields SW of SMR 608 look like they are medieval in origin</p> <p>SMR 452 - APs of ?med fields</p>
51/9		No identifiable earthworks but undulations
51/8		Not possible to survey
51/11		Probable medieval field. Drop of c.2m from 51/7 along hedgeline, possible lynchet. Possible hollow way leaving field at southern boundary
51/7		Not possible to survey
52/7		Two possible lynchets, now ploughed out, not impacted by this route
53/2		No visible earthworks
53/4		Undulations, no visible earthworks
53/5		Undulations. Possible med. field shape for SE boundary
53/6		Possible ridge and furrow
Unsurveyed fields		<p>Mostly of pm/modern layout, but passes through Hoggington - possibility of shrunken M.V?</p> <p>South of Frome Road, probable medieval field</p>

58/7		No visible earthworks
58/8		No visible earthworks
58/9		No visible earthworks SMR 24247 ring ditch
58/10} 58/11}		Former field boundary visible, lynchet
61/13		Not possible to survey
61/12		No earthworks visible
Unsurveyed fields		
61/9		Possible earthworks adjacent to Somerset SMR 23139 prehistoric flint scatter
61/10		No obvious earthworks - demolished cottage "Billingsgate" in southern corner
61/7		No visible earthworks
Unsurveyed fields		
	47/5	Undulations, no visible earthworks
	50/4	No earthworks
	50/5	Broad ditch separating 50/5 and 50/8, impacted by PCR. No identifiable earthworks in field itself, possible banks and raised areas. Ditch around perimeter. Close to SMR 304 - R-B finds, AP cropmarks and SMR 452 - Deserted Medieval Village. No direct impact on known sites
	51/2	Linear bank visible. Find of neolithic polished axe. Extensive cropmark complex in 1976 reported
	52/1	Two possible lynchets now ploughed out
	52/2	Undulations, possibly undefined earthworks

	52/3	Possible traces of terracing. Low bank, probable former field boundary. SMR 606 - broad ditch separating from 52/4
	52/4	Low bank dividing field. Medieval field shape
	52/5	Former field boundaries in evidence. Find of medieval coins SMR 466

PAPER 8

PCA Route 14 & PCR in Avon Valley at Bathford

PCA 14	PCR	Field Descriptions
N/A	12/1	Embankment c1.5m high c4m wide in line with Bathford Hill possible former bridge, causeway? Bathford Bridge SMR Avon 1737 affected (SAM)
	12/2	One of three possible sites for SMR Avon 1739 - Romano-British Buildings, but no earthworks visible on the floodplain
	12/3	Earthworks of unclear nature on eastern boundary. Close to one of three possible sites for SMR Avon 1739 Romano- British Buildings
	12/4	Earthworks of unclear nature on eastern boundary affected. Impact on one of three possible sites for SMR Avon 1739 Romano-British Buildings
13/1	13/1	Survey not possible
	13/3	Crosses conjectured line of Roman Road (SMR 4560).
Unassessed field west of River Avon		No obvious earthworks, but further assessment needed

ARCHAEOLOGY

APPENDIX III

SUPPLEMENTARY SITES

Reported Archaeological Features (not on the sites and monuments records)

- A Field north of Seymours Court, Rode/Beckington earthworks present, possibly settlement earthworks. NGR: ST 811528.
- B Field north-east of Seymours Court, Rode/Beckington, reported pond barrow (pers. comm. Mr Slay, tenant farmer). Inspected during walkover survey, two large sarcen stones present, lying flat, on opposite edges of a roughly circular shallow depression, orientated c.east-west. NGR: c.ST 81355293.
- C South-east corner of field 61/10, at NGR: ST 81655220 (pers. comm. tenant farmer, Mr Slay): a cottage, of unknown date was demolished within the past 30 years. This cottage was called Billingsgate, from which the adjacent field takes its present day name.
- D¹ North-east of the Devil's Bed and Bolster long barrow, aerial photographs
D² showing ring ditches are reported. (pers. comm. Mr Slay, tenant farmer. Mr Slay was shown these photographs by P.C. Prescott, who can be contacted at Frome police station). NGR c.ST 816534.
- E Field 52/1 pers. comm. Mr Fuller (farmer): Find of neolithic polished axe in this field, now kept in farmhouse. Also, in 1976, cropmarks were readily visible, forming squares, ovals, lines and circles. No aerial photographs have yet been traced. NGR: ST 829579.
- F Field 33/1 at Woolley Park Farm, possible denuded settlement earthworks at NGR ST 841617.

ARCHAEOLOGY

APPENDIX IV

**PROFORMA WALKOVER
RECORD SHEET**

**A36 EAST OF BATH: ARCHAEOLOGY
WALK OVER RECORD**

21 JULY 1993

DATE OF VISIT(S):	RECORD NO:	OS PARCEL NO:
WALKER:		OS GRID REF:
COUNTY:	DIST:	PARISH:
OTHER DESCRIPTIVE NAME:		
OWNER	TENANT:	
PRESENT LAND USE:		
PAST LAND USE:		
TOPOGRAPHY (tick as appropriate) <input type="radio"/> FLAT <input type="radio"/> HILLCREST <input type="radio"/> HILLSIDE <input type="radio"/> VALLEY FLOOR		
DIRECTION OF SLOPE(S):		
WATERCOURSE PRESENT?	LOCATION:	
GEOLOGY:	SOIL TYPE:	
POTENTIAL HAZARDS:		
DESCRIPTION (continue overleaf)		

East of Bath Archaeological Consultants May
(wherever survey info. incorporated).
21.7.93

Field visited and survey attempted
No earthmarks observed

Field visited but impossible to survey
(eg due to high crops)

Field identification (first the land holding
number, second the field number for that
land holding)

Field contains clear settlement earthwork

Field contains clear field system earthwork

Field contains undefined, unclear, earthwork

Field contains other earthmarks


Area of ^{Special} Archaeological Significance (with AAS)
water courses

Sites and monuments record.

Aerial photograph traces

Ridge and furrow.
Listed Building

~~Archaeology reported~~ Supplementary sites



A36 EAST OF BATH: ARCHAEOLOGY
WALKOVER SURVEY FIELDS (NORTH)

R1551 RPS 1

1:25000 JULY 1992

ORIGINAL AT A3 RPS CLOUSTON
THE ENVIRONMENTAL CONSULTANTS

ORIGINAL IN
COLOUR



A36 EAST OF BATH: ARCHITECTURAL
WALKOVER SURVEY FIELDS CENTRE

R1551


1.25.000

JULY 1993

ORIGINAL AT A3

RPS CLOUSTON

ORIGINAL IN
COLOUR




A36 EAST OF BATH: ARCHAEOLOGY
WALKOVER SURVEY FIELDS(SOUTH)

PROJECT NUMBER: RPS 3
DATE: July 1993

ORIGINAL AT A3
ORIGINAL IN COLOUR

RPS CLOUSTON
THE ENVIRONMENTAL CONSULTANCY



V A PLAN RE TITLED ROUTE 5C CORRECTED TO 5B

RPS CLOUSTON
THE ENVIRONMENTAL CONSULTANCY

ENVIRONMENTAL PLANNERS AND SCIENTISTS

AS6 EAST OF BATH: ARCHAEOLOGY


WALKOVER SURVEY FEATURES

RPS 4

1:10000 July 1993

RPS CLOUSTON
BY PHOTOGRAMMETRIC CORRELATION

ORIGINAL AT A3
ORIGINAL IN
COLOUR



13

13B

BATHFORD CP

Bathford

Monkton Farleigh

AMPTON CP

4182

4183

4184

4185

4186

4187

4188

4189

4190

4191

4192

4193

4194

4560

4561

4562

4563

4564

4565

4566

4567

4568

4569

4570

4571

4572

4573

4574

4575

4576

4577

4578

4579

4580

4581

4582

4583

4584

4585

4586

4587

4588

4589

4590

4591

4592

4593

4594

4595

4596

4597

4598

4599

4600

4601

4602

4603

4604

4605

4606

4607

4608

4609

4610

4611

4612

4613

4614

4615

4616

4617

4618

4619

4620

4621

4622

4623

4624

4625

4626

4627

4628

4629

4630

4631

4632

4633

4634

4635

4636

4637

4638

4639

4640

4641

4642

4643

4644

4645

4646

4647

4648

4649

4650

4651

4652

4653

4654

4655

4656

4657

4658

4659

4660

4661

4662

4663

4664

4665

4666

4667

4668

4669

4670

4671

4672

4673

4674

4675

4676

4677

4678

4679

4680

4681

4682

4683

4684

4685

4686

4687

4688

4689

4690

4691

4692

4693

4694

4695

4696

4697

4698

4699

4700

4701

4702

4703

4704

4705

4706

4707

4708

4709

4710

4711

4712

4713

4714

4715

4716

4717

4718

4719

4720

4721

4722

4723

4724

4725

4726

4727

4728

4729

4730

4731

4732

4733

4734

4735

4736

4737

4738

4739

4740

4741

4742

4743

4744

4745

4746

4747

4748

4749

4750

4751

4752

4753

4754

4755

4756

4757

4758

4759

4760

4761

4762

4763

4764

4765

4766

4767

4768

4769

4770

4771

4772

4773

4774

4775

4776

4777

4778

4779

4780

4781

4782

4783

4784

4785

4786

4787

4788

4789

4790

4791

4792

4793

4794

4795

4796

4797

4798

4799

4800

4801

4802

4803

4804

4805

4806

4807

4808

4809

4810

4811

4812

4813

4814

4815

4816

4817

4818

4819

4820

4821

4822

4823

4824

4825

4826

4827

4828

4829

4830

4831

4832

4833

4834

4835

4836


4837

4838

4839

4840

PROJECT **AS6 EAST OF BATH**
 TITLE **WALKOVER SURVEY FEATURES**
 PROJECT NUMBER **R1551B**
 DRAWING NUMBER **RPS 10**
 DATE **JULY '93**
RPS CLOUSTON
 ORIGINAL AT A3
 ORIGINAL IN **COLOUR**



A ●
 B ●
 C ●

1B

BECKINGTON CP

23139

22

102

103

104

105

106

107

108

109

110

111

112

113

114

115

116

117

118

119

120

121

122

123

124

125

126

127

128

129

130

131

132

133

134

135

136

137

138

139

140

141

142

143

144

145

146

147

148

149

150

151

152

153

154

155

156

157

158

159

160

161

162

163

164

165

166

167

168

169

170

171

172

173

174

175

176

177

178

179

180

181

182

183

184

185

186

187

188

189

190

191

192

193

194

195

196

197

198

199

200

201

202

203

204

205

206

207

208

209

210

211

212

213

214

215

216

217

218

219

220

221

222

223

224

225

226

227

228

229

230

231

232

233

234

235

236

237

238

239

240

241

242

243

244

245

246

247

248

249

250

251

252

253

254

255

256

257

258

259

260

261

262

263

264

265

266

267

268

269

270

271

272

273

274

275

276

277

278

279

280

281

282

283

284

285

286

287

288

289

290

291

292

293

294

295

296

297

298

299

300

301

302

303

304

305

306

307

308

309

310

311

312

313

314

315

316

317

318

319

320

321

322

323

324

325

326

327

328

329

330

331

332

333

334

335

336

337

338

339

340

341

342

343

344

345

346

347

348

349

350

351

352

353

354

355

356

357

358

359

360

361

362

363

364

365

366

367

368

369

370

371

372

373

374

375

376

377

378

379

380

381

382

38

