Barrow Farm Ganton Hill Ganton Scarborough North Yorkshire SE 0026 7505

Archaeological Strip and Record Report

© MAP Archaeological Practice Ltd.

September 2011

Barrow Farm Ganton Hill Ganton Scarborough North Yorkshire SE 0026 7505

11/00336/FUL

Archaeological 'Strip and Record' Report

Contents	Page
Figure List	2
Plate List	2
Summary	3
1. Introduction	3
2. Topography and Geology	4
3. Historical and Archaeological Background	4
4. Methodology	5
5. Results	6
6. Discussion	6
7. Bibliography	6
Appendix 1. Written Scheme of Works	11

Figure List	Page
1. Site Location. Scale 1:25,000	7
2. Area of Archaeological Strip and Record.	8
Plate List	
1. General View of Site. Facing North.	9
2. Wind Turbine Base. Facing North-east.	9
3. Cable Trench. Facing North.	10

1 Section Through Cable Trench, Easing East	10
	10

Barrow Farm Ganton Hill Ganton Scarborough North Yorkshire SE 0026 7505

11/00336/FUL

Archaeological 'Strip and Record' Report

Summary

An Archaeological Strip and Record excavation was carried out by MAP Archaeological Practice Ltd on land to the south of Barrow Farm, Ganton Hill, Ganton, Scarborough, North Yorkshire on September 9th 2011. The work was undertaken in order to fulfil a condition attached to the Planning Application Consent (Ref. 11/00336/FUL) and involved monitoring the groundworks associated with the erection of a 24.6m wind turbine to generate electricity for on farm use.

No archaeological features, deposits or finds were encountered during the Archaeological Strip and Record.

1. Introduction

- 1.1 This report sets out the results of an Archaeological 'Strip and Record' excavation that was carried out during the groundworks associated with the erection of a 24.6m wind turbine to generate electricity for on farm use at Barrow Farm, Ganton Hill, Ganton, Scarborough, North Yorkshire (SE 0026 7505, Fig. 1).
- 1.2 The Watching Brief was designed to provide the appropriate level of recording for archaeological remains, deposits or finds that might be affected by the development, in accordance with the archaeology policy

issued by the Secretary of State for the Environment contained in *Planning Policy Statement 5 (PPS 5)*.

- 1.3 The work was funded by Earthmill Ltd.
- 1.4 The Ordnance Survey maps are reproduced under licence from the Ordnance Survey, licence no. AL 50453A, with permission from the Controller of Her Majesty's Stationery Office, (c) Crown Copyright.

2. Topography and Geology

2.1 The site lies in the field immediately south of Barrow Farm, which is situated off the A64, on Ganton Hill road leading from Ganton to Foxholes (Fig. 1). The site was in use as arable cultivation.

3. Historical and Archaeological Background

- 3.1 The Yorkshire Wolds contain relict landscapes dating from the Neolithic through to the medieval periods, and cropmarks exist within the vicinity of the site that give evidence for possible settlement activity. The remains of round barrows and square barrows have been identified to the south and east of the proposed development site (Fenton-Thomas, 2005). Cropmarks of further pit alignments, linear and sub-rectangular features possibly representing settlement of the Iron age or roman periods, have been recorded in close proximity to the proposed development site, suggesting wide spread activity.
- 3.2 In the medieval period the site fell within the lands of Dickering Wapentake. Ganton existed at the time of the Domesday Survey (1084) when it was referred to as *Galmeton*, the name probably meaning *"farmstead of a man called Galmrl*". The church at Ganton was dedicated to St Nicholas.

3.3 At the time of the 1854 First Edition Ordnance Survey map the site lay within an open agricultural field just west of Ganton Dale Plantation. Barrow Farm is not present on the 1972-1979 Edition Ordnance Survey Map and it is therefore presumed that it was established after this time.

4. Methodology

- 4.1 The installation of the wind turbine base involved the preliminary topsoil strip of an area c. 5m by 5m using a 360^o tracked excavator with a broad, toothless ditching bucket, operating under close archaeological supervision. Machining ceased at the top of archaeological or naturally-formed deposits, depending upon which was located soonest.
- 4.2 The machine subsequently excavated the trench for the cable using a 0.60m wide toothless bucket under archaeological supervision. The cable trench ran approximately south-northwards from the turbine for a length of c.120m, and was 0.90m deep.
- 4.3 All work was carried out in line with the Institute of Field Archaeologists Code of Conduct (IFA 1998).
- 4.4 A photographic record of the monitored groundworks was maintained throughout the Recording Brief on a high resolution digital camera.

5. Results (Pls. 2-4)

5.1 Natural deposits of chalk were encountered at the location of the wind turbine. A dark brown loamy topsoil deposit lay directly above a brownish orange loamy clay which in turn sealed the natural chalk. The topsoil deposit and had a maximum depth of 0.28m (PI. 2).

- 5.2 Similar deposits were encountered throughout the cable trench (Pls. 3-4). Loose, modern topsoil overlaid the subsoil which sealed the hard compact natural chalk.
- 5.3 No archaeological features, deposits or finds were present within the turbine base or cable trench.

6. Discussion

6.1 Natural deposits were reached in both the turbine base and cable trench and *in situ* subsoil deposits were also observed. No archaeological features, finds or deposits were observed on the site.

7. Bibliography

Fenton-Thomas, C	2005	The Forgotten Landscape of the Yorkshire Wolds.
Smith, A H	1937	The Place-Names of the East Riding of Yorkshire and York.



Figure 1. Site Location



Figure 2. Archaeological Watching Brief Area.



Plate 1. General View of Site. Facing North.

Plate 2. Wind Turbine Base. Facing North-east.







Plate 3. Cable Trench. Facing North.

WRITTEN SCHEME OF INVESTIGATION FOR ARCHAEOLOGICAL STRIP AND RECORD

Barrow Farm Ganton Hill Ganton Scarborough North Yorkshire

Prepared for Earthmill

by

MAP Archaeological Practice Ltd Tel. 01653 697752

24th August

Barrow Farm Ganton Hill Ganton Scarborough North Yorkshire

WRITTEN SCHEME OF INVESTIGATION FOR ARCHAEOLOGICAL STRIP AND RECORD

1. Summary

1.1 The topsoil, overburden strip and archaeological recording is to take place during the erection of a 24.6m high wind turbine to generate electricity for on farm use associated with the (planning application 11/00337/FUL).

2. Purpose

2.1 This written scheme of investigation (WSI) represents a summary of the broad archaeological requirements to mitigate the impact of development proposals upon the archaeological resource and to comply with the archaeological planning condition. This is in accordance with the guidance of Planning Policy Statement 5. No work on site should commence until the implementation of the scheme is the subject of a standard ICE Conditions of Contract for Archaeological Investigation agreement between the Client and the selected archaeological contractor.

3. Location and Description

3.1 The Proposed Development Area is located at Barrow Farm, Ganton Hill, Ganton, Scarborough, North Yorkshire.

4. Archaeological and Historical Background

4.1 The proposed development area lies in an area of high archaeological potential. The possible remains of round barrows and square barrows have been identified to the south and east of the proposed

development site. Cropmarks of further pit alignments, linear and subrectangular features possibly representing settlement of the Iron age or roman periods, have been recorded in close proximity to the proposed development site, suggesting wide spread activity. There is the potential therefore for sub-surface archaeological remains to be present within the proposed development site.

5. Objectives

5.1 The objectives of the archaeological work are:

1. to determine by means of targeted archaeological excavation the character, extent and nature of the archaeological remains within the development area,

2. to locate, recover, identify, assess and conserve (as appropriate) any archaeological artefacts exposed during the course of the excavation,

3. where appropriate, to undertake a post-excavation assessment after completion of fieldwork and site archive to assess the potential for further analysis and publication, and to undertake such analysis and publication as appropriate,

4. to prepare and submit a suitable archive to the appropriate museum.

6. Access, Safety and Monitoring

- 6.1 Access to the site should be arranged through the commissioning body.
- 6.2 It is the archaeological contractor's responsibility to ensure that Health and Safety requirements are fulfilled. Necessary precautions should be taken near underground services and overhead lines. A risk assessment

should be provided to the commissioning body before the commencement of works.

- 6.3 The project will be monitored by the Historic Environment Team, NYCC, to whom written documentation should be sent ten days before the start of the excavation including:
 - 1. the date of commencement,
 - 2. an opportunity to monitor the works.
- 6.4 Where appropriate, the advice of the English Heritage Regional Advisor for Archaeological Science, (Yorkshire and Humber Region) may be called upon to monitor the archaeological science components of the project. Archaeological contractors may wish to contact him to discuss the science components of the project before submission of tenders.
- 6.5 It is the archaeological contractor's responsibility to ensure that monitoring takes place by arranging monitoring points as follows:
 - 1. a preliminary meeting or discussion at the commencement of the contract.
 - progress meeting(s) during the fieldwork phase at appropriate points in the work schedule, to be agreed.
 - a meeting during the post-fieldwork phase to discuss the draft report and archive before completion.
- 6.6 It is the responsibility of the archaeological contractor to ensure that any significant results are brought to the attention of the Historic Environment Team, NYCC and the commissioning body as soon as is practically possible. This is particularly important where there is any likelihood of contingency arrangements being required.

7. Brief

7.1 The archaeological contractor should be informed in advance of the correct timing and schedule of site preparation and preliminary excavation works associated with the construction of the proposed

development. A specified timetable should be agreed within which the archaeological excavation may be carried out prior to further construction commencing.

- 7.2 Archaeological work within the area of proposed development should include the initial supervision of the preliminary site/topsoil strip areas down to the top of archaeological deposits. Overburden such as turf, topsoil, made ground, rubble or other superficial fill materials may be removed by machine using a back-acting excavator which should be fitted with a toothless or ditching bucket. Mechanical excavation equipment shall be used judiciously, under archaeological supervision down to the top of archaeological deposits, or the natural subsoil (C Horizon or soil parent material), whichever appears first. Bulldozers or wheeled scraper buckets should not be used to remove overburden above archaeological deposits. Topsoil should be kept separate from subsoil or fill materials.
- 7.3 Once overburden/topsoil has been removed, any further machine or hand excavation should be halted to allow the archaeological contractor to observe, clean and assess any archaeological remains on the site. Using the information and artefacts collected to this stage, all features and deposits should be assessed as to their origin or function, probable date, and importance for further recording. Features and layers identified as having potential for further recording should be excavated by hand, sampled, and recorded as set out below. This is in order to fulfil Objectives 5.1.1 and 5.1.2 above and in order to understand the full stratigraphic sequence. In case of query as to the extent of investigation, a site meeting shall be convened with the Historic Environment Team Leader, NYCC.
- 7.4 The character, information content and stratigraphic relationships of features and deposits should be determined. All linear features, such as ditches, should have their shape, character, and depth determined by hand excavation of sections. A minimum sample of 20% of each

linear feature of less than 5m in length and a minimum sample of 10% of each linear feature greater than 5m in length (each section will be not less than 1m wide) should be excavated. All junctions of linear features should have their stratigraphic relationships determined, if necessary using box sections. A 100% sample of all stake-holes should be excavated, and all pits, post-holes and other discrete features should be half-sectioned by hand to record a minimum of 50% of their fills, and their shape. Any other unknown or enigmatic features should be investigated similarly. Large pits, post-holes or deposits of over 1.5m diameter should be excavated sufficiently to define their extent and to achieve the objectives of the investigation, but should not be less than 25%. All intersections should be investigated to determine the relationship(s) between features.

- 7.5 The project should be undertaken in a manner consistent with the guidance of MAP2 (English Heritage 1991) and professional standards and guidance (IFA 2001). Scientific investigations should be undertaken in a manner consistent with the English Heritage bestpractice guidelines (2003). An outline strategy of sampling for scientific dating, geoarchaeology and soil science (Canti 1996), biological analysis (English Heritage 2002), artefact conservation and analysis (Watkinson and Neal 1998), and analysis of technological residues (English Heritage 2001), ceramics, and stone should be agreed with the Local Authority, in consultation with the English Heritage Regional Advisor for Archaeological Science (RA) before commencement of site work. This strategy should be based on the results of previous archaeological work in the area. The strategy will be subject to variation as appears necessary during the excavation, following consultation with the Local Authority and the RA.
- 7.6 All specialists in Archaeological Science (both those employed inhouse by the archaeological contractor or those sub-contracted) should be named in project documents. Agreement of specialists must always be obtained before their names are listed. Their competence to

undertake proposed investigations, and the availability of adequate laboratory facilities and reference collections should be demonstrated. There should be agreement in writing on timetables and deadlines for all stages of work.

- 7.7 All deposits should be fully recorded on standard context sheets, photographs and conventionally-scaled plans and sections. Each excavation area should be recorded to show the horizontal and vertical distribution of contexts. The elevation of the underlying natural subsoil where encountered should be recorded. The limits of excavation should be shown in all plans and sections, including where these limits are coterminous with context boundaries.
- 7.8 Any significant unstratified artefacts or small finds should be collected. Metal detecting, including the scanning of topsoil and spoil heaps, should only be permitted subject to archaeological supervision and recording so that metal finds are properly located, identified, and conserved.
- 7.9 Using the information and artefacts collected to this stage, all features and deposits should be assessed as to their origin or function, probable date, and importance for further excavation. Features and layers identified as having potential for further recording should be fully excavated, sampled, and recorded. Full excavation should be carried out on features and deposits of limited potential where the stratigraphic relationships, phasing or origin of these are still unclear. Further excavation may also be needed to expose the full stratigraphic sequence across the site.
- 7.10 All artefacts and ecofacts visible during excavation should be collected and processed, unless variations in this principle are agreed with the Senior Archaeologist, NYCC. In some cases, sampling may be most appropriate. Finds should be appropriately packaged and stored under optimum conditions, as detailed in *First Aid for Finds* (Watkinson &

Neal, 1998). A regular transfer of finds from the site to the conservation laboratory is desirable, particularly in the case of long term excavations

- 7.11 Where there is evidence for industrial activity, macroscopic technological residues (or a sample of them) should be collected by hand. Separate samples (*c*. 10ml) should be collected for micro-slags hammer-scale and spherical droplets). In these instances, the guidance of English Heritage (2001) should be followed.
- 7.12 Samples should be collected for scientific dating (radiocarbon, dendrochronology, luminescence dating, archaeomagnetism and/or other techniques as appropriate). For this excavation, tenders should allow provision for a minimum of four dates using scientific techniques.
- 7.13 Buried soils and sediment sequences should be inspected and recorded on site by a recognised geoarchaeologist. Samples may be collected for analysis of chemistry, magnetic susceptibility, particle size, micromorphology and/or other techniques as appropriate, following the outline strategy presented in the Project Design, and in consultation with the geoarchaeologist. The guidance of Canti (1996) and English Heritage (2002) should be followed.
- 7.14 All securely stratified deposits should be sampled, from a range of representative features, including pit and ditch fills, postholes, floor deposits, ring gullies and other negative features. Positive features should also be sampled. Sampling should also be considered for those features where dating by other methods (for example pottery and artefacts) is uncertain. Bulk samples should be collected from contexts containing a high density of bones. Spot finds of other material should be recovered where applicable.
- 7.15 Coarse sieved samples for the recovery of animal bones and other artefact/ecofact categories should be 100 litres plus. Flotation samples, for the recovery of charred plant remains, charcoal, small animal bones

and mineralised plant remains, should be between 40 and 60 litres in size, although this will be dependent upon the volume of the context. Entire contexts should be sampled if the volume is low. Whenever possible, coarse sieved samples (wet or dry) and flotation samples should be processed during fieldwork to allow the continuous reassessment and refinement of sampling strategies. Samples from waterlogged and anoxic deposits, which might contain plant macros and entomological evidence, taken for General Biological Analysis (GBA), should normally be 20 litres in size. The English Heritage guidance should be consulted for details of sample size for other specialist samples that may be required. Allowance should be made for a site visit from the contractor's environmental specialists/consultants where appropriate.

7.16 In the event that any human remains are encountered, they must be treated at all stages with care and respect. Excavators must be aware of, and comply with, the relevant legislation and any Department of Constitutional Affairs and local environmental health concerns. Burials should be recorded *in situ* and subsequently lifted, washed in water (without additives), marked and packed to standards compatible with McKinley and Roberts (1993). Site inspection by a recognised specialist is desirable in the case of isolated burials, and necessary for cemeteries. Proposals for the final placing of human remains following study and analysis will be required in the Project Design. Further guidance is provided by English Heritage (2004). For this excavation, tenders should allow provision for any human remains to be subject to carbon and nitrogen isotope study.

Post-Excavation Assessment

7.17 Upon completion of archaeological fieldwork, where appropriate, a post-excavation assessment should be undertaken and an assessment report produced in accordance with the guidance of MAP2 (English Heritage 1991). The assessment report should summarise the

evidence recovered and should consider its potential for further analysis, review the programme of archaeological science, update the project design as necessary and provide costings for the postexcavation analysis stage of work, with proposals for the production of a final report and/or publication. The site assessment report should include reports on all aspects of Archaeological Science investigated, and include assessment of their suitability for analysis, so as to inform the updated project design.

- 7.18 Assessment of artefacts should include x-radiography of all iron objects (Jones ed. 2006), after initial screening to separate obviously modern debris, and a selection of non-ferrous artefacts (including all coins and a sample of any industrial debris relating to metallurgy). An assessment of all excavated material should be undertaken by conservators and finds researchers in collaboration. Where necessary, active stabilisation/consolidation will be carried out, to ensure long term survival of the material, but with due consideration to possible future investigations. Once assessed, all material should be packed and stored in optimum conditions, as described in Watkinson and Neal (1998).
- 7.19 Assessment of any technological residues should be undertaken. Processing of all samples collected for biological assessment, or subsamples of them, should be completed. Assessment will include recording the preservation state, density and significance of material retrieved, to inform up-dated project designs. Methods presented in English Heritage (2002) should be followed. Unprocessed sub-samples should be stored in conditions specified by the appropriate specialists.
- 7.20 Samples collected for geoarchaeological assessment should be processed as deemed necessary by the specialist, particularly where storage of unprocessed samples is thought likely to result in deterioration. Appropriate assessment should be undertaken (see Canti 1996, English Heritage 2002). Animal bone assemblages, or sub-

samples of them, should be assessed by a recognised specialist (English Heritage 2002). Assessment of human remains should be undertaken by a recognised specialist (English Heritage 2004).

<u>Analysis</u>

- 7.21 Within a time agreed with the Historic Environment Team Leader, NYCC, a timetable for post-excavation work should be produced, following consultation (including team meetings for larger-scale sites), with all specialists involved in the project. Agreement of timetables should be made in writing with external specialists.
- 7.22 A detailed and cost-effective strategy for scientific dating should be prepared, in consultation with appropriate specialists. Samples for dating should be submitted to promptly, and prior agreement should be made with the laboratory on turn-around time and report production.
- 7.23 All artefacts should be conserved and stored in accordance with Watkinson and Neal (1998). Investigative conservation should be undertaken on those objects selected during the assessment phase, with the aim of maximising information whilst minimising intervention. Where necessary, active stabilisation/consolidation will be carried out, to ensure long-term survival of the material, but with due consideration to possible future investigations. Proposals for ultimate storage should follow Walker (1990).
- 7.24 Appropriate analysis of technological residues should be undertaken, as outlined in English Heritage (2001). Samples or sub-samples collected for all types of biological and geoarchaeological analysis should be processed, and material retrieved analysed by recognised specialists. Any unprocessed sub-samples should be stored in conditions specified by the specialists, or a reasoned discard policy should be developed (English Heritage 2002).

7.25 Analysis of animal bones should be undertaken by a recognised specialist, as specified in the updated project design (see also English Heritage 2002). Analysis of human remains should be undertaken by a recognised specialist, as specified in the up-dated project design.

8. Archive

- 8.1 A field archive should be compiled consisting of all primary written documents, plans, sections and photographs should be produced and cross-referenced. Archive deposition should be undertaken with reference to the County Council's *Guidelines on the Transfer and Deposition of Archaeological Archives.*
- 8.2 The archaeological contractor should liase with an appropriate museum to establish the detailed requirements of the museum and discuss archive transfer in advance of fieldwork commencing. The relevant museum curator should be afforded to visit the site and discuss the project results. In this instance, Scarborough Museum is suggested.
- 8.3 The archiving of any digital data arising from the project should be undertaken in a manner consistent with professional standards and guidance (Richards & Robinson, 2000). The archaeological contractor should liaise with an appropriate digital archive repository to establish their requirements and discuss the transfer of the digital archive.
- 8.4 The archaeological contractor should also liaise with the HER Officer, North Yorkshire County Council, to make arrangements for digital information arising from the project to be submitted to the North Yorkshire Historic Environment Record for HER enhancement purposes. The North Yorkshire HER is not an appropriate repository for digital archives arising from projects.

9. Copyright

- 9.1 Copyright in the documentation prepared by the archaeological contractor and specialist sub-contractors should be the subject of an additional licence in favour of the museum accepting the archive to use such documentation for their statutory educational and museum service functions, and to provide copies to third parties as an incidental to such functions.
- 9.2 Under the Environmental Information Regulations 2005 (EIR), information submitted to the HER becomes publicly accessible, except where disclosure might lead to environmental damage, and reports cannot be embargoed as 'confidential' or 'commercially sensitive'. Requests for sensitive information are subject to a public interest test, and if this is met, then the information has to be disclosed. The archaeological contractor should inform the client of EIR requirements, and ensure that any information disclosure issues are resolved before completion of the work. Intellectual property rights are not affected by the EIR.

10. Report

- 10.1 Following post-excavation assessment and analysis as appropriate, a report should be prepared following the County Council's guidance on reporting: *Reporting Check-List.* The report should set out the aims of the work and the results as achieved, including photographs of operations, description of the remains including all relevant plans and sections, interpretation and assessment of the significance of the remains. The report should also include a listing of contexts, finds, plans and sections, and photographs.
- 10.2 The results from investigations in Archaeological Science, *including negative results*, should be included in the Site Archive and reported to the HER.

- 10.3 A timetable for completion of reports should be agreed with all specialists, and agreements in writing with sub-contracted external specialists are desirable. The time-table should allow for adequate provision by the excavator of contextual information, provisional dating and stratigraphic relationships of contexts. Reports should include clear statements of methodology. The results from scientific analysis should be clearly distinguished from their interpretation. Non-technical summaries of results should be included. Reports on Archaeological Science should be published fully, in the text of printed reports or in the main body of reports disseminated by electronic means, wherever the results merit it.
- 10.4 At least six copies of the report should be produced and submitted to the commissioning body, the Local Planning Authority, the museum accepting the archive, the English Heritage Regional Advisor for Archaeological Science and, under separate cover, North Yorkshire County Council Heritage Section.
- 10.5 If the archaeological fieldwork produces results of sufficient significance to merit publication in their own right, allowance should be made for the preparation and publication of a summary in a local journal, such as the *Yorkshire Archaeological Journal*. This should comprise, as a minimum, a brief note on the results and a summary of the material held within the site archive, and its location.
- 10.6 Upon completion of the work, the archaeological contractor should make their work accessible to the wider research community by submitting digital data and copies of reports online to OASIS (<u>http://ads.ahds.ac.uk/project/oasis/</u>). Submission of data to OASIS does not discharge the planning requirements for the archaeological contractor to notify the Historic Environment Team Leader, NYCC of the details of the work and to provide the Historic Environment Record (HER) with a report on the work.

11. Further Information

11.1 Further information or clarification of any aspects of this brief may be obtained from:

MAP Archaeological Practice Ltd 01653 697752

11.2 This written scheme of investigation is valid for a period of six months from the date of issue. After that time it may need to be revised to take into account new discoveries, changes in policy or the introduction of new working practices or techniques. In addition, depending upon the final design of development, the methodology of the archaeological excavation may need to be modified accordingly.

11.3 <u>References</u>

_

Association for	1995 Environmental Archaeology and					
Environmental	Archaeological Evaluations,					
Archaeology	Recommendations Concerning the					
	Component of Archaeological Evaluations			ions		
	in Eng	gland.	Working	Papers	of	the
	Association for Environmental Archaeolog Number 2. <u>http://www.envarch.net/publications/papers</u> <u>evaluations.html</u>			ogy,		
				/pape	pers/	
Canti, M	1996 G	Guideline	es for	carryin	g	out
	Assessr	nents i	n Geoarcl	naeology.	Anc	cient

Assessments in Geoarchaeology, Ancient Monuments Laboratory Report 34/96, English Heritage

English Heritage 1991 Management of Archaeological Projects (MAP2) <u>http://www.eng-h.gov.uk/guidance/map2/</u>

English Heritage	2001 Archaeometallurgy:		Centre f	or
	Archaeology	Guidelines	2001/0)1
	http://194.164.6	1.131/Filestore	e/archaeology	'/
	pdf/cfa_archaec	metallurgy.pd	<u>f</u>	

English Heritage 2002 Environmental Archaeology : A guide to the theory and practice of methods, from sampling and recovery to post-excavation. Centre for Archaeology Guidelines 20002/01 <u>http://194.164.61.131/Filestore/archaeology/</u> <u>pdf/enviroarch.pdf</u> (5.93mb)

English Heritage 2003 Archaeological Science at PPG16 interventions: Best Practice Guidance for Curators and Commissioning Archaeologists <u>http://194.164.61.131/filestore/archaeology/p</u> <u>df/briefs%20version%2022.pdf</u>

English Heritage 2004 Human Bones from Archaeological sites. Guidelines for producing assessment documents and analytical reports. Centre for Archaeology Guidelines, unnumbered. <u>http://194.164.61.131/filestore/publications/p</u> df/free/human_bones_2004.pdf

Fenton-Thomas C.2005 The Forgotten Landscape of the
Yorkshire Wolds.

Geoquest

2004 Land to the north of Main Street, Weaverthorpe

Institute of Field 2001 Standards and Guidance for Archaeologists Archaeological Excavation http://www.archaeologists.net/modules/icont

ent/inPages/docs/codes/exc2.pdf

Jones, D M (ed.)	2006 Guidelines on the X-radiography of Archaeological Metalwork. English Heritage.
McKinley, J & Roberts, C	1993 IFA Technical Paper 13 , <i>Excavation</i> and post-excavation treatment of cremated and inhumed human remains.
MAP	2007 27 Wood Street, Norton, North Yorkshire. Archaeological Evaluation. MAP Archaeological Consultanct Ltd.
Smith, A.H.	1937 The Place-Names of the East Riding of Yorkshire and York.
Society of Museum Archaeologists	1993 Selection, retention and dispersal of archaeological collections. Guidelines for use in England, Northern Ireland, Scotland and Wales.
Walker, K.	1990 <i>Guidelines for the preparation of</i> <i>excavation archives for long-term storage</i> , Archaeology Section of the United Kingdom Institute for Conservation.
Watkinson, D & Neal, V	1998 First Aid for Finds (3 rd edition), RESCUE & the Archaeological Section of the United Kingdom Institute for Conservation.

_

APPENDIX 1- SPECIALISTS

Conservation	Ian Panter	YAT	01904 663036
Prehistoric Pottery	Terry Manby		01430 873147
Roman Pottery	Jeremy Evans		0121 7784024
	Paula Ware	MAP	01653 697752
Pre-conquest Pottery	Mark Stephens	MAP	01653 697752
Medieval Pottery	Mark Stephens	MAP	01653 697752
Post Medieval	Mark Stephens	MAP	01653 697752
Pottery			
Clay Tobacco Pipe	Mark Stephens	MAP	01653 697752
CBM	S.Garside –		01904 621339
	Neville		
Animal Bone		WYAS	0113 3837517
Small Finds	Hilary Cool		0116 9819065
Leather	lan Carlisle	YAT	01904 663000
Textile	Penelope	Textile Research in	01904 634585
	Walton Rogers	Archaeology	
Slag/Hearths		Bradford University	01274 3835131
Flint	Pete Makey		01377 253695
Environmental		Diane Alldritt	0141 649 877
Sampling			
Human Remains	Malin Holst	York Osteology Ltd	01904 737509
C14 Dating		SUERAC	0141 270136
Dendro		Sheffield University	0114 2220123
Archaeomagnetic	Mark Noel	Geoquest	01624819364
		Associates	

_