

# Land West of SWISS Centre, Scrivener Drive, Pinewood, Suffolk PIN 004

#### Archaeological Evaluation Report

SCCAS Report No. 2014/111 Client: Poole & Pattle Chartered Architects Author: M. Sommers

© Suffolk County Council Archaeological Service

## Land West of SWISS Centre, Scrivener Drive, Pinewood, Suffolk PIN 004

Archaeological Evaluation Report SCCAS Report No. 2014/111 Author: M. Sommers Contributions By: n/a Editor: Dr R. Gardner Report Date: September 2014

### **HER Information**

| Report Number:           | 2014/111   |
|--------------------------|--|
| Site Name:               | Land West of SWISS Centre, Scrivener Drive,<br>Pinewood, Suffolk |
| Planning Application No: | B/11/01514/FUL   |
| Dates of Fieldwork:      | 16th & 31st July 2014 & 19th September 2014                      |
| Grid Reference:          | TM 1287 4278   |
| Client/Funding Body:     | Poole & Pattle Chartered Architects (on behalf of their client)  |
| Client Reference:        | n/a  |
| Curatorial Officer:      | Dr Jess Tipper   |
| Project Officer:         | M. Sommers   |
| Oasis Reference:         | suffolkc1-184521   |
| Site Code:               | PIN 004  |

Digital report submitted to Archaeological Data Service: http://ads.ahds.ac.uk/catalogue/library/greylit

#### Disclaimer

Any opinions expressed in this report about the need for further archaeological work are those of the Field Projects Team alone. Ultimately the need for further work will be determined by the Local Planning Authority and its Archaeological Advisors when a planning application is registered. Suffolk County Council's archaeological contracting services cannot accept responsibility for inconvenience caused to the clients should the Planning Authority take a different view to that expressed in the report.

Prepared By:M. SommersDate:29th September 2014Approved By:Dr R. GardnerPosition:Contracts ManagerDate:29th September 2014Signed:

### Contents

### Summary

| 1.    | Introduction                                       | 1 |
|-------|--|---|
| 2.    | Geology and topography                             | 1 |
| 3.    | Archaeology and historical background              | 3 |
| 4.    | Methodology  | 4 |
| 5.    | Results  | 5 |
| 6.    | Finds and environmental evidence                   | 6 |
| 7.    | Discussion   | 6 |
| 8.    | Conclusions and recommendations for further work   | 6 |
| 9.    | Archive deposition                                 | 6 |
| 10.   | Acknowledgements                                   | 6 |
| 11.   | Plates   | 7 |
|       |  |   |
| List  | of Figures   |   |
| Figu  | e 1. Location map (Site in red; HER data in black) | 2 |
| Figu  | re 2. Trench location                              | 5 |
| List  | of Plates  |   |
| Plate | e 1. Trench 2, camera facing northwest             | 7 |
| Plate | 2. Trench 2, camera facing northeast               | 7 |
| List  | of Appendices                                      |   |
| Appe  | endix 1. Written Scheme of Investigation           |   |
| Арре  | endix 2. OASIS data collection form                |   |

#### Summary

An archaeological evaluation was carried out on a site known as 'Land West of SWISS Centre' in advance of a commercial development. The site comprises a *c*. 4000m<sup>2</sup> area of land to the northwest of Scrivener Drive, Pinewood, Suffolk. A series of seven trial trenches were excavated across the site but no archaeological deposits, features or artefacts were identified. (Suffolk County Council Archaeological Service Field Team for Poole & Pattle Chartered Architects)

### 1. Introduction

Planning permission has been granted for the construction of a veterinary surgery on a site known as 'Land West of the SWISS Centre' Scrivener Drive, Pinewood, Suffolk (application number B/11/01514/FUL). One of the conditions attached to the planning consent called for an agreed programme of archaeological work to be in place in advance of this development.

The first stage of the programme of work, as specified in a Brief produced by Dr. Jess Tipper of the Suffolk County Council Conservation Team, was the undertaking of a trenched evaluation in order to ascertain what levels of archaeological evidence may be present within the development area and to inform any mitigation strategies that may then be deemed necessary. Based on this brief a Written Scheme of Investigation (WSI) was produced and subsequently approved by the Conservation Team (Appendix 1).

The National Grid Reference for the approximate centre of the site is TM 1287 4278. Figure 1 shows a location plan of the site.

Due to the presence of nesting birds the archaeological evaluation was undertaken over three separate days, namely the 16th and 31st July 2014 and the 19th September 2014, by Suffolk County Council Archaeological Service's Field Team who were commissioned and funded by Poole & Pattle Chartered Architects, on behalf of their client.

### 2. Geology and topography

The site is situated on a raised, level plateau at a height of 40m OD, which forms part of a ridge between two river valleys that runs approximately northwest to southeast. The larger, northeastern valley is drained by the River Gipping, the lower reaches of which are known as the River Orwell, whilst the southwestern valley contains Belstead Brook, which runs in a channel some 950m to the south and southwest of the site.




Figure 1. Location map (Site in red; HER data in black)

The British Geological Survey records that the superficial geology in this area consists of the Lowestoft Formation, a chalky till with outwash sands and gravels, silts and clays with an occasional erratic (BGS, 2014). The uppermost 2m of this deposit tend to have been weathered to a yellowish brown, largely decalcified, stony silty clay.

### 3. Archaeology and historical background

No archaeological sites or findspots were recorded on the County Historic Environment Record (HER) within the development area itself although it does lie within an area of significant archaeological interest. This is primarily due to the presence of a group of Middle Bronze Age cremations that were excavated on a site 100m to the northeast (HER ref. SPT 035, location of cremation cemetery marked in Figure 1).

A small number of other sites are also recorded on the HER in the vicinity. These comprise a thin scatter of Roman pottery and a ditch containing Early Anglo-Saxon pottery 260m to the southwest (HER ref. WSH 012); the documented site of a medieval church 250m to the northwest (HER ref. WSH 006); and a site of a post-medieval milestone 140m to the west (HER ref. WSH 015).

A recent archaeological project involved monitoring and excavation of the soil strip for a new access road off Scrivener Drive (PIN003). The majority of the stripped area was devoid of archaeological features although a single ditch, aligned approximately north-south, was recorded close to Scrivener Drive. A spread of broken Roman tile associated with a charcoal deposit, which has been radiocarbon dated to the 1st/2nd century AD, was recovered from the ditch fill indicating the probable presence of a Roman occupation site in the vicinity.

Given the proximity of the cremation cemetery and the presence of Roman activity there was a high potential for further archaeological deposits to be present within the development area.

### 4. Methodology

The trial trenches were machine excavated down to the level of the natural subsoil using a tracked excavator fitted with a toothless ditching bucket. The location of the trenches was broadly in accordance with the trench plan approved by the County Conservation Team although the presence of a spoil heap resulted in one trench (T3) being moved slightly to the west although an additional trench (T4) was excavated after the spoil's removal.

The machining of the trenches was closely observed throughout in order to identify any archaeological features and deposits and to recover any artefacts that might be revealed. Excavation continued until undisturbed natural deposits were encountered, the exposed surface of which was then examined for cut features. Had any features or significant deposits been identified they would have been sampled through hand excavation in order to determine their depth and shape and to recover datable artefacts.

Following excavation of the trenches, the nature of the overburden was recorded and their locations plotted.

A photographic record of the work undertaken was also compiled using an 18 megapixel digital camera.

### 5. Results

A total of seven evaluation trenches were excavated (fig. 2). The trenches possessed a fairly uniform soil profile comprising 0.2m to 0.3m of topsoil overlying a compact midorangey-brown slightly sandy-silty-clay that was quite compact and contained inclusions of occasional small rounded chalk pebbles and moderate quantities of irregular, unsorted flint stones. Plates 1 and 2 depict Trench 2 as excavated; the other six trenches were of a similar appearance.

The natural geology appeared to be a classic diamicton with thick bands of reddishbrown sands, red-orangey-brown clays and occasional patches of lighter yellowygreyish-brown clay containing frequent chalk inclusions.

No archaeological features were identified in any of the trenches and no significant artefacts were present within the excavated spoil.




Figure 2. Trench location

### 6. Finds and environmental evidence

No artefacts of any period were recovered during the evaluation.

### 7. Discussion

The results of evaluation suggest that no significant archaeological features or deposits are present within the site. The surface of the exposed natural subsoil was cleanly cut and had any buried remains been present it is highly likely they would have been identified.

### 8. Conclusions and recommendations for further work

The evaluation did not identify any archaeological deposits or features that could be under threat from the proposed development. Based on these results, no further work is recommended, although the final decision is at the discretion of the County Conservation Team.

### 9. Archive deposition

Historic Environment Record reference under which the archive is held: PIN 004. Digital archive can be found on the SCC servers at the following location:

A summary has also been entered into OASIS, the online database, ref. suffolkc1-184521

### 10. Acknowledgements

The evaluation was carried out by Andrew Beverton and Mark Sommers from the Suffolk County Council Archaeological Service Field Team.

The project was directed by Mark Sommers and managed by Dr Rhodri Gardner, who also provided advice during the production of the report.

R:\Environmental Protection\Conservation\Archaeology\Current Recording Projects\Pinewood\ PIN 004 Evaluation (Scrivener Drive Vets)

### 11. Plates



Plate 1. Trench 2, camera facing northwest



Plate 2. Trench 2, camera facing northeast



## Land W Swiss Centre, Scrivener Drive, Pinewood, Suffolk

Archaeological Evaluation by Trial Trench

Written Scheme of Investigation & Safety Statement and Risk Assessment

Prepared by Suffolk County Council Archaeological Service July 2014

#### **Document Control**

Title: Land W Swiss Centre, Scrivener Drive, Pinewood

Date: 08/07/2014

Issued by: Suffolk County Council Archaeological Service Field Team

Author: Rhodri Gardner

#### <u>Contents</u>

- 1. Background
- 2. Project Details
- 3. Archaeological Method Statement
- 4. Risk Assessment

#### Figures

- 1. Site location
- 2. Trench layout

#### Appendices

- 1. SCC Health and Safety Policy
- 2. Risk Assessments

### 1. Background

- 1.1 The Field Team of the Suffolk County Council Archaeological Service (SCCAS) have been asked to prepare documentation for a programme of archaeological evaluation by trial trench at the above site (Fig 1). This Written Scheme of Investigation (WSI) covers the evaluation only. Any further stages of archaeological work that might be required in relation to the proposed development would be subject to new documentation.
- 1.2 The site is a roughly rectangular grassed area covering *c*. 0.4ha, centred on NGR TM 1287 4278.
- 1.3 The work is to be undertaken as a condition of planning application B/11/01514/FUL. This is at the request of the local planning authority, following guidance set out in the National Planning Policy Framework.
- 1.4 The archaeological investigation will be conducted in accordance with a Brief produced by Jess Tipper of the SCCAS Conservation Team (dated 13<sup>th</sup> May 2014).
- 1.5 This application lies in an area of archaeological importance, as recorded in the County HER. The site lies just to the south of the site of a recent excavation which identified a Bronze Age cremation cemetery (HER No. SPT 035) in the location of the adjacent SWISS centre car parking. It is therefore thought possible by the planning authority that these remains could continue in the area of the currently proposed development and that this should be established via trial trench evaluation.
- 1.6 The proposed development comprises the construction of a new veterinary centre/surgery and associated car parking.
- 1.7 The site outline and proposed trench location are shown on Figure 2.
- 1.8 This WSI complies with the requirements of SCC's standard Requirements for a Trenched Archaeological Evaluation (2011 Ver 1.3), as well as the following national and regional guidance 'Standards and Guidance for Archaeological Excavation' (IFA, 1995, revised 2001) and 'Standards for Field Archaeology in the East of England (EAA Occasional Papers 14, 2003).

#### 1.1 Research aims

The research aims of this trial trench evaluations are as follows, as described in the LPA brief (Section 4.4):

- RA1: Identify the date, approximate form and purpose of any archaeological deposit within the application area, together with its likely extent, localised depth and quality of preservation.
- RA2: Evaluate the likely impact of past land uses, and the possible presence of masking colluvial/alluvial deposits.

- RA3: Establish the potential for the survival of environmental evidence.
- RA4: Provide sufficient information to construct an archaeological conservation strategy, dealing with preservation, the recording of archaeological deposits, working practices, timetables and orders of cost.





Figure 1. Site Location



Crown Copyright. All Rights Reserved. Suffolk County Council Licence No. 100023395 2014 Figure 2. Trench location

### 2 Project details

| Site Name                   | Land W Swiss Centre        |
|-----------------------------|----------------------------|
| Site Location/Parish        | Pinewood                   |
| Grid Reference              | TM 1287 4278               |
| Access                      | Off Scrivener Drive        |
| Planning No                 | B/11/01514/FUL             |
| HER code                    | ТВА                        |
| OASIS Ref                   | ТВА                        |
| Туре:                       | Trial trench evaluation    |
| Area                        | 0.4ha                      |
| Project start date          | 16 <sup>th</sup> July 2014 |
| Fieldwork duration          | c. 2 days                  |
| Number of personnel on site | 2-3                        |

#### Personnel and contact numbers

| Contracts Manager                 | Rhodri Gardner            | 01473 581743  |
|-----------------------------------|---------------------------|---------------|
| Project Officer (on-site contact) | Andrew Beverton           | 07841 255066  |
| Finds Dept                        | Richenda Goffin           | 01284 352447  |
| Consultant                        | Poole & Pattle Architects | 01473 230 580 |
| Developer                         |                           |               |
| Site landowner                    |                           |               |

#### Emergency contacts

| Local Police            | Ipswich Police Station, Civic Drive,<br>Ipswich, IP1 2AW | 101          |
|-------------------------|--|--------------|
| Location of nearest A&E | Heath Road, Ipswich, Suffolk, IP4<br>5PD                 | 01473 712233 |
| Qualified First Aiders  | SCC Project Officer attending                            |              |

#### Hire details

| Plant:      | Client's own |  |
|-------------|--------------|--|
| Toilet Hire | TBC          |  |
| Tool hire:  | N/A          |  |

#### **Other Contacts**

| Suffolk Fleet Maintenance | 01359 270777 |
|---------------------------|--------------|
| Suffolk Press Office      | 01473 264395 |
| SCC EMS (Jezz Meredith)   | 01473 583288 |
| SCC H&S (Stuart Boulter)  | 01473 583290 |

### 3 Archaeological method statement

#### 3.1 Evaluation by trial trench

- 3.1.1 The archaeological fieldwork will be carried out by members of the SCCAS field team led in the field by an experienced member of staff of Project Officer Grade. The excavation team will comprise up to 2 experienced excavators and surveyors from a pool of suitable staff at SCCAS.
- 3.1.2 Evaluation of the proposed development area will employ a sample of 5% to cover approximately 0.4ha the area affected by the new building itself and the car parking. The open land to the north-west is excluded as the landscaping proposed is non-destructive and therefore presents no risk to buried archaeological deposits.
- 3.1.3 This 5% sample requires approx.  $200m^2$  of trial trench to be excavated, distributed in such a manner as to give the most even coverage of the site possible. In this instance we would deploy six (6) trenches each measuring 20m long by *c*. 1.8m wide (the width of a machine ditching bucket). The trench location plan is shown in Figure 2.
- 3.1.4 No information has been provided about the presence or otherwise of services at the present time. If previously unknown services or similar restrictions are encountered during work on site then trench layout will be amended accordingly.
- 3.1.5 General trial trench methodology
- 3.1.6 All trenches will be cut using a tracked mechanical excavator equipped with a toothless ditching bucket, under the constant supervision of an archaeologist. All overburden (topsoil and subsoil) will be removed stratigraphically until either the first archaeological horizon or natural deposits are encountered. Spoil will be stored adjacent to each trench and topsoil, subsoil and concrete/overburden will be kept separate for sequential backfilling if requested by the client prior to excavation.
- 3.1.7 Archaeological deposits and features will be sampled by hand excavation and the trench bases and sections cleaned as necessary in order to satisfy the project aims and in compliance with the SCCAS Requirements for Archaeological Evaluation, 2012.
- 3.1.8 Trenches requiring access by staff for hand excavation and recording will not exceed a depth of 1.2m. Any trench in which this depth is not sufficient to meet the archaeological requirements of the Brief and Specification will be brought to the attention of the client or their agent and the Archaeological Advisor to the LPA so that further requirements can be discussed (and costed).
- 3.1.9 Deeper excavation can be undertaken provided suitable trench support is used or, where practicable, the trench sides are stepped or battered.
- 3.1.10 A site plan, which will show all trench locations, feature positions and levels AOD will be recorded using an RTK GPS or TST, depending on the specific requirements of the project. A minimum of one to two sections per trench will be

recorded at 1:20. Feature sections and plans will be recorded at 1:20 and trench and feature plans at 1:20 or 1:50 as appropriate. Normal Field Team conventions, compatible with the County HER, will be used during the site recording.

- 3.1.11 The site will be recorded under a unique Suffolk HER site code (TBA), acquired from the Suffolk HER Office. All archaeological contexts will be recorded using standard SCCAS Context Recording sheets and associated database.
- 3.1.12 A digital photographic record will be made throughout the evaluation.
- 3.1.13 All pre-modern finds will be kept and no discard policy will be considered until all the finds have been processed and assessed.
- 3.1.14 All finds will be brought back to the SCCAS Bury St Edmunds office for processing, preliminary conservation and packing. Much of the archive and assessment preparation work will be done in house, but in some circumstances it may be necessary to send some categories of finds to specialists working in other parts of the country.
- 3.1.15 Bulk environmental soil samples (40 litres each) will be taken from suitable archaeological features and retained until an appropriate specialist has assessed their potential for palaeo-environmental remains. Decisions will be made on the need for further analysis following this assessment. If necessary advice will be sought from English Heritage's Regional Advisor in Archaeological Science on the need for specialist environmental sampling.
- 3.1.16 In the event of human remains being encountered on the site, guidelines from the Ministry of Justice will be followed. The evaluation will attempt to establish the extent, depth and date of burials whilst leaving remains *in situ*. During the evaluation any exposed human remains will be securely covered and hidden from the public view at all times when they are not attended by staff. At the conclusion of the work backfilling will be carried out in a manner sensitive to the preservation of such remains.
- 3.1.17 If circumstances dictate that the lifting of human remains is unavoidable then a Ministry of Justice Licence for their removal will be obtained prior to their removal from site.

#### 3.3 Reporting, archive and OASIS record

- 3.3.1 The unique HER number will be clearly marked on all documentation relating to the project.
- 3.3.2 All artefactual material recovered will be held by the SCC Contracting Team until their analysis of the material is complete. Ownership of all such archaeological finds will then be given over to the relevant authority. There is a presumption that this will be SCCAS/CT, who will hold the material in suitable storage to facilitate future study and ensure its proper preservation.
- 3.3.3 In the event that artefacts of significant monetary value are discovered separate ownership arrangements may be negotiated, provided they are not subject to Treasure Act legislation.
- 3.3.4 The project archive shall be compiled in accordance with the guidelines issued by the SCCAS/CT (Anderson, 2014). The client is aware of the costs of archiving and provision has been made to cover these costs in our agreement with them. The archive will be deposited with the County Archaeology Store unless another suitable repository is agreed with SCCAS/CT.
- 3.3.5 Specialist finds staff will be used, who are experienced in local and regional types and periods for their field.
- 3.3.6 All site data will be entered on a computerised database compatible with the County HER. All site plans and sections will be copied to form a permanent archive on archivally stable material. Ordnance Datum levels will be on the section sheets. The photographic archive will be fully catalogued within the County HER photographic index.
- 3.3.7 All finds will be processed, marked and bagged/boxed to County HER requirements. Where appropriate finds will be marked with a site code and a context number.
- 3.3.8 Bulk finds will be fully quantified on a computerised database compatible with the County HER. Quantification will fully cover weights and numbers of finds by context with a clear statement for specialists on the degree of apparent residuality observed.
- 3.3.9 Metal finds on site will be stored in accordance with ICON guidelines, initially recorded assessed for significance before dispatch to a conservation laboratory within 4 weeks of the end of the excavation. All pre-modern silver, copper alloy and ferrous metal artefacts will be x-rayed and coins will be x-rayed if necessary for identification. Sensitive finds will be conserved if necessary and deposited in bags/boxes suitable for long term storage to ICON standards. All coins will be identified to a standard acceptable to normal numismatic research.
- 3.3.10 The pottery will be recorded and archived to a standard consistent with the Draft Guidelines of the Medieval Pottery Research Group and Guidelines for the archiving of Roman Pottery, SGRP (ed. M.G. Darling, 1994) and to The Study of Later Prehistoric Pottery: General Policies and Guidelines for analysis and

Publications, Occasional Papers No.1 and No. 2, 3rd Edition (Revised 2010, Prehistoric Ceramic Research Group).

- 3.3.11 Environmental samples will be processed and assessed to standards set by the Regional Environmental Archaeologist with a clear statement of potential for further analysis.
- 3.3.12 Animal and human bone will be quantified and assessed to a standard acceptable to national and regional English Heritage specialists.
- 3.3.13 An industrial waste assessment will cover all relevant material (i.e. fired clay finds as well as slag).
- 3.3.14 A report on the results of the evaluation will be completed *c*. 6 weeks after the completion of the fieldwork. A draft of the report will be submitted to SCCAS/CT for approval.
- 3.3.15 On receipt of approval of the report from SCCAS/CT hard and digital copies will be sent to the Suffolk HER.
- 3.3.16 The Suffolk HER is registered with the Online Access to Index of Archaeological Investigations (OASIS) project. The SCCAS Contracting Team will provide appropriate details relating to this project by completing the OASIS form at http://ads.ahds.ac.uk/project/oasis. The completed form (reference suffolkc1-167299) will be included as an appendix to the final report.

### 4 Risk Assessment

#### 4.1 General

4.1.1 The project will be carried out in accordance with the Suffolk County Council statement on Health and Safety at all times. Particular hazards to SCCAS staff and subcontractors identified with this project are as follows:

**Outdoor working** –hazards to staff from weather conditions and uneven ground.

**Manual excavation** – the main hazards are to staff from the use of tools, shallow holes and the resultant trip hazards, live services and ground contamination.

**Mechanised excavation, site stripping etc.** – the most significant hazard from this activity is working in close proximity with plant machinery.

- 4.1.3 All SCCAS staff are experienced in working under similar conditions and on similar sites to the present site and are aware of all SCCAS H&S policies. All staff will be issued with a copy of the project's risk assessment and will receive a safety induction from the Project Officer. All permanent SCCAS excavation staff are holders of CSCS cards.
- 4.1.4 It may be necessary for site visits by external specialists, SCCAS Conservation Team members and other SCC staff. All such staff and visitors will be issued with the appropriate PPE and will undergo the required inductions. PPE is not restricted to the list below additional items will be provided if circumstances require it.
- 4.1.5 PPE required in this case includes:
  - Hard Hat (to EN397)
  - High Visibility Clothing (EN471 Class 2 or greater)
  - Safety Footwear (EN345/EN ISO 20346 or greater to include additional penetration-resistant midsole)
- 4.1.6 Other PPE that may be deployed as necessary includes:
  - Gloves (to EN388)
  - Eye Protection (safety glasses to at least EN 166 1F)
- 4.1.7 Site staff, official visitors and volunteers are all covered by Suffolk County Council insurance policies (available upon request).
- 4.1.8 On a short term project such as this there will be no site-based temporary accommodation provided van will be available with fresh water and a first aid kit.

#### 4.2 Environmental controls

4.2.1 Suffolk County Council is firmly dedicated to following an EMS policy. All our preferred providers and subcontractors have been issued with environmental guidelines.

4.2.2 On site the SCCAS Project Officer will police environmental concerns. In the event of spillage or contamination EMS reporting and procedures will be carried out in consultation with Jezz Meredith (SCCAS EMS Officer). All rubbish will be bagged and removed either to areas designated by the client or returned to SCC property for disposal.

#### 4.3 Plant and equipment details

- 4.3.1 A 360° tracked mechanical excavator equipped with a full suite of buckets will be required for the trial trenching. The sub-contracted plant machinery will be accompanied by a fully qualified operator who will hold an up-to-date Construction Plant Competence Scheme (CPCS) card (approved by the Construction Industry Training Board).
- 4.3.2 The plant machinery will be well serviced and be as quiet a model as is practicable. It will come equipped with appropriate spill kit and drip trays. It will only refuel in a single designated area, as defined by the SCCAS. If required all refuelling, will be carried out using electrically operated pumps and will only be done when drip trays are deployed.
- 4.3.3 Other plant details and appropriate certification can be supplied by the machine provider.

#### 4.4 Hazardous substances

4.4.1 No hazardous substances are specifically required in order to undertake the archaeological works.

#### 4.5 Services

4.5.1 A full services survey had not been provided at the time of writing this document. Appropriate measures will be taken to avoid previously unidentified services.

#### 4.6 Lighting

4.6.1 No trenches are to be excavated indoors and no special requirements are necessary.

#### 4.7 Access/Egress

4.7.1 All movements to and from site will respect any existing perimeter fencing/hoarding with all points of entry returned to their locked condition (if applicable), with the site kept secure via any existing means at all times.

### Site induction sign off sheet

| Name | Signature | Company/organisation | Date |
|------|-----------|----------------------|------|
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |
|      |           |                      |      |

### Appendix 1. Suffolk County Council Health and Safety Policy

Health & Safety Policy - HS01



### Health and Safety Policy Section 1 - General Statement of Policy

Suffolk County Council is fully committed to comply with the Health and Safety at Work Act etc 1974 and associated legislation.

We recognise that good health, safety and wellbeing is integral to our organisational and business performance by reducing injuries and ill health, protecting the environment and reducing unnecessary losses and liabilities. Our service delivery decisions will always consider the impact on health, safety and wellbeing.

We aim to be exemplary in all matters relating to the health, safety and welfare of our staff and all those who may be affected by our activities . To this end we will:

- benchmark our health & safety performance against other similar organisations;
- · provide adequate control of the health and safety risks arising from our work activities;
- · consult with our employees on matters affecting their health and safety;
- provide and maintain safe plant and equipment;
- ensure safe handling and use of substances;
- · provide information, instruction and supervision with adequate professional advice;
- ensure all employees are competent to do their tasks, and give them adequate training;
- prevent incidents, injuries and cases of work-related ill health;
- maintain safe and healthy working conditions;
- commit to progressive improvement in health & safety performance using current recognised good practice such as 'HSG65' and similar models of continuous improvement;

review, and revise this policy as necessary at regular intervals.

Signed: Chief Executive. Signed: ... Leader.

Date: Date:

Review date:

Date: January 2014

If you need help to understand this information in another language or would like this information in another format, including audio tape or large print, please call **08456 066 067**.

HS01

Page 1 of 2

Version 3.0

**Appendix 2. Risk Assessments** 



## Specific Risk Assessments for Archaeological Evaluation: Land W Swiss Centre, Scrivener Drive, Pinewood

- 1 Working with plant machinery
- 2 Physical work in an outdoor setting
- 3 Deep excavations
- 4 Use of hand tools
- 5 Damage to services

1-5 = Low risk 6-12 = Medium risk 20-25 = High risk

## Risk Assessment 1 Wor

## Working with plant machinery

| Activity   | Location | Hazard  | Risks   | Persons<br>affected  | Initial risk | Control<br>measures  | Residual<br>Risk | Name      | Date     | Rescue<br>procedures  |
|--|----------|---|---|--|--------------|--|------------------|-----------|----------|---|
| Direction and<br>supervision<br>of tracked<br>360 <sup>0</sup><br>excavator. | Various. | Staff in close<br>proximity to<br>excavation<br>(operation of<br>bucket &<br>manoeuvre of<br>boom). | Accidental<br>contact with<br>boom or<br>bucket or<br>unexpected<br>movement of<br>machine. | Principally<br>SPO/PO, but<br>at times may<br>involve<br>others. | 10           | Only PO to<br>supervise<br>machinery.<br>No personnel<br>to be within<br>radius of<br>boom.                  | 5                | R Gardner | 08/07/14 | Call<br>emergency<br>services.<br>First Aid if<br>required. |
|  |          |   |   |  |              | All staff to<br>wear high<br>visibility<br>clothing, hard<br>hats and<br>safety<br>footwear at<br>all times. |                  |           |          |   |

|          | Likelihood |    |    |    |    |
|----------|------------|----|----|----|----|
| Severity | 1          | 2  | 3  | 4  | 5  |
| 1        | 1          | 2  | 3  | 4  | 5  |
| 2        | 2          | 4  | 6  | 8  | 10 |
| 3        | 3          | 6  | 9  | 12 | 15 |
| 4        | 4          | 8  | 12 | 16 | 20 |
| 5        | 5          | 10 | 15 | 20 | 25 |

| Likelihood                      | Severity  | Risk (likelihood x severity) |
|---------------------------------|---|------------------------------|
| 1. Highly unlikely              | 1. Slight inconvenience                                 | 1-5 Low                      |
| 2. May occur but<br>very rarely | 2. Minor injury requiring first aid                     |                              |
| 3. Does occur but only rarely   | 3. Medical attention required                           | 6-12 Medium                  |
| 4. Occurs from time             | <ol> <li>Major injury leading to</li> </ol>             |                              |
| to time                         | hospitalisation   |                              |
| 5. Likely to occur<br>often     | 5. Fatality or serious injury<br>leading to disablement | 13-25 High                   |

## Physical work in an outdoor setting

| Activity   | Location | Hazard   | Risks  | Persons<br>affected | Initial<br>risk | Control<br>measures   | Residual<br>risk | Name         | Date     | Rescue<br>procedures   |
|--|----------|--|--|---------------------|-----------------|---|------------------|--------------|----------|--|
| Hand excavations<br>of archaeological<br>features. | Various. | Extremes of<br>heat, cold and<br>wet weather.<br>Trip hazards. | Hypothermia, heat<br>stroke, sunburn.<br>Minor injuries. | All field<br>staff. | 9               | All staff provided<br>with appropriate<br>clothing for<br>weather<br>conditions.<br>No staff to work<br>alone in extreme<br>conditions.<br>Regular sweep for<br>trip hazards. | 2                | R<br>Gardner | 08/07/14 | First Aid if<br>required.<br>Call emergency<br>services if<br>necessary. |

|          | Likelihood |    |    |    |    |
|----------|------------|----|----|----|----|
| Severity | 1          | 2  | 3  | 4  | 5  |
| 1        | 1          | 2  | 3  | 4  | 5  |
| 2        | 2          | 4  | 6  | 8  | 10 |
| 3        | 3          | 6  | 9  | 12 | 15 |
| 4        | 4          | 8  | 12 | 16 | 20 |
| 5        | 5          | 10 | 15 | 20 | 25 |



| Likelihood                       | Severity                            | Risk (likelihood x severity) |
|----------------------------------|-------------------------------------|------------------------------|
| 1. Highly unlikely               | 1. Slight inconvenience             | 1-5 Low                      |
| 2. May occur but<br>very rarely  | 2. Minor injury requiring first aid |                              |
| 3. Does occur but<br>only rarely | 3. Medical attention required       | 6-12 Medium                  |
| 4. Occurs from time              | 4. Major injury leading to          |                              |
| to time                          | hospitalisation                     |                              |
| 5. Likely to occur               | 5. Fatality or serious injury       | 13-25 High                   |
| often                            | leading to disablement              |                              |

## Deep excavations

| Activity  | Location | Hazard  | Risks  | Persons<br>affected | Initial<br>risk | Control<br>measures  | Residual<br>risk | Name         | Date     | Rescue<br>procedures  |
|---|----------|---|--|---------------------|-----------------|--|------------------|--------------|----------|---|
| Excavation of trial<br>trenches and<br>archaeological<br>features within. | Various. | Trench<br>collapse,<br>falls, and<br>work in<br>confined<br>spaces. | Physical injury<br>(minor to rare<br>major<br>examples),<br>suffocation. | All field<br>staff. | 12              | No excavation beyond safe<br>depth in any circumstances<br>(not necessary for<br>evaluation stage of works).<br>No excavation of trenches<br>beyond depth of 1.2m (or<br>shallower where there is<br>risk of collapse in the<br>judgement of the PO if<br>deposits are<br>unconsolidated). | 2                | R<br>Gardner | 08/07/14 | Call<br>emergency<br>services.<br>First Aid if<br>required. |

|          | Likelihood |    |    |    |    |
|----------|------------|----|----|----|----|
| Severity | 1          | 2  | 3  | 4  | 5  |
| 1        | 1          | 2  | 3  | 4  | 5  |
| 2        | 2          | 4  | 6  | 8  | 10 |
| 3        | 3          | 6  | 9  | 12 | 15 |
| 4        | 4          | 8  | 12 | 16 | 20 |
| 5        | 5          | 10 | 15 | 20 | 25 |

| Likelihood                      | Severity  | Risk (likelihood x severity) |
|---------------------------------|---|------------------------------|
| 1. Highly unlikely              | 1. Slight inconvenience   | 1-5 Low                      |
| 2. May occur but<br>very rarely | 2. Minor injury requiring first aid                             |                              |
| 3. Does occur but only rarely   | 3. Medical attention required                                   | 6-12 Medium                  |
| 4. Occurs from time to time     | <ol> <li>Major injury leading to<br/>hospitalisation</li> </ol> |                              |
| 5. Likely to occur<br>often     | 5. Fatality or serious injury<br>leading to disablement         | 13-25 High                   |

Use of hand tools

| Activity  | Location | Hazard  | Risks              | Persons<br>affected | Initial<br>risk | Control<br>measures  | Residual<br>risk | Name         | Date     | Rescue<br>procedures   |
|---|----------|---|--------------------|---------------------|-----------------|--|------------------|--------------|----------|------------------------|
| Excavation of<br>archaeological<br>features using<br>shovels, mattocks,<br>forks, wheelbarrows<br>and small tools | Various. | Splinters from poorly<br>maintained equipment,<br>trip hazards from<br>unused equipment,<br>accidental striking of<br>personnel in close<br>proximity, some heavy<br>lifting. | Minor<br>injuries. | All field<br>staff. | 8               | Ensure all tools in<br>serviceable<br>condition.<br>Careful policing of<br>temporarily unused<br>equipment (e.g. no<br>discarded hand tools<br>near trench edges).<br>Ensure all tools | 4                | R<br>Gardner | 08/07/14 | First Aid if required. |
|   |          |   |                    |                     |                 | carried appropriately.   |                  |              |          |                        |

|          | Likelihood |    |    |    |    |
|----------|------------|----|----|----|----|
| Severity | 1          | 2  | 3  | 4  | 5  |
| 1        | 1          | 2  | 3  | 4  | 5  |
| 2        | 2          | 4  | 6  | 8  | 10 |
| 3        | 3          | 6  | 9  | 12 | 15 |
| 4        | 4          | 8  | 12 | 16 | 20 |
| 5        | 5          | 10 | 15 | 20 | 25 |

| Likelihood                      | Severity  | Risk (likelihood x severity) |
|---------------------------------|---|------------------------------|
| 1. Highly unlikely              | 1. Slight inconvenience   | 1-5 Low                      |
| 2. May occur but<br>very rarely | 2. Minor injury requiring first aid                             |                              |
| 3. Does occur but only rarely   | 3. Medical attention required                                   | 6-12 Medium                  |
| 4. Occurs from time to time     | <ol> <li>Major injury leading to<br/>hospitalisation</li> </ol> |                              |
| 5. Likely to occur often        | 5. Fatality or serious injury<br>leading to disablement         | 13-25 High                   |

Damage to services

| Activity                                    | Location | Hazard  | Risks  | Persons<br>affected            | Initial<br>risk | Control<br>measures  | Residual<br>risk | Name         | Date     | Rescue<br>procedures  |
|---|----------|---|--|--------------------------------|-----------------|--|------------------|--------------|----------|---|
| Machine<br>cutting of<br>trial<br>trenches. | Various. | Accidental<br>damage to<br>cables or<br>services (water,<br>electrical etc.). | Electrocution,<br>environmental<br>damage/pollution, cost<br>implications. | Machine<br>operator<br>and PO. | 6               | Client to provide<br>survey of any<br>known services.<br>Carefully<br>observed<br>machine<br>excavation under<br>full supervision.<br>Use of CAT<br>scanner. | 2                | R<br>Gardner | 08/07/14 | Call emergency<br>services.<br>First Aid if required.<br>Any pollution to be<br>reported to<br>Environmental<br>Manager<br>immediately. |

|          | Likelihood |    |    |    |    |
|----------|------------|----|----|----|----|
| Severity | 1          | 2  | 3  | 4  | 5  |
| 1        | 1          | 2  | 3  | 4  | 5  |
| 2        | 2          | 4  | 6  | 8  | 10 |
| 3        | 3          | 6  | 9  | 12 | 15 |
| 4        | 4          | 8  | 12 | 16 | 20 |
| 5        | 5          | 10 | 15 | 20 | 25 |

| Likelihood                       | Severity  | Risk (likelihood x severity) |
|----------------------------------|---|------------------------------|
| 1. Highly unlikely               | 1. Slight inconvenience                                 | 1-5 Low                      |
| 2. May occur but<br>very rarely  | 2. Minor injury requiring first aid                     |                              |
| 3. Does occur but<br>only rarely | 3. Medical attention required                           | 6-12 Medium                  |
| 4. Occurs from time              | 4. Major injury leading to                              |                              |
| to time                          | hospitalisation   |                              |
| 5. Likely to occur<br>often      | 5. Fatality or serious injury<br>leading to disablement | 13-25 High                   |



To Whom It May Concern

Our ref: SR/B'HAM

#### 9 July, 2013

Zurich Municipal Customer: Suffolk County Council

This is to confirm that Suffolk County Council have in force with this Company until the policy expiry on 31 July 2014 Insurance incorporating the following essential features:

Policy Number: QLA-19A004-0013

| Limit of Indemnity:   |   |                  |                               |
|-----------------------|---|------------------|-------------------------------|
| Public Liability:     | £ | 50,000,000       | any one event                 |
| Products Liability:)  | £ | 50,000,000       | for all claims in the         |
| Pollution: )          |   | aggregate during | g any one period of insurance |
| Employers' Liability: | £ | 50,000,000       | any one event                 |
|                       | • |                  | inclusive of costs            |

Zurich Municipal Zurich House 2 Gladiator Way Farnborough Hampshire GU14 6GB

Public Liability/Products Liability/Pollution: £ 313,500 any one event Employers' Liability: £ 313,500 any one claim

Telephone 0870 2418050 Direct Phone 0121 697 4594 Direct Fax 0121 697 8585 E-mail Sally.rose@vk.zurich.com

Communications will be monitored regularly to improve our service and for security and regulatory purposes

Zurich Municipal is a trading name of Zurich Insurance pic.

A publ c Imited company incorporated in testand, Registration No. 13460. Registered Office: Zarich House, Balvinidge Park, Dublin 4, keland. UK Branch registered in England and Vv3rs. Registration No. 187365. UK Branch Head Office: The Zarich Centre, 3000 Parkway, Whitely, Fareham, Hangshale POIS 7/Z.

Zurich Insurance pic is authorised by the Central Bank of Ireland and subject to Imited regulation by the Financial Conduct Authority. Dealis about the extent of our regulation by the Financial Conduct Authority are available from us on request

These details can be checked on the FCA's Financial Services register via their website <u>vovv/lea.org us</u> or by contacting them on B00 111 6768. Our FCA Firm Reference Number is 203093.

ğ

(108052A02)

20.00175

Indemnity to Principals : Covers include a standard Indemnity to Principals Clause in respect of

Excess :

contractual obligations.

The policy documents should be referred to for details of full cover.

Full Policy :

Yours faithfully NUO

Sally Rose Underwriting Services Zurich Municipal

### OASIS ID: suffolkc1-184521

#### Project details

| Project name                           | PIN004 - Land West of SWISS Centre, Scrivener Drive, Pinewood                  |  |  |
|--|--|--|--|
| Short description of the project       | Trenched evaluation failed to identify any archaeological deposits or features |  |  |
| Project dates                          | Start: 16-07-2014 End: 29-09-2014  |  |  |
| Previous/future work                   | Yes / No   |  |  |
| Any associated project reference codes | PIN004 - HER event no.   |  |  |
| Any associated project reference codes | B/11/01514/FUL - Planning Application No.                                      |  |  |
| Any associated project reference codes | PIN003 - Related HER No.   |  |  |
| Type of project                        | Field evaluation   |  |  |
| Current Land use                       | Other 13 - Waste ground  |  |  |
| Monument type                          | NONE None  |  |  |
| Significant Finds                      | NONE None  |  |  |
| Methods & techniques                   | "Sample Trenches"  |  |  |
| Development type                       | Urban commercial (e.g. offices, shops, banks, etc.)                            |  |  |
| Prompt                                 | National Planning Policy Framework - NPPF                                      |  |  |
| Position in the planning process       | After full determination (eg. As a condition)                                  |  |  |
|  |  |  |  |

#### **Project location**

| Country          | England  |
|------------------|--|
| Site location    | SUFFOLK BABERGH PINEWOOD PIN004 - Land West of SWISS Centre, Scrivener Drive |
| Study area       | 4075.00 Square metres  |
| Site coordinates | TM 1287 4278 52.0419458525 1.10435555333 52 02 31 N 001 06<br>15 E Point     |

#### **Project creators**

| Name of Organisation         | Suffolk County Council Archaeological Service                         |
|------------------------------|---|
| Project brief originator     | Local Authority Archaeologist and/or Planning Authority/advisory body |
| Project design originator    | Suffolk County Council Archaeological Service, Field Team             |
| Project director/manager     | Rhodri Gardner  |
| Project supervisor           | M. Sommers  |
| Type of sponsor/funding body | Developer   |

### **Project archives**

| Physical Archive Exists?  | No   |
|---------------------------|--|
| Digital Archive recipient | Suffolk County SMR                                 |
| Digital Archive ID        | PIN004   |
| Digital Contents          | "other"  |
| Digital Media available   | "GIS","Images raster / digital photography","Text" |
| Paper Archive recipient   | Suffolk County SMR                                 |
| Paper Archive ID          | PIN004   |
| Paper Contents            | "other"  |
| Paper Media available     | "Correspondence","Report"                          |

### Project bibliography 1

| Publication type              | Grey literature (unpublished document/manuscript)   |
|-------------------------------|---|
| Title                         | Archaeological Evaluation Report: Land West of SWISS Centre,<br>Scrivener Drive, Pinewood |
| Author(s)/Editor(s)           | Sommers, M.   |
| Other bibliographic details   | SCCAS Report No. 2014/111   |
| Date                          | 2014  |
| Issuer or publisher           | SCCAS   |
| Place of issue or publication | Ipswich   |
| Description                   | Printed sheets of A4 paper with card covers and a plastic comb binding                    |

Entered by

MS (mark.sommers@suffolk.gov.uk)

Entered on

26 September 2014



# Archaeological Services Field Projects Team

Delivering a full range of archaeological services

- Desk-based assessments and advice
- Site investigation
- Outreach and educational resources
- Historic Building Recording
- Environmental processing
- Finds analysis and photography
- Graphics design and illustration

Contact:

Rhodri Gardner Tel: 01473 265879 rhodri.gardner@suffolk.gov.uk www.suffolk.gov.uk/Environment/Archaeology/