

A



**Guide Cards**

*B-Quality A-Z*

**REFERENCE 5B5325 SIZE 127x76mm**

ABASSANTUS Check C.A. Soc. Coll. 1891 no 68. <sup>chester</sup>  
~~Chestnut~~ Expansion or Mus/57K

~~Sitter North Wales or Chester~~ [406/1930 Two labels - a) late (P.A.D.)

North Wales ~~404~~ 1930. <sup>See letter</sup> Rev. F. A. Polts; a modern <sup>label</sup> says  
'bolt found in Chester?'] flakes from both sides of a large  
mortar <sup>with</sup> each with stamp; <sup>marks</sup> Keying on the underside. Fine  
orange-brown <sup>fabric</sup> with <sup>red-</sup> brown slip on top of flange - apparently  
polished in recent times. Paring or smoothing marks from flange to  
end of spout going along. A very neat little stamp with fairly  
sharp lettering on the left side. Guide lines for lettering visible in  
parts; <sup>the</sup> area outside this is not clearly cut away as in the other; in  
fact it looks as though they cut out guide lines and rectangle  
round stamp & only completed it on the right side.

ABASCANTUS ow. of Domitian's freedman secretaries.

ABB1A

London [New Fresh Wharf; Upper Thames St. 25363, 9H  
1972. 290K] ? is stamp complete, l-facing,  
Hard but very porous pink fabric with skin of cream  
probably not a slip. Core in flange greyish. Some  
v. tiny grit on piece - colour indistinguishable. D. 32cm  
Smooth. DK source ~~but south-east Kent or Colchester~~  
most likely. NB neither m. has distinctive fabric  
- odd.




ABB  
or ABBL

Months dirt? with vegetation we!

Baldock WF W 34 (Letchworth M) <sup>NEEDS CHECKING</sup> flange fragment. Sandy greyish

cream fabric containing a few transparent particles as well as other grit. Heavy + dense fabric looks rather like Venham in fabric!

Saham Toney [83K Norwich M] r. facing <sup>NEEDS CHECKING</sup> Venhamium region SK fabric.

St. Albans [A91] <sup>Folly lane</sup> B DDJ <sup>Ros Niblett</sup> 6 <sup>Roya</sup> hate pit cutting across access route to south entrance into royal enclosure. 1K] (facing)

Fairly thin skin of cream with v. thick brownish-pink core; inclusions rather more than moderate! ill-sorted transparent/white + pinkish quartz + some

opaque red-brown natural iron compounds. Inturation: black iron slag; surface is buff-cream? a slip + survives inside v. little wear. Dr. 31 cars.

J151/11

Rob Perrin

~~to Perrin~~

Cambridge [NWCR2 SLOT 1231 [5826] F1936 18K]

305 gm Diam 360; 11% (It says part of [25987] but that was not sent) original surface seems to have been drab cream - This could be the slip.

Fabric appears to be mainly pale slate grey with cream at the surface. Inclusions: fairly frequent random, mostly quartz, rare black + red-brown. A very few trillite grains survive - quartz, black. There are a few softish cream grains or inclusions which are calcareous. The inside surface has been heavily worn, going through the

P. 10


the cream surface into the grey layer,  
There is a graffiti on the flange in the form  
of 2 parallel slashes near to the break.

CATU Cambridge Archaeological Unit.  
NWC12 Context 5826 Pit F1936 with  
large assemblage of local regional grey &  
oxidised wares including poppy head beaker,  
flagon, beaded rim bowl & samian (?EG)  
Date range ② possibly into early ③

ABICOF

ABICOF (et) West Stow Heath  
xxvi pt 1, 37

VCH Suff <sup>T.p. 318</sup> and PSIA  
↙



ABR 198A

ABRF retrograde see AEBRIS


Towcester, Northants [WST02 GTPit (Geological Test Pit), 1.1 m. below ground surface. Towcester Town Wall Site 13K]

Two joining shreds. L facing stamp - 335g Diam. 320m  
22% Burnt before fracture - upper part of fabric burnt. black & underneath part dark grey, same buff inside in core  $\frac{1}{3}$ . Inclusions: packed with quartz, largely to small ~~thin~~ medium not badly sorted. No lamination survives.

S



1798A AEBRIS? + ABR FveTwo

Gochambury, [ GOR 78 (1274) 2617 joins  
GOR 78 (1271) 2617  left facing joins

GOR 78 (741) 2617  right facing. 4 k. ]

Granular, pale orange-brown fabric, with drab core, frequent inclusions of quartz. Trituration of flint and quartz. Dr. 30 cms. Left facing burnt, right facing piece slightly burnt.

GOR 78 (1274) 2617 border of stamp joins left facing stamp.

L.K

GOR 78

2617

1291

2553



break

l. fac

4k. Gorhambury



ACCEPTVS also made Samian & colour-coated ware which  
he stamped with same die.

COLCHESTER

? 170-200

Colchester [Trans. Essex A.S. xxi, 303.] J.R.S. xxiv, 1934, p. 210-11.  
[C33 CWS (94); 204K] stamped once vertically and once on top  
on each side of spout; pale brown buff ware with slightly pinkish tinge in  
centre; no grit visible. D = c. 9 ins.

Colchester Kiln 1959 [486K not seen] wall-sided *montanum*.

N.B. Unstamped ones from Colchester probably by ACCEPTVS - eg. one with  
Colchester vase.

Top  
ACCEPTVS F

Bottom

204K. Calchester 10/1

ADA or ACA FEZIT HDA ADA or HDA? hincorn??  
 A DIT ADA L. fac ~~Heavily worn~~ but fabric a relatively softish one.

Dragonby (181) DR 67 AGY (100/125 - mid 2c) / (223) DR 68 I-V (mid 2c) NOT  
 - 200/225) / (227) DB 68 ABT (Honyon III A early to mid 2). Other frags ↓  
 joining (226) DR 68 UX (early 3 + later); (187) DR 67 CU (mid 2 - 200) 225

(225) DR 68 SE (u/s) 16K both stamps survive. Identified from L. facing. r. facing poorly impressed & chipped - can't be said it really looks like this stamp but L. fac is certain. Dr. 33. Heavily worn. Criss-cross slashes for adding extra clay part. Sl. micaceous, off-white, fabric; surface v. slightly abrasive; inclusions: v. moderate ill-sorted but mostly <sup>small</sup> brown ~~white~~ inclusions occasional PTO  
 large white (non reactive to HCl). Intertaxation: quartz, polybreunite, red-brown sandstone, black. (quartz in chunky).

May 1996

Fig. 20.29, no. 1392

H.D.A.A. ? The border is similar to VIATOR  
Die 4 READ NG NOT CERTAIN

Yorkshire Museum [17K] coarse white fabric; medium to large grit mainly light  
or medium brown; some white & little black; from N.Y. Postgate [F. Oswald]

Temby Brickyard, [4K Scunthorpe Mus.; J. Frank] a very faint stamp,  
cream fabric; grey, red-brown, grit on flange + one other


Lincoln [<sup>Residual in this rampart which is not the earliest.</sup> in "Colonia" Rampart; 2.21; 1958] fragmentary; drab cream fabric;

abuttship on flange top + inside; mixed, brown + white, small + medium + few  
black, abundant to b. b; worn near bottom part of fragment; no slip on

outside. D.F. Petch, Arch. J. CXVII, 1960 fig 7 no. 1. <sup>Coin considered</sup> dropped end @

Slack [YAS. 26 p. 70, fig 44b., no. 8; Huddersfield M.] white pipeclay; a little red-  
brown grit. CHECK

how Bonens Bridge [PSAL 2. X. 1884 p. 33] <sup>probably A.S. or not found</sup> HDA ← <sup>see</sup> offprint



~~AD A~~ ~~??~~

Carlisle, The lanes [CAR 81 CAL A (66) 161K] L. facing Hard,

faintly fine-textured, greyish-white (5Y 8/1 nearest) slightly micaceous fabric with brownish-<sup>cream</sup> yellow slip; inclusions: moderate, quartz & red-brown inclusions, ill-sorted. Dr. c.c. 35cws.

Castleford [CAS 78 F 715 <sup>no 2031</sup> 66K] more likely to be r. facing than left.

Micaceous, fine-textured, cream fabric; smooth, inclusions: moderate, tiny orange-brown and apparently fewer quartz and rare larger opaque white material. Interstratification: worn away completely. Dense slip, pale brown, slightly pinkish. Dr. 33cws. 16 joining shreds. only 16 shreds survive. A up side down. Parts of AD seen to survive.

Malton [Old Felling Mill; IP; 5K.] red-brown fabric with

cream slip; flange fragment.

Yorkshire Museum [17K.] Fairly fine-textured, <sup>finely</sup> slightly greyish cream fabric with ~~cream~~ <sup>yellowish</sup> slip. medium-sized, abundant, red-brown, white and grey grit. scoring with sharp instrument for spout addition. Found near Pontefract. n facing. Dr. = 30 cm

Dringhouses, York

No bone sherds survive - ADHFECIT FECT HDA ~~ADA~~

Waterdale, Doncaster [YAT+R. Leamy 2012. DONMG 2011.4

PO (ROMAN) [6045] P: 5436 [10~~4~~PK] (facing;  
Diam. c. 380mm. 27% + 29% <sup>mostly diameter</sup> made up of mostly of  
flange fragments which do not join the stamped &  
joining sherd. Fabric: fine-textured cream with pink &  
black in the core. It appears to have had a matt pinkish-  
brown slip which survives in patches on and near the  
spout. Inclusions: moderate, ill-sorted, random, red-  
brownish, with rare black, with tiny flecks of mica in  
fabric. Intentional grit: mostly <sup>orange</sup> red-brown sandstone, some  
{ 2 joining sherds + 8 other joining sherds + upto c. 120 other shds  
many very tiny.

(See note for further details),  
<sup>quartz</sup> <sup>rare</sup> <sup>? qtz sandstone</sup> hard angular black rock. Vessel was  
shattered in antiquity. Deep cracking under  
flange probably occurred during initial  
firing. Two l-facing stamps, impressed  
close together. Part of stamp ~~eroded~~ eroded  
and not completely impressed but the end of the stamp  
towards inside of vessel is clearly impressed.  
Slashes on r. facing side of spout, exposed keeping for extra  
clay - 1085 gms

ADIVTOR

A DIVTOR

Continental POTER : BAVAI

Bowes [Bow 67 DI (12) Archwieno. 82. HK] Range fragment

? L. facing. Fine-textured, brown fabric (Hensell 7.5YR 6/b (reddish-yellow)). Self-coloured. Inclusions: fairly frequent, minute to v. tiny, mostly transparent & pinkish quartz, rare opaque black & red-brown material, one opaque green. No inclusions of gnt surrounds.

5 Δ

ADIVTOR FE I See Pro Nencia Tone T, Liv. 1st. 59. 3 dies drawn. E

Colchester ~~no. no.~~ <sup>Fine, pale brown</sup> 364K [slightly pinkish cream fabric; diagonally, no  
grit to speak of; a big hooked rim like 363K approx. but curves more  
normally at the end of the flange] <sup>dated A.D. 100 by Hull. \*</sup> probably p. 126, no. 24; R. Colchester; ADIV Δ

Colchester <sup>Assumed 'col' on pottery.</sup> [British Museum according to CIL VII, 1334 no. 2; ADIVTOR E  
~~not seen~~ <sup>135K</sup>] 53.3.12.7 r. facing diagonal; fine cream fabric;  
red-brown, grey & transparent tiny fragmented grit in fabric.  
Stamped once only. I can't distinguish this from Colchester  
fabric. Query - are there traces of guide-lines. Check if  
could have been stamped more than once. Check colour of fabric  
Has 'Col' in faint blue letters on it but BM do not have find  
place.

\* In pit dated 5 A.D. 100 - dating good.

AID 10710 R2 II Continental  
Sec Roman Kiln at Halder (Box)

Bauer?


Vendanium [Ver. 60 B x III ④ 218K.] two flange fragments from two different  
stamps, presumably for a single vessel; stamped along; surface  
burnt; fine-textured, fabric probably intended to be brownish buff but  
somewhat discolored, at least in parts to various shades of grey.  
Fabric contains small fragment of white + red-brown grit; surface v. C  
smooth. Die # C

AEBRIS

P no 259


Regus House, London [KWS94 Con 3465 Mus Acc <1959> 4.76K]

r. and left facing. 445g W. 28.5. 34% Buff-cream fabric with pale grey core and brown-buff slip. Inclusions: abundant quartz, moderately well-sorted with rare red-brown. Virtually no frituration. (few flint & quartz) - it never had more. Some grooves found in side. Brownish buff slip. Slight burnishing. No wear on sherds. 2 joining sherds



AEFRIS  
No One Pottery, Hondan [Context 11690 Mus Acc (No. 4221 One 94 438K)]

r-facing 185g. Dr. 33cms 16% Sandwich fabric: Cream with  
brownish pink and inner core of greyish cream. Frequent quartz,  
moderately well-sorted, mostly pinkish and brownish rather than  
transparent (some); some opaque orange-brown, rare black.  
greyish-cream slip. No titivation survives. Fabric not typical  
for Ver region




AEBRIS <sup>see</sup> ABRF 1210

London Guildhall Amphitheatre 94E92 Mus Acc. <5093>

context 15831 508K Pd 4 AD120-160] L. facing  
Mus. Acc <5093> Cont. 15831. 295gm. Diam. 340<sup>m</sup>

15% Burnt or fired black throughout but per a  
of orange buff slip + on outside. Inclusions:  
abundant, fairly well-sorted, quartz. Interstratification:  
No gnt for 20 mm then a little for another 20 mm; mixed  
tiny to <sup>rare</sup> medium quartz & flint.



AE BR! S      Nominal c or Schittare!      SEE VEBRVS

Brixworth, Northants [P.S. Woods. 1967.] r. facing. Beginning of stamp

appears like complete. Sandy, cream fabric with buff slip. One  
flint-like spot. Not enough to get diameter  $c = 13''$  Ver Reg.      P.  
End may be impressed, Not clear whether any borders at  
ends but would be expected.

London? [Cambridge (Mass). II. d. A. E.] R.C. 23.615 Ransome Coll<sup>n</sup>.

Buff fabric.

W  
P  
O

Burdworth, Northants.


See Holder *Alt-celtische Sprachschatz* I, p. 48 Aebro-M  
aus Aulun. Fortunatus, vita Germanici - Aebronis.

Burdworth Excav. vol. 1. The R-B villa, 1965-70, P. J. Woods Reprinted from  
*Journal of the Northampton Mus. & Art Gallery*. p 32 + Fig. 33 no. 242.

# AEBRIS?

Gorhambury [Attributed? GOR 82 3021 (3091) (2) . 17K] 1. facing complete vessel profile, concentric scoring on inside of vessel. Fragmentary stamp, border only. Pinkish-cream fabric with drab grey ware; granular texture, frequent inclusions of quartz and sparse red-brown fragments. Trituration grit flint, quartz and hard red-brown fragments.

Folly Hill, St. Albans [A91/4 A15 (2) (Ritual shaft Fill early Antonine) 5K] + facing. Dv. 29(15%) granular buff-cream fabric. Inclusions: abundant ~~mostly~~ sub-rounded quartz with rare opaque red-brown. Trituration: flint (probably had quartz & red-brown) only 2 grits



Gorhambury 17k l. fac.

Top border of stebins?  
Camp 10. 11. 12.

Gorhambury [GOR 79 (1651) 2822  $\triangle 18$  .6k] left facing, slightly

burnt along rim. Cream fabric with thin pinkish core; fairly granular texture, frequent inclusions of quartz and sparse orange-brown fragments. Trituration grit mainly flint with some quartz. Dr. c. 29 cms.

Stamp fairly deeply impressed.

[GOR 75 2117 (536)  $\triangle 2$  .6k] right facing, incomplete stamp, slightly burnt joins the above l. facing piece.

letter from A. M. Woodward to B. R. H. 26/9/57

'They were handed over to me, in 1913 or '14, I fancy, by the late Professor Kendall then head of the Dept. of Geology, but I did not make a note at the time of the exact location of the site where he picked them up; I only gathered it was in N. Lincs. probably N.W. of Lincoln itself.'

Other material found with A5100 stamps.

15 rim-fragments (5-19 inclusive). 2 have waste cracks; fabrics and grit similar to stamped pieces. 7 of the 15 show the groove in end of flange; the beading and spout are very boldly moulded; the bead seems to have been cut away smoothly for the spout but a slight groove survives on the 2 most complete spouts.

brings to A M Woodward at Leeds by the then Professor of  
Geology <sup>c. 1920</sup> who had picked them up on the surface  
with kith debris at a kith-site. Woodward could not  
remember whether it was in NW lines or NW of line dln.

Find pot

DIAMETER

Kiln-site [LNCS (D.A.L.) LKS] hard, sandy, dirty white fabric

with amber (brownish buff slip); brown, grey + colourless grits ① A

Kiln-site [LNCS (D.A.L.) LKS] hard sandy cream fabric with  
remains of brownish buff slip; largish to smallish; grey, brown,  
colourless + black grit; (grey is flint); stamped twice close  
together; - sporadic gritting, strays to b. ② A

Kiln-site [LKS] hard, sandy, dirty white fabric with drab cream  
slip; stamped twice close together; brown, grey, white + colourless,  
medium grit - well spread to near b.b. flange broken. ③ A

Kiln-site [LNCS (D.A.L.) LKS] hard, slightly sandy cream with some  
brown grits mixed in; brownish buff slip; white, brown + grey; stamped twice tog. ④ B  
Dr. 27cwo

## AESICO

Mid 2nd. Century ?

Elstach [YAJ xxi pt II p. 163] AESICO (it) ~~MISSISSIPPI~~

In Skipton museum.

Aldborough [7K unpub] very sandy white fabric; medium + large white + brown grit. Assigned AESICO. too worn to read.

York [P. Wenham, Daveygate] D. 57/10. smooth, drab, greyish cream fabric from which most of the surface has exfoliated; a little brown and white grit survives; most of surface of stamp gone. Assigned.

Thealby, [3/2E/12; N; Scunthorpe M. 3K] smooth, cream fabric; medium black, grey, rather sparse grit. DIAMETER

Beauwell ['38, c. bel. I - information B<sub>2</sub>] 001237

AESIC 0


Ribchester [RB89 03/31 6304 Phase 5.1 74K] FF.

Slightly granular drab cream fabric self-colored.

Inclusions: fairly frequent (at X20) transp. & pinkish quartz  
red-brown (opaque) & black. ill-sorted. Dv. 26-28 B'

West Heslerton, N. Yorks. 8m/13km E of Malton [HP11CE 5/8 00GL 20999]

Drg. 17a] 8 grams. burnt. Flange fragment. Off-white fabric  
with dark grey core; frequent, tiny <sup>small (ill-sorted)</sup> granular inclusions, rare black, large  
inclusions (?slag); may be self-colored. AB.



AESICO

now E Yalks!

Arram, Lincs, in Chapel Garthfield TA 037 445 [AC 606

588. Excavations <sup>ERAS</sup> 2006 Context 588 (ditch filling) 1K]

Flange frequent surface eroded. sandy texture.  
cream surface with grey almost to surface.

Inclusions: Tiny to small, frequent, sand-sized,  
quartz + rare red-brown + black. the A

Elslack [YAS XXI p.163; PL ~~not~~ not drawn. Skipton M.] read as VESTAL.

stamped twice close together; the A is blind. Hard, pale buff fabric with brownish buff slip; stamps retrograde. (See also 1120-160)  
York, Blossom Street. Stewart 1967. 1st visit at York?

Welton [Rod Mackey Mc 199a

? [Rod Mackey ? not worked ? N; Cawce

Navit Cawce, Humberside [Rod Mackey B

Winterton

MEXICO of VESTAL

TYPE STAMPS

Grit - <sup>grey & white h.</sup> ~~grey & white h.~~ <sup>almost colorless</sup> ~~stones producing almost colorless,~~

brown & red grits & occasionally black <sup>some</sup> grit; <sup>white</sup> ~~medium~~ <sup>mostly</sup> ~~mostly~~  
(These are probably 2 kinds of stone <sup>used for the white grit</sup>)

Hard, slightly sandy dirty white fabric in the buff or umber  
slip; fabric sometimes buff to tan buff.

The grit is all un worn.

A.

VERCO

ins

outs

VESTICO

35K Yorkshire Mus. 27.

Winterton [WH/HE SF46] 2K] In softish, slightly sandy, cream

fabric with darker slip and a few crystalline grits surviving. Burnt. SICOF  
Context gw = Antonine. DIAMETER?

York [SM 2 1989.24 [72050] Residual 114K] stamped twice close  
together. Cream fabric at outside, mostly brownish pink  
slightly sandy, moderate + tiny quartz inclusions, rare slag  
Inclusion: quartz only survives. Butt slip. Dr. 27cms.

Attributed - faintly orange  
York [SM 10 1989.24 [71893] 129K] L-facing. Dr. 26cms.

Six joining sherds, making up about  $\frac{3}{4}$  of whole vessel.  
Very hard, dense, light brown fabric with self-coloured slip fired to  
a darker shade. Inclusions: sporadic, large quartz + dark brown slag with  
same v. tiny probably similar grit in matrix. PTO

Interrater: mostly quartz, much of it greyish with  
some dark brown slag. Well worn but fairly thick.

Context for 71893<sup>(1)</sup> is 170 + / 71196<sup>(1)</sup> AD 175 + / 71888<sup>(4)</sup> Resid.

Probably LINC S.

AESIC... (cf VESICO)

AESICOF Brough (Sud. early, <sup>2</sup>) 1937, 5, 21, Dirty yellow to drabf.  
From a site in Lincolnshire (In Dept. of Latin, Leeds U.) A, B, C. Hard dirty wh. fabric with amber warts.  
(3 A, 1 B, 1 C, 1 D, 1 E, 1 F, 1 G, 1 H, 1 I, 1 J, 1 K, 1 L, 1 M, 1 N, 1 O, 1 P, 1 Q, 1 R, 1 S, 1 T, 1 U, 1 V, 1 W, 1 X, 1 Y, 1 Z)

The grit in all is unworm and there is kilm. familiar with them. a = A

Brough [Dept. V 1937 fig. 15 no. 22 B 22 8] misread part of retrograde stamp

\* Like A from hines. Orange buff, mixed grit. A


Yorkshire Museum [15K] on fragment of rim. Stamped twice close together.

coarse white fabric, slightly sandy surface with traces of light slip B.

Yorkshire Museum [Blossom St, York 1958] buff fabric, yellowish cream slip; Bar, C

red, white, brown grit, some large; AESICO (vett) twice on each side of spot

(rubbing in B<sub>2</sub> North Folder) On show; no A. DRAWING



Brough 1937 fig. 15, 21 (1/4)

Fabric dirt,  
yellow to  
drab



From a site in hinds,  
In Dept. of hain, Leeds



From a site in hinds,  
In Dept. of hain, Leeds



Brough


AESICO No. 4611715 Paul  
Frid no 2 young shreds Stamped twice close together  
Malton [HA 70 25K] 17K #. hard, greyish cream fabric, basically fine -  
textured / but toughened with a lot of <sup>fairly frequent.</sup> fine varicoloured quartz ✓  
ill-sorted <sup>rare</sup> + red-brown? <sup>+ sparse blackish</sup> <sup>only</sup> flange + bead. sl. singed. B? D. 28.5

Castleford [(686) CAS 81 S10 L472 (1572) .43k] Micaceous,  
burnt throughout <sup>fairly frequent</sup>  
grey fabric, <sup>cream?</sup> moderate inclusions quartz. Trituration grit  
quartz; slip may be present. Dr. <sup>27</sup> ~~26~~ cms. Inclusions B.  
difficult to see: of burning; includes opaque white calcareous  
material (reacts) ✓

Old Witheringham [WGM 81 (530) 2 Ditch PM.2 9K] IRS  
stamped close together. Burnt heavily in flange. Sent by  
J. Farrimond H. A. U. Beverley. Fabric micaceous and generally  
PTO

typical of fabric at Killy-site. Greyish-cream fabric. Inclusions: frequent, small quartz, sub-rounded, transparent with a few pinkish. Rare grey dot, know what? quartz; few opaque red-brown. Not badly sorted.  
Interstratification: mostly transparent quartz; greyish; few pinkish; opaque v/b + pale brown? sandstone

B



Winterton [ZW/KQ 2 FN 2725 11K] stamped along, v. slightly  
 diagonally. 2 pieces joining. Dr. 26cms. Worn. <sup>yellowish-</sup>  
~~greyish-~~ cream  
 fabric, <sup>micaceous</sup> fairly fine-textured. Few visible inclusions even at X20  
 quartz <sup>(transp + green)</sup> & opaque red-brown <sup>mostly</sup> for tinturation: <sup>mostly</sup> quartz, transparent & greyish;  
 blackish iron slag (rare); <sup>opaque red brown</sup> (rare). S-colored. A

Winterton [ZW/LA (\$) FN 2740 236] <sup>12K</sup> l. facing presumed. Very slightly  
 diagonal. Heavily burnt. Well worn. Dr. 26cms. 2 pieces joining.  
 A different pat. Micaceous <sup>yellowish-</sup>  
~~greyish-~~ cream fabric. Fairly fine-  
 textured like 11K. Tinturation: <sup>mostly</sup> quartz, transparent. Flint; iron-  
 slag; red-brown sandstone. Pale brown <sup>? sandstone</sup> Fabric as 11K

Boston  
MASS

Top  
H K Weston stamped along

South Shields [AA<sup>2</sup> 8 pt. 2 facing p. 274, no. 18, upside down; Die Barkan

was missing [2] stamped twice together

in Harber

Brough [Rept. V 1937 fig. 15 no. 21 p. ~~222~~] unstratified 4K. Hull M.

[21] on pot; r. facing; slightly sandy, greyish cream fabric with cream  
to orange buff slip; slip greyish in places. D = 11"; abundant grit -  
brown, grey, white, black + colorless; mostly medium to coarse, but few a bit smaller + larger.  
Dr. 288 nos.

Brough [Rept. V 1937 fig. 15 no. 22 ~~p. 222~~] underneath clay of rampart  
retrograde; published wrong way up tread [R.T.C. 22 on pot; Hull M. 3K.

stamped twice together; slightly sandy, yellowish fabric with brownish buff  
slip; flint, grey + white grit + white of a different kind. DIAMETER

IAESTIËVS

see BRAESTICUS

Littlechester [Brassington. The Square 1967-10 K] L-facing. Dirty sl. greenish brownish fabric with greyish brown core; <sup>sandwiched by dark or greyish brown core</sup> heavily tempered with grit. Surface yellowish brown, almost greenish + grey towards spout. It looks misfired. Only three tinturation quite surviving but to judge also from fabric - blackish, white + sparkling, probably transparent grit. (Hals) Perhaps a local product.

AESTIVUS

+ F 68 2330

moderate +

hercynite [224] A78 .1975 .180K] Fine cream fabric with a little

quartz + red-brown <sup>(86)</sup> tempering; cream-buff slip; few r-b  
<sup>probably sandstone</sup>  
with hercynite grains; stamped twice close together. Too small for  
c/d. 38 cons. Inclusions: ill-sorted, random, quartz, red-brown, red Δ,  
black. }

# AESTIC VS

or No. 917?

Tiddington [TP&I 895 No. 914. 7K] hard white fabric with some

voids (opal)

quartz inclusions; no trituration survives Dr. c.33. IRS.

Castleford [1051 CAS 85 [18] 077  $\triangle$  73. 44K] <sup>slightly</sup> Micaceous,  
cream fabric, moderate inclusions 'rose' quartz and

Flange with spots.

spare orange-brown fragments. No trituration grit survives.

left-facing stamp. Quite well made. Fabric B3.2

no 48 GSK 74 could be part of same vessel from the

side of IRS. Pale brownish cream slip?

Templebrough [W.V.W. 1948]; white pipe clay; pinkish brown and white

gills; double stamp near ~~spout~~ reading from outside.

Shenstone [Birm. A.S. <sup>1870</sup> LXIII, Pl. VIII no. 5 / <sup>p. 28</sup> on no. 6] soft sandy <sup>yellowish fabric</sup> brown buff.

Mancetter [Birm. A.S. Trans. Proc. for 1956; vol. 7 (1958) p 48, fig 12 no 81 & p 17] 1 large black grit in body of range; has grey, white & pink gills; slip worn.

26K Birm. Mus. M 14-18 10] hard creamy buff fabric to slightly brown buff surface; sl. sandy; cream slip, a little medium grey grit.

7. facing.

High Cross [Chance find in Roadworks. J. Pickering 1958] "creamware" information G.W.

? Hartshill? [Walter, Hartshill High School, Warwick information SW.] very faint.

ESTIK

ESTIK

Templebrough  
N.V.W. 1948.

ESTIK

5

( $\frac{1}{2}$ )

Shenstone.

ESTIK

( $\frac{1}{4}$ ) 6

Shenstone;

AESVMINVS

Corbridge <sup>AA<sup>4</sup> xviii p. 192 no. 61, & p 191, 199</sup>  
④  $\alpha, \beta$ ; <sup>xii A</sup>; 5/47; 212/21 61; 10K] 1st p each side of spout.

drab cream fabric, with some, large to small, r/b, grey, black grits; not  
clearly impressed. Die as given - yidomach. Destruction de point  
Is it worn?

AESVMINVS

Inveresk [FV10 Final civilian 29K] Two joining sherds .700 g

Diam. 31.5 cm (35%) Self-coloured, creamy brown fabric (Munsell 10YR 7.5/4 'very pale brown'), slightly more open in texture than FV300 (26K Herringsbone E?) but otherwise identical in macroscopic examination and in intonation grit. Some, random, ill-sorted but smallish inclusions consisting of transparent quartz and orange-brown material with perhaps a little flint. Intonation grit consists of flint with quartz and some red-brown ? sandstone. ltr. facing

AEEUMINVS

Pakenham (Iude.)

## AESVMINVS

Fodder Fen, Manea [Walker Collection

reddish buff

fabric. Die as Upwell ex.

220-225

B

Mr. Upwell, Norfolk [Cambridge M. A+E.] buff fabric; gnt large &amp; plentiful, quartzite &amp; ironstone.

B

Welney [Cambridge M. Arch. &amp; Ethnol.] reddish buff fabric, sparse white gnt.

B

Lutterby, Norwich [Not. &amp; Norwich Arch. Soc. xxvi part II. p. 214, no. 29; 229; D12 &amp; D13, 43K &amp; 60K. from same mortarium] cream buff fabric and surface,

brownish slip; sparse, large &amp; medium flint grits mostly c. 1-1 1/2 in. below head

D = 12 7/8 ins. Spout as others; form much as Boramplin <sup>copied bedroom,</sup>

Lincoln [B.M. M2765 misread Walters; 66/12/3/98; 1866; 90K] r. facing; hard, fine, pale buff fabric; no gnt on fragment.

A

INTELVN  
MVEA

Nr. Upwell, Norfolk  
Cambridge A. Mus.)

I 71

NVSFECIT  
AESVMI

From 7 (1) Lincoln (in B. 10)

Brampton [<sup>106K</sup>~~29K~~ D 2/8 Norwich M.] orangy pink fabric; surface cream in patches; white, pink & grey trituration grit. Formas 32K.

Brampton [D 2/7 107K] r. facing. Drab, brownish buff fabric with orangy sandwich streaks in it; surface creamy brown; black, white, grey & red-brown grit. XIX A

Brampton [D 2/3 108K] Drab buff cream fabric containing grit; much grey, white, red-brown grit. Dr. 31 curs. A

Brampton [109K] Dr. 30 curs. stamped each side. XX Δ

Brampton [114K D 2/2 sport & part of flange missing.

Brampton 4 spots all as  $\Delta$ . 26K + 25K perhaps more  
like 30K than 31-32K but difficult to tell. Both completed.

AESUMINUS NOT certain of total

BRAMPTON

Brampton [102K Norwich M. D|2|4] Spout exactly like others. Waste cracks. Colour varies, brownish pink in parts and in core but mostly cream on top; much, grey + white + some red-brown grit. Form similar to D2|3. Dr. 31 cms.

Brampton [103K D2|1.] complete save for bottom. Diameter ✓ 30 cms. Slightly sandy, brownish cream fabric containing grit; brownish pink in parts. grey, white, brown + red-brown grit.

Brampton [104K Norwich M] pale creamy green fabric containing grit.

Brampton [105K Norwich M] + flange fragment. Cream fabric.

AFRICANVS

misreading for VERECVS ?

VASSONVS (?)  
See ~~Interpolate~~ Stamps (?) - no. x

L. ATISIVS SECVNDVS c/ SECUNDVS

C. XII 5685. 5 + 38 ; XIII 10006, 12 ~~12~~

Lyon C. XIII 10006, 13 L. ATISIVS  
SECUNDVS

ACRIPPA

Apple Tree Farm, Hewarth, York [19. Lawton <sup>8K</sup> ~~7K~~ ATF 1987.3] 33

l. facing. Quite thin-walled. Dr. 30. 14% orange-brown fabric with thick, near black core; frequent fine quartz inclusions. Traces of cream slip.  
Inturation quite almost all quartz (angular), some mica; occasional limestone.

Apple Tree Farm, Hewarth, York [19. Lawton 7K. U/S ATF 87] Flange  
Jaquent. Different pot. Or Sintered, black, dense.

AGRIPPA

Note - tile stamp at York

Malton [LP 2K. Malton] r. facing. Flange-fragment; orange-brown fabric, rather coarse in texture and incorporating some very fine crystalline + dark grits (not much); surface redder + there has been an attempt to smooth it. The stamp has horizontal grain-marking throughout pointing to a wooden die. The letters are not of even height; ansate ends. 2 red brown grits on flange. The surface may have a slip but it does not really look like it. Surface bickelcoloured.




o  
9  
r

Maitton

AGRIPPA

\*

Yorkshire Mus. [HK] Hard, sandy, orange brown fabric with cream slip & greyish white gut. D = 32 cms. Fabric like Mercator. Striation marks in stamp.

York [Rougier street (colonia) stamp on IMBEX.  ]

Bainesse [46.2317.240 + 2318.242 + 1958.222] 14K r-facing.

Dr. approx 32 but not circular; groove in underneath at distal end has opened up and this and the distortion suggests it is almost a waster. Heavily fired. Very heavily worn. Hard, red-brown fabric with drab grey core; fair amount of tiny quartz, occasional black & red-brown (blk & r-b may be slag & are sometimes larger than other inclusions). Buff-cream slip; tint just mostly quartz (transparent and opaque); grey <sup>limestone</sup> stone; probably some red brown & black slag. Stamp has striation marks in it. Although I have given it a separate <sup>B/3</sup> fabric category & it could be distinguished from rest in B/6<sup>1/2</sup> it could probably have been accommodated therein but for stamp.

ALB....

See 9.238 with [BINVS stamps]\*

Richborough [ii, p. 94, 8(A); M. 8; 11K] unstratified; soft and smooth, cream fabric with buff tinge; some small greyish grit, not on flange.

Bush - Fox 14/18. v. facing.

12840M

\* From London, now in Merseyside County Mus. Liverpool 7K

~~ALBANI MATUGEN.~~

~~ALBANI MATUGEN~~

See MATUGENS.

ALBINUS

FOR CHECKING

~~London [CRESSIDA LA 1854]~~

not checked

Albinus has no fecis ? MARINUS - PETS

London [C: LVII, 1834 no. 6. CRES R. London 1854, CRESSIDA LA 1854] ALBINUS  
FECIS

Curious - no fecis - PARALBINUS

not seen

17.

check VCH 2 p. 187

Norton [Northants] hereafter Rep. Norton parish <sup>Bainnamenta</sup> name for

Cock house, Smithfield. 4/1844 p 77th book to the collection of Pottery  
Pottery + Brackham in the <sup>(Germans + 3)</sup> Museum of Practical Geology 1893 ALBINUS

Notes Albin ~~to see if~~ How many each die for  
Check if clearance stamp - 1 only in  
ALBIN works

Could VIANNVACAPE be read ELUSUOV?  
VIANNVACA PE ? on the road to Sullivan's?  
What die is B. Hill one.

Numbers for each die at Ver. & London \*  
to see if he supplied them from diff. Kilbas pieces \*

P. PR. 1

N.B. CIL, 1334, no. 38 gives find spot as Derbyshire erroneously & misreads it P.P.P; see CRS p. 89.

London [Fish St. Hill; GI; P. Bateman Collection, p. 146, 32 in

Catalogue; 10th July 1844. Sheffield Mus] slightly sandy, pinkish buff; buff core in flange; medium to fairly large, red, white, grey, brown grits.

London [London R. CRS p. 59; 1854; CIL VII, 1334, 39; 1854; CIL VII, 1334, 37 misread as P.P.B;

Ed. Ant.; p. 149; C. Combe; Arch. 8, 1789 p. 130; British M. 531

54/3/9/3; M2826; sandy, greyish fabric, surface pale buff + grey; no grit on it. If found in 1854 with Combe's + in any case R to clear + he reads P.P.B. <sup>most probably</sup> given by Sir A. W. Franks whose step stamps were.

? London [96/2/1/9] (18) British M. hard, pink fabric, rather coarse

and tile-like in appearance, very large (clumpy) to medium, white grit; few or fragment to just b.b. Pub. on amphora CIL VII 1331, 91; (certainly this one P. PR B)

ALBINUS - SSI = VERULAMIUM V87 i, no. 11

58 BITV (21A) V87 i, 11

195K

ALBINUS

(SSIF) VERULATIUM

As no 3 + 56

SSIF

56 G III C (19)

vol III no 56.

6K

58 B II (31E)

← vol i, no. 3.

138K

ALBINUS - SSF VERULAMIUM no. 4 + no. 57.

59 VI (12) vol III, nos 57

174K

58 AVI (31) vol I, no. 4

220K

ALBINUS VERULAMIUM (SSF) A's no. 6 and 59  
 N.B. in Vert die 6A + 6B should have been drawn.

56 HV 20	vol III, 59, 6	14K
58 BT (65)	vol i (6)	226K
57 VII (36)	vol i, no. 6 = no. 365.	224K
58 A II (42)	vol i, no. 6.	139K
57 IV (8)	vol i, no. 6.	8K
58 BI (38)	vol i, no. 6	125K
— I —	— I —	126K
57 I VII (19)	— " —	9K
59 BI (64)	— " —	173K

ALBINUS - SSF VERULAMUM As vol i no. 5.

572 II (26) vol i, no. 5.

5K

5913 IV (37) ——— " ———

172K

57X XI (2) ——— " ———

3K

57T VII (29) ——— " ———

4K

ALBINUS

VERULAMIUM as no 2 + no 55.  
(SSF)

60 A I (5) /

vol III no 55

272K

56 F XXIX (7)

vol III no. 55

7K

58 B I (45)

vol i, no. 2.

157K

o

ALBINUS - SSF VERULAMIUM As. vol. i, no. 7.

58AVI (23)	vol i, no. 7 = no. 545.	221K
57IVIII (26) <sup>N</sup>	vol III, no (60), ( <u>not here</u> ).	223K
58AVII (33)	vol i, no. 7 <u>AND</u> NO 8	134K
58BIT (45)	vol i, no. 7.	214K

ALBINUS -	VERULAMIUM As no. 8 + no. 61 (SSIF)	
60 K VIII (20)	vol III no. 61.	198K
56 G III C (48)	vol III, no. 61.	10K
58 B I P 7	vol I, no. 8.	222K

ALBINUS - SSF - VERULAMIUM AS vol 10

57 T XX (5)	vol i, no. 10	225K
58, AVII (52)	vol i, no. 10.	131K
58 BI (45)	vol i, no. 10.	132K
58 BT (45)	_____ " _____	125K
58 BI (45)	_____ " _____	130K
59 BI (63)	_____ " _____	193K



ALBINVS stamped material

Bryan Sitch at M/C Museum sent  $\phi$ s of a complete  
workpiece with stamp of ALBINVS & a counter stamp.  
Heavily worn. Complete except for hole in centre  
? Provenance

ALBINVS

(Holiday Inn)

32cms

Leicester [164-1969 III (45) SF/116 153K] Dr. 12 1/4" stamped each side.

Complete except for hole <sup>broken</sup> worn in bottom. Brownish cream fabric with brownish buff slip. <sup>Trist</sup> flint, grey & white grit & some quartz like; concentric grooving near top. Worn away <sup>below 3/4" p. band</sup> lower down.

hole worn in base. Stamped each side: sl. burnings on pad of flange. A No grit on flange; tiny grit to b.b. internal concentric scoring.

Springhead [Arch. Cantons p. 144, fig 2, no. 5 ALBINVS] TQ 61777252]

die as no. 153K x Leicester H.I.I. LXXXV (1970) F

Springhead [du do. do. no. 7 G.V.D. ? same die.

Writer says it is a different vessel, LXXXV (1970) Die as 153K F

Leicester.

## ALBINVS

BSE  
hendon [Guildhall M. 1934.68; 156K] r. facing; slightly sandy, greyish

cream fabric with some r/b. fragments in it; internal scoring; black, v/b,  
 small grits, few. B.F. 34. H.

hendon, G.P.O. [1914, M.A. 2545; F3 Arch 66, p. 253 probably no. 8, misread  
 as NIMVG; Guildhall M. 52K] blurred, stamped diagonally; sandy,  
 pink fabric changing to cream with pink tinge; internal scoring; much  
 tiny, r/b, white + grey grits to c.  $\frac{1}{4}$  in. b.b.b.; B.F. 34/38 - but not close.  
 A

D = 12 ins.

BSE ✓ X P. 8 scoring inside not on flange.  
hendon [1937.256 Guildhall M. 187 K] sandy, greyish fabric; white + grey  
 grits to near bead; internal scoring; D = c.  $1\frac{3}{4}$  ins; Albinoid with  
 thickening in lower half of flange. ALBINVS II. F. LUG. VOV. K

ALBINVS

hondon [294K 24044 5 or 5 208 9H] r. facing diagonal;  
internal scoring; abundant white, brown + black grit.  
sketch. B

hondon [295K 78. 9H] flange fragment BF 38. Flange  
pressed down under flange spout.

hondon [296K 9H] r. facing. Scoops for addition of clay  
for spout. Cream fabric with brownish orange slip  
purplish brown to outside.

hondon [1925. 74. 11407; 313K] St. Martin le Grand.  
Nearly complete but holed.

## ALBINVS

London [Guildhall M.  
74; St. Paul's Churchyard 1930; 1930-189; 165K] sandy, orange

brown cream. Scoring inside only.  
- brown fabric and surface but surface grey in parts; hole worn in bottom;  
much, small, white & grey, black grit; internal scoring; much worn;  
D = 11 ins; c. half of mortar; BF nearest. ALBINVS || F. LVGV DV. H


<sup>B or E</sup>  
London [1937.66; Guildhall Mus.; 91K] r. facing; sandy, greyish white  
fabric with thin pink core in places; internal scoring; smallish, white,  
grey grits, quite a lot to c.  $\frac{1}{2}$  b. b. B.F. 34. J

London [1937.95; Guildhall Mus.; 65K] sandy, grey fabric to cream at surfaces  
tinged with buff; but dark grey & black in parts? due to burning; large to smallish,  
black, grey grits to bead; BF 34. D = c. 12 ins. G

ALBINUS

London [Quiddhall Amphitheatre GXE92 MusAcc (1550)

Context 15254 Pd4 AD120-160 505K] L-facing 620gm  
Diam 360mm 20% Eves. Heavily worn and  
burnt black in areas & pre parts of surface.  
Tined to greyish-cream in flange & at surfaces where  
not burnt. It had pink in part of core. Inclusions:  
abundant transp. quartz, rare red-brown & opaque  
black. ~~Interractions~~ worn away except in top 20  
mm. 66 of bead, all in this 20mm band are small to tiny,  
flint, transp. quartz & rare v/brown combined with concentric scoring.  
No gut or c. scoring on flange.



Regis House, London [KWS94 Con <sup>3059</sup> ~~3951~~ Pno 262 Mus Acc. <2359> 467K]

l. facing 365g Dr 33 20% Cream fabric, hard; cream slip. Packed with moderately well-sated, small sized inclusions, mostly quartz & very rare red-brown. Little intonation survives; small quartz & flint on sherd. <sup>d. 7</sup>

Regis House, London [KWS94 Con <sup>Pno 255</sup> 3187 Mus Acc <1690> 469K]

n. facing ~~assumed some surface flaked off, probably where spatula added.~~ 265g Dr. 32 15% surface fairly smooth, internal scoring. Intonation little survives. Small quartz, flint, occasional black (?slag). Prob slip. greyish cream fabric. Inclusions: moderately well-sated, very <sub>Pno</sub>


d. 8  
frequent, mostly quartz, ~~with~~ occasional black, rare red-brown.

ALBINUS

Pro 266

Regent House, London [KWS 94 Con 1742 Mus. Acc. ~~(892)~~ 468K.]

FF Surface slip overfired to greyish brown. Surface smooth  
Auriferous brown fabric; Inclusions very frequent, mostly <sup>small,</sup> mostly  
arseniferous quartz, v v rare black. [Munsell 2.5YR 6/6 'light  
red'] 55g 7% ] QVDV die not identified almost certainly d. 6




ALBINUS

Lloyds Registry, London [Site FCC95 Acc no. 90 context 0

Landuse v/s Pd. - Fab VRW 422K] 240g. Diam 34mm  
13.5% Slightly granular, greyish-cream fabric, packed  
with quartz and very rare orange-brown inclusions. Pale  
brownish-cream slip. Inclusions: tiny to medium flint with  
some quartz and very rare opaque black fragments  
distributed upto the bottom bead. Concentric scoring  
on inside, but flange was probably smooth. Worn.  
stamp diagonal and likely to be C. Pacific. Freer 1972 no. 3.

ALB INVS

London Guildhall Amphitheatre 9492 [94E92 <12817 Contd  
14598 Pd 12 1230-70 506K] r. facing. 360gr.  
Diam 310mm. 20% diagonally impressed. Cream  
fabric with thick pink core and buff slip. Inclusions:  
abundant, tiny to mediumish trans. quartz, few opaque  
black & red-brown. Fine end of VRW - not as packed as norm.  
Inclusions: tiny to mediumish, flint, quartz on sherd.  
combined with concentric scoring. Both worn away  
below 20mm. & bottom of bead. No gut or fragment on flange.  
d. 3.



Greenwich Park [Trans. of the Greenwich and Lewisham Antiquarian Society for 1925. Vol. III, no. 2. Published 1925. p. 62-75.

Roman Remains from Greenwich Park by F. C. Ekiston  
 Erwood. p. 69. "Of the mortar fragments found at Greenwich only one bears a stamp. This is no. 200, half the rim of a first century type, probably Bushe-Fox though the inner bead is missing. The portion remaining includes the spout, on either side of which is : ... BINUS F. LUG. VDV.

Also recorded VCH Kent III p. 166 <sup>SANIA</sup> check up - mention them as 2 stamps?  
 ? Present whereabouts.

Albino

? London [SK. R838 Sh. O. Collection] Manchester Miss Complete

save for centre hole in bottom. heavily worn. As Nos 7 and VER 1.

\*\*

London, Old Bailey [M. 2822; Sawills Collection 1863; ~~etc. vi 238, 1b~~; Foundries;

63/4/28; "43K British M.] l. facing; FIVEVDI on label; slightly sandy, greyish cream fabric with pink core; pale, drab buff surface; largish to tiny, white, grey, black grit to b.b. D = C. 14 ins; B.F. 38 approximately but head high; stamp diagonal; J

London [CRS. p. 89; M. 2820; CIL VII, 1334, 1b; Coll. Antiqua. i p. 149; 45K British Mus.] r. facing; cream buff fabric with thick pink core; small, white + grey grits to b.b., not many survive. B.F. 38. Die K

London [M. 2821; CRS. p. 89; CIL VII, 1334, 1b; British M. 46K] l. facing; slightly sandy, greyish cream fabric; largish to smallest, white, grey, black, few brown to b.b.; internal scoring. Assigned

London, City of London [purchased 1856; CRS. p. 89; British M. 47K] hard,  
 cream fabric with pink core in flange; pale buff surface; much, white, grey,  
 black, smallest to medium gut to b. b; internal scoring; very slightly  
 diagonal stamp. sketch J

<sup>BDE</sup>  
London [1937. 113; Guildhall M.; 139K] l. facing; sandy, grey fabric; gut gone  
 save 1 whitish gut; BF. 34. Die K

London, Public Cleansing Dept, Upper Thames St [E.R. 472; Guildhall  
 M. no. 259K] r. facing; burnt black in parts; greenish in others NA

<sup>NB</sup>  
 All the F.LVGVDS in B.M are from different vessels.

ALBINVS

Lock have, Smithfield, London. April 1844 formerly in the Chaffers-Poll<sup>n</sup>.

no. 109. Catalogue of specimens in the Museum of Practical Geology, 1855.  
by Sir Henry de la Beche & Trenham Keels. p. 91 ALBINV

Also referred to in Handbook to the Collection of British Pottery & Porcelain in  
the Museum of Practical Geology (Germaine St). 1893. p. 77.

Should be checked at art installeid.

## ALBINUS

London [65, Friday St. 1929.36 Guildhall M; 126K] L. facing; sandy, buff fabric, pinker near surface; blackened on underside; smallish r/b + black qnts mostly worn away; BF 34 but bead more prominent. G

London [FS. Y; 1932.180; 122K Guildhall M] sandy, buff fabric, with greyish core, changing to orangish in parts; internal scoring; grey r/b qnts to near bead; BF 34 with unusual bead. <sup>looks early sketch</sup> C

London [18, 769; 140K] slightly sandy, buff fabric with pink core in flange; good amount, grey, white, r/b, qnts near beads and some internal scoring all worn away below. BF 38. ALBINUS || F.K.V.G.V.DV E(?)

London [1937.65; 162K] r. facing; sandy, grey fabric with some qnts in it; some, med. + small, r/b, grey black qnts to c. 1/2 b. but most worn away D=14 ins. BF 38 but flange intumed at bottom. D

ALBINUS

LONDON

London [ER 880, GH. 318K] St. Nicholas Acon. stamped diagonally. Flange only.

London [16725 1946.25 GH 321K] Fosterhane. holed.

Both stamps

London [~~214~~ 56/7/1/45. CRS. 1856. BM] L-facing. 1 stamp only, across rim. ALBINUS on label. Nearly complete except for hole in base; scoring inside, not on rim. H = 3½"  
Pr. 290mm.


London 4x9h Chapman. 316K GH

- BAE ✓  
London [Guildhall M. 1937.96; 120K] very slightly sandy, grey fabric,  
 blackened on inside and on part of outside and underside. BF. 34. K
- London [Guildhall M. Cannon St., R. XI. 646; 1852; 121K] sandy, pinky buff fabric,  
 smallish, r/b, grey grit to c. 1/2 b. b; internal scoring; accretions of orange &  
 rusty coloured stuff; D=13 ins; BF. 34. J
- London [11593 Scoring inside, not on top. 926.72; Old G.P.O.; S.E. corner Nov. 1925; 171K Guildhall M.] buff,  
 slightly sandy fabric; traces of internal scoring; tiny, white, grey grits, a few  
 larger, and r/b; most grit worn away; D=12 ins; small 34/38. ALBINUS//LUGO. FEC  
 stamped along, not published. A
- London [Guildhall Mus. R. XI. 646; 180K] r. facing; <sup>D=10 1/2" to 11 1/4"</sup> sandy, greyish cream fabric, surface  
 buff in parts, dirty cream buff in others, profic, l. to sm, r/b, black, grey grit to b. b BF 34; stamped diag.

ALBINUS

London (BBB05 Bow Bells House context 1194 Acc <854>

Pd. 3 822K) L. facing. 330gms. Dv. 300mm 19% Burnt  
<sup>inside</sup> before fracture. Traces of concentric scoring which began  
c 1 cm below bottom of bead. Heavily worn. V.R.W.  
pale brownish cream with slip self colour of fired  
w pale ochre brown. Packed with quartz with rare  
orange-brown + black. Quartz flint inclusions a  
- [LV9V] - not de possible @ Kueschletter Die 6A w 68



ALBINUS

London\* [CRS unregistered remainder. 137K BM] Cream

fabric with orangey cream slip. Big hooked fragment.

London\* [CRS unregistered remainder 138K BM. no. 61]

Diagonal stamp. Rim fragment.

B.

London\* [CRS unregistered remainder 139K BM]

different vessel. Diagonal stamp. Sketch in book.

London\* [CRS unregistered remainder 145K BM] r.

Facing. Scoring + grit on flange. Cream fabric.

Sketch in book. (This needs checking - scoring on rim???)

LUCUDV

London

12837

Merseyside County Museum, Liverpool.

not found

ELVEY, Eugene

Ans: Kray Bros

(2) re Shaw's 13/6/65

LUGUDV (see ALBINUS ?).

Reculver (Arch <sup>1890</sup> J. XLVII p. 234 no. 6. (now in possession of the Rev. E. Field, Petrockstow (N. Devon). Copied by Haverfield.) The stamp has not been found but could obviously be from a variation of ALBINUS or the type stamped LUGUDV only. FAEVS. broken.

Not found. It could be ALBINUS or the LUGUDV alone ~~potentially~~ which is Continental. It doesn't say that it's broken so it might work best as an Albinus counterstamp with F used impressed.

ALBINVS  
London, No. 1, Poultry [Context 18089 Mus Acc. 5361 (ALBINVS)  
joining Context 1112 M. Acc. no. 539 (FLVSVDV) 428K]  
L. facing  
L. facing  
ctr. slightly singed. } graffiti on FNGVDV.  
5361 3859 diam 22%  
Diam. 315mm 33% Break between sherds is modern. both stamps  
6359 diagonal. Probably the finer end of Venetian range.  
Greyish-cream fabric with frequent quartz, not as well  
-sorted as it often is with few, random, mostly  
larger orange-brown inclusions. Probably has a s.c  
slip. Flange definitely smooth. Inclusion grit  
frequent, mostly small to med-sized upto 6 of bead; flint  
and quartz with few r-b & rare black<sup>slag</sup>. Concentric scoring  
inside summings below bead. Very heavily worn from about T 2  
5mm - 60 bl. bead. PTO Dies 5 + 6 AS

428K  
Spent as 9K Manchester.  
ch

ALBINUS

Southwark [TLMAS 25 (1974), 44, Fig 23 no 46 + 47]

C-facing.

Southwark [Hibernia Chambers 74 (6)] A gut + scoring  
a flange; scoring + fine grit inside.

Southwark [Borough High St. Unstrat] Diagonal B

Southwark [St. Thomas St 74 u/s  $\triangleleft$  226] Diagonal Counterstamp.

Southwark [R 207, Borough High St. T1 F5 L1 53] Counterstamp

Southwark<sup>199</sup> [Borough Borough High St, 75  $\nabla$  (25) 16K] slightly  
diagonal. Granular cream fabric with pinkish core,  
slightly burnt. worn; flint & v-b grit.

ALBINUS

Southwark, 175, Borough High St. (B.H.S.) [H. T. (19) 4 no. 48. 41K]

L-facing, stamped along. Dr. <sup>3115</sup> 32cms. Granular, greyish cream fabric with pink core; packed with quartz: worn. Rim smooth; concentric scoring inside, worn away below about  $\frac{1}{2}$  inch. A

Southwark, Hooper St., [H00.88 (888) (1702) 45K] counterstamp Fren 1972

~~no. 10 in fig. 145~~ Julia St. John Albin. Rubbing.

~~Southwark [H. T. 16.43a. 175 B.H.S. 41K] FF band. Probably  
Albinus Die B [117] granular fabric. Engrave is bottom flange as often.~~

ALBINUS

Southwark [Crypt 77 ⑦ 2 Southwark Cathedral] Flange frequent

Venlamin fabric. Die 6B counterstamp - 46K

Southwark [213 Borough High St. v/s 26/8/77. 47K] Venlamin fabric. r. facing v/s. <sup>Edge of stamp.</sup> AB v/s Cream with pink cap Dam. 33c

Southwark [175 Borough High St. H.T. 16 ③ 43a. 44K] FF

brnt. v/s: Almost certainly Albinus Die 5.  $\Delta$

Southwark [Hunt House HH 097 ⑫ 53K sent via Malcolm

Hyne 1999. Assessment trench 1] <sup>ALBINUS</sup> L. facing and edge of

<sup>FL. JUDY.</sup> r. facing stamp. c856g. Dr. 26.75 45% Concentric scoring inside only. v. Heavily worn. Intonation just ting t

small, frequent, up to bottom of bead & some on flange but  
flange is definitely smoothed; has had concentric scoring  
inside, survives for about 2 cm. below b.d.b. Die as VER 1, nos,  
counterstamp too fragile to identify <sup>die</sup> Boston & D survives. Greyish-cream  
fabric slightly brownish <sup>er</sup> in thick core [Munsell 10 YR 7/2.5]  
with frequent, ill sorted inclusions, almost all quartz  
and rare orange-brown and opaque black; also rare <sup>large</sup> random  
reddish-brown. Inclusions: mostly flint, but rare <sup>large</sup> red-brown,  
quartz and black (opaque? slag) may have had a buff-  
cream slip. (The inclusions are more mixed & ill-sorted than  
often, more as frequent)

## ALBINUS

Southwark [199 Borough High St., 75 XIX (K) 17K]

Flange fragment; big hook. cream fabric with buff core; flint and white grits in fabric. FLUGUD [

do. [ do. B.T. XXIII (15) 18K ] DV read as

1K Maidstone. Granular greyish cream fabric, slightly burnt.

L. facing.

Southwark [199, Borough High St. 1975 XXIII 18. 23K]

diagonally stamped. burnt slightly; few flints. MVC/ ▲

Southwark attrib. to Albinus; [199, Borough High St., B.T. IV/V (2)]

end of flange with beg. of A on it. Reading certain. Granular cream with pink to surface + buff wear slip. F/F/i. probably Albinus.


London, Southwark [Fd. on site of Barclay + Perkins Brewery, Park St. in 1912; now  
in museum of Barclay + Courage Brewery on Southwark Bridge Rd. <sup>not actually</sup> Arch.  
<sup>mentioned here</sup> LXIII p. 327 + p. 342] ALBINVS (r. facing) + F. LUGVDV (l. facing). K

London [Crypt of All Hallows Church by the Tower] slightly diagonal. ALBINV<sup>NA</sup>  
London, <sup>Port</sup> London Wall <sup>note</sup> [A. 1256; from W. M. Newton Collection; London M. & K.]

l. facing, diagonal stamp ALBIN; 1 stamp only on mortarium;  
whole save for small hole - ? due to wear - in base; <sup>brown cream</sup> pinky buff  
fabric; internal scoring; smallest & tiny, red-brown, grey grit; probably  
a buff slip; no scoring on flange; B.F. 34/38. D. = 28<sup>1</sup>/<sub>2</sub> cm. C  
Research paper of the Surrey Arch. Society, No. 5. Excavations in Southwark K.M.K. 1959 p. 44  
Southwark (at Durham in 1968; S.P. 5.8. EXXII 52/2; 25K) l. facing; stamped once only; sandy  
greyish fabric; cream slip. Flint grit; mostly worn away. D = 10<sup>1</sup>/<sub>2</sub>". no. 3 + fig. 14, p. 48 no. 3.

ALBINUS


London, Cheapside [CHP12 <71] [221] 897K sent by  
Charlotte <sup>Sum</sup> <sup>2015</sup> outside flange broken off. 188gms.  
Worn in lower half + some burring inside before  
fracture. Concentric scoring (above where worn away)  
up to 6.0 bead. <sup>and traces survive lower down</sup> Flange smooth. VS i survives  
VRW. (The gnt combined with the scoring is tiny to small)  
(Imp gnt as on 857K) Die 5 A



ALBINVS

London, Cheap side CDPO4 [Access <718> Context 1814

857K] 240g Diameter 310mm 10% : Warm at bottom of sherd. Heavily burnt on inside penetrating  $\frac{1}{2}$  way through fabric + on top of bead. Pale brown with cream fabric. Inclusions: packed tiny and small mostly quartz, more red-brown than usual. Inclusions more ill-sorted than usual. Inclusions: flint + quartz with some red-brown. Concentric scoring inside. Flange smooth: Very well made - F. LIVERD d. 6



ALBINUS

London, Number One Poultry, City of London [Con. 8728;  
Mus Acc. no. 2614 429K] L-facing name stamp. 190g  
Diam 34 cms. 10% Burnt. Fabric friable & <sup>smooth</sup> ~~letters~~ smoother  
than 428K fabric grey throughout; frequent relatively  
well-sorted quartz & few larger o/brown inclusions.  
Cream slip. Flint & quartz trinituration gulls as herd. Traces  
of concentric scumg b.b. bead. Slightly sandy to <sup>d. 5 A</sup> form  
London, No. 1, Poultry, [Con 3579 Mus Acc. 1567 430K]  
r-facing. IRS. Greyish cream fabric with pink core  
in surviving <sup>sometimes</sup> sherd; frequent, mod, well sorted qtz  
inclusions, rare/larger o/b. Cream slip. Not trinituration.  
survives. Surviving flange smooth. pto die 5 <sup>S</sup> Δ


429K Summer Page smooth

430K 100g. 25cms. 14%

ALBINUS

London, No 1, Poultry [Context 18087 Mus. Acc 4976 433K]

IRS 115g. stamp diagonal. Drab buff fabric with  
orange slip; inclusions: frequent quartz, few orange-  
brown. Surface flatter smooth. Not enough  
surfaces inside to show of had concentric scoring there  
but it had gut upto bottom of bead. Die 6



ALBINVS

London, Mr. Mansion House [1869. Presented a school by  
Guildhall Museum] information Margaret Roxan.  
Nonubings but read as ALBINVS // LVSV D, 289K.  
sandy buff fabric with light coloured grits; bowl nearly  
complete apart from small hole in base, and part of rim.  
#Creighton Down Comprehensive School, used to be  
Tollington Grammar School, Tetherdown, N. 10  
[GHC. p. 102 no. 618]

London [inform. E. Johns. British Museum.] "foreshare by Cannon  
St. Station" Cream fabric with pink ink core probably.  
rubbing sent.

ALBIN VS

Northgate Kilns [KH598 Can B102 Acc <48> 568K] IRS

Burnt. heavily worn burnt before fracture. Cream fabric with  
Thick buff-brown<sup>\*</sup> core Inclusions: fairly frequent, very poorly  
sorted quartz, somewhat random, rare red-brown, rare  
large quartz sandstone. The core is well-defined ~~at base~~  
surface. Inclusions: concentric scoring, flint and quartz  
red-brown rare. 185g. Core quite well-defined. Fabric  
<sup>fairly</sup> normal for Ver but not totally certain.  
<sup>\*</sup> buff-brown where discoloured near base; <sup>chab</sup> pink core  
at top.

KHS 98 Con B102



breed break  
o o

Acc (110) 568K Northgate Koko

569K Northgate Koko KHS 98 Con B145

## ALBINUS.

FOUND IN LONDON

<sup>Fosterham</sup>  
London [1946.205 Guildhall M. 188K] hole in base; slightly sandy,  
 pinkish cream fabric + surface, but latter buff in places; most of grit  
 worn away; few grey r/b, survive; whole  $D = 12\frac{1}{10}$  ins. BF.34.  
 ALBINUS || F. LVGVDU. H

London [18, Billiter St., Feb., 1926; 1926.17.B; Guildhall M. 202K] L. facing;  
 slightly sandy, pink fabric, burnt black on fragment of flange remaining;  
 very few, r/b, + black grits remain. Assigned to ALBINUS. Not assigned NA.

London, Southwark [<sup>Erection of St. Albinus - R.M.K.P. 47, no. 3.</sup>  
 Institute; S.P. 5.8/CXXII 52/2; information B<sup>2</sup>]  
 pinkish fabric; much darker in core with ample fabric grits, black + white,  
 Sparseset much worn; outer  $D = 10\frac{1}{4}$ " ; inner  $D = 7\frac{3}{4}$ ". G

~ B<sup>2</sup> -

ALBINUS choker.

London [4K ~~Low~~ Merseyside County Museum 178. H. S. Roach  
Smith.] Greyish cream fabric with very thin pink core.  
Granular fabric. No grit on flange. Scoring inside only.  
Worn. Flint (grey & white); transparent & red-brown  
quartz tintation grit. Probably cream slip fired to  
orange brown in parts. L. facing diagonal.

ALBINVS

London, Basinghall St (BAZ05 <sup>Pd.6 OAH</sup> <167> Context 585 797K)


heavily worn, 395 gms, Diam 360 mm. 18% slightly diagonal, VRW fabric. Concentric scoring, FVGVDV die 6/8

London, Basinghall St (BAZ05 Pd 4 <168> Context- 608; OA10 798K) stamped diagonally, 158 gms Diam 310 mm. 12% VRW ALBINVS. Different vessel. Concentric scoring die 5 A

London, Basinghall St (BAZ05 <170> Context 1215 Pd 2 OA2 800K J+L: Heavily worn 1135 gms Diam. 320 mm 55% Fabric VRW scoring. 2 young shevds at angles: die 9+10

duplicate entry Oct 2020 deleted from database

die 9+10  
die 13



ALBINUS

London, Basinghall St. (BAZ 05 (168) 608) Pd 4 OA 10

798K) 158 gms. Diameter 310 mm s 12% impressed diagonally. Finger impression under stamp. Fabric: cream ~~near~~ surface but thick black core. ~~Fab~~ may have white slip. Inclusions: frequent, fairly well-sorted quartz with v rare o-b. Normal VFW. Broken near top. Concentric scoring inside only. Die 5

ALBINS

London, Basinghall St (BAZ05 1912) Pd 2. OA2 802K)

90 gms. Diam 320 mm 57% Fabric: discoloured  
over fracture as well as the surface. Drab brownish  
grey. Inclusions: abundant small quartz with  
base orange-brown. Concentric scoring inside only.  
Intuition: quartz & flint. stamped at right angles.  
As dr 5 but marginally larger. S

ALBINVS

London, Basinghall St. [BAZ05 (167) 585] Pd 6.0A11

797K) Diam 360mm 18% 395gms. Heavily worn.

Flattened in interior. Fabric: drabs; inclusions: fairly frequent quartz with occasional red-brown. Fabric

fairly fine for VRW & not typical for VRW. Interactions: flint, quartz & rare red-brown. Concentric scoring.

No interaction on top of flange; Stamps Freese 6b, & impressed slightly diagonal. S.

ALBINYS

London, Basinghall St (BAZ05 <170> [1215] Pd. 2.0A2  
800K) L and r. facing heavily worn Stamped at rt.  
angles. 1135 gms Diam 320 mm 55% Tw  
joining pieces. Fabric; greyish-cream with pink  
core. Inturatur: flint and quartz. Inclusions:  
frequent quartz; v rare orange-brown (vll-s). Concentric  
scoring inside only. Normal VRW Die 5 and 6 q/b 5

ALBINVS

Residual

The Baltic House Site, St. Mary Axe EC3 (BAX95) London

[BAX95 ~~Accession no.~~ <sup>MOLAS</sup> 796 Context 1163 404K] flange

fragment, stamped diagonally. Slightly burnt. dent under flange where stamp has been impressed.

Dr. c. 31 cms. 9% 70gms. Greyish-cream fabric with sand and

fabric pink (thin) / greyish-cream / pink (thin) with greyish-cream near flat surface. Inclusions: abundant, moderately

well-sorted quartz with rare opaque red-brown. Fabric is not as granular as it can be. 1 piece probably flint in surface. Probably left-facing. di

ALBINVS

\*

Probably London [Bought by Stephen Castle from Louis Meier  
(Antique shop) 23, Cecil Court, Charing Cross Rd.,  
London W.C.2] Provenance not known but purchased  
at an auction in London a long time ago. Well-worn  
& hole worn in bottom; cream to buff ware with pink  
core; usual granular ware, gnt, white, grey, blk  
and red. In private possession. S. Castle.

\* ?  
 London [CIL VII 1334, 4 b. Does not quote provenance  
 C.R.S. ~~115~~ ~~116~~ ~~117~~ ~~118~~ ~~119~~ ~~120~~ ~~121~~ ~~122~~ ~~123~~ ~~124~~ ~~125~~ ~~126~~ ~~127~~ ~~128~~ ~~129~~ ~~130~~ ~~131~~ ~~132~~ ~~133~~ ~~134~~ ~~135~~ ~~136~~ ~~137~~ ~~138~~ ~~139~~ ~~140~~ ~~141~~ ~~142~~ ~~143~~ ~~144~~ ~~145~~ ~~146~~ ~~147~~ ~~148~~ ~~149~~ ~~150~~ ~~151~~ ~~152~~ ~~153~~ ~~154~~ ~~155~~ ~~156~~ ~~157~~ ~~158~~ ~~159~~ ~~160~~ ~~161~~ ~~162~~ ~~163~~ ~~164~~ ~~165~~ ~~166~~ ~~167~~ ~~168~~ ~~169~~ ~~170~~ ~~171~~ ~~172~~ ~~173~~ ~~174~~ ~~175~~ ~~176~~ ~~177~~ ~~178~~ ~~179~~ ~~180~~ ~~181~~ ~~182~~ ~~183~~ ~~184~~ ~~185~~ ~~186~~ ~~187~~ ~~188~~ ~~189~~ ~~190~~ ~~191~~ ~~192~~ ~~193~~ ~~194~~ ~~195~~ ~~196~~ ~~197~~ ~~198~~ ~~199~~ ~~200~~ ~~201~~ ~~202~~ ~~203~~ ~~204~~ ~~205~~ ~~206~~ ~~207~~ ~~208~~ ~~209~~ ~~210~~ ~~211~~ ~~212~~ ~~213~~ ~~214~~ ~~215~~ ~~216~~ ~~217~~ ~~218~~ ~~219~~ ~~220~~ ~~221~~ ~~222~~ ~~223~~ ~~224~~ ~~225~~ ~~226~~ ~~227~~ ~~228~~ ~~229~~ ~~230~~ ~~231~~ ~~232~~ ~~233~~ ~~234~~ ~~235~~ ~~236~~ ~~237~~ ~~238~~ ~~239~~ ~~240~~ ~~241~~ ~~242~~ ~~243~~ ~~244~~ ~~245~~ ~~246~~ ~~247~~ ~~248~~ ~~249~~ ~~250~~ ~~251~~ ~~252~~ ~~253~~ ~~254~~ ~~255~~ ~~256~~ ~~257~~ ~~258~~ ~~259~~ ~~260~~ ~~261~~ ~~262~~ ~~263~~ ~~264~~ ~~265~~ ~~266~~ ~~267~~ ~~268~~ ~~269~~ ~~270~~ ~~271~~ ~~272~~ ~~273~~ ~~274~~ ~~275~~ ~~276~~ ~~277~~ ~~278~~ ~~279~~ ~~280~~ ~~281~~ ~~282~~ ~~283~~ ~~284~~ ~~285~~ ~~286~~ ~~287~~ ~~288~~ ~~289~~ ~~290~~ ~~291~~ ~~292~~ ~~293~~ ~~294~~ ~~295~~ ~~296~~ ~~297~~ ~~298~~ ~~299~~ ~~300~~ ~~301~~ ~~302~~ ~~303~~ ~~304~~ ~~305~~ ~~306~~ ~~307~~ ~~308~~ ~~309~~ ~~310~~ ~~311~~ ~~312~~ ~~313~~ ~~314~~ ~~315~~ ~~316~~ ~~317~~ ~~318~~ ~~319~~ ~~320~~ ~~321~~ ~~322~~ ~~323~~ ~~324~~ ~~325~~ ~~326~~ ~~327~~ ~~328~~ ~~329~~ ~~330~~ ~~331~~ ~~332~~ ~~333~~ ~~334~~ ~~335~~ ~~336~~ ~~337~~ ~~338~~ ~~339~~ ~~340~~ ~~341~~ ~~342~~ ~~343~~ ~~344~~ ~~345~~ ~~346~~ ~~347~~ ~~348~~ ~~349~~ ~~350~~ ~~351~~ ~~352~~ ~~353~~ ~~354~~ ~~355~~ ~~356~~ ~~357~~ ~~358~~ ~~359~~ ~~360~~ ~~361~~ ~~362~~ ~~363~~ ~~364~~ ~~365~~ ~~366~~ ~~367~~ ~~368~~ ~~369~~ ~~370~~ ~~371~~ ~~372~~ ~~373~~ ~~374~~ ~~375~~ ~~376~~ ~~377~~ ~~378~~ ~~379~~ ~~380~~ ~~381~~ ~~382~~ ~~383~~ ~~384~~ ~~385~~ ~~386~~ ~~387~~ ~~388~~ ~~389~~ ~~390~~ ~~391~~ ~~392~~ ~~393~~ ~~394~~ ~~395~~ ~~396~~ ~~397~~ ~~398~~ ~~399~~ ~~400~~ ~~401~~ ~~402~~ ~~403~~ ~~404~~ ~~405~~ ~~406~~ ~~407~~ ~~408~~ ~~409~~ ~~410~~ ~~411~~ ~~412~~ ~~413~~ ~~414~~ ~~415~~ ~~416~~ ~~417~~ ~~418~~ ~~419~~ ~~420~~ ~~421~~ ~~422~~ ~~423~~ ~~424~~ ~~425~~ ~~426~~ ~~427~~ ~~428~~ ~~429~~ ~~430~~ ~~431~~ ~~432~~ ~~433~~ ~~434~~ ~~435~~ ~~436~~ ~~437~~ ~~438~~ ~~439~~ ~~440~~ ~~441~~ ~~442~~ ~~443~~ ~~444~~ ~~445~~ ~~446~~ ~~447~~ ~~448~~ ~~449~~ ~~450~~ ~~451~~ ~~452~~ ~~453~~ ~~454~~ ~~455~~ ~~456~~ ~~457~~ ~~458~~ ~~459~~ ~~460~~ ~~461~~ ~~462~~ ~~463~~ ~~464~~ ~~465~~ ~~466~~ ~~467~~ ~~468~~ ~~469~~ ~~470~~ ~~471~~ ~~472~~ ~~473~~ ~~474~~ ~~475~~ ~~476~~ ~~477~~ ~~478~~ ~~479~~ ~~480~~ ~~481~~ ~~482~~ ~~483~~ ~~484~~ ~~485~~ ~~486~~ ~~487~~ ~~488~~ ~~489~~ ~~490~~ ~~491~~ ~~492~~ ~~493~~ ~~494~~ ~~495~~ ~~496~~ ~~497~~ ~~498~~ ~~499~~ ~~500~~ ~~501~~ ~~502~~ ~~503~~ ~~504~~ ~~505~~ ~~506~~ ~~507~~ ~~508~~ ~~509~~ ~~510~~ ~~511~~ ~~512~~ ~~513~~ ~~514~~ ~~515~~ ~~516~~ ~~517~~ ~~518~~ ~~519~~ ~~520~~ ~~521~~ ~~522~~ ~~523~~ ~~524~~ ~~525~~ ~~526~~ ~~527~~ ~~528~~ ~~529~~ ~~530~~ ~~531~~ ~~532~~ ~~533~~ ~~534~~ ~~535~~ ~~536~~ ~~537~~ ~~538~~ ~~539~~ ~~540~~ ~~541~~ ~~542~~ ~~543~~ ~~544~~ ~~545~~ ~~546~~ ~~547~~ ~~548~~ ~~549~~ ~~550~~ ~~551~~ ~~552~~ ~~553~~ ~~554~~ ~~555~~ ~~556~~ ~~557~~ ~~558~~ ~~559~~ ~~560~~ ~~561~~ ~~562~~ ~~563~~ ~~564~~ ~~565~~ ~~566~~ ~~567~~ ~~568~~ ~~569~~ ~~570~~ ~~571~~ ~~572~~ ~~573~~ ~~574~~ ~~575~~ ~~576~~ ~~577~~ ~~578~~ ~~579~~ ~~580~~ ~~581~~ ~~582~~ ~~583~~ ~~584~~ ~~585~~ ~~586~~ ~~587~~ ~~588~~ ~~589~~ ~~590~~ ~~591~~ ~~592~~ ~~593~~ ~~594~~ ~~595~~ ~~596~~ ~~597~~ ~~598~~ ~~599~~ ~~600~~ ~~601~~ ~~602~~ ~~603~~ ~~604~~ ~~605~~ ~~606~~ ~~607~~ ~~608~~ ~~609~~ ~~610~~ ~~611~~ ~~612~~ ~~613~~ ~~614~~ ~~615~~ ~~616~~ ~~617~~ ~~618~~ ~~619~~ ~~620~~ ~~621~~ ~~622~~ ~~623~~ ~~624~~ ~~625~~ ~~626~~ ~~627~~ ~~628~~ ~~629~~ ~~630~~ ~~631~~ ~~632~~ ~~633~~ ~~634~~ ~~635~~ ~~636~~ ~~637~~ ~~638~~ ~~639~~ ~~640~~ ~~641~~ ~~642~~ ~~643~~ ~~644~~ ~~645~~ ~~646~~ ~~647~~ ~~648~~ ~~649~~ ~~650~~ ~~651~~ ~~652~~ ~~653~~ ~~654~~ ~~655~~ ~~656~~ ~~657~~ ~~658~~ ~~659~~ ~~660~~ ~~661~~ ~~662~~ ~~663~~ ~~664~~ ~~665~~ ~~666~~ ~~667~~ ~~668~~ ~~669~~ ~~670~~ ~~671~~ ~~672~~ ~~673~~ ~~674~~ ~~675~~ ~~676~~ ~~677~~ ~~678~~ ~~679~~ ~~680~~ ~~681~~ ~~682~~ ~~683~~ ~~684~~ ~~685~~ ~~686~~ ~~687~~ ~~688~~ ~~689~~ ~~690~~ ~~691~~ ~~692~~ ~~693~~ ~~694~~ ~~695~~ ~~696~~ ~~697~~ ~~698~~ ~~699~~ ~~700~~ ~~701~~ ~~702~~ ~~703~~ ~~704~~ ~~705~~ ~~706~~ ~~707~~ ~~708~~ ~~709~~ ~~710~~ ~~711~~ ~~712~~ ~~713~~ ~~714~~ ~~715~~ ~~716~~ ~~717~~ ~~718~~ ~~719~~ ~~720~~ ~~721~~ ~~722~~ ~~723~~ ~~724~~ ~~725~~ ~~726~~ ~~727~~ ~~728~~ ~~729~~ ~~730~~ ~~731~~ ~~732~~ ~~733~~ ~~734~~ ~~735~~ ~~736~~ ~~737~~ ~~738~~ ~~739~~ ~~740~~ ~~741~~ ~~742~~ ~~743~~ ~~744~~ ~~745~~ ~~746~~ ~~747~~ ~~748~~ ~~749~~ ~~750~~ ~~751~~ ~~752~~ ~~753~~ ~~754~~ ~~755~~ ~~756~~ ~~757~~ ~~758~~ ~~759~~ ~~760~~ ~~761~~ ~~762~~ ~~763~~ ~~764~~ ~~765~~ ~~766~~ ~~767~~ ~~768~~ ~~769~~ ~~770~~ ~~771~~ ~~772~~ ~~773~~ ~~774~~ ~~775~~ ~~776~~ ~~777~~ ~~778~~ ~~779~~ ~~780~~ ~~781~~ ~~782~~ ~~783~~ ~~784~~ ~~785~~ ~~786~~ ~~787~~ ~~788~~ ~~789~~ ~~790~~ ~~791~~ ~~792~~ ~~793~~ ~~794~~ ~~795~~ ~~796~~ ~~797~~ ~~798~~ ~~799~~ ~~800~~ ~~801~~ ~~802~~ ~~803~~ ~~804~~ ~~805~~ ~~806~~ ~~807~~ ~~808~~ ~~809~~ ~~810~~ ~~811~~ ~~812~~ ~~813~~ ~~814~~ ~~815~~ ~~816~~ ~~817~~ ~~818~~ ~~819~~ ~~820~~ ~~821~~ ~~822~~ ~~823~~ ~~824~~ ~~825~~ ~~826~~ ~~827~~ ~~828~~ ~~829~~ ~~830~~ ~~831~~ ~~832~~ ~~833~~ ~~834~~ ~~835~~ ~~836~~ ~~837~~ ~~838~~ ~~839~~ ~~840~~ ~~841~~ ~~842~~ ~~843~~ ~~844~~ ~~845~~ ~~846~~ ~~847~~ ~~848~~ ~~849~~ ~~850~~ ~~851~~ ~~852~~ ~~853~~ ~~854~~ ~~855~~ ~~856~~ ~~857~~ ~~858~~ ~~859~~ ~~860~~ ~~861~~ ~~862~~ ~~863~~ ~~864~~ ~~865~~ ~~866~~ ~~867~~ ~~868~~ ~~869~~ ~~870~~ ~~871~~ ~~872~~ ~~873~~ ~~874~~ ~~875~~ ~~876~~ ~~877~~ ~~878~~ ~~879~~ ~~880~~ ~~881~~ ~~882~~ ~~883~~ ~~884~~ ~~885~~ ~~886~~ ~~887~~ ~~888~~ ~~889~~ ~~890~~ ~~891~~ ~~892~~ ~~893~~ ~~894~~ ~~895~~ ~~896~~ ~~897~~ ~~898~~ ~~899~~ ~~900~~ ~~901~~ ~~902~~ ~~903~~ ~~904~~ ~~905~~ ~~906~~ ~~907~~ ~~908~~ ~~909~~ ~~910~~ ~~911~~ ~~912~~ ~~913~~ ~~914~~ ~~915~~ ~~916~~ ~~917~~ ~~918~~ ~~919~~ ~~920~~ ~~921~~ ~~922~~ ~~923~~ ~~924~~ ~~925~~ ~~926~~ ~~927~~ ~~928~~ ~~929~~ ~~930~~ ~~931~~ ~~932~~ ~~933~~ ~~934~~ ~~935~~ ~~936~~ ~~937~~ ~~938~~ ~~939~~ ~~940~~ ~~941~~ ~~942~~ ~~943~~ ~~944~~ ~~945~~ ~~946~~ ~~947~~ ~~948~~ ~~949~~ ~~950~~ ~~951~~ ~~952~~ ~~953~~ ~~954~~ ~~955~~ ~~956~~ ~~957~~ ~~958~~ ~~959~~ ~~960~~ ~~961~~ ~~962~~ ~~963~~ ~~964~~ ~~965~~ ~~966~~ ~~967~~ ~~968~~ ~~969~~ ~~970~~ ~~971~~ ~~972~~ ~~973~~ ~~974~~ ~~975~~ ~~976~~ ~~977~~ ~~978~~ ~~979~~ ~~980~~ ~~981~~ ~~982~~ ~~983~~ ~~984~~ ~~985~~ ~~986~~ ~~987~~ ~~988~~ ~~989~~ ~~990~~ ~~991~~ ~~992~~ ~~993~~ ~~994~~ ~~995~~ ~~996~~ ~~997~~ ~~998~~ ~~999~~ ~~1000~~ ~~1001~~ ~~1002~~ ~~1003~~ ~~1004~~ ~~1005~~ ~~1006~~ ~~1007~~ ~~1008~~ ~~1009~~ ~~1010~~ ~~1011~~ ~~1012~~ ~~1013~~ ~~1014~~ ~~1015~~ ~~1016~~ ~~1017~~ ~~1018~~ ~~1019~~ ~~1020~~ ~~1021~~ ~~1022~~ ~~1023~~ ~~1024~~ ~~1025~~ ~~1026~~ ~~1027~~ ~~1028~~ ~~1029~~ ~~1030~~ ~~1031~~ ~~1032~~ ~~1033~~ ~~1034~~ ~~1035~~ ~~1036~~ ~~1037~~ ~~1038~~ ~~1039~~ ~~1040~~ ~~1041~~ ~~1042~~ ~~1043~~ ~~1044~~ ~~1045~~ ~~1046~~ ~~1047~~ ~~1048~~ ~~1049~~ ~~1050~~ ~~1051~~ ~~1052~~ ~~1053~~ ~~1054~~ ~~1055~~ ~~1056~~ ~~1057~~ ~~1058~~ ~~1059~~ ~~1060~~ ~~1061~~ ~~1062~~ ~~1063~~ ~~1064~~ ~~1065~~ ~~1066~~ ~~1067~~ ~~1068~~ ~~1069~~ ~~1070~~ ~~1071~~ ~~1072~~ ~~1073~~ ~~1074~~ ~~1075~~ ~~1076~~ ~~1077~~ ~~1078~~ ~~1079~~ ~~1080~~ ~~1081~~ ~~1082~~ ~~1083~~ ~~1084~~ ~~1085~~ ~~1086~~ ~~1087~~ ~~1088~~ ~~1089~~ ~~1090~~ ~~1091~~ ~~1092~~ ~~1093~~ ~~1094~~ ~~1095~~ ~~1096~~ ~~1097~~ ~~1098~~ ~~1099~~ ~~1100~~ ~~1101~~ ~~1102~~ ~~1103~~ ~~1104~~ ~~1105~~ ~~1106~~ ~~1107~~ ~~1108~~ ~~1109~~ ~~1110~~ ~~1111~~ ~~1112~~ ~~1113~~ ~~1114~~ ~~1115~~ ~~1116~~ ~~1117~~ ~~1118~~ ~~1119~~ ~~1120~~ ~~1121~~ ~~1122~~ ~~1123~~ ~~1124~~ ~~1125~~ ~~1126~~ ~~1127~~ ~~1128~~ ~~1129~~ ~~1130~~ ~~1131~~ ~~1132~~ ~~1133~~ ~~1134~~ ~~1135~~ ~~1136~~ ~~1137~~ ~~1138~~ ~~1139~~ ~~1140~~ ~~1141~~ ~~1142~~ ~~1143~~ ~~1144~~ ~~1145~~ ~~1146~~ ~~1147~~ ~~1148~~ ~~1149~~ ~~1150~~ ~~1151~~ ~~1152~~ ~~1153~~ ~~1154~~ ~~1155~~ ~~1156~~ ~~1157~~ ~~1158~~ ~~1159~~ ~~1160~~ ~~1161~~ ~~1162~~ ~~1163~~ ~~1164~~ ~~1165~~ ~~1166~~ ~~1167~~ ~~1168~~ ~~1169~~ ~~1170~~ ~~1171~~ ~~1172~~ ~~1173~~ ~~1174~~ ~~1175~~ ~~1176~~ ~~1177~~ ~~1178~~ ~~1179~~ ~~1180~~ ~~1181~~ ~~1182~~ ~~1183~~ ~~1184~~ ~~1185~~ ~~1186~~ ~~1187~~ ~~1188~~ ~~1189~~ ~~1190~~ ~~1191~~ ~~1192~~ ~~1193~~ ~~1194~~ ~~1195~~ ~~1196~~ ~~1197~~ ~~1198~~ ~~1199~~ ~~1200~~ ~~1201~~ ~~1202~~ ~~1203~~ ~~1204~~ ~~1205~~ ~~1206~~ ~~1207~~ ~~1208~~ ~~1209~~ ~~1210~~ ~~1211~~ ~~1212~~ ~~1213~~ ~~1214~~ ~~1215~~ ~~1216~~ ~~1217~~ ~~1218~~ ~~1219~~ ~~1220~~ ~~1221~~ ~~1222~~ ~~1223~~ ~~1224~~ ~~1225~~ ~~1226~~ ~~1227~~ ~~1228~~ ~~1229~~ ~~1230~~ ~~1231~~ ~~1232~~ ~~1233~~ ~~1234~~ ~~1235~~ ~~1236~~ ~~1237~~ ~~1238~~ ~~1239~~ ~~1240~~ ~~1241~~ ~~1242~~ ~~1243~~ ~~1244~~ ~~1245~~ ~~1246~~ ~~1247~~ ~~1248~~ ~~1249~~ ~~1250~~ ~~1251~~ ~~1252~~ ~~1253~~ ~~1254~~ ~~1255~~ ~~1256~~ ~~1257~~ ~~1258~~ ~~1259~~ ~~1260~~ ~~1261~~ ~~1262~~ ~~1263~~ ~~1264~~ ~~1265~~ ~~1266~~ ~~1267~~ ~~1268~~ ~~1269~~ ~~1270~~ ~~1271~~ ~~1272~~ ~~1273~~ ~~1274~~ ~~1275~~ ~~1276~~ ~~1277~~ ~~1278~~ ~~1279~~ ~~1280~~ ~~1281~~ ~~1282~~ ~~1283~~ ~~1284~~ ~~1285~~ ~~1286~~ ~~1287~~ ~~1288~~ ~~1289~~ ~~1290~~ ~~1291~~ ~~1292~~ ~~1293~~ ~~1294~~ ~~1295~~ ~~1296~~ ~~1297~~ ~~1298~~ ~~1299~~ ~~1300~~ ~~1301~~ ~~1302~~ ~~1303~~ ~~1304~~ ~~1305~~ ~~1306~~ ~~1307~~ ~~1308~~ ~~1309~~ ~~1310~~ ~~1311~~ ~~1312~~ ~~1313~~ ~~1314~~ ~~1315~~ ~~1316~~ ~~1317~~ ~~1318~~ ~~1319~~ ~~1320~~ ~~1321~~ ~~1322~~ ~~1323~~ ~~1324~~ ~~1325~~ ~~1326~~ ~~1327~~ ~~1328~~ ~~1329~~ ~~1330~~ ~~1331~~ ~~1332~~ ~~1333~~ ~~1334~~ ~~1335~~ ~~1336~~ ~~1337~~ ~~1338~~ ~~1339~~ ~~1340~~ ~~1341~~ ~~1342~~ ~~1343~~ ~~1344~~ ~~1345~~ ~~1346~~ ~~1347~~ ~~1348~~ ~~1349~~ ~~1350~~ ~~1351~~ ~~1352~~ ~~1353~~ ~~1354~~ ~~1355~~ ~~1356~~ ~~1357~~ ~~1358~~ ~~1359~~ ~~1360~~ ~~1361~~ ~~1362~~ ~~1363~~ ~~1364~~ ~~1365~~ ~~1366~~ ~~1367~~ ~~1368~~ ~~1369~~ ~~1370~~ ~~1371~~ ~~1372~~ ~~1373~~ ~~1374~~ ~~1375~~ ~~1376~~ ~~1377~~ ~~1378~~ ~~1379~~ ~~1380~~ ~~1381~~ ~~1382~~ ~~1383~~ ~~1384~~ ~~1385~~ ~~1386~~ ~~1387~~ ~~1388~~ ~~1389~~ ~~1390~~ ~~1391~~ ~~1392~~ ~~1393~~ ~~1394~~ ~~1395~~ ~~1396~~ ~~1397~~ ~~1398~~ ~~1399~~ ~~1400~~ ~~1401~~ ~~1402~~ ~~1403~~ ~~1404~~ ~~1405~~ ~~1406~~ ~~1407~~ ~~1408~~ ~~1409~~ ~~1410~~ ~~1411~~ ~~1412~~ ~~1413~~ ~~1414~~ ~~1415~~ ~~1416~~ ~~1417~~ ~~1418~~ ~~1419~~ ~~1420~~ ~~1421~~ ~~1422~~ ~~1423~~ ~~1424~~ ~~1425~~ ~~1426~~ ~~1427~~ ~~1428~~ <

ALBINUS

London, No 1 Poultry [Can 3204 Mus Accno. 889 437K]

stamp diagonal. VIANVACA #70g. Diam. 4.3a 8%  
smooth flange. Greyish-cream fabric with thick pink  
core; cream slip fired to buff & orange in parts.  
Frequent, fairly well-sorted quartz and few opaque o/b  
inclusions. Concentric scoring to b. d) b.; flint and  
quartz inclusion gut.

London, Tokenhouse Yard, Walbrook City of London  
[70grams. 581K] 423 Phase 75-85. Flange

fragment in greyish-white fabric fired to buff-cream  
on upper surface near spout. Inclusions; abundant,  
moderately well-sorted, quartz & v. rare orange-brown.  
Some possibly burning. Die 9

ALBINUS  
~~London Feat 18089 Mus Ace no. 6437~~

mix iron

London [C.R.S. Mt. d/R. London p. 89; Brit. Museum. 39K] L-facing; slightly sandy,

pinkish buff fabric; worn smooth 1 1/2" below b.b; very, very smooth grit; scoring; moderate,

smallish to medium, black, white, brown, grey grit; scoring on flange. B.F. 34/38; D=15 1/2

London [1901.7; British Museum 27K] stamped diagonally; pink fabric changing

to cream very near surface; surface slip, buff; medium & smaller, grey

& black flint; worn away in lower half of fragment. B

~~London~~ or Presumably C. 11 VII, 1334, 14, 5A 18 ALBINVS 22 Colchester.

London [65/12/20/26; British Museum. 42K] ALBINVS // LVGD FEC; stamped

diagonally; almost whole; slightly sandy, pale buff fabric; well worn; medium

to small, black, white, brown, grey grits to b.b; large - B.F. 38; D=13 1/2 ins. A

London [British Museum 44K] v-facing; slightly sandy, grey cream fabric; well worn;

large to smaller, grey, black, white grit to b.b; very few remain; large B.F. 38. F. UGVDV. B

London, Old G. P. O. [134K; 1926.121; S.E. Corner Oct. 1925; see Arch. 66,

not published; Guildhall M] sandy, pinky fabric, dark buff surface,  
 large to medium, few, v/b, grey grits D = 12½ in; BF = 34 in turned at end of  
 flange. Assigned # K.

London [18,863; <sup>Bucklersbury Ho</sup> Guildhall M; 135K] l. facing; sandy, red-orange, thick  
 core changing to very slightly pinkish cream near and at surfaces; smallish  
 grey grits; BF. 34. Die K

London, St. Paul's Churchyard [1930.190; 74; Guildhall M; 242K] r. facing  
 stamped diagonally; slightly sandy, pinkish fabric with orange-buff  
 surface; outside half of flange blackened. J

ALBINS.

Plantation Ho; Tencherch St.

London [Guildhall M. 17, 402; 183K] L-facing; sandy, cream fabric but part of

flange burnt grey; grit worn away save some r/b, white, black, grey  
grits just near beads, rilling; surface fairly smooth. D = c. 13 ins. G

London [Guildhall M. R. xi. 646; 241K] stamped diagonally; cream fabric  
with pinkish tinge in core; internal scoring; white, r/b, grey grits; not  
many near bead; very approximate B.F. 38. J

London [Guildhall M; 1934.255; 233K] L-facing; sandy, pink fabric;  
surface brown buff, in parts purple; grey, r/b. grit to bead; D = 11½ H

London [Guildhall M; 1937.67; 232K] L-facing; sandy, very slightly  
pinkish cream fabric. D

ALBINVS // VIANVACA

In the City 3326  
London [R.XI.62] Guildhall M.174K] ALBINVS r. facing; VIANVACA

l. facing; complete but for restored patch inside; slightly sandy, pinkish buff fabric so far as can be seen; surface drab buff, pinkish in parts, black in parts; smallish, red-brown, white, black grit, most worn away; stamps dia g on at; D = 12<sup>6</sup>/<sub>10</sub>; BF 34/38.

<sup>Midland Bank, Gracechurch St.</sup>  
London [ER 560; Guildhall M; 255K] dia g onally stamped; entire; sandy, creamy buff fabric with buff slip; sketch; ALBINVS stamp badly pitted.

London Hill [see ALBINVS F. 1956.8; fragment stamped  
~~VIANVACA~~ joins this.]

~~London [M2833, British Mus. 124K] see ALBINUS || ]A)IVVIV~~

London, Bank of England [E. Birley 1929 rubbing of drawing] G

London, The City, 1844 [Bateman's Collection of Ants. p. 145, no. C. LVII, 1334 (6A)]

London, Southwark 'Gent's Mag. Lib. part 2 p. 325' LBINI ? one already recorded

London [1937-III; 133 K Guildhall M] <sup>2 dres</sup> r. facing; diagonal; sandy, greyish fabric; largest to smallest, grey girth to b. b; B.F. 34 with more prominent bead; internal scoring; D = 12 ins; counterstamp of Die A. A

London [Behind Bank of England at corner of Coleman Street & Basinghall Avenue]. Stamp & counterstamp. Rubbing sent by A. H. Margatroyd 19/4/64.

[Bateman Collection; check if Catalogue mentions 'the City,  
1844' because (found a) 'part of a <sup>v.c.</sup> ~~maternin~~ <sup>maternin</sup> impressed  
with the name of the maker, ALBINUS']

ALBINUS

Note any rubbing for London which could be read

AEB - - - -

no. 93

London [CIL VII, 1334, 77  
Howard St + Birchm-lane. Gough, Arch. 8, 1787 Pl. X (p. 123) fig 15 + p. 124

Fairly certainly a ~~coin~~ stamp not seen by me. Counterstamp A.

London [do. <sup>+ p. 124 no. 94</sup> do. fig 16] stamped along Counterstamp A.

Fairly certainly not seen by me. ~~Coin~~

London [CIL VII 1334, 16.  
do. Chas. Coombe + J. Jackson, Ar p. 127-132; p. 130

FLVGVDV not identified yet.

London [293 K no. no.] r. facing diagonally. BF 38;  
quite very fresh - smallish + small, abundant, grey,  
white + black flint. 9H A

London [TR 174 433 4K TR 1] r. fac. diagonal. no gilt  
on flange but gilt up to b. b. SK.

London [Guildhall M.; 224K] slightly sandy, cream fabric; cream surface,  
 internal scoring; medium to tiny, grey, r/b, black, white grit to bead;  
 smooth surface. D

London [Guildhall M.; 194K] l. facing; diagonally stamped; very thick,  
 pink core to cream very near surface and surface; buff in places;  
 internal scoring; medium to tiny, r/b, grey, white grit to b. b. D=14ins.  
 E. R. 343 on fragment. J

<sup>130 F E</sup> <sup>145 76</sup>  
London [Guildhall M.; 190K; 1937-254] sandy, pink fabric, tends to paler  
 near surface; surface probably pinkish cream; grit mostly worn away,  
 small to medium, to c.  $\frac{1}{2}$  b. b; r/b, grey, white; BF 38; D = 11ins; with  
 counterstamp. Die H

? ~~no~~  
~~COLLECTOR'S~~ ? ?

BM

London [C.R.S. Illustrations of R. London p. 89; C. L. on pot; 2K] cream buff

fabric with buff surface; 1 grey, flint grit on fragment; flange broken; B.F. 34 but  
bead slightly higher.

No Provenance

London [C.R.S. Illust. of R. London p. 89; 3K. British Museum] flange only; slightly

sandy, slightly pinkish buff fabric with brownish surface; stamp diagonal.

No Provenance

London [C.R.S. Illust. of R. London p. 89; 15K Brit. Museum] r-facing; stamp faintish;

some grit on top of flange; white, blackish and grey, medium + smallest grits to

b.b.; good amount; internal scoring.

No prov.

London [C.R.S. Illust. of R. London p. 89; 25K; Brit. Museum] r-facing stamped along;

slightly sandy, brownish pink fabric with cream surface (could be slip); grit worn  
away save a few, small, brown rhyolite grits. LVGD FEC. Δ A

ALBINUS

London [22a 12 B 8] \* Mary's Aldermanbury Flange bag.

Greenish cream fabric; brownish slip. Darkened to blackish  
brown in places. Within R. ~~at~~ R. London. A

## ALBINUS

London, Barge Yard, 1879 (Price Collection). Pitt Rivers Mus. BMD.

"Putty-coloured fabric with thin pink core; very fine angular brown, grey & white grit." Sketch.

London, at the corner of St. Mildred's Court, Poultry [ILMAS III, 1870 p. 218; (where Union Bank of London erected) ALBINUS, a good mortarium. Checked.

London [Dove Bros Collection now in Company Offices in Choudsley St., N.1.; ~~now~~] Complete vessel, slightly distorted.

London [20046 Bucklesbury Ho, Walbrook] 292K L. facing internal scoring; burnt round bead; hook splayed a bit at bottom.

London [R. XI. 627 Guildhall M. 174K] l. facing; slightly sandy, pinkish buff fabric  
 apparently; vessel restored); surface drab buff, pinkish in parts, black in others;  
 smallish grit, red-brown, white, black; stamped diagonally; D = 12 6/10; BF 34/38

London [M 2833; British M. 124K] SEE ALBINUS || EAVVIV

<sup>ing. thin</sup>  
London [M 2834, British M. 119K] diagonal; slightly sandy, pale buff  
 fabric; abundant, white, grey and brown grit to b.b; Typical B.F. 38;  
 D = 16" <sup>well scored &</sup> gutted inside; some scoring wide apart on flange but no grit

<sup>renew</sup>  
London [CRS. Unquarterd; bl faint. British M. 6K] r. facing; v. slightly sandy,  
 cream fabric with pink core; buff under head; (flint) medium, white, blackish grey  
 grit to head, few on flange which is smoothed; worn smooth below c. lin. b.b.b.  
 diagonally stamp. No grit on the flange.

## ALBINUS

London [A. 16877; F. Ransom Coll; London Mus. 5K] l. facing FLVSDL, v. facing

ALBINUS; given to museum 1915; but of flange broken and hole in base which is very thin; buff fabric with traces of slip, heavy wear; no. few small gints survive; blackened; B.F. 34. SK referred to in DdE ~~J~~

London, Cannon St [Nov. 1919; A. 20937; London Mus. 8K] diagonally stamped each side of spout; whole but for hole in bottom; heavy wear; pinky buff fabric; large to small, grey + brown gints. <sup>stent ch. "of a fine in DdE water book + SK"</sup>

London, S.W. angle of Wood St. + Gresham St [Deposited by L. A. Probert, 27, Watling St., E.C. 4; no. acc. no.; London Mus. 18K] seen by Suggett. "smooth

off white fabric; sparse largish gints; B.F. 34/38; D = 12"; <sup>see Aspiney 1954"</sup> Found 1/54. G

ALBINUS  
ALBINUS

stamped once only. 71. 133. l. fac. B.F. 38 button rounded bead.

ALBINS  
London, No 1, Poultry [Con. 18161 MusAcc. 5272] 434K] 85g

IRS stamp diagonal. Burnt. Greyish-cream fabric with black in parts of core. Frequent, moderately well-sorted, quartz inclusions with few o/b (opaque). Cream slip, fired a grey + brown-grey - parts. Concentric scoring inside. small to medium flint and quartz inclusions gut.

upto bottom of bead with flint and quartz. <sup>see also 1972<sub>n</sub> 3</sup>  
London, No 1 Poultry [Con 18089 Acc no 6434 435K]


refacing Diam 30cms. 130/ 170g. Burnt. Frequent, quartz & few o/b inclusions brownish pink, fired to cream at surface. orange buff slip. Concentric <sup>inside</sup> scoring! flint & quartz inclusions gut.

TRISH has not put Tut<sup>n</sup> gut arscarig  
inside

ALBINUS

London, Basinghall St [BAZ05 context 1912 <172> Pd2  
OA2 802K] VRW discoloured by context (covers fractures)  
vt. angles ALBINUS as die 5 but marginally larger. see report.  
for surmountage suggestions Concentric scoring. 90 grams  
Diam 320 mms 7%

London, Bow Bell's House [BBB05 Acc <1304> Context 142  
Pd 3 Open area 811K] diagonal; ? l/ac (change in bead)  
175 gms Diam 330 mms 10% VRW Clean chip fixed to  
orange brown in part. Concentric scoring upto b. of bead,  
mostly worn away.  $\Delta$  d. 12



ALBINUS

BBB05

London [Bow Bells House BBB05 <794> 2037 837K] Albinus r. fac

L. facing 1. fac. As Freese 1972, 9 & 10 3 joining sherds.  
 1020 gms Dr. 270 mm s 50% breaks modern VRW fabric  
 with unusual r-brown streaks in fabric; surface has been fired to  
 red-brown in parts. Very heavily worn so that concentric scoring  
 survives for only 1-5 cm below lead. The wear on the underside  
 of base is also clearly visible. A fourth piece may not be from  
 same vessel.  $\phi$ ;  $\Delta$  + plan.

London [BBB05 <150> 701 816K] L. facing and  
 stamped only once. 1094 gms Dr 310 mm s 31% 3  
 joining sherds = nearly  $\frac{1}{3}$  of a murrine. VRW fabric but pink-

but cream in parts  
brown: slip mostly orange-brown. <sup>Transparent</sup> Flint grit: qtz white & ~~transparent~~  
flint & occasional opaque red-brown. Heavy & continuous  
wear, concentric scoring curves only in area immediately  
below bead of worn so that a plug fell out of base. Wear  
clear on underside of base. Die as Freve 1972 no 2.

Saller's Hall.

hendon [Guildhall M; 18786; 192K] r. facing; stamped diagonally; sandy,

buff fabric, grey near <sup>to</sup> surface inside, in parts; surface buff; most of gnt worn away; much, r/b., white, grey, gnts to b; flange like BF 38 but head a little higher than flange. D =  $14\frac{1}{2}$  ins. Die as 171K. A

~~hendon [Guildhall Mus. R.XI.627; 174K] r. facing; complete but for restored patch inside; slightly sandy, pinkish buff so far as can see; surface drab buff, pinkish in parts & black in others; smallish, r/b., white, black, gnt, most gone in wear; diagonally stamped; D =  $12\frac{6}{10}$ . BF 34/38 B~~

hendon [Guildhall Mus. R.XI.616 Bowlane; GHC p102; <sup>(our ref. 175K)</sup> Arch. 63 p.324]

1 stamp each side spout both from same die; whole almost; hole in bottom; sandy, greyish fabric; gnt mostly gone, some grey; BF 34/38; D =  $17\frac{3}{4}$  45.5 cms. G

ALBINVS v. slightly diagonal old A+B 12+13  
London (BBB05 Bow Bell's House Context 1190 <367> 821K  
Pd 3 821K) Burnt before fracture. 2 joining sherds,  
break modern. Definitely the finer version of VRW  
Packed with tiny quartz, <sup>trace</sup> tiny opaque red-brown/black  
material. Intercation gut: gut packed over whole  
surface up to bottom & just over bottom of head & partly  
over it. Inharqth to tiny, flint, quartz. HAS NEVER  
HAD CONCENTRIC SCORING. Similar to 811K. On  
outside there are unusual shallow, concentric grooves  
at intervals of c 13 mm on the ~~outside~~ - these continue  
underneath the very deep flange, some wear showing at  
PTD.

bottom of shear:

6

ALBINVS

ALBIN // ALBIN

London, [BBB05 BowBells House Context 2043 Acc <801> Pd 2

AD 50-100/120 open Area 2 838K] 4750que Dr. 390mm, 100%

Worn through in centre base. Stamped ALBIN (+ v. but /  $\sqrt{v}$  /<sup>v</sup>).

<sup>i.e. wider wider</sup>  
Spout wears from norm for ALBINVS. Intonation worn away below  
c. 2 1/2 cms. below bottom of bead. VRW fabric. Greyish-cream

Intonation grit: closely packed flint, quartz with few red-brown  
(opaque). This is highly exceptional in that it had no  
concentric scoring. NB 821K [LVSD-FEC] was the same.

Worn smooth on base. It may have had a darker cream/buff  
slip aspects of the surface (not all) were fired to this colour

γ. Δ φ

Bucklersbury Ho.

London [Guildhall M. 18, 884; 54K] sandy, slightly greyish, white fabric with buff to orange-brown <sup>at</sup> outside surface; internal scoring; small, white, r/b, grey gnts; B.F. 38 with bead rising a bit above flange.

London, 18, Billiter St., [Feb. 1926; 1926-17-A; 66K; Guildhall M.] sandy, softish, brick-pink fabric; surface slightly pinkish dark buff to purplish buff; internal scoring; r/b, white, grey gnt to e.  $\frac{1}{2}$  b.b. broken flange.

London [1937-428; in other ink 14749; 92K; Guildhall M.] L. facing; slightly sandy; pinkish buff core to cream near surfaces; tiny to medium, r/b, grey black gnts to e. 1 in b.b. B.F. 3k but bead a bit higher. Assigned E

- London [1937.110; Guildhall M; 114K] sandy, grey fabric with buff surface; blackened under flange & on parts of top of flange; largish to small, r/b, grey, black grits; D = 13½ ins. BF 34. Die K
- London [19705; 113K Guildhall M] r. facing; sandy, grey fabric; drab cream to buff surface; grit worn out; BF. 34. Assigned E
- London, Blossom's Inn Yard [1930.105; Guildhall M; 136K] l. facing; sandy, greyish fabric, with blackened surface in parts; few, smallish, grey, r/b, & black grits. BF. 34. Assigned H
- London 112, Fenchurch St. [1923-19; Guildhall M; 225K] pink fabric changing to cream near surface; most of grit gone; grey r/b; D = 10½; BF. 34. Assigned H

## ALBINVS

hondon [Guildhall M. R. XI. 646; 239K] <sup>nt facing</sup> stamped diagonally; slightly <sup>ALBIN probably</sup> complete; gilt v. fresh & abundant.

sandy, dirty cream fabric with pink core; prolific, white, grey, black gilt to bead. Nearest 165K. hooks early. B

hondon [19524 Guildhall M. 2K] <sup>Bucklersbury Ho. Site; Walbrook</sup> l. facing; sandy, grey fabric; smallish to tiny, white & grey gits; internal scoring; D = 10½ ins. G

hondon [Guildhall M; no. no; 55K] <sup>Assumed</sup> sandy, orangy fabric; drab surface; dark grey on outside. ~~Bucklersbury Ho. position not noted.~~ B

hondon [Guildhall M; 18,864; 58K] r. facing; sandy, creamy buff fabric, grey in parts; buff surface slightly pinky in some places, orangy in others; internal scoring; some, white, grey, r/b gits to near b. b.; flange broken. Bucklersbury Ho. K

✓ \*\*  
Found in London

London [C.R.S. Collection 1856; M. 2766; C.R.S. p. 89; CIL VII, 1334, 4a; British Mus. 56K;

9/12/12] stamped diagonally; very slightly sandy, greyish cream fabric with orangy buff slip; abundant, white, brown, grey, large to small gut to b.b. D = 15 1/2; B.F. 38 with typical underflange. sketch. Jii

London [C.R.S. <sup>London in new notes</sup> ~~West of R.~~ London p. 89; British Museum 59K] L. facing, diagonal; cream fabric with thick pink core; abundant, white, grey and brown (flint mostly) gut, medium to small to b.b.; internal scoring. no gut scoring on flange B

London [C.R.S. <sup>CIL VII 1334, 4a</sup> ~~West of R.~~ London p. 89; M. 2767; British Mus. 73K] L. facing, hard, greyish fabric and surface. NO purple green. K

London [Satchell's Sale 19 July 1848; M. 2769; 48/8/5/54; <sup>CIL VII 5a</sup> British M. 74K] L. facing, slightly sandy cream fabric; gut worn away save few, black, brown, grey, medium to small gut to b.b. Seeover G


74K Walter does not say where found.

ALBINUS  
London, No. 1 Pottery [con. 17895 Mus Acc 6374 431K] IRS

55g. friable. Smoother than usual + probably fine-textured  
but usual frequent quartz inclusions; fabric is brownish-  
pink. Surviving flange smooth. Remained conc.  
scoring b. bead. Few tinturation spots left: flint  
and quartz. ALBINUS likely to be r. fac. d. 5.

London, No. 1 Pottery [con 8727 Mus Acc 2784 432K]

Probably l. facing. FF. 220g Diam. 33cms. 20%  
Surface very smooth. Frequent (probably not as frequent as in other)  
quartz inclusions, mod. well-sorted; few larger o/b inclusions.  
greyish-cream with very thick pinkish core. d. 6.  
buff slip. l. likely to be l. fac.



ALBINUS

- 22757 Scoring inside, not on flange; Kings Arms Vd.  
London [E.R. 455 Guildhall M. 254 K] stamp each side;  
almost whole; greyish cream fabric; brown, grey & black grit. K  
London [E.R. 241; Guildhall M. 256 K] ALBINUS || FLUSVOR; sandy,  
greyish cream fabric with cream slip; very worn inside; grit gone in  
lower  $\frac{2}{3}$ ; some, grey & brown, tiny & small survivors near b. b.H  
London [E.R. 546; River Gravel; Guildhall M. 254 K] stamp v. faint;  
sandy greyish cream fabric with buff slip; scoring inside;  
tiny, black, grey, brown grit. ? ? ? ? ?  
London [Aldgate CASS 72 (4) 9H] H. Chapman. 326K  
flange packet

ALBIVS

Enfield, Mdx [Bush Hill Park, Enfield Settlement

TO3412595642 13K] L. facing 398gms. Diam 350m  
17% CR fairly typical VRW. Slightly granular, cream  
fabric with a thin pinkish layer near surface at spt  
end where it may be slightly thicker, packed  
with inclusions very moderately sorted, mostly quartz  
with some black & rare red-brown material.

Some tiny to small, flint & quartz fragmentation gut  
survived in combination with <sup>summed</sup> concentric  
scoring. The scoring is worn away by the bottom

P50

of the shard. Burnt inside before fracture,  
with some scorching on the flange. d.5  
Report sent to M. Deane, December 2016  
TOPSOIL

ALBINVS

Enfield, Mddx [~~Not~~ Not seen. Rubbings and drawings  
from Martin Deane. 1915] ALBINVS. From same die as  
Trene 1972 Fig 145, no. 7. L-facing Enfield Mus.

Dafford M. [provenance unknown; found in Mus. with DOWNS<sup>55</sup> (167)]; buff fabric but showing very pink in break in places; fairly coarse texture; sparse, small white, brown + grey (flint?); some rubbed out; most lying in upper 1/2" inside, up to rim; a few on top of rim; pink-orange surface. internal D = 11". G

Buxton M [M. Holmes Collection, probably local BK; part of flange; 34/38 BF. L facing; diagonal, sandy, grey creamy fabric. K  
London (findspot not known. Donor w. Sharp Ogden. In Manchester Mus. R838)] v. worn, had hole in bottom; sandy, creamy buff fabric, probably had cream slip; surface orangy in parts probably due to firing conditions; small, white, brown, grey grits. r. facing. D = 11 <sup>3</sup>/<sub>10</sub> in. Almost whole. BF 34 but more intumed at bottom of flange + FLVAVDV counterstamp.

Colchester M [7236.27; 410K] stamped diagonally; slightly sandy, pinkish fabric, slightly

more creamy, top surface, burnt orange quite extensively outside body; large to small, red-brown, black, white grit, fairly prolific to b.b; worn away in bottom. <sup>YGD-FEC</sup> A

Colchester M [no. no. 281K] <sup>May 2</sup> slightly sandy, pinky brown fabric, more cream at surface but tinged with pink; traces of nilling; a few large, mostly small, brown white and black and grey grit to b.b. Nearest B.F. 34. D=12 1/2 ins. sl. diagonal

l. facing. B

Colchester, Holly Trees Drain <sup>May 1</sup> [310.97; 344K] v. slightly sandy, pinkish cream fabric; large to small, whitish grit to bead. Near BF 38. r. facing. G

Colchester M [85.35; 383K] sandy fabric, greyish core to orange, but cream surface with orange or buff patches; flange & bead only; stamp appears to be complete. C

ALBINVS

344K Colchester

x

ALBIN

383K Colchester, M.

x

# ALBINVS

No 1, in Paul's list.

Malton [MA 70 (317), Bag label (159) 20K] Flange Fragment,

r. facing. [Frere No 11A VER I, fig. 45] Granular, greyish-cream fabric, frequent inclusions quartz with sparse red-brown fragments. No trituration grit survives.

Carlisle, Annetwell St. [SF72. C78/69<sup>red</sup> C78/66<sup>blue</sup> 1096 127K] D<sub>u</sub>.33


granular brownish fabric with frequent quartz inclusions; slips black on top & angry brownish red under flange. Fabric unusual - ? in a cuspit.

NB. Pat says C78/66 Note on bag says Probably from (69)


Carlisle, Abbey St., Tullie Ho. [Drawing only na BMD]

not seen.

Carole, A. Esbey St. (Tullie Ha)



20/5



20/5

ABIN

pale  
~~slip~~ brown

Baginton, Warks [no no. on piece. 1968] Sampled at Oxford. Sandy /

~~buff~~ cream fabric with <sup>orangey</sup> brown slip, still buff towards outside of flange.

1 red-brown grit; one white + 1 flint on top. 23K

Vendarnium [60 A.T. ⑤ / 1. 272K] flange + bead. Sandy cream

fabric with very thick brownish pink core; cream slip; with

superficial burning on top of flange turning surface greyish or

grey + white in places; concentric scoring; flat red-brown grit

scattered on top of flange. v. n. III no 55 (2)



Baqinton.

ALBINUS

Richborough [ex Merseyside County M., Liverpool. C. Roach Smith,

The Antiquities of Richborough, Reculver & Ynne in Kent.

(London 1850) p. 64. "The potter names on the Richborough  
-ware are Albinus + Q. Vs Veranus. 70<sup>37</sup> M  
(ex Mayer Collection) r. facing. Slightly sandy brownish cream  
fabric with terra cotta like slip; gilt, worn. Gilt scoring  
on flange. Waste crack (slight) across back of spout or  
behind stamp. Transparent quartz + red-brown gilt. The  
fabric is very fine for Brockley Hill + could have been  
made somewhere else. (ex Mayer Collection)

ALBINUS

19K

Melaudra Castle [MEL <sup>Trench</sup> T 34 E. Rampart Context 34

Burnt material underlying 17 + 22 + overlying 32.

715 gms Diam 280 mm s 27% + 38% VRW.

5 joining sherds (4 flange & one body + bead. 1 flange fragment has the abraded ALBINUS stamp with upper

border. 1 P [surviving]; 2 large joining sherds with

presumed counterstamp too damaged to read but seems to have a V. Some blackening on part of distal

end of rim. All sherds probably weathered & probably

well-worn = Not to be taken as ~~gilt~~, Same die as Hemel

Gradebridge villa, Hemel Hempstead (D. Neal)

ALBINVS

Mantana made in Colchester only

Adolfabuc

Colchester [P5632 BKC J435 Tz 77 S15] v. facing. Dr. c. 280 AD <sup>Δ</sup>

Here with an unstamped fragment from the same or a similar  
material. Die as Freese 1972, no. 2

Check 2K Merseyside Museum.

Fort Maucette Village [MCT R76-11. K. Scott Maiter House Farm. Die H. A. ② W6.]

Coarsular cream fabric with brownish buff slip: heavy quartz tempering, no grit <sup>or conc. scoring</sup> in flange; concentric scoring inside + fine grit inside upto bead; flint, quartz, red-brown ls bottom of bead.

Netherfield, north of Battle, Sussex. [information from Randall Bingley, ~~Gweys~~ Thurock Museum, Gweys.] L. facing striped along. Gweysish cream fabric much quartz + a little v/b. Temper - but not packed; smooth on flange; some concentric scoring inside.

## ALBINVS

Hambleden Villa, Bucks. [Arch. 71 p 188, fig. 19, no. 1, 4K Aylesbury M.] slightly

sandy, grey cream fabric burnt grey in parts; internal scoring; some, small grey and black + white grit to bead; worn away completely towards bottom. D = c. 12 ins. B-F 34 a very close parallel. J ~~E~~

Hambleden Villa, Bucks [Arch. 71, p 188, fig. A no 2; 3K Aylesbury M.] may possibly belong to 2K F. LUGUDV; stamped diagonally; slightly sandy but surface smooth; grey cream core changing to creamy pink. J?? E

Hambleden Villa, Bucks [Arch. 71, p 188 but not referred to. unpub.; 19K Aylesbury M.]

fragmentary; L-facing; sandy, pink core, changing near surfaces to creamy buff; Brockley Hill type fabric; internal scoring; small grey, black, white, brown grits to b. A stubby B-F 34. G?

ALBINUS

31977/290 (300)

Cremit ground in pressed in the 12.

Wanborough, Wilt's [B. Walter. 11K] / Cream fabric with deep salmon

pink, thick core; sandy; brownish buff slip; white + red-bran  
+ grey grit; slightly burnt on flange. Unusual form for Albinus.

Die as no 11 (Veri.) (D) worn

Godmanchester [PL 5.27.4 [2] 3K] l. facing. Stamped.

diagonally. Sandy, cream fabric with pink core; flint, grey +  
white plus one reddish grit. Die B name die. Worn in lower A  
part.

Wall, Staffs [W10/7/1 35K] l. facing. Diagonal; internal scoring; flint, grey

+ white + quartz-like grit; sandy, cream fabric with pinker core + orangy  
buff slip.

VITINU AT AE

A B

\* Yorkshire Museum [36K] buff surface, sandy buff fabric, box. 34.

? ALBINUS

(Banded  $\neq$ ) J. ~~not assigned~~ ~~E~~

Leicester [T.L.A.S. xxxii p.90; 435.1955] 15K; found at Northgates.

(Banded  $\neq$ ) J. Assigned ~~E~~

Verulamium [56 B. III d(48)] coarse greyish white fabric 10K. ✓ vol III, b1 (9)

Verulamium [56, H v(20)] <sup>14K</sup> or pinkish orange fabric changing to cream with

tiny particles in fabric; prolific small grits + rilled; qnt up to rim J  
Chester [Infirmay Field 451 (IF4); Box DB; 39K]; hard, buff fabric with pinkish

core, cream slip. Stamp as Yorkshire Mus + Ver. (20) J. 7  
Fig. 2, no 1, p. 3 J. Chester on Wales Archit. Arch. Y.Hist. Soc. vol. 49 (1962) check literature in the one.

F L V C V D I

3615 Yorkshire Mus.

$\frac{1}{17}$ .

out V C V D I in  
Verulamium m'56 (4. 11c (48)) 17

out V C V D I in  
Verulamium m'56 (H v (40) (157)) 17

Ribchester [RIB 78 BFH 1 44K] L-facing. About  $\frac{1}{4}$  of upper part in granular, very greyish cream fabric faced with quartz grit; brown-buff slip; conc. scoring inside but not on remaining part of rim + probably not at all on the rim. Hint of quartz small + tiny titivation grit to bead. shallow scoops for spat, no keying. D. 32cms.

Ribchester Graveyard [RBG 80.012 49K] stamp diagonal. A small piece; granular pale greyish fabric at surface with fabric blackish to near surface; filled with quartz inclusion combined with concentric scoring. Age smooth. small quartz titivation, small; upto 6.6. No grit or flange on this frag. but may be too near bead.  $\leq$  30cms

F. LVGUDV

Leicester, Cullens Warehouse, Chantry Ditch surface; in box numbered

20.1939; 105K] fine, creamy pink, sandy fabric; white & brown grit; B.F. 34/38. H

Bourne, hinc [G.S. 1959] r. facing; counterstamp only. In hincolu  
M. slightly sandy cream fabric with thick pink core; one or two  
tiny grey & white grit. H

Templeborough [w.v. Wade 1948 13K] dirty, pinky white cream, sandy,  
fabric. K

Wchester [May p. 241 no 8; Culver St. no. no. 415K] coarsish, sandy;  
pink core & greyish white surface; darker grey on top; flange only. J<sup>2</sup>

## ALBINVS

✓  
Silchester [May, pl. LXXXIIA, no. 1, + p. 275; 12K] l. facing; dirty cream,  
 coarsish fabric with buff surface; some white, black, grey, smallish  
 grits to b., but most worn away entirely. K

Silchester [May, pl. LXXXIIA, <sup>misread as NARRINVS</sup> no. 10 + p. 296; 13K] r. facing; greyish white,  
 slightly sandy; surface same colour but blackened towards spout; most  
 of grits worn away, few black, r/b, grey, smallish. D = 9½; BF 34 H

Silchester [May, pl. LXXXIII A, no. 2 + p. 275; 14K] coarse fabric, pink core  
 changing to buff very near surfaces; buff surfaces; medium to smallish, grey  
 r white grit to bead; much gone; traces of internal scoring; different vessel,  
 stamped diagonally. D = 12 ins. B

F. LVGV DV

? 2 diff stamps.

Verulamium [IK v.A.N. 33p273  
A. vol. 90, p123 no. 4]; slightly pinkish, sandy fabric, to cream surface  
thickish grey core; frequent off-flange (not in index) ~~Buried F. <sup>g</sup>~~  
~~Call. C. no 619~~ ~~FLVGVDV~~

Leicester [p 214, + p 216 f. 58 19 + 15] a. a fragment; b. part of a rim from a hook-  
rimmed mortar; hard, reddish fabric with cream wash on rim and exterior.

Birley have attributes FLVGVDV stamp to ALBINVS alone (LANA) <sup>K</sup> 16 J

Leicester [Keyon, p 220 no 20 not illustrated] [L] V G D V F E C assigned by B<sub>2</sub> to  
MARINVS. On large & boldly modelled fl. hook-rim, hard, smooth light buff ware,  
with large variegated glaze. — see ALBINVS ]

FVCG

Verulamium

Arch. 90, p. 123

no. 4

From red dentils  
wash layer

c. A.D. 55-61

FVCG



FVCG

( $\frac{0}{4}$ )

Laicester.

## ALBIVS

Wroxeter [1912, p. 16, no. 1, 105K] coarse, sandy, orange-buff fabric in flange, grey to orange in body section, surface drab; yellowish brown slip; <sup>clay</sup> filled inside, medium & small black & white grit up to bead. no. M no. J

Wroxeter [1913 p. 46 no. 1, (M 70, 9K)] Type 38; sandy, dirty cream fabric; grit on flange red, white, black; flange fragment. Die as 6K. ALBIVS || F. LUGVDU D

Wroxeter [1913, p. 46, no. 1 M 103, 6K] Type 38; sandy, white fabric, little white, brown, black grit, some on top of rim. Pit 33. ~~ALBIVS || F. LUGVDU~~ D

Wroxeter [1914 p. 61, no. 1, M 116, 8K] Type 34, yellowish red, sandy fabric; internal nothing; white grit and a little on rim. Pit 32. Die as 105K. ~~ESJ~~ J

AIBINVS

7 1/2

Wroseter 105K.

AIBVA <sup>end  
not  
imported</sup>

M103, 6K Wroseter

1/2

AIBII

M116, 8K Wroseter

1/2

ALBINUS

327

Staines [BBS 69 B~~K~~ 3 52 2K] r. facing slightly diagonal;

well-worn, matanium in oatmeal colour; reddish patches on surface; flint + red-brown grit. buff slip <sup>No scoring or flange.</sup> Dv. = 5.40 cm. A

Staines [M + L T5 13K] Mumford + Hobbs Below

Gravel layer. Stamped each side ALBINUS || F. LVGVDV

Both slightly diagonal. Granular cream fabric and slip. A

Staines [CAD 77 A 8 19 Pit. 32K] Crawla pink


fabric with thin cream core.

# ALBINVS

Alcester [65, LXII (7) Mahany-17K] flange fragment. Cream fabric, hard; contains much small grit. Prob. F

Alcester [64 C. IXA (17)] stamped diagonally; sandy, cream fabric with very very thick bluish sea black core; surface grey on outside, grey ~ part of inside, & pink in one part. Firing was probably unusual but could have been burnt as well. D = 11 1/2" 24K. Frases of internal scoring but irregular; cream slip; white and grey smallish to tiny grits. B

BAWIA. Counterstamp's of ALB IN VS.  
same form as E.36. P.3 ALB IN (2K) but not same vessel. <sup>position used</sup>  
Wroxeter [Rowley Ho. E.20. P.2. p.281, fig. 40. no.3; 2.7.K.] greyish cream to grey  
at bottom of flange. In body - inside half - dark grey to pinkish buff in  
outside half (flange); <sup>discoloured.</sup> prolific, small and medium grit to c. 1/2 in below bead.  
Venulamium [1933, v. A VII '4' p. 60(4) 117, 84 K] tracing of PR's  
rubbing] d. = 12 1/4; drab fabric; stamped almost parallel to bead.  
Leicester [9K Sarah Street unpub.] orange fabric, sandy, cream slip;  
mixed grit. Grit like ATTIC. (See Leicester)  
Silchester [May pl. lxxxiii A, no. 11; 24K] r. facing; stamped diagonally, sandy,  
pink core changing to cream; drab cream on top of flange, buff outside,  
under and inside; prolific, largish to tiny, grey, r/b. grits to b. b. D = c. 11 ins.  
label SOH 11 VE no 19K Silchester.



## ALBINS

Waist - by - Nainich [D. Atkinson 1961] r-facing; along, slightly diagonally; sandy cream fabric with thick sandy salmon pink core & a brownish buff slip; gut worn away below about  $\frac{1}{4}$  b.b.b; small, flint + brown guts immediately below bead. D =  $15\frac{1}{2}$ " ; deep finger depression from back to front of flange for additional clay for spout; unstratified. A Wall [WL/580/6. Gould 1963] sandy, greyish cream fabric; surface near bead burnt dark grey to black; medium + small, white, & grey gut in uppermost inch; worn away below.

Ratchiff-on-Soan, Notts [RAT. 274. M.S. 1963. E. Greenfield] stamped diagonally, minute skin of cream fabric with white & core pink; sl. sdq; buff slip, mostly gone; internal scaring, some flint gut little gut in fabric.

ALBINUS

Roecliffe, nr. Boroughbridge, N. Yorks [WD 93 14005] FV 103 IK] Dr. 31 cms.


Lfac. Brownish cream fabric, faded to cream at surface, with buff-cream slip. Inclusions: packed with quartz, rare <sup>larger</sup> red-brown.

Intonation: flint and quartz <sup>scrapers</sup> up to top of bead. Surface as smooth as the inclusions permit. Probable traces of concentric scoring inside. Too close to spot to know what happens on flange. Die 2 AS

Netleton, hks [SH 93: 4919 IK] IRS. Worn. Greyish-cream

fabric with <sup>a little</sup> ~~some~~ pink in core. Abundant, quartz inclusions, v rare vlb.

Intonation worn away. Found in field-walking by Phil. Cath<sup>er</sup>all, British Gas. Temple site. Sent by Ruth Burss. Die as no. 8 in Ver. 1972.



ALBINVS

SITES IN SCOTLAND

~~Castle Dykes [R. Occupation of S.W. Scotland] hard white clay~~  
[R. Occupation of S.W. Scotland] hard white clay

Feb 1950 V.

~~[NMA, FX 232 - no. no. E.B.]~~

~~Barrhead - Irons Glasgow A.S. p. 15 XIV p. 15 MARINVS~~  
~~Its bowl has to be from a set of (ALBINVS)~~

heister [Kenyon p. 220 not illustrated] [L] VGVDVTEC assigned by B<sub>2</sub> to MARINVS;  
on "large & boldly modelled Flavian look-ism," hard, smooth, light buff ware,  
with large, variegated grit; unpublished as MARINVS. A

NB. Mortaria in Rowley's House - E 20 [~~E 8 in kept~~ has the stamp published as Fig. 40, no. 3 and entered as E 8.

E 44 in museum has stamp [Fig. 40, no. 10] entered as E 18.

The ALBINI and HVGV DV stamps are correctly entered and it is possible that only 5 pots are represented. 4 ALBINI and the 3 HVGV DVs are from the same die (S:). The other ALBINUS a different die.

ALBINS

~~Colchester [May, p. 241, Pl. I, 101]~~

~~Bank of England [E. Birley, 1929, a ... of ...]~~

Colchester Museum Rept. 1913 p. 31;

Colchester Museum Rept. 1924 p. 15; reddish ware, buff slip. } hose  
Up.

~~Sitchester [May p. 275, Pl. LXXXIII A, 1];~~

~~Sitchester [May p. 275, Pl. LXXXIII A, 2];~~

Gillingham Regional Museum. Complete. ? brownish fabric

ALBINV

(1) sichester p 715

ALBINVS

COLCHESTER p 715 (L) V

ALBINV

(4) sichester p 715

ALBINUS

M.I.

P4297 S7 2

Colchester [LWC79 Δ1337 B617 605K] diagonal stamp. Dr. 39cm.

Burnt. Granular, (greyish-cream) fabric with very thick black core changing to thin pink & then greyish-cream skin; flint & quartz inclusions. Dr. 39. This appears to be S7. A Δ

Tiddington [RW22 no. 218 M528] r. fac. die B. Cream fabric (no Munsell equivalent), with pink core; quartz inclusions, occasional black fragments, micaceous. No trituration survives, but quartz and red-brown fragments on rim. Dr. 31cms. (Paul Booth Fabric 7) B position not noted see NOTE

ALBINVS.

Alchester, Oxon. [Ant. J. XII, pl. XVI, IV + p. 61; Ashmolean M. 5K] stamped

along; sandy, cream fabric with buff slip; gilt worn away but a few tiny, white & grey gits just below bead. A

Provenance unknown, Ashmolean M. 40K; whole save for hole in bottom; sandy, probably greyish cream with cream slip, mostly worn off; little white, grey & black gilt survives just below bead; rest worn away; sketch.  $D = 10\%$  l. facing; 1 stamp only in mortar. G

Provenance uncertain but possibly Rochester [no. no. Stoke M. 5K] l.

facing, slightly diagonal; slightly sandy pink with cream slip. C

## ALBINS

Wroxeter [Rowley Ho. E. 46. P. 18; p. 278 1K] pink buff core, changing to creamy buff near surfaces, sandy, small brown <sup>flint (grey)</sup> & grey grit. + occasionally a colorless grit. Diagonal stamp; beq. imperfectly impressed & broken; Pit 12. Same vessel Jain VANNACA 25K. [E 18 in Rept]. B

Wroxeter [Rowley Ho. E. 36, P. 3, p. 278 2K] hard, fairly smooth pinkish buff core changing to cream buff near surfaces; buff slip(?); prolific, small & medium brown (rarely,) grey and white (? flint), inking; diagonal stamp, not completely impressed. Pit 14. Is not on same vessel as VANNACA 27K. B

Wroxeter [Rowley Ho. E. 40. P. 19, 4K p. 278] rather coarse, sandy pinky orange fabric changing to cream buff near surfaces; diagonal stamp; buff slip(?) near Wrox 34; flange only. J

BIMVZ

1K Rowley House: E.16 P.18 1/2

ALBIMVZ

2K Rowley House: E.36 P.3 1/2

IBINVS

4K Rowley House: E.40 P.19 1/2

Wroxeter [iii G3. no 50] on T.34. M124, 52K; buff & grey fabric, dark grey to black

under rim and outside. Same die and shape as 51K. not Y or Δ NA

Wroxeter [Rowley House E33, P.8. (M2, p279) 9K] Very small fragment Wrox  
34/38; coarse greyish cream fabric; stamp broken at inside. D

Wroxeter [Rowley Ho. E34, P.10, p279, 10K] rather coarse, sandy fabric, under  
half buff creamish, upper half greyish cream. D

Wroxeter [Rowley Ho. E32, P.11. p279, 11K] coarse, greyish white with  
internal rilling, grey & white (?flint) up to bead. Shape as 2K,  
broken on flange at outside. D

50  
LVCV  
K E32

LVL

10K E34 Pio Rowley House

111  
LV

111K Rowley House  
E32, P11

Ratcliffe-on-Soar [RH 63-193 2K] Stamped diagonally. Dr. 37<sup>1/2</sup>

Granular greyish cream fabric with pink core. No scoring on flange but clear on inside combined with flint and quartz tituration. Fabric is packed with quartz temper. [Freve 1972, fig. 145, no. 6 <sup>A</sup>fordie]

Herester [<sup>A</sup>475. 1979 (21) / 43] F || (21) 205K ] ~~probably~~ v. fac. Worn. granular pink fabric, fired to cream at surface packed with whitish quartz Dr. v/6 inclusions; surface smoothed but does look as if it has had concentric scoring; internal scoring surface survives at top but is worn away below  $c. \frac{3}{4}$ "; tituration grit quartz, red-brown + flint. IRS. Burnt.

## ALBINVS.

Richborough [ii, p. 94, 8(A); M. 8; 11K.] unstratified; soft and smooth, cream fabric with buff tinge; some small greyish grit, not on flange. r. facing. B.F. 14/18. NS Is this really ALBINVS. E

Richborough [v p. 251, no 8(B)? unpublished; 40; 62K.] sandy, grey-cream fabric; about B.F. 34 flange fragment. NA

Richborough [unpublished; counterstamp A; 43; iv/1; 63K.] west of section 47 above burnt layer; sandy, burnt black throughout in many places; in some parts pink fabric; probably B.F. 38; flange fragment stamped diagonally. A

Richborough [unpublished. VA area, M. 24; 80K.] pink core changing to cream, heavy internal scoring; pebbles, white, brown, grey grit. D = 1/4 ins. G

F. LUGVDV

~~heicester [3279-1884] [42K-Sr. Martins] hard, sandy buff, rilling, sparse black and white  
git. ? Ch. Moved to AVGVD~~

~~Thurston, heics [5K unpub?] sandy, yellowish buff, rilling; sparse white <sup>Die K</sup> git~~

~~heicester, The Newark [Trans. L. AS. v. xxviii, 1959 p. 2.6 no. 4.] misread  
as. G.IVCVNDVS~~

Chelmsford Mus. [provenance not known but probably near. 3K] no. 192 on pot.

Creamish pink fabric; internal scoring; some, large to small r/b, white  
grey grits; worn. D = 12 1/2 ins. Stamp diagonal. Assigned (E)

Maidstone [Charles collection; Coll. Ant. i, p. 149; 11.30; information P. Suggett]

sandy, <sup>greenish</sup> drab fabric; ~~BF. 38~~; internal scoring; black, white + grey git. Δ

D

ALBINUS

Easton, Lincs [drawing sent by Mrs Wilson, Lincoln] B?

Manchester [249] Mc 72 + 99 140 B 9K] cream fabric.

Drawing, no rubbing,

Manchester [10K. Mc 72 + 66] rubbing. Spander  
cream fabric

Wall, Staffs. [W12/3/2. 45K] rubbing. fragmentary stamp  
top of BINV - die not assignable. Greyish cream fabric,

blackened on inside + partly on flange - surface elsewhere,  
brownish ochre, & perhaps ash; few, tiny white + brown  
bits surviving. Dr. 30  
cms.

ALBINUS

Caerleon [1954. 54.3898.P15 NMW 111K] fragment; sandy cream.

Caerleon [1963. A.180. NMW 112K] r<sup>1</sup>acing. counterstamp. sandy, cream fabric + slip; internal scoring; small, grey, white + a little translucent grit.

Caerleon [P.S.A.L. VII (1876-8) p.221] ALBINUS || F. LVGD. Di. = 10". This is the counterpart of one which was found at Usk... when diggers the foundations of the new gaol. The potter's mark was the same on both". Check IL VII 1334 no. 5(b). to see whether Usk or Caerleon]

Melander Castle [66 A13 (2). 13K] L-facing, diagonally placed worn stamp. ~~fine~~ cream fabric with pinkish core; 2 indeterminate grits. Slightly burnt.

Chester [CA 5 xxvi, p. 34. <sup>8K.</sup> mis read as MARINVS] rather sandy buff; internal rilling;

very sparse white and brown grit, some on rim.

Cambridge Museum [2K no. provenance given] Albinoid rim; coarse whitish buff.

Red Oxon, Cambridge [pinkish buff fabric with sparse, small white and brown grit. <sup>FLVAVDV</sup> ~~FLVAVDV~~]

Wall-Rentery [Site this 10K] sandy, pinkish buff fabric; v. worn inside; grit worn

away - ~~W 2 34/38~~ - ALBINVS || FLVAVDV A

Alchester, Oxon [1928; A.J. xii pl. xvi no. 5] Ditch 2, under tower. <sup>Proba 2</sup>

cl. A. The latest pottery ditch is Trajanic with nice <sup>much</sup> ~~cl. A~~

th. ca. AD 100.

Caistor by Norwich  
Brendall, Norfolk [58K Norwich Museum. D22; 258] sandy pinky cream to cream

surface, buff slip, small black? white grit; rilling; stamp diagonal. Sketch. C

ALBIN V C

8K Chester (no prove).

C D I

ALBIN V C

B I N

8K Caister by Norwich.

C D N F E O

On opposite sides of spout.  
Cambridge Mass.

Hambleden Villa, Bucks. [Arch. 71, p. 188, fig. 19, no. 6] 2K. Aylesbury M.; J  
 sandy, creamy pink fabric with cream core; flange only; diagonal; possibly belongs with 3K but cannot be certain.

Hambleden Villa, Bucks. [Arch. 71, p. 188, fig. 19, no. 7; 1K Aylesbury M.] sandy, pink fabric changing to grey cream near upper surface but pinker underneath. Traces of creamy buff on surface - ? slip or due to firing; internal scoring; median to small, white, v. dark red-brown, grey grits. D = 12 ins. but flange marked in 1 place; does not seem to belong to either of ALBINUS stamps, diagonal; L-facing. J

Margidunum [v. CH. NOTTS. II, p. 17; Arch. J. xxxv, p. 290] JGV DV <sup>check whether should go in</sup>  
 East Bridgford, Notts (parish?) ← [h] guda [in factum] <sub>LVGVDV</sub>

F. LVGV DV

Silchester [May p. 235 Pl. LXXXIII A, 9]

Duplicate - crossed  
out in pencil

Wroxeter [II, fig. 3 no 50]; ~~2000~~ on T. 34. 117M, 51K; sandy buff fabric, pinker  
on lower part of inner surface; worn; signs of filling; small to medium red brown and white grit

Brockley Hill [LMAS x Part. II fig. 113] rough, cream coloured  
with grits on rim.

Q Rutilius Ripanus die 3A  
KH Oct 2020

~~Brockley Hill [LMAS II Pl. II fig. 113] buff ware, yellowish  
surface~~

~~Richborough [II. p. 95. no. 10(A)]; grey ware, pale bluish white surface,  
mixed grit in flange.~~



LVGDA  
Rich. II 95  
no 10(A)

LVGV  
no 96

LF.LV.LVL

503 Wrexler.

VH

## ALBINUS

Wroxeter [Rowley Ho. E 28, P 13, <sup>p. 278</sup> 5K] sandy, greyish cream fabric; buff slip (2)  
 Flange fragment, v. near W. 34; beginning of stamp insufficiently impressed.

Wroxeter [Rowley Ho. E 29, P 9 <sup>p. 278</sup> 6K] rather coarse, greyish cream fabric +  
 surface, 1 piece red gnt. in <sup>fabric of</sup> fragment; beg. not fully impressed; die as 5K (ALB) no 7

Wroxeter [Rowley Ho. E 31, P 6: p 278; 7K] rather coarse, greyish cream fabric,  
 yellowish staining underneath; flange fragment. Die as 5K ALBINUS; nr. W. 34.

Wroxeter [Rowley Ho. E 30; P 14 + P 12, p 278, 8K] 2 frags. joined; rather coarse  
 greyish cream fabric, very worn inside; some flut in fabric + 1 in interior, sign  
 of rilling; beg. not fully impressed, same die as 5K ALBINUS; nr. W. 34.

Wroxeter [1944 p. 611 no 11] On W. 34. NOT seen. NA

ALBIN<sup>in</sup>

Rowley House 5K E 28. P. 18  $\frac{1}{2}$

## NOTE ON ALBINS

Wroeter - Bushe-Fox Reports. The different stamps at Site Museum cannot be satisfactorily sorted out according to the reports, i.e. it can't be said in which year which one was found. 1 stamp mentioned in Reports has not been seen probably a 1914 one, possibly 1912. Sorted rather arbitrarily on cards.

Checked.

## ALBIVS

Chichester [CH/82 | EP pit ASI  $\triangle$  248 : 7k] 2 pieces joining, r. + l.

facing stamps. Cream fabric, granular texture; abundant inclusions quartz, sparse red-brown fragments and flint with occasional clusters of red-stained quartz grains. No trituration grit survives.

Dr. 26 cms. Dies as Vaulahin nos 7 and 8.

Chichester [338 CH/78 | CH 123 County Hall. 8k] 1-facing stamp

joins piece <sup>Verul. I no. 2</sup> 331 with right side of spout. Greyish-cream fabric

with granular texture, abundant inclusions quartz, sparse tiny black and orange-brown fragments. Trituration grit flint with

some quartz. orange-brown slip which is slightly micaceous. Dr. c. 44 cms. Little if any use. Concretion showing complete inside.

F. LVGUDV.

Silchester [May pl. LXXXIII A no 9; 10K.] fragmentary; ? overfired, black

core changing to pink, + greyish cream surface, black comes through occasionally. Much white, black, grey, smallish grit up to top of bead.

BT-38 with rather high bead.

~~Atterbury~~ (E)

Silchester [May pl. LXXXIII A, no. 8; 21K] L-facing, slightly sandy, dirty cream fabric with buff surface; much, large to tiny, r/b, white, grey grit to top of b; type as 12K [ALBINUS] but bigger.

Die K

Richborough [v unpublished. Site M. 95K; 112; Stray, Area v.1] diagonally stamped; flange fragment; slightly sandy; cream fabric with pink core and buff surface.

J

Fenny Stratford [3K H. Peugelly 1970. MSP 70 (22) - (23) ABOVE

L-facing. Coarse cream fabric with brownish pink core; fabric contains fine grit: white + grey grit. small. Δ

Gadebridge Park Villa [Hemel Hempstead, Herts. '3K (50)] Flange fragment.

Sandy cream fabric with pink core + buff slip. D A

Gadebridge Park Villa [H.H., Herts (50) (527) 4K] fragment F. Lf. Cream fabric with pink core + buff(?) slip. surface faint in colour; sandy. Probably D from same vessel.

Hayes, Kent, Boston Manor c TQ 5409.1645. Sent by B. Philip. BM-B 8-1 (-52°)

sandy; cream fabric, very slightly pinkish to near surface; brownish buff slip; red-brown white grits. Will be left facing diagonal. Δ B

hercynia [247-1968 BC, I (94) ~~47~~ 144K] sandy, greyish  
 cream fabric <sup>packed with quartz</sup> containing some ~~temporarily~~ grit. Darker  
 cream fabric <sup>of fine chert</sup> found to orange-brown on outside of flange.  
 Flint - small grey, white & black; + quartz-like grit.  $D = c 39''$   
 Smoothly outside; slight conc. seaming inside; wall away near bottom of treatment.  
 Good finger depression below flange under stamp.  
Tumby, hincs [TF 259566 Lincoln M. Brought by B. Whitwell] A  
 Sandy cream fabric with thick pinkish or pinkish brown core  
 nearby to surfaces; cream slip; internal scoring; grey & white  
 flint grit; stamp diagonal.  $D = c 13\frac{1}{2}''$  Lincs. History +  
Archaeology (Arch. Notes for 1968), I, no. 4, 1969, 106.

## ALBINUS

Margidunum [Ant. J. 1944 xxiv p. 50 <sup>not</sup> fig, no. 4; 33-121; 2K; Not. U. Mus. Well,

F-45W] sandy, pinkish buff fabric; at right angles to rim. S is not retrograde.

Vembium [57-21. (26) 5K] r. facing; very dark grey core changing to cream  
near surface; sandy; surface cream but top of flange buff; internal scoring; tiny  
to medium, black, red-brown, grey grits, much to b. b. J H

1K [see, Isca pt. 21, 5; + pt. 23, 13 <sup>p. 43</sup> 110K NMW] see ALBINUS // 7 ADAMIAN.

Gravesend Museum [Provenance not known; Milton Chantry 2K] whole but worn  
through in bottom; well worn; greyish cream fabric with pink core; stamps  
diagonal. Curbed under flange. A

LVGD/FEC (413) Albinus

Redhill, Shropshire [P 3798 E 001.59 (85) 2K] 385 gms

Diam  $30 \text{ mm}$  <sup>diagonal</sup> 21% 2 young sherds (break modern)  
r. facing stamp. Probably overfired rather than burnt  
Traces of creamy buff slip. Inclusions: packed with  
moderately well-sorted quartz with occasional red-  
brown & rare black. Rim smooth, <sup>close</sup> concentric scoring  
inside, int & scoring worn away below c 2 cms  
b. b. b. intonation: frequent, tiny to small overall  
up to bottom of bead — combined with the concentric  
scoring.

Δ

## ALBINVS

Chester [Foregate 1938, Box 80, eAJ. xxxv, pt. 2 p. 79, 3; 11K] hard, pinkish buff, slightly sandy surface; stamped diagonally. ~~J~~ J

Chester. [Eastgate St, south side, 1914, Hayter I, 40K] hard, fairly smooth, buff fabric with pinkish buff core; internal scoring; fairly abundant small white, grey, black grit; none on rim; stamped diagonally. Die as Rowley Ho. 1424

Richborough [iv, p. 251, 8(B) unstratified; 1K] ALBINVS // F. LVGV DV; almost whole.

B-F. 34 head on level with flange and end of flange slightly inturned; sandy, pinkish orange fabric; inside well worn, very few grits left, smallish r/b, whitish grey to head. Hole through bottom but not wear, I think. D=c. 10 ins.   
 ~~J~~ J

no scoring on flange.

ALBIN

Chester (Foregate 1938 Box 80) 11H

ALBINUS

Baginton [sent by B. Hobley 16/8/66. J. Dearna key, 3 Francis Rd.,

Baginton, Rubbish Pit] r-tacing. F. LV9 — Coarse, cream fabric. Grit, grey & blk. probably flint; mostly gone. cream slip. Thumb depression under stamp. D=11"

Baginton [sent by B. Hobley. LRF 66V ①] l-tacing, coarse brownish pink fabric tempered with fine r/b. grit. Much white, r/b, grey grit, mostly flint. Well-worn - grit gone below about 1/2". Traces of internal scoring. Could be a brownish cream slip.

ALBINVS.

Mandussedum [① W70 ①F 50. 72k] Flange fragment Ver. I, no 8.

Slightly brownish-cream fabric, coarse granular texture, frequent inclusions of quartz with occasional black fragments.

No trituration grit survives. Dr. 28 cms.

Piddington, Northants [101/102 archive PID H/F 84 F149 Z14 R5(c)/  
Y/2 12 L4 H/F 79 7K] Surface battered & damaged.  
Very heavily burnt before fracture (2 young sherds) Interbedded  
with greyish-cream may have had a sc. slip. Abundant  
quartz inclusions. Just slight traces of scoring on int. inside.  
Dr. 43 cms. Grit v. small

ALBINVS  
Sherston

## ALBIVVS

Colchester M [4630.23; 396K] sandy, pinky fabric to cream-grey surface, buff in parts; rilling; prolific, white, grey, black grit to b.b. D = 213 in. Near BF34. diagonal stamp; l. facing. B

Colchester [Pope's haue. May 1. 2619. 12 not seen] Now seen 575K.

Colchester M. [Price's Catalogue 1455, now lost?] not seen.

Colchester [Wine's Diary, apparently complete, in a chevroned frame. Found at the Grammar School]. If this is not the same stamp it is probably from the same die as 310.97. Sketch in Wine] not seen. See 344K.

Colchester [Ben Edwards] rubbing & drawing 1903. Both done by B.E. Presumably in his possession. no information on position of stamp.

Chesterfield [6K . SR75 F 360 (179)] 2 joining fragments  
body + tiny frag. of flange surviving. Much worn. H.

Broughing [T. Potter BR72AHL L 1 (6). 9K] granular cream  
fabric with brownish core & brownish buff slip varying in color.  
Bath [RB 1253 3K.]

Eastcotts, Bedford Southern bypass [E94 1297 3K] L facing  
3 young sherds and one other, giving c. a third of the vessel.  
Dr. 23cms. Bunt black throughout except for <sup>lighter colored</sup> skin of the  
~~lighter material~~ outside which points to the greyish-cream  
fabric it was originally. Inclusions: frequent fairly ill-sorted for Ver.  
region. quartz with rare larger orange-brown. Concentric scoring  
PTD

Survives only just under the bead worn away with turturative grit  
everywhere else. One or two tiny fragments of flint and quartz  
turturative survive. | Frere 1972, 145, no. 2.

Surface smoother than usual Verulamian region fabric.

Gochambury [GOR 79 (1540) 2873  $\triangle$  4.21k] Buret CRS. Ver. 16 B.

very faint stamp. Pinkish-brown fabric, cream at the surface in places. Granular texture, frequent inclusions mainly opaque white quartz. Tribulation grit quartz and some flint. Dr. 32 cms.

Castleford [no. 433 cas 83  $\square$  141 101 (36) SF 145 70K] FF granular, greyish-cream fabric with black core; faded to pinkish colour on underside. Packed with sub-rounded quartz. Stamp slightly diagonal; could well be r. facing. 5 body and side sherds, joining each other but not flange. Heavily burnt and very heavily worn. Die 6B



o

GOR 79

(1540)



Gorhambury

2

ALBINVS

✓ unpublished.  
Templeborough [May 1916/17; 6K] flange fragment; sandy, pale buff fabric,

surface orange under flange, greyish on top, with orangy patches. K

Castleford [1965] stamped each side; stamped diagonally; sandy, greyish cream fabric with orangy slips; internal scoring; small, flat, grey, white and cobblestone grit - lower half worn; in whole; A

Woolworths site JAC. A. 3. 085/52, 1967 fig 4, no 7 & p. 16 no 7.  
Chester [Box 576; 1959; 58K] Diagonally stamped; typical grooving under flange, like 20K; sandy pinkish fabric. JCAS 54, 1967 p. 18 fig 4, no 7. B

Chester [Delamere St; 1914; 20K] whitish friable fabric; sparse, grey and brown grit; rilling, stamped diagonally.

ALBINVS chevrons

De. 2

Fishbourne [FBEO2 1026] 15219 14K] Reasonably  
assumed to be facing. 3 sherds making c.  $\frac{1}{4}$  of vessel  
Diam 270mm. 22% fired to cream at surfaces but  
pink through rest of fabric. Inclusions: abundant  
fairly well-sorted quartz; very rare black. Top of  
flange smooth. Conc. scoring down to 1cm. b.b.b.  
Tiny quartz & flint grit combined with it. Below  
c. 1cm. b.b.b. grit and conc. sc. worn away. S  $\Delta$

# ALBINVS

Leicester, Redcross Street. [A316.1962.215 Jx 139 238k.]

L. facing. Granular, <sup>greyish</sup> ~~brownish~~-cream fabric, at the surface and core with pinkish layers as a 'sandwich'; frequent inclusions of opaque white quartz and sparse orange-brown fragments. Texture is less coarse than some Verulamian region fabrics. Trituration grit quartz and flint; orange-brown slip present. Worn and concentric <sup>in side only</sup> scoring. Dr. <sup>33</sup> ~~27~~ cmbs. Ver. I 6B

Silchester [Basilica 80/30 137/1250] Information + rubbing + Δ from Jane

Timby. Residual in ③ context;

Ver 9<sup>th</sup>

C

Brockley Hill \* [L.M.A.S. <sup>(1953)</sup> xi Part ii p. 181, fig. 4, M. 3; 4K] sandy, greyish

fabric with slightly pinker core; surface buff, flange fragment D  
Venlamium [160 K VIII <sup>no. 1</sup> (20) <sup>no. 6</sup> (8); 198 K] l. facing; sandy, greyish  
cream fabric; burning <sup>inside</sup> Lat sprout; 1 or 2 grey grits; perhaps a slip. K

Canterbury [C. XXIV, LIII, (3A) <sup>sand</sup>; L.S.S.F. May 1961 to] flange only; sandy  
pale buff fabric with thick reddish pink core; 2 reddish brown  
& white grits in fabric. K.

Coerhan [W. Greenhalgh; 12, Bryntinion Park, CONWAY, Caerns. N. Wales]  
vicin. flange fragment. Sandy cream with slightly pinkish core. Burnt

\* after fracture.

\* NB. L.M.A.S. 19 p. 11 p. 74 final list suggest lists 1 (1947 presumably LVGV) of Bunter ref. as above M4 but  
the in handlets illegible.

ALBINUS

~~Bootham, London [GTC p102 no 616 (3315)] Arch. 63; p327.~~

Arch 63; p 327 ALBINI R. HANSON (Barclay & R. Breinsey) <sup>wrongly by</sup> attributed to ALB.

Thames St, London [GTC 620] <sup>Mentioned as a Guildhall M. - [unclear], b) Thames St,</sup> Arch. 63, p. 327 ~~of [unclear] [unclear]~~

~~Nr. Mansion Ht 1869, London [GTC p102 no 618];~~ ? 140K <sup>not checked</sup> with LVG 122V

~~Mgr. Roxan. Noted elsewhere;~~ p. 103 300 ?

~~Radlett [VCH (Herts) 161 & Procs [xvii] p 261];~~ VCH M.V. Taylor p 161

London


~~Black [unclear] [unclear] p 218] 5% off [unclear] [unclear]~~

~~London [LVGD] <sup>Not seen. Museum not mentioned.</sup> FEC [unclear] [unclear] [unclear] p 334, 27 April 81787~~

ALBINUS

Die II a

Pentehyling fort, Brompton, Salop [K BR 90 III 3020] flange  
fragment. Burnt before fracture. Granular greyish-cream  
fabric packed with quartz, well-sorted inclusions. Dr. c. 27  
Kiaale; rare orange-brown inclusions.



ALBINVS

Stamps 253 173 252

2320-21; 2324; 2319 V F33, F39 & F4 162 207

Leicester [A78. 1975. V 133 253 and 78 1975 V 134 173. 229K  
on IRS at rt. angles

two FF joining/giving fragment of counter stamp, r. facing  
joining a spout [78 1975 V 133 253]. Granular, <sup>greyish</sup> brownish-cream fabric, <sup>packed</sup> frequent inclusions of quartz, occasional rare red-brown fragments. Trituration - grit ~~at~~ surviving only at top. traces of <sup>both</sup> orange-brown slip. Join 78 <sup>(old 178K)</sup> 1975 V 162 252  
r. facing Dr. 33cm. friable; he only burnt & v. heavily Δ worn. Concentric scoring survives at top of vessel inside. No scoring or grit on flange. Spout usual type. 7 frags in all. Dr. c 33cm Trituration: small flint & quartz. Stamped across rim.

## ALBINUS

Leicester [322] 302 1971 163K] stamped diagonally should  
 be right facing. Internal scoring <sup>VII</sup> + a little on flange + grit on flange.  
 Granular, greyish cream fabric with thick pink core; fairly  
 heavily tempered. Quartz + flint grits upto + onto side of bead  
 and on flange. Dr. c. 32cms. A Δ

Leicester [252] 78 1975 178K] Fragmentary flange + body frag.  
 internal scoring upto bead inside; not visible on flange. Good  
 amount of largish quartz tempering; v. granular greyish cream  
 fabric; mostly flint + quartz with odd v/b. Intonation grit. Slightly  
 burnt. worn. Probably IV of F.LVSVDU - virtually certain.

JOINS [229K]

ALBINVS n At least 7 pots on this card,  
Colchester not entered elsewhere (Symonds + Wade 1999)

S.1	Die 2	}	All different pots
S 2	Die 2		
S 3	Die 2		
S 4	Die 2		
S 5	Die		not in here, ALBINV2
S 6	P3163	LVSD FEC	Could be transcribed as S5.
S 9	P4296	— " —	
S10	P4302		ALBINVS (Freere 1972 no 5)
[S8 ?? = 578K]	4295		not at all certain.
[S7 = 605K]	P4297		

Wall [W5/10/1 38K] Flange fragment; stamped diagonally.

Granular brownish cream fabric with paler core; slip darker.

Wall [W5/3/7 39K] r. facing. Granular brown fabric; slip generally brownish buff but paler in buff & cream in parts; much white? flint & dark grey grits.

Deanshanger, nr. Towcester <sup>2K</sup> [P. J. Woods % 7 Stone Close, Wollaston, →  
Wellingborough, Northants.] off-white ware with white, brown &  
dark grey grits, a few reddish-brown. The counter stamp is B  
clearer. with Albinus stamp Ver 1 pg 145 no <sup>3</sup> (4).

Lyng Kiln, Norwich [86.K. Norwich M. 35.957] stamped along.  
check no. ? 30.957 or 35,957

Northamptonshire SMR . Position of stamp not noted

ALBINVS

OK

Deanshanger, Northants [Vol 34, 2006, Brown 2006, p75,


296, no 7 + p. 73 no 4, The Roman Pottery by

J. Timbery] not seen, see over: either 5 or 9 probably?


~~Partia~~



7



Deanhangar 2K



ALBINVS

Middlewich [1980/IK cl<sup>+</sup> RPC(1) Site C King St. Middlewich Lib.]

Whole of top  $\frac{3}{4}$  of vessel there. Worn. Granular greyish cream fabric Dv. 34.5 cms. (See nos 9 + 10 in Ver. 1.)

Ratcliffe-on-Soar, Notts. [RAT. 274. M5 1963. IK] Probably (fac.

Stamped diagonally along. Cream fabric with ~~brown~~ pink core right upto the skin. The fabric is most unusual for the ~~the~~ Venulamian region in being fairly fine-textured + having only a moderate amount of fine quartz + occasional r/sb. Temper. Concentric Scoring on inside combined with fine quartz + flint intrusion. Dv 30.  $\Delta$  brownish-buff slip. Probably never had grit on flange. Die C

ALBINUS


described as late Iron Age

Heybridge, Elm Farm project [HYEF94\_13456 bottom of pit

11465 47K] r-facing 645g. Fired to cream at surfaces  
but pink almost throughout. Fired to black throughout most  
of rim. Inclusions: frequent - packed, tiny to smallish  
quartz, very rare red-brown + black. Diam. 32cms. 31%.

Interpretation: traces of internal concentric scoring - top of  
flange smooth; quartz, flint, rare red-brown. die 6  
Eastern Maudit villa site

Robert + Wendy



F. LVGV DV

(Banned F)

Venulamium [Theatre V.T. + 1934 Training P.C. 12K] dirty, drab fabric, with pinkish core; some medium white grit. J  
E

Venulamium? [no. no. D.110. P.C. 13K not seen, rubbing by P.C.] gritty drab fabric probably LVGV DV stamp but could be ~~LVGV DV~~? NA

Reculver [Arch J. 47 p 243] SEE LVGV DV LVGV DV NA

~~? could this be the one for now at Maidstone No.~~

~~Greenwich Park [in Greenwich Town Hall; VCH. Kent III p 166] NA~~

Fen Ditton [Cambridge Mus.] pinkish buff fabric with v. sparse, small, white & brown grit H

(Kinderton), Chestine [R. Chestine, Watkin p. 248]

Middlewich

NA

~~Jan~~ JGV DV East Bridgford (Notts) Arch. J XLVII (1890)

p 234.

Attributed to Albinus, Counterstamp Vev 1972 6B.

Verulamium [D86 AX. 321k] L-facing, fragmentary stamp.

Cream fabric with a thick pink core, fine granular texture, frequent inclusions of quartz, occasional red-brown fragments. Trituration grit flint and quartz <sup>occasional red-brown and opaque black.</sup> Fired to ~~orange-brown~~ <sup>cream</sup> at the surface or maybe a slip inner vessel surface, worn.

Inclusions tiny to small, may include occasional flint.

Fine end of range in Vev fabric. Concentric scoring survives inside to nearly  $\frac{1}{2}$  way down vessel - this & grit completely worn away in lower half. Scoring & tiny grit go right up to bead. Flange is smooth. [MK] 6B

ALBINUS

Southwark [199 BHS XXIII (3) on pp 45/239] Borong L High Street;

drawing sent by M. Hammerson 15.3.82] Die A. Name stamp  
diagonal.

Chelmsford, Essex [① Chelm 69. + onh +  $\triangle 194$  .17k] l facing, stamped  
(but not packed)  
diagonally. Cream fabric with thick pink core; frequent inclusions  
fairly well-sorted quartz, some red-brown and flint fragments.  
Trituration grit quartz and flint, fired to darker colour near the  
spout. Dr. 33 cm. Flange smooth. Tiny bit of scum. Verul. I no. 5  
inside, remaining. Spout has label off.

## ALBINVS

Leicester [185. 1966. 57  $\triangle$  124K] r. facing. Brownish cream with darker brownish cream slip; flint grit (grey & white) + some colourless quartz-like grit. Hole worn in bottom + grit worn away in lower part. i = LVGV DV

Verulamium [Sr Alban's Rubbing sent V. Rugby ST/AO 24]

Verulamium [ " " " " SS (IN 374) ] LVGV DL

counterstamp only.

Verulamium Insula XVIII 76.1 FH  $\triangle$  305K Granula greyish cream fabric with <sup>very</sup> thick salmon pink core almost to surface. Internal scoring but none on flange; red-brown, grey & white (q<sup>5</sup>) grit, much of it tinged to b. of head. l. facing. no grit on flange as far as it survives. Pr. 31/10/55  
no 5

ALBINUS

Netherfield, north of Battle, Sussex. [


] stamped along, l. facing.

greyish-cream; very frequent inclusions, mostly quartz  
& rare red-brown. Inclusions not as packed as they  
can be.

Silchester [late Iron Age and Roman Silchester Michael Fulford and Jane  
Timby Britannia Monograph Ser. No. 15, 2002] p. 219 NOT SEEN

<sup>think Albinus</sup>  
NOT CERTAIN. JINVS p. 219 and fig. 11.2.2.1a could be DOINVS

Ashted [David Bird], Surrey



ALBINVS.

~~London [Arch 63 p 327] ALBINI F. MATUGEN - clouds ? = 9H. x.~~

~~Verleon [PSAL 2, VII, 1877 p 221] ALBINI F. LUGUD. D=10" NOT SEEN. (Different in bottom. NOT SEEN. C. VII 123. 5(B), see, 1 sea 47. Feb. 23/134. Lab 21 F. 5. Vsk [reference in PSAL 2, VII, p 221] ... } the same vessel.~~

Borough Hill, Daventry [PSAL 2, VIII 1880, p 326].

Ritcheater [found 1813. by Dr. Whitaker, Watkin's R. houses p 161]; "white earth".  
Historic Soc. L & C. No. XVII B.M. — NOT SEEN.  
Not necessarily in B.M. Found at different date from RORIEDO.

## ALBINVS

~~Heicester (27K) is possibly ALBINVS INV [S-H] - see DOINVS for description.~~

~~Sequentium [P150 not] Wrox. 38. 7/15. 5. 6. 7. 8. envelope~~

Cambridge Museum (5 at b.) sandy buff fabric, variegated coloured grit. H

Heicester, 1844.

Baldernigh's collection of Ant. p. 145 no. 8. CIL VII 1334 - 06(a)

ALBINVS

Heicester<sup>M</sup> 18K no. no. Mus. 3 no. provenance] sandy buff fabric, brown core; rilling; fine

brown and grey grit. Die not yet entered. I think like <sup>or Colchester</sup> a Verulamium one. G

Wilderspool (p. 64 'BINVS] now lost. ALBINVS most likely as

suggested by T. May.

NA

Yorkshire Museum [37K] Wrox. T. 34 with bead; sandy buff fabric, buff

surface; small white grit. An FHVGV DV stamp there too but not same pot though similar fabric Victoria; ? = CIL VII, 1331. 9 "amphora" B

37  
RINVAH

37K. Yoshikawa Mus.

37.

ALBINUS — attributed assigned.

Brentford [4K 74 C (87)] fragment. Roxley Hill fabric

[ ? Die A  
Dunrobin Strips  
Nelson Place, Bath [NPL 89/228 (69) 8K] <sup>? counterstrip of Albinus B.</sup> <sup>slightly diagonal</sup> Assumed L-facing. The fine.

textured Venetian fabric. Hard, fine-textured, greyish-cream fabric.  
Inclusions: fairly frequent; <sup>mostly tiny and very fine</sup> quartz, <sup>sorted</sup> and sporadic largish  
red-brown material. <sup>rare</sup> Inclusions: flint, quartz, <sup>rare</sup> red-brown.  
Concentric scoring up to bottom of head. Flange smooth. Dv. 31cms. <sup>No 45 wear</sup>

Bath [RB 1253 3K] Berry-Cum-liffe

Colchester [2619.12.575K] L. facing. Scoring inside but  
 worn rim. Complete save for hole in base, through  
 wear. Only stamped once. Sandy, mostly  
 pinkish fabric with cream skin & slip; tiny grit,  
 mixed flint, colorless tr/b. D = 114/10. Pope's Lane (H)  
 excavations Oct. 1912.

(Form exactly like, an unstamped complete  
 Ver. water (except hole in base) with no  
 stamp).

# ALBINUS

Margidunum [A.J. xxiv p. 50 no. 5 and fig. 1, no. 5; 27K] L-facing;  
2 joining fragments; pale buff, sandy fabric with thick salmon,  
pink core; internal scoring; very small, white, grey + brownish  
grit in parts; probably has buff slip or cream. D = c. 12½. G.

Margidunum [A.J. xxiv p. 50 no. 6 + fig. 1, no. 6] this stamp is missing +  
the reading ALBINVSFE is clearly wrong. F74 4'

Margidunum [A.J. xxiv p. 52, no. 12 + fig. 2 no. 12; 12K] ]GV DV  
the full section is drawn but only part of the section is here though  
from find-spot it is clearly the one intended; sandy, cream fabric  
with cream core sandwiched in pinkish buff; internal scoring;  
much, small, grey, white + brown grit.

ALBINUS


Castleford [no. no. CAS 80/81 S.10 L.76.3 58K] fragmentary FT.

Almost certainly ALBINUS die <sup>from 1472</sup> lla - fits in every way of hoodlike  
right type of flange. Greyish cream but black almost throughout.

Fairly frequent quartz inclusions <sup>B&Z?</sup> not v. evenly distributed.

York [SM14 1980.21 2239 131K] diagonal MW Dr.  $\bar{c}$ . 31cm.

greyish-cream with pink core to rear surface. Frequent tiny grit  
but not as granular as often. I would count as finer fabric. All  
quartz but few rare red-brown. Flange showing smooth  
but fairly near to spout. Tinturation: small flint, some quartz  
upto bead. Context residual.



# ALBINS

Colchester [Pit K9 38 / A53] stamped diagonally.

[V.G. DIFE] 578K Maybe P4295. S. 8 <sup>needs</sup> checking  
Greenbridge, Kinner [J.C. Hockin, 26, Belbroughton Road,

Blakedown, Kidderminster, Worcs. Field O.G. 1054.

G/F 3/5. Top parts of fill to defensive ditch. Sandy,  
coarse, buff cream fabric; only flange & bed.

Cambridge [no. 78. Sect M.R. Hull 5K] coarse buff fabric, bent  
grey. Chequer border as 344K Colchester.

Lillechester [M. Brassington 1968] layer 9 - underneath rampart

almost on natural subsoil. 16K

G  
J.


Usk [Lee, Isea Sijunum p. 38; pl. 21, 5; + pl. 23, 13; 31 - 78 | 119;  
 110K; NMMW] 1862; found while building a Tail; had hole in centre;  
 pinkish, sandy fabric, surface creamy buff tinge; worn + scoring; large  
 to small, mixed, white, brown, red-brown, black to bead; below  
 c. 2 ins. grit worn almost wholly away; outside of spout gone; D = 13 9/10  
 some cracking under flange.

<sup>from uncertain</sup> London [M2833; British M. 124K] 1 stamp each side of spout;  
 slightly ~~pi~~ sandy, pinkish buff fabric with cream surface; some, largeish  
 to smallish, white, brown, grey, black grit to b.b. D = 13 1/2'  
 no grit on flange. Walter has counterstamp only of ALBINOVS  
 and no provenance given.

ALBIN VS

heicester [Causeway lane. A1. 1991. (2987) <sup>ARLGA 2</sup> 17709. M07]

Drab cream with some pink brown in it. Inclusions: abundant quartz, sub-rounded; v. rare black & orange-brown. Dv. 35 cms. Probably L. face. orange, buff slip. Heavily worn gut worn away.



ALBINUS


R. Clark

Causeway Lane, Area 1.

Leicester [A1.1991.17720 (1459) M010 K] L-facing. Greyish-cream, rather smoother than it can be; inclusions fairly well sorted, quartz perhaps with some flint. Does not appear to have v/b or black inclusions so if there rare. Tinturation: flint, some quartz & rare opaque black. Bunt. Dv. 26 cms.

Leicester, Causeway Lane [A1.1991.17719 (1259) M07 ] Flange frequent diagonal. Greyish-cream with thick pink core. Inclusions: abundant quartz, probably occasional flint. anything else very rare but black seen & orange-brown. Dv. 33 cms.

Leicester Causeway Lane [A1.1991.17721 (1481) M07 ] Bunt black throughout diagonal LUGDIPZ. Dv. 31 cms Flange smooth. Tiny gut & concentric scoring base of bead. Inclusions: abundant quartz, rare red-brown. tinturation? flint, some quartz, v. rare red-brown.



See ALBINUS [E 46] <sup>core to stamp of ALBINUS</sup> from same vessel UK.

Wroxeter [Rawley Ho. E 44, P 21; p 81, fig 40, no 10; 25 K] coarse, sandy; greyish cream core quickly changing to salmon pink near surfaces back to greyish cream; stamp diagonal; flange bead only. Pt. 15. [E 18 in Rapt.] AD 129.

Vsk [see, see pt. 21 no. 5; pt. 23 no. 13; NOK NMD] See ALBINUS || ~~ALBINUS~~

Vendanium [Ver. 59 VI (12); 174 K] r. facing, diagonal stamp; slightly sandy, cream fabric with pink core and buff slip; abundant white, grey and brown, smallish grit to b-b. Vol III (57 (4))

Vendanium [220K '58. AvI (31) 1.] Sandy, <sup>Vol 12 no. 4</sup> greyish cream with thick pink core with small internal core in flange of greyish area. Buff  
Orangy slip, discoloured grey in parts. Internal staining; medium to heavy, abundant grey + white flint + brown grit. D = 2.16". Diagonal. R II.



Malton [52/CK. At Durham 1963; 35K] counterstrip, worn; orange-  
 green fabric with cream at surface with buff slip; brown to white grit.  
Heicester [122. 1962. Leicester M. 120K].

Venlaminum [225K. 57. Txx (15)] flange fragment. Sandy cream fabric  
 with bits of grit - it; cream slip. vol 1 (no 10)

Venlaminum [226K. 58. B. I. ~~45~~ or (65)] l. facing. <sup>vol. 1a (6)</sup> Sandy, pink fabric,  
 the outer skin, cream; internal seaming; grey to white flint grit to brown red  
 grit; a little translucent <sup>white</sup> grit; smallish + tiny.

Wall [WL. 721. M. 18. 26K] l. facing; flange only. Upper surface  
 burnt. Sandy, cream fabric.

## ALBINVS

Magiovinium (Dropshot, Bucks) 1220 - 18 - 2000 2K Die J) Dr. c29<sub>on</sub>

Flange fragment A; granular greyish-cream fabric, packed with quartz inclusions, perhaps a cream slip.

Wood Burcote [F 218 W B 4K.] Granular fabric but qtz inclusions seem to be smaller than usual in B.H. fabric + may perhaps be fewer.

Buff fabric, surface a little paler. Dr. <sup>39</sup>~~4~~ cum. Die as Ver. no 7.

Haynes, Parish of Southern, <sup>Cleeve Hill 4 1/2 miles to</sup> nr. Cheltenham on M5 1K. B. Rawes.

Granular, greyish-cream fabric with pink core almost to surface. Tinturatum almost gone; surface eroded. Dr. 34. A cotswold escarpment

Not possible to say whether from Die 6 B or Die 10. Tinturatum mostly gone.

ARBINVS

- Vendaniium [56 G. III. C. (9)] <sup>6K ✓</sup> dark grey fabric, in parts brownish orange changing to pinkish orange surface. Position not noted. <sup>no III (56 (3))</sup>
- Vendaniium [56 FXXIX (7)] <sup>7K</sup> creamy fabric; small white grit up to rim. <sup>no 55 (2) B</sup> G.
- Vendaniium [1933 A VII. 2 p57 (B) 70] P.C. 1K] pinkish buff, flaky; some fine white grit; sandy. <sup>G</sup>
- Vendaniium [Mus. P.C. 2K] <sup>A. IV. 33; P. 21 (32)</sup> ~~dark fabric~~, flange fragment; d = 19 <sup>3</sup>/<sub>4</sub> K
- Stratford-on-Avon [provenance, Stratford M.] slightly diagonal; sandy, orange to cream buff surface, with buff core; flange only. <sup>7</sup> B
- Crastorby Norwich [unpub. 63K; D40, 237.] pinky fabric with darker core, changing to cream, and pale buff slip; core grey in parts. Flange only. <sup>J</sup>

BIWV

out

Vendaminum '56 (a inc (13)) 7 1/2

ALBI

Vendaminum 1933 HK  
A VII . 2. P57 (B) 70 PC

ALD

out out.

Vendaminum '56 (F xxv) (1)  
7 1/2

ALBING

Vendaminum Mus. P.C. 2K

Venlamium [1958, BI (45) 135K] L-facing; flange fragment showing

some of edge of spout; sandy, greyish cream with thick pink  
core, surface buff on top. vol 1 (9) H

Venlamium [1958; BI (32G) 136K] sandy greyish cream fabric;  
internal scoring; some grey flint grits to c. 1 in. b. top of b; flange  
broken. vol 1 (9) H

Venlamium [1958. BI (45) 137K] L-facing; sl. sandy, fabric<sup>(2)</sup> apparently  
discoloured throughout by burning or mut firing; varies from  
buff-brown to dirty brown, grey & black; surface, grey,  
drab buff, black; inside appears heavily worn; brown & grey (c. 3) grit  
rest worn away; marks of scoring on flange, none away inside.  $\Delta D = 11 \frac{1}{2}$  in G

Venlamium [1958 SS. F. BIV <sup>2</sup>(36) <sup>vol 1 (10)</sup>]; 128K] flange fragment; stamped slightly diagonally; sandy, greyish cream fabric; intumed at end like BF. 38. ~~Assigned~~ H

Venlamium [1958 A. VI (29) <sup>vol 1 no (6)</sup>]; 129K] stamped diagonally; drab, dusty brown fabric with some grey in core, surface grey save for bright orange/brown patch; burnt or mistired; internal scoring, tan/fig. abundant, flint, white, black & grey, few brown grits to head & some on flange. A. J

Venlamium [1958 B1 (45) <sup>vol 1 (10)</sup>]; 130K] fragmentary flange & side; sandy, greyish cream fabric; internal scoring; much brown, grey, white, medium grit & about 1 in b.b.b.; few above. K

ALBINUS ? published


St. Albans, Venetian. extra-mural. ALBINUS Die B. ST/AD/24.

r-facing - slightly diagonal. slightly sandy creamy pink fabric with brownish slip, mostly gone. red-brown; white, grey & transparent gut. Tiny to medium; abundant; interned flange, bead slightly lower than flange. 293K

do. s.s./I N 374 294K ] LVA VD [ Die D. l-facing. Sandy greyish fabric with thick brownish pink core; brownish slip; red-brown; white; grey gut. Well-worn.

St. Michael's, St. Albans between 3 wall of V. + river V. [Herts. Arch.

vol 2, 1970 (p. 51-61) p. 59, Fig III, no 2. + p. 58. see over. 314K  
not seen.



2

p. 58 Cream fabric with stamp on the  
rim of ALBINUS. Associated  
with clay bank.

(vol I no. 3)

Venlamium [VER 58 B II - (31E); 138K] s.l. sandy; thick, pink buff  
 core to cream v. near surface; surface an orangey buff slip(?);  
 stamped diagonally; similar to 125K; no grit on fragment;  
 red/brown accretion under bead - dab (BRH) ~~slip~~ B.

Venlamium [1954 x XI (2) 3K] r. facing <sup>vol III 58 (405)</sup> sandy fabric, pink in outside  $\frac{2}{3}$   
 + most of flange throughout; to inside + inside top of flange dirty  
 buff; surface buff; few grits survive; white, black, grey, medium to  
 small grits; top of flange fingered for addition of spout. J.

Venlamium [57 TVII (29); 4K] l. facing <sup>vol I (5)</sup>; stamped diagonally;  
 fairly compact, buff fabric; internal scoring; buff slip; largish to  
 small, red/b; white; grey; black to b.b. D = 15 ~~ms.~~ J.

Venlamium [221K. 58. AVI (23)/1] r. facing. sandy, cream fabric with thick pink core + cream slip; traces of internal scoring; grey + brown gut vol I (no 7) = no. 545

Venlamium [222K. 58. BI. Pt 7/15] flanged fragment; sandy, cream fabric + slip. vol I, no. 8 K

Venlamium [223K. 57. TVII (26)<sup>n</sup>/1.] sandy cream fabric with pink core, enclosing further cream core with ~~brown~~ orange creamy buff slip changed to brownish buff in places. vol III (60 (7)) (not here)

Venlamium [224K. 57. TVII (36)/1.] <sup>vol I</sup> diagonal stamp; <sup>no 6 = 365</sup> fabric heavily burnt inside + in ner half of flange; sandy, reddish brown fabric; surface drab brownish cream; traces of internal scoring; fluff + white translucent gut. D = c. 15<sup>J</sup>!

Venlamium [57 T. VII. (89); 9K] almost certainly = ARBINVS 4K; flange  
 Vol i (6)

fragment; sandy fabric; greyish core changing to pink, to cream  
 surface; buff.

Venlamium [Ver. 59. BI (64) Pit 7; 173K] probably l. facing; sandy, orange.  
 Vol i (6)

buff fabric with bright orange buff surface, possibly a slip; inside grey surface  
 & ind. fabric; internal scoring; much small, white, r.b. and grey grit to c.  $\frac{3}{4}$  in.  
 b.b.b. ~~Assigned~~ J

Venlamium [Ver. 59; BI (63); 193K] l. facing; sandy cream; burnt  
 Vol i (10)

grey towards outside<sup>or top</sup>; buff slip; flange & spt. fragment.

Venlamium [58 BI (45) / 6.214K] flange fragment. ~~Assigned~~ H  
 ARBINVS sandy cream fabric. Vol i (7)

vol 1 (no. 6)

Venlanium [1958 S.S.F. B1. (38); 125K] rather sandy, pinkish buff

fabric with very thick drab cream slip which has covered a few of the  
gits; grey and few red/brown, flint, tiny to medium gits to  
b. b. D = 15 ins. Δ internal scoring; slightly diagonal. J

Venlanium [1958 S.S.F. B1. (38); 126K] <sup>Vol 1 (no 6)</sup> different vessel from 125K;

r. facing; diagonally stamped; slightly sandy, pink, almost brownish  
pink fabric with cream slip; internal scoring; moderate amount,  
largish to small, grey, brown gits to b. b. D = 13 ins. Δ. (? not here) J

Venlanium [1958 S.S.F. B1. (45) 127K] <sup>vol 1 (10)</sup> r. facing; flange fragment

only, intuming like BF. 38; sandy, greyish cream fabric with a few flint  
gits in it; moulded with fingers for addition of spout; pink cover on end of flange.

- Venlanium [59; BI (63); 171K] flange fragment; <sup>vol 1 (9)</sup> sandy, greyish cream fabric with buff slip; brown to very dark grey in parts. H
- Venlanium [59; BIV (37a); 172K], <sup>vol 1 (5)</sup> r. facing; cream, sandy fabric with a very thick pink core almost to surface; cream slip possibly; <sup>internal</sup> scoring; much white and grey grits to c.  $\frac{1}{2}$  b.b.b. <sup>distance</sup> <sup>or BI + H</sup>
- Venlanium [59 BI (63); 187K] flange fragment; <sup>vol 1 (9)</sup> sandy greyish cream fabric with buff slip. H
- Venlanium [58 BIV (21A); 195K] flange fragment; <sup>vol 1 (11)</sup> slightly sandy, greyish fabric with <sup>brown</sup> pink core. D

## ALBINVS

Vendamiium [z. iv. 7  $\Delta$  65] CarPark; 106K] white, coarse, sandy fabric; J

internal scoring; medium and large, white & brown grit, perpendicular to ring.

Vendamiium [CarPark; B. III. 23  $\Delta$  170] 116K G

Vendamiium [Car Park; B. III. 23  $\Delta$  180] 118K G

Vendamiium [1958. B1  $\textcircled{88}$ ; 133K] <sup>vol 7 (no 9)</sup> flange fragment; pink buff, slightly sandy fabric changing to cream outside under flange. H

Vendamiium [1958. A. VII  $\textcircled{33}$ . 134K] <sup>vol 7 (no 9)</sup> ALBINVS || F. LVGV D; sandy, ~~pinkish~~ buff fabric, tinged with pink in parts & core, surface buff but inside surface & growing thickness of fabric from bead, inside differing shades of grey; ? due to stacking; blackish, brown, whitish flint like grits to bead. D = c. 12 ins.  $\Delta$ . K

Venlanium [1958; A VII (32); 131K] L-facing <sup>vol I (10)</sup> sandy fabric varying

in colour from greyish cream to dark grey; cream slip (some grey & brown, smallish flintlike grits to b. internal scoring; ~~Assigned H~~ A

Venlanium [1958 B I. (45); 132K] flange <sup>vol I (10)</sup> fragment; slightly sandy; pink fabric & surface changing to nr. buff ~~outside~~ under flange; intumed end of flange; ~~Assigned H~~

Venlanium [58 A II (42) 139K] <sup>vol I, no. 6</sup> fragment of flange & fragmentary stamp; thick pink core to cream nr. surfaces; some r/b NA frags. in fabric; sl. sandy; end of flange slightly intumed.

Venlanium [57; T VI (8); 8K] <sup>vol I (no. 6)</sup> sandy; fabric varies; dark grey in outer  $\frac{2}{3}$  pink in center  $\frac{1}{3}$  to cream in nr. surface; pink to nr. surface in flange then cream, some q inside; small wh, r/b, grey. ~~Assigned H J~~

ALBINUS

Llanio, Wales [L0 69 M 1. 2K] 4 joining fragments. burnt inside.

Sandy greyish cream fabric; grit virtually all worn away.

but few tiny red-brown, grey, white & brown translucent grit.

Die as 254K GH London with bent

Sogontium [SE 978 (1004) <sup>7 8</sup> 1057 <sup>no 184</sup> Ardie] v. fac. Granular, greyish-cream fabric packed with quartz. Part of first depression  $\frac{1}{2}$  spat.

survives. Dr. 26. (Die as Ver. 1 fig. 145, no. 11)

Dolaucothi [Dol 72 Trench 2 (19) 71] IK Barri Jones 1972

FF Cream fabric with pink core. Inclusions: fairly frequent, quartz, ill-sorted.

ALBINUS

Coersws [10/1195 9 8K] IRS. Stamped diagonally.

Faint bars in border, top right to bottom left. Granular, cream fabric with pink core. Good amount of fairly well-sorted quartz inclusions and occasional larger brown (? iron rich); tintation included quartz & flint. Obvious Ver region montanus. s.

## ALBINVS

Caerhun [LXXXIX pt. i, fig. 37, no. 11 on p. 79; + p. 80, no. 11 read CIVLP

(or Bar R.) or possibly CIVER (or Par B.); Rapallo House] flange fragment; stamped diagonally; cream fabric with black then pink-brown core; A


Caerlawr Farm, Segontium [67K Caernarvon] B.F. 38; stamped diagonally; sandy cream fabric, pale buff slip; small grey, black grit to b. 6; D = 12½"; not published. A

Segontium [p. 150 no. 1; Segontium 63K] flange fragment of large 38.5h flange, but bead does not survive; sandy greyish fabric with buff slip. J

ALBINS

Elginhaugh [EH 86 | ABO 000 | EQ 120 10V


IRS smooth flange. Con. scov inside to b.b. YRW  
but really pale orange brown with dk cream slip  
some cream fabric in core. ] = EC l. facing . 1



ALBINVS

Elginhaugh (74) EH86 BC 1531 [A.Q.] 11162 9K] FF

Stamp badly damaged but VGV visible  
surface cream slip. fused to o/b with v thick black  
core, (71) may be some pot-black throughout in  
places. VR V but odd fabric, heavily reduced. ? die




ALBINGS

Elginhaugh <sup>EH 86</sup> [53+54] joining; AC 463 [AJ] <sup>6860</sup> ~~7832~~ young

A 64-63 [AJ] 7832 [K] F. NQVD [.] r. fac. Cream surface; black is c 1 mm from surface. Under flange pink before surface but a thin pink/cream layers. Diam 340 mm. Smooth inside at top before d/b break; no con scar on flange either


Elginhaugh [EH 87 trench 8 topsoil vs ool] [BJ] (33#) [K] FF. ??? r. fac. not quite at right angles. Dr 290 mm, cream fab through onto packed, well-sorted quartz

d/b



## ALBINS

Elginhaugh [ABI @ 1K] Stamp twice close together  
 probably L facing, Burnt after fracture, Diam 360  
 19% 3 joining sherds, Smooth flange. Cone scar  
 on inside, ~~only~~ Pat only survives 1.5 cms down &  
 wear unknown, Cream VRW inclusion packed  
 quartz, rare black not well sorted, 1 flint but gut dir  
 Elginhaugh (16) EH 86 ABI [W @] 6K] Diagonal.  
 RF Cream, with black in core on one end? suggesting  
 that it is L-fac. VRW.



London Hill [F. 1951.5; Hunterian M. 92K] l. facing, at right angles on

Sheet would most certainly be considered as obvious, though not unusable  
waster; deep finger indentations on outside of body; a bad  
crack under the flange at one point; and flange "waves" in  
& out a bit; colour varies, mostly shades of grey to black on a few  
parts of surface and very near surface; pale pinky buff in  
other parts; larvae to small, grey brown & black gnt, most  
of it flint. D = c. 13 ins. J:

Castledykes [R. Occupation of S.W. Scotland; pl. I vol. 1 p. 166.  
1939 (500), F. 1939.52 + 82; Hunterian M. 102K] stamped  
diagonally; greyish cream fabric with pink core in places; no rubbing.  
1370 13 DIE A i

21 stamps in Scotland.

Roman Occupation of S-W Scotland 1952: A.S. Robertson,  
Castledykes (Cobriehall) pl. LV, no. 1

Camelon [ <sup>ser.</sup> (16) CAM 76 GX  .17k ] IRS with stamp No. 5 Ver. I

Camelon [ (15) CAM 76 GX  .16k ] flake <sup>not necessarily from same pot,</sup> with counter stamp No. 6. Ver. I,

6a or 6b. <sup>greyish-</sup> Cream fabric with granular texture, abundant packed inclusions quartz, sparse orange-brown fragments and

some grass tempering. Trituration grit fine quartz and flint (imp)

orange-brown slip. Concentric scoring remaining on upper (2cm)

inner surface below bead; <sup>not visible</sup> ~~and faintly seen~~ on flange.

Too small a flake (16k) to know if from same vessel as 17k.

Heavily worn. <sup>192</sup> CAM 76 VM is from same pot as (16) but does not join. ~~has~~ Some patches of burning or scorching on flange of bead in one area.

Camelon [Ref. in Leicester Report.  
FX 232; NMA.45K] l. facing; broken flange; sandy, cream fabric;  
flint grit; c. B. F. 34 turning in a bit at end of flange. Ji

Camelon [unregistered; NMA.65K] ?? facing; sandy, black fabric; grit worn  
away; 1 large, dark red grit survives; BF 34 but bead not shown on top  
at all; stamped diagonal. D = 11 ins. #J

Crawford [G. Maxwell 1965 (18)] loose soil between ditch systems (13)  
diagonally stamped; sandy cream fabric with cream slip. A:  
Strageath attributed only. Diagonally stamped. flange fragment.  
Bunt grey throughout 4K

Strageath [I ②/1 1979. 5K] SKETCH. Flange fragment.

A Cream with pink core. F. LUGUDU well-worn. (no. in Venetian).

Barochan [Hunterian M. BH. 138.72] pale brownish, granular fabric with darker slips, faint intonation & scoring upto bead; none on bead. stamped diagonally r. fac. As no. 5 (Frave)

Strageath [82 G II ⑫ 15K] stamped diagonally; granular cream fabric but blue-black almost throughout. DIE B(2) sketch. ✓


Strageath [80 E I ⑳ joining 80 E I ⑳ 16K] F. LUGUDU 6 DIE 6B ✓

fragments. Heavily worn; with intonation on stamp fragment E I ⑳.

Strageath [82 G II ③ 17K] IRS. ] vs. Possibly burnt. DIE 5 & 6

ALBINUS

Cardean [CAR 1972 (275) 3K] IRS. Heavily burnt to black all over surface and through out fabric or reduced throughout. Frequent, fine (small), subrounded quartz inclusions; Inturation grit: quartz probably with some flint & rare brown. D.  $\approx$  28 cm E. (there 72 uo 5)



- houder Hill [L.H. 1946 (4); Hunterian M. 89K] cream fabric with dark  
 grey core; surface orange in part, drab grey in other; grey flint grit.  
 NA <sup>Free</sup> no 6
- Newstead [FRA 1456; VII. 15. 50 p. 266, fig. 35, no. 5; NMA. 96K] r. facing;  
 slightly sandy, buff cream fabric; few flint grits; B5. 38 <sup>Free no 5</sup> Die ~~III~~
- Newstead [p. 266, fig. 35, no. 6; FRA. 1457; NMA. 112K] L facing flange  
 broken; sandy, slightly pinkish fabric with buff slip; grey in part  
 in core and ~~on~~ surface; burnt; white, black, <sup>darkish</sup> grey grit <sup>6693</sup> Assigned ~~IE~~
- Inchtuthil [Found on surface; now in private hands - hoped to get it for the NMA]  
 r. facing. Cream fabric at surface but largely pink core. Brownish  
 slip. fingerprint under stamp. Flat & red-brown grits. Tweak  
 smallish. <sup>Free no 5</sup>

Hendon Hill [Hunterian M. 85K] flange fragment; sandy, greyish cream fabric with drab surface; B.F. 38 probably. ~~J~~ J

Hendon Hill [F. 1945. 11; Hunterian M. 90K] r. facing; probably ALBINVS Die A; slightly sandy, cream fabric with pinkish tinge; brown, black, grey grit, most of it flint; medium to b. b., probably abundant but much gone; stamped diagonally. NA ~~A~~

Hendon Hill [F. 1956. 8 Hunterian M. 91K] r. facing, <sup>diagonal</sup> slightly sandy, cream fabric with pink core medium to smallest, grey, v/b. grit to b. b. D = 12 ius; this joins a piece stamped 'VIANVACA' in B

private hands, information J. Beattie from the Hunterian museum.  
See VIANVACA both stamps (3/4)

ALBINUS

LVAD REC

London [Arch 8, 1787, <sup>p12pt4</sup> fig 15] Cl. VII 1334, 77




ALBINUS - Memoranda.

N13 Arch 8 P1 10 figs 15 & 16 @ LUGD FEL are

2 different stamps, neither ~~accompany~~ with name stamp  
surviving. They could be some stamp CHECK.

ALBINUS, EVGD. FEC

London ~~1787~~ [Arch 8, 1787, Fig 16]



ALBINUS.

Fig. 16.

~~words~~  
ALEX VAR ??

should be

Misread ~~for~~ SEX.VAL.

See Incomplete Stamps (1) no. ix - JEX VAR

Bushe-Fox suggests restoration as ALEX VAR...

(and quotes JVARO - C XII 5685, 40)

ALEX · VIR

— Misread <sup>should be</sup> see SEX · VAL.

Reading suggested by Bushe-Fox for Incomplete  
Stamps (2) no. xiii — ALEX · VIR (.....?)

IR/COE(?)

(1) Newstead (p. 265 ff. 35, 12);

15c 175.

## ALPIN[

Neronian. W. early Flavian.

ALPINUS (or possibly ALPIANUS) ~~2A. 11115~~

- (i) Oxford (A. Cant. xlii, 167 H. 32 ~~AKPIN.FE - Messer~~) <sup>Kiln 1930</sup> ~~MS~~ <sup>JRS also Maidstone HK</sup> Soft orange-red stamped diagonally down flange; l. facing; fine-textured but v. friable-terra-cotta colour; possibly a slip of same colour; v. roughly finished. Not to be confused with ANBINUS

Oxford [do. H. 33 Maidstone SK] flange fragment; stamped diagonally; stamp poorly impressed and is a second effort, the first having been apparently smoothed; from a similar vessel - could even be from same one; same fabric.

[NB Oxford - another unstamped <sup>(at least on one side surviving)</sup> mortar clearly from same workshop same fabric & shape finish but less clumsy.]

ALPINE

Maidstone Mus. from '0

82A. 1908


AMENUS? Jar ~~MALLI~~ ~~Atmenis~~?

Wilderspool [Warr. M. 137'01 11K] soft, <sup>fine textured brownish</sup> smooth, pale orange fabric with light  
bluish <sup>traced cream slip.</sup> grey ~~core~~ <sup>argill & medium-sized, prolific black + whitish, pale + red-</sup>  
<sup>+ whitish quartz like</sup> sporadic to b. D = c. 11 1/2. <sup>two stamps, could be same vessel but not</sup>  
<sup>certainly so</sup> label saying Wilderspool 1899, stuck on. Dr. = 29 cms.

Wilderspool [66 F7 (1) (46)] L. facing. Basically a fine-textured orange-brown  
fabric but contains vast amount of tiny sandy particles; abundant grit -  
translucent whitish, grey, white + brown medium to tiny. Dr. = 10 1/2" 86K

Wilderspool [Warr. M. 89K Old] see no. 11K. The stamps are differently  
arranged, so are more likely to be from a different vessel than the same.

NB 11K fabric had heavily tempered with much fine sandy material  
to make it slip a bracing to touch



1903-1907 98

d. 10  
m. 1  
n. 1

AMMINVS?

Colchester

Colchester [P3186 <sup>431</sup> MID 1269 <sup>775</sup> Tz 285 S16] Δ

Colchester [P5633 BKC V658 S17] Fragment probably  
from different vessel.

AMMINVS

Source unknown; ? Bradwell-on-Sea. Hull 1963, p. 9 footnote.

Colchester M [63.29 no 342K.] slightly coarse cream; near 285K (REACTIS) - a

Colchester, Butt Rd, Kiln [49K] cream fabric, smallish white, black + grey grit.

[Hull 1963 p. 9 Research Report. fig. 58, no. 26B. M.R. Hull "The date of this rim should be late second century or possibly early third, though the latter date is rather late for legible stamps."



AMM IV S graffiti (before)

Venlaminum [202K Ver. Mus. VA. IV. 33. T. T. South of Red House  
Wheeler 1933] Description sent by A. Havercroft "Frag. of nit  
spout only in very coarse ware - buff-yellow with orange-red  
inclusions (occasional) <sup>and</sup> with rounded quartz ~~var~~ grains which  
give the surface a speckly appearance. On the surviving  
piece the intimation grits are rare but grey, white, brown &  
red grit can be seen. Decoration by incised line. Photograph

Check refs in Cat of M. of London Antiquities CRS 1854 p. 16.  
CIL VII 133418 ~~sq~~ (not seen) London; R. London CRS. p. 89.

AMSOR

902A (?)

Colchester. Mrs Rep 1931, 25

123

456

789

012

345

678

901

234

T. IV. AF

A.F. - cf. IV. AF, T.

---

- Chester [Ring o' Bells 1940, Box 80; CAS. xx xvi, pt. 2, p<sup>98</sup>~~99~~.5] 13K; <sup>fabric</sup>creamy buff  
<sup>core</sup> fabric; l. facing; brownish buff, sandy; lighter surface; drab, <sup>buff</sup> <sup>side</sup> ~~cream slip~~.  
 Chester [no provenance; Box <sup>211</sup>~~15~~; 17K] internal rilling; white, grey, brown gut,  
 none on rim. l. facing. BF. 34/38. Definitely Venetian fabric.

AWBTOVND

CHESTER RINGO BELLS 1960 (25) BK. 17

Anaus WSP 241  
Walksend [WAL (E14) 1 SF 1458 8K] L-facing Dr. 2 1/2 cms.

pale orange-brown fabric (Munsell  
iv<sup>tan</sup> cream at surface buff-brown slip. (At x20) Inclusions:  
moderate to fairly frequent, large to tiny, random. Mostly  
quartz, rare brown. No tubulation yet survives. Die A

WSP 245  
Walksend [WAL (G4) 1 Context 94-1 SF no 189 11K] FF  
Fine textured, powdery, drab cream fabric; probably  
self-coloured. Inclusions: fairly frequent, absolutely tiny  
almost all quartz, v v rare o/b and possibly flk.  
L-facing. Die A

ANAVS

Walsend 9

Walsend (2)

[WSP545 4161 WV97 <sup>45</sup>~~50~~g. 6K] r. facing.

Hard, fine-textured, pale orange-brown matrix  
(Munsell 7.5YR 7/6); ill-sorted, fairly frequent  
mostly quartz with moderate brown<sup>dk.</sup> and blackish material  
(probably both slag). Thick cream slip. 1 quartz inclusion  
grit survives. 2 open cracks across bead - second?  
Dr. not possible. Stamp fragmentary. die 1

ANAVS (and other numbers?) 97 or 197 on draft to surface  
Wallsend [WAL NS 23 (9 sherds) and WAL NS 19 (4<sup>3</sup>/<sub>4</sub> sherds)]  
WSP 2.55  
Other breaks modern? 18 sherds in all. SF ~~29~~ 7K] L and  
r. facing. Dr. <sup>30</sup> 29 cm. More than <sup>3</sup>/<sub>4</sub> s.d. vessel survives.  
slip worn away over whole of inside. Orange-brown  
fabric (Munsell ) throughout except for thin trail  
of buff brown in centre flange & <sup>top</sup> edge of base. Inclusions:  
(x20) fairly frequent, random, ill-sorted mostly quartz,  
<sup>few</sup> some (much much less) black and red brown fragments; cream  
slip. Inturation grit: mostly concentrated in base:  
large (up to 7mm) <sup>r-b</sup> sandstone, quartz, <sup>+ 9/12 sandstone</sup> Base Dr. 11.5 to 12 cm.

ANAVS  
Wallsend [WAL <sup>WSP 239</sup> (E9) 41 SF-2368 12K] FF. ~~Some burning~~ A

~~made of large possibly but uncertain~~. Orange-brown fabric (Munsell ) throughout except for 2mm <sup>padding</sup> on underside changing to only surface (thickness of slip) on the small fragment. DK slip if any. Inclusions: fairly frequent, ill-sorted, tiny to smallish, mostly quartz with rare v/b and black. r. facing. A

Wallsend [<sup>WSP 96</sup> no SF Context Q04.-35 loc - phase v/s 36K WSP96]

178g. Diam. 280mm 19% parts of C. and r. facing stamps survive. Hard, orange-brown fabric throughout with cream slip. Fairly frequent, tiny to small inclusions are A mostly quartz with v. rare black. Only spart (like 7K + 8K) + f. frag


remains - plain end - Not split. <sup>at distal end</sup> ~~not obvious.~~

ANAPS  
Willsend [WSP 562 7310 WF98 16K] Land r. facing.

Diam. 26cm. More than  $\frac{3}{4}$  of vessel. Self-colored. Cream at  $\frac{2}{3}$  towards inside surface and brownish-cream to outside.

Crumby. Inclusions: fairly frequent v. tiny quartz, black trace r/b in matrix only visible at x20. Also a few random, large, red-brown, blackish and probably quartz.

Interstratification: Large to medium, ill sorted, angular, sandstone quartz, quartz sandstone mostly in base but some <sup>med. sized</sup> higher. Graffito on outside. Distal bead and groove in end of flange. Could be Corbridge cream but a v. poor version compared to Cudae (Bridgeton) Graffito on outside. A



Context P4-10 SF no 170 15K] Lfacing with dent  
 in end of spout. Diam. c28cms. Very hard orange-  
 brown fabric (Munsell ) with thinish grey  
 core. Cream slip. Inclusions: fairly frequent, <sup>117 scattered</sup> v. tiny  
 and smallish, random inclusions mostly quartz with few  
 red-brown (x20). Fine-textured. Interiation: all quartz  
 mostly in lower half of vessel medium sized, angular. Die B  
 Modern break as WAL N5-23. Possible <sup>Different pot</sup> extra sherds:  
 1 base sherd P4-10 definitely similar m. but not  
 necessarily this; 8 joining sherds all with modern breaks.

ANAVS Context 95-6 WSP 246  
Walsend [WAL (95) 6 SF 403 9K] L-facing. Dr. 2<sup>g</sup> cms

Orange-brown, fine-textured (Munsell ) fabric with thin buff-brownish core in flange. No part of body or intonation survives. Inclusions: fairly frequent, mostly small to tiny inclusions with few larger ones. Mostly quartz with some red-brown. Cream slip Die C

Walsend [SF No. 511 Context N4-21 10K] FF. Orange brown with lighter almost drab cream core. Inclusions: fairly frequent, ill-sorted, mostly quartz, some black and r/b cream slip. Fragmentary stamp <sup>probably</sup> attributed ANAVS ? B

ANAVG  
5688  
Walsend [WSP549 WF98 17K] Ltr. facing. Diam. 26cms

Extremely hard orange-brown fabric (Munsell ) with  
v. thick, well-defined blue-black core (Munsell )

Inclusions: moderate, random, ill-sorted quartz and coarse  
black and red-brown. cream-slips only worn round edged  
base and in bottom half interior. Inclusion: medium  
and smallish quartz, red-brown sandstone, blackish, and quartz  
sandstone. Although constituents similar to 16K the grit is  
better prepared and seems to be more evenly distributed.

Deep groove made by instrument - bone, wood etc. L-facing  
has a border on one side.

ANAVS

Walsend [WSP 153 <sup>context</sup> Kill-3 noSF phase 15. 40K] 20g. Flange

Frequent in slightly pardeny, very pale brown fabric with slightly greenish-grey core and cream slip. Fairly frequent or frequent, ill-sorted inclusions consisting of quartz with rare brown material. Broken and partly impressed stamp from die 1A of Anaus.

~~Walsend [WSP 545 4161 / WV 97 53K] r. facing. 45g. <sup>50%</sup> 2 joining  
shards. hard orange-brown (Mussell) with thick  
cream slip. Inclusions: tiny, fairly frequent, mostly quartz,  
some black? slag. Intentional included quartz A~~

ANAVS  
Wallsend [WAL (N5) 2 SF no (62) 13K] FF. Cream slip.

Very hard fine textured orange-brown fabric (Munsell )  
with thick blackish core. Inclusions: moderate to fairly  
frequent tiny to small inclusions; mostly quartz with  
some red-brown pebbly inclusions. Diam. c 26 cms. Die B  
Other possible sherds N5-23 (1 sherd); N4-11 (4 tiny joining FF).  
+ 1 not joining.

Wallsend [WSP 254  
WAL (N5) 7 (6 sherds) / WAL (N5) 23 (1 sherd) all join  
SF 296 14K] L facing. Diam. 29 cms. Very hard, fine-  
textured, orange-brown fabric (Munsell ) with buff-brown  
core (Munsell ) and cream slip. Inclusions: (x20)  
fairly frequent but extremely tiny mostly quartz, some r/b. PTO  
B

ANAVS  
Walsend ~~(N5) WAL~~

<sup>14K</sup>  
(Extra sherds probably belonging to this pot but not joining  
N5 - 7 (1 sherd))

Intonation: all quartz, largish to smallish, angular <sup>chunky</sup> <sub>rich</sub>  
milky but not as white as Caerleon gnt. Four grooves on the side  
in upper half of vessel. Dr 29 cm.

? ANAVS Almost certainly

Wallsend [WSP95 H14-23 37K] 290mm 23% 444g. r. fac.

Five joining sherds making up c. a  $\frac{1}{4}$  of matanium in orange-brown fabric with drab, greyish core with traces of cream slip. (Sample

frequent inclusions mostly  $q_{ual} \bar{z}$  with some red-brown material. Abundant inclusions <sup>grit</sup> is mostly quartz with quartz sandstone + red-brown material (?ss). Worn. One

letter survives, too fragmentary for certain identification but could well be the reversed  $\bar{z}$  in middle of Anaus die 1 Bi. Spont similar to Anaus 17K Wallsend.

Wallsend [WSP98 H15-6 38K] FF. Hard orange-brown with drab greyish core; traces of cream slip; moderate inclusions, ill-

sorted, mostly quartz, rare black + red-brown. (sampled) B?

Colbridge [S.160 [IA] Drawn (S) g) / X, 47; 280K] L-facing; softish, sandy,

orange-buff fabric with cream slip; no grit; Approx Type 1 Bi rim. A

Colbridge [S.125; 355; Drawn 5a, / X, 47; 287K] r-facing; hard, yellowish buff fabric; no grit; probably drawn as 1Ai. A

South Shields [AA<sup>2</sup> facing p. 274, no. 16; 19. IV. 815; 14/56. L. 28. 6. 79. JMN/457

14/55; Mrs. Acc<sup>n</sup> no. 1956. 128. 27. A; King's College N. 5K].

stamped each side of spat ie. two pieces probably from

same vessel but not joining; brownish fabric with grey core. Nos 1-2 in Dove & Gull am 1979. A

Find others?

Corbridge [Us. 42; Drawn ⑤ L/XI, 47; EAS 14; [C] 279K] l. facing; brick red

fabric with grey core, with cream slip, hard fabric; 1 brown grit. C

Benwell [But 38, <sup>AA4 XXXIII - Box 7</sup> Bin 1938, Box 9 no. 4a, <sup>probably a different pot from 29K</sup> r. facing; 306K; ✓

orangy-pink fabric with cream slip; like 1A; without cleft. ✓ C

Binchester [Bin ②; B. 4. 54; See KAS. pl. XLIX + p. 153; Durham 8K] hard, red fabric with cream slip; small and medium, rounded quartz grits. Δ C

Binchester [BIN H11; Durham DC 8; See KAS. pl. XLIX no. 9 + p. 153] r. facing; orange-brown fabric with cream slip white and brown grit; stamped twice together. Δ C

ANAVUS

London Bow Bells House (BBB05 Context 1355 Acc <856)

Building 27 Pd. 8 831K) r. Facing 75gms. Diam 300 mm s.  
905%. Hard, orange-brown fabric smallish grey core, fairly  
well-defined. Cream slip. In fine-textured. Inclusions:  
fairly frequent, very small to small, quartz, with some  
dark red-brown + black material. Inclusions:  
included quartz, quartz sandstone + red-brown material  
(only 1 eq. of each).

B

ANPUS

Böchergrate, Carlisle - site  
L200/151. Context 198/1464 ~~245K~~ 245K Phase 5.


Context 198 is ~~with~~ in upper filling of well. Context contains medieval pottery. (facing) Pinkish cream fabric with drab cream core, quite thick in places. Inclusions: ~~fairly~~ frequent but most of it sand-sized making fabric slightly abrasive, mostly quartz, some red-brown and black plus moderate medium to large quartz, red-brown, dark red/black? slag). Appears to be self-colored or self-colored slip. No tinting - gut survives. 100g 2 joining sherd because end of spat had flaked off.

ANAVS

Attributed on border fragment die as 245K

Bot chergate, Carlisle [L200/151. Lated 370/1698 246K Phase 2]

r. facing with stamp very clear to spot. Spot similar to Anavo  
245K. Pinkish (dusty) fabric with thick greyish cream to near  
surface. Fine-textured. Inclusions: abundant sand-sized  
almost all small to see with moderate small <sup>sub-rounded</sup> quartz, black &  
red-brown material. No <sup>black sub-rounded</sup> striae. No  
indication of slip. Slightly pearly. ? self coloured



ANAVS

Attributed unstamped fragments:

Bücherle A 2454 · 79.2 131.N · with groove in  
distal end of flange.

Corbridge - 15 1938 - AA<sup>4</sup> xxvi p.174. Fabrics re-examined 1963 -

a.) Red-buff cream slip, sometimes with grey core; white, red-brown and grey gut, & translucent white; hard & finish texture [XII. C. 6/4 LIII etc / US. 39/69 / 42/40 / 38/41/36/ and S. 391/105/159 / 106/31/96/321 / 21/4 / 305 / 7/160 / 392 (says S 75 on dth side) / ① / ① / 39 / 46 XII B below LI 30/7/47, ①, 1947.

b.) ~~Pinkish red or red-brown fabric sometimes with grey core; usually fine & softish; cream slip; translucent white & brown (s.s type); large to small; sometimes sandy; S. 34/63 / 395/153 / 390/112 / 303 / and US 22/21.~~

Other fabric: hard, creamy buff flecked with tiny grit; brown  
+ translucent whitish grit seen - fragments.

S. 127 || S. 110 | no. no. | §. 109.

John Dove (1988-9). See S. Shields report p. 160,  
no 1-8. Suggests 130 - 170 for various at wallsend.

<sup>M?</sup>  
 JHN/658/ No. 3 in Dore + Gilligan  
 South Shields [Box 658; 1956/128/115A with label saying on log for R. Blair;

Kings College H. Possibly AA<sup>2</sup>X facing p. 274, no. ~~14~~ <sup>no. 14</sup> <sub>possibly</sub> L. facing.

pinkish brown fabric with blue grey core; white, grey + brown grit. 3KB

South Shields [At Site Museum. <sup>no. 8 in Dore + Gilligan</sup> Fragmentary flange; orange-brn 8K  
 fabric; <sup>grey core</sup> drab core; cream slip. Seen 1963 from cupboard in stone room.

Binchester [Bowes Museum. Seen 1966. 1K. 1958/15.P40] Very hard, heavily  
 gritted, buff fabric with drab, greyish core and orangy slip; very  
 abundant grit - white (quartz?), brown and grey, tiny to largish.

Quite badly distorted but no doubt usable. A new die. D

Check the section of this to make sure it is diff. vessel D  
 can't find A. 1995

J. Collingwood Bruce, On the recent discoveries in the  
Roman Camp on the <sup>LAWE</sup> ledge, South Shields. 223-310

in AA2 <sup>MS.</sup> X (1884) (the volume says 1885).

Corbridge (24 eqs. B. 1938) (AA<sup>o</sup> XXVI p. 174) fine hard clay, light reddish brown fabric with pinkish-grey core, sometimes with white slip (grit vaines in size, usually brought in... begins at base)  
 Report (p. 26 of 35, 20),

South Shields (5) (AA<sup>2</sup> X, ~~175~~<sup>being p. 27/4</sup>) [Hooppell p. 32 no. 69] nos. 73, 14, 16, 17, 20, 21  
 Those not in Dave Tillam are missing  
 to Murray die B. look in S. Studd's folder.  
 in Dave Tillam.

Bainbridge (Droop fig. 1, 1); misinterpreted from Report by B. 2. to Murray die L. S. ] NB

Binchester (6) (KAS. 100, 11, 20) B. 2

Carthage (3) (T.H.C. 141, 142) red with blue core, drab slip. Bla. gnt

 **ANAN**  
18. Corbridge, Carlisle

**ANSE**  
19. Corbridge.

**V'NSP**

 **ANAN**  
18. Corbridge.

 **ANAS**  
19. Corbridge.

iv S. Shields (from ?)

**ANAN**  
1c.

**ANAN**  
1d.

 **ANAS**  
1e.

**ANAS**  
iii S. Shields from ?

**MAV**  
ii. Newstead.

ANANS Beuwell Vallen Filling - late 3rd of <sup>15th</sup> century (1500) (Liberale Swell - aft. AD 160 found at  
Risingham, nothing pre-Antoine; (Parsenburgh - not earlier = AD 160) 1588  
(ltad: fact also) = AD 135-175

Beuwell [Bul. '38 ▽; At Durham 1963; 28K] l. facing; worn, poor  
impression; orange-brown fabric with cream slip; brown & colorless, medium  
- sized in piece. C

Beuwell [Bul. 1938 Box 9. no 4a. At Durham 1963. 29K] l. facing  
red-brown fabric with cream slip; no gilt or fragment; grooves down  
side of letters. Similar to 28K in form. C

Beuwell [Bul. 38. Box no. 2a + 2b. At Durham 1963. 30K] striped  
each side - 2 pieces joining; pinkish orange fabric & cream slip;  
largish to smallish, white, brown & gray gits. C

[These ~~strips~~ were previously seen at Carbridge].  
+ may be entered twice!

~~Box~~ Bennell Vallum AA4 xxxiii (1955) fig. 5 p. 159, Box 7 & p. 161.

Box 7 1-8. Ledge fragments from 8 mortaria in orange fabric with  
cream slip topaque white thrown glaze; all are assignable to the pottery  
Anous, six of the exx having the characteristic groove at the edge  
of the rim, & 2 carrying stamps. The peak of the pottery  
activity is believed to have fallen between the years AD. 160  
& 180 - B. Swinbank, Pottery from levels of the 2 + 3 century,  
covering the Vallum at Bennell 142-162.

Benwell [AA<sup>4</sup> IV, p. 167, fig. 6, no. 2] unstratified. ? = 10K

Benwell [AA<sup>4</sup> IV p. 167, fig. 6, no. 5.]

Benwell. (Sent to Malin in Nov. 1964 from Durham.)

Benwell (AA4 XXXIII (1955) fig 5 nos 1 and 2 cannot  
identify from rubbings. Die C

B OV die clay

AT Carb. I in Ant: II

ANAVS (contd)

~~(4) Chesters~~

Housesteads B<sup>2</sup>


Risingham (PSAN<sup>2</sup> vi., 146) FIND NEVER seen  
~~bridge (S14)~~;

~~Barnwell (AA<sup>4</sup> p. 171, 170-171, 173)~~, Checks.

Bireus - unstamped rim assigned by B<sup>2</sup>.


~~Birtwistle (3) = K.B.~~

Birley thinks Templeborough no. 19 may be his cipher type.  
London, New Cannon #1. [SBA-A - X p 193] c. NO! Sir



T.H.C. 141 + 142  
9 pl. xvii 1a 7b

Red with blue core: drab slip  
Black grit (iron oxide?)



= 26 K Bank St, Carlisle  
(Museum).

ANAVS (He can have all qtz <sup>tituration</sup>  
TL 142079


Folly Lane, St. Albans [A91/5 CSC  $\Delta$  HK] <sup>ass</sup> L facing. Dr. 30cm

Orange-brown fabric merging <sup>buff-brown</sup> to thin core width in core of grey  
in flange and at the side of the base where the  
clay is thicker. Inclusions: fairly frequent, tiny, and  
small sized <sup>to medium</sup> angular quartz mostly, some black <sup>opaque brown</sup>. Tituration:  
entirely quartz (large and medium with hackly fracture.  
No indication of any slip. Worn in base. Fabric feels  
abrasive. Stamp worn. Retro grade reading possible  
(~~V.A.V~~) probably high sand content. Fabric eroded to  
ANAVS die B) some extent but definitely worn. Tit<sup>n</sup>  
WORN away in most of base. Die 2

ANAVS

Halton Chesters [HALT 99.115 A. Groom 31/1/01 2K] Flange frequent  
in herd, orange-brown fabric <sup>with mid-green core</sup> with traces of cream slip. Inclusions:  
fairly frequent, tiny quartz with some red-brown material and rare  
black. ~~Dr. 2 lens 10% 85g~~ 10g, 4% Should be different  
pot from earlier finds

B+G | B<sub>11</sub>



ANAVS

Assigned

Chesters [1816/2043; 2K] probably ANAVS "B" but heavily restored  
over half of stamp which survives; r-facing survives; soft, reddish  
fabric, with cream slip; little brown grit. D =  $10\frac{1}{4}$ ". Restored. B

Birdoswald [B'd 1931. J.P.G's stone at Newcastle 25K] v. facing; no

rubbing; pink, slightly sandy fabric; cream slip; brown grit. ?B

Birdoswald [1932. Seen in 1964 at Carbridge] l. facing brownish

<sup>B</sup> pink fabric with creamier core; cream slip; (Black layer at base of rampart. Section west of south-east angle-tower).<sup>o</sup>  
written on sherd. A

Binchester [1958/15. PH. 4K. Bowes N.] Hard, orangy brown fabric well-tempered with grit; surface paler, almost buff but not a slip. Much white quartz-like and some small brown grit. D

Binchester [1958/15. PH.2. Bowes M.6K] Stamped each side. r. side 7. Hard, orange-red; drab core in places; creamy buff slip; white, red-brown grit. Mortarium rather distorted. A

Bowes [Bow 67D I 1a] 3K Flange fragment. Pinkish brown compact fine textured fabric but containing of tiny gritty particles; creamy slip. ?  
 have SSF + BRH Archer no 7/a I(A)

S. Shields [P311 15550 SS88 30K] L-facing. P. Bidwell <sup>seen</sup> 1991.

Hard, brownish-buff fabric with paler core in flange; fairly frequent quartz, black + red-brown inclusions; no tubulation on the piece. <sup>No slip noted</sup> Die 1

S. Shields [P227 152 SS 1978 31K] <sup>P. Bidwell seen 1991</sup> flange frequent. Hard, orange-brown fabric (5YR 6/6), with thin pale grey core (5Y 7/1) in flange + cream slip. Moderate quartz + red brown + black inclusions, but possible iron compounds. Die 1

S. Shields [P152 13081 SS86 32K] <sup>seen</sup> P. Bidwell 1991 r-facing. Die 2  
5 small sherds (3 joining) perhaps finer textured than 31K but similar colour (0/62. 5YR 6/8) + grey 5Y 6/1. Cream slip. No tubulation PTD

Survives. Clearly made at same source as 31K.

---

ANAES

S. Shields - 2 joining sheds -  
[S.S. 70 AT 33K] Seen P. Bidwell <sup>Roma Fort 1991</sup> ~~How~~ Die 2

presumed r. facing. V. hard fabric exactly as 32K but  
<sup>2.5 YR 5/8</sup> no core in mid-body. Perhaps harder than 32K; core slightly  
<sup>5Y 5/1</sup> darker. Clearly from same source. Inturation gut quartz  
& sandstone with rare, hard red-brown material Dr. 23cm Die 2

S. Shields [SS 78 L 53 M 410 34K] b. fac. 3 pieces, 2 joining.  
Seen P. Bidwell R. Fort 1991. Hand fabric pale like 30K & 31K.

Pink-brown, surface-textured 5YR 7/7 with 5Y 7/1 core but v. pale  
creamship. Moderate v. tiny inclusions as before. Inturation gut  
as before. Dr. 27cm. Die 2

All of Anaes from S. Shields, seen in 1991 are from one source.

537

Add

Bis.

✓ r. facing.

Piercebridge [~~208~~] HS 77 22.3 BC or HS 77 15.2 BC. ~~208~~ Hard

orange fabric (5YR 6/6), <sup>tainy</sup> fine texture, inclusions quartz and black fragments. No trituration survives. FF with <sup>PTO</sup> 9 deeply impressed stamp, die 9. Thick cream slip. ~~208~~ (B)

Piercebridge [~~403~~] TF 74 28C (583). 7K] FF.?, joins another <sup>PTO</sup> FF piece, plus same vessel as further 4 pieces including right spout. Hard orange fabric (5YR 6/8) with <sup>PTO</sup> fine texture, inclusions quartz and black fragments, slightly micaceous, occasional large inclusions (3mm) red-brown material, quartz and yellow-brown pebbles? (trituration) grit fine (1-2mm) quartz and <sup>mostly</sup> brownish-black <sup>one</sup>. Thick cream slip. PTO Die 8 (B)

8K Inclusions: moderate to fairly frequent, medium to tiny sized  
Die J

7K Inclusion: mostly quartz, tiny & black; moderate plus  
occasional larger quartz, angular & yellowish-cream  
pebbles.

~~Inclusion: moderate, tiny black & quartz  
Either Die 3 or Die 8? ✓~~

Int pit is on non joining fragment.

ANAVS

3 from 9 fragments

See stamp report.

from change in bead  
r. facing and smooth

Piercebridge [402 Arch. TF 74 28C (375) 10k] / Hard orange fabric


with ~~light grey~~ <sup>light grey</sup> grey core; <sup>fairly frequent</sup> inclusions quartz <sup>mainly</sup>  
~~and red-brown fragments~~ <sup>black</sup> <sup>PTO</sup> Little <sup>2-3</sup> intonation, grit survives, some  
~~DK slip self-coloured slip~~ <sup>cream slip</sup> quartz, fired to pale brown-cream at surface. Dr. 32 DIE 18 ANAVS

Cattenck Bridge [240 - 626 - (104) 2K] <sup>Phase 7 p. 467 MS 24</sup> CEO. FF + bead. Hard,  
orange-brown fabric with thick dark grey core; some quartz  
inclusions with occasional red-brown inclusions. cream slip. <sup>Residual</sup> D9I

Cattenck Racecourse [273 <sup>Had/Paint</sup> - 512 (29) 6K] l. facing. Very hard, dense,  
orange-brown fabric with thin grey core. Moderate ill-sorted quartz  
occasional red-brown & black; intonation mostly quartz occasional red-brown  
cream slip. Dent in summit of nos. 1 p. 479 MS 30 Phase 1 Dr. 26 <sup>FABRIC</sup> MB 16 B

Pavement bridge  
Inclusions: ill-sorted / fairly frequent, mostly quartz, few  
Black red-brown. Not certain if a slip

Catt Race course bk Phases /  
Hardmanite - primary part



ANAPUS

Possibly  
ANAPUS II

Bowes [unstratified from vicus at Bowes] facing  
spout with

stamps either side. Pinkish fabric, moderate, ill-sorted inclusions  
quartz (upto 2mm.) rare <sup>black</sup> red-brown fragments. No trituration grit  
survives. Softish

A



break  
Unstratified from  
vicus at Bowes

Corbridge [IA]; S 96; EAN; ⑤ XI/47, c.; 260K] pink core to buff, cream or buff slip; l. facing. G

Corbridge [IE]; v s 37; EAS; ⑤ m; XI/47; 262K] dark, greyish brown fabric, surface seems to be black; misfired(?) E

Hall on Chester [At Newcastle <sup>in Under 18 Floor</sup> 1963. HAL EU 60; 37K] l. facing; flange & head fragment; pink-brown fabric; grey core; cream slip; hard C

Northy Cahole [Tullie House. 66K] seen 1963. not red fabric with cream slip. A

Chester-le-Street [1886; <sup>check</sup> PSAN<sup>2</sup> p. 287 + PSAN<sup>3</sup> X, p. 31; Box 192; 156. 75. A; Kings College Museum] l. facing; pale buff fabric with brown & wh. grit A

Benwell [At. Corbridge AA<sup>4</sup> ~~XXXX~~ = 28K possibly (Durham) Bul. '38 v.; 305K] L-facing; slightly sandy, slightly ~~orange~~ <sup>orange</sup>

~~orange~~, buff fabric with cream slip; Approx IAi = 28K ✓ C#

Carraburgh [Mithraeum HZ 52; at Corbridge; unpublished; 100K];

L-facing; dark grey-black core changing to brick-orange, with cream-buff surface; much, largest to smallest, grey, black, r/b, grit, unevenly spread, to b.b; very coarse signs of internal scoring. <sup>Corbridge</sup> B

Benwell [1938 Vallum filling; <sup>Box 7</sup> Box 9; Bn. 1938, N. 26; Bul. '38 v. 2, 1; 301K]

r-facing; hard, orange buff fabric with cream slip; largest to medium, r/b, grey, whitish grit. Type IAi exactly. Die B. as 2.98K B

ANAVS

Carlisle [Civic Centre Site. Tullis Ho. 49. 1965.6 97K] Very hard,  
muddy buff fabric with thin grey core A D  
Birdswood [v/s flower bed int. T. Wilcott 65K] Meally kind  
of texture. Very pale, brownish almost creamy brown (6.5 YR 7/4)  
with <sup>thick</sup> light grey core (10 YR 7/1) merging into surface color.  
Inclusions: moderate quartz & red-brown sandstone. Tituration grit: fairly  
frequent, white quartz & red-brown sandstone; occasional soft tile.  
Cream slip. Dv. 33 cms. r-facing plus fragy l-facing. Well-worn

ANAVS

Carlsle Millennium excavations [CAR 98 (245) MIL Tr 1

251K] Some cracking under flange reason unknown.

125 gm. Diam 260mm 10% Hard, orange-brown fabric with very thick well-defined, light blue-grey core.

Buttercream slip. Inclusions: fairly frequent, tiny to smallish, opaque and somewhat vesicular black material and less dominant quartz, rare red-brown and quartz sandstone. Interstratification: abundant, small to medium, quartz (dominant) quartz sandstone, rare red-brown and black material. No wear or sherd. (109) same pot.

Bronghunder - Stainmore. [Small find no (97) Bus 72.XIV (15) in layer

also containing @ pottery [Michael Jones] v. facing brownish orange fabric with cream slip - no grit on fabric. A Δ

Piercebridge [HS 79 20.7 YK 2 (1954). 9K] Very hard, sintered,

purplish-grey fabric (SYR 7/1) with darker grey core, inclusions of <sup>fine</sup> ~~subhedral~~ <sup>+ voids</sup> v. ill-crystallized transparent quartz and large black fragments (2mm). Trituration

grit does not survive, though piece of quartz on flange.

Fired to <sup>intended colour</sup> orange colour <sup>bottom of flange</sup> in places <sup>near</sup> surface <sup>PTO</sup> DIE 4 D

Catterick [H. VI (8) 1959 13K 444 in archive] Flange fragment.

Dr. 35 cms (2%) ? is there a description anywhere? <sup>YES</sup> bis I  
Phase 2 p 340, MS 43 AD 125-60!

Pierce  
intended to be 0/6 - outside skin only. Not possible to know about  
slip

Watercrock sent by D.C.A. Shotton, Bowland College, Bailrigg,  
Lancaster. W 72/60. Fine textured red-brown fabric with dark  
green core + cream slips. Grit not distinguishable  
but seems to contain red-brown r. facing. Fragment C  
Lancaster [LW 75 XXI. 23K] l. facing burnt. St. sandy  
brown buff fabric; 1 quartz grit on fragment. A

Different vessel from DC9. Phase <sup>8a</sup> Residual

PTO →

Biochester [BIN 77 ~~799~~ A357. S.17. 6k Louisa Gidney] 2 stamps  
 - brown moderately sanded

right and left facing. Orange fabric (SYR 7/6), inclusions mostly  
 transparent quartz and ~~Some black + v rare~~ red-brown fragments. Trituration grit does not  
 covered with slip. Inner surface very irregular with lumps of clay. DIE A  
 survive, but, <sup>groom 1</sup> surface very irregular with lumps of clay. Dr. 26

Biochester [BIN 77 A 378 77-121 ~~249~~ 7k] CRS l. fac. joins  
 Hard

[BIN 79.2 A1801 ~~2169~~ 8k FF. l. fac.] Yellowish-orange fabric  
 fired to near cream at surface. Inclusions quartz and v. occasional black and red-brown fragments

Trituration grit quartz (2mm). Dr. 27 CMS. cream slip DIE ~~H~~ H  
 Inclusions: moderate to fairly frequent. Flange smooth if fairly regular.  
 concentric scoring  
 unworn

Coarse irregular scumming!

6K: Fired to near cream at surface. ~~Trace only~~ Matt orange-brown

slip. Mild groove <sup>under</sup> distal end of flange. ~~7~~ joining fragments  
inclusions: fairly frequent, moderately sorted; tiny brownish.  
fired to paler colour? cream at surface only.

NB 7/8K is much lighter in colour than the rest from Jones' dig.

6K The L-facing stamp reads inward from the <sup>distal</sup> outside of flange  
The r-facing reads from the inside outward.

ANAS

Phase 9 Residual

Binchester [79.2 BIN A2068 b 22K] L-facing Flange + spot

fragment. V Hard, fine-textured matrix orange-brown, with <sup>thick</sup> cream slip. Inclusions: moderate to fairly frequent, ill-sorted, mostly quartz, transparent and rare opaque black + red-brown fragments. Stamp impressed too close to spot as with bK.

Die B

~~[unmarked] L-facing~~

ANAVS

and orange brown lines  
with greyish brown parts

Binchester [79.3 Fieldwalking 23K] FF. Drab pale brown fabric  
~~not~~ hard ~~softish~~. Fairly frequent, ill-sorted  
inclusions: <sup>mostly</sup> some ~~very~~ quartz, rarer  
black to red-brown. (Die A) The flaking of clay from the  
flange suggests that this is the r. facing stamp.

ANAVS

Different mountains <sup>from PTO</sup> [22K

Binchester [BIN 70 AM 78:34 (1453) Sample (16) .9K] r. facing  
with thin ~~pink~~ grey core ill-sorted <sup>to smallish.</sup>

Hard, orange fabric (5YR 6/6), inclusions <sup>mostly</sup> transparent quartz, <sup>some</sup> ~~and some~~  
black & rare red-brown fragments. Trituration grit / quartz, cream slip. ✓ DIE B  
Dr. 27 cms. Inclusions: fairly frequent. Fine textured. ~~Probably~~

no concentric zoning ~~across~~ away at bead level.

Binchester [BIN 78. A536C 25K] Flange frequent, very <sup>streak</sup> ~~streak~~  
orange-brown fabric with <sup>shades</sup> orange-brown matt slip. <sup>thick blue-grey</sup> grey core <sup>ilk</sup>

Inclusions: moderate to fairly frequent quartz, ill-sorted. Rare  
black and red-brown fragments. ~~Attributed to D1-D~~ ✓

Stamp not identified with certainty probably Anavs

I have seen 6 Binchester Anasomatina  
at Durham and 3 at Bowes Mus. C.

Could any of these be ones which I have  
here? I think not!

ANAVS No stamp or survival fragments but duples in  
Fairdale, Darlington [FAV04 Context 616, Mat. 15]

$\frac{3}{4}$  of spent survives. At least 3 young fragments,  
195 gms. Diam c 260 mm, 11% Matarium has  
fractured and <sup>flaked</sup> ~~coached~~ along hairline cracks  
Fabric: abrasive, As but brittle / Misfired to grey  
with buff tones; the inner half of fabric of body  
is yellowish-brown, with outside  $\frac{2}{3}$  grey. Traces  
of a cream slip. It appears to be grossly  
overfired & texture brittle but not misshapen  
in any way. In theory a waste but may have  
been usable though it does not appear to have so.

been used. Broken rudimentary concentric scoring on inside. Apparently used. Dimples in spout.

Interruption gut: mixed quartz & quartz sandstone with some red-brown material. Faverdale, Darlington [FAV04 (614) Mat 16] Spout fired black throughout. Dimples in ends of spout. Thin hairline crack. 100 grams.

ANAVS

No dimples in ~~the~~ IK ~~2K~~

Mar 14

Faverdale, Darlington [FAV 04 Fontest 1303 1K] L

† <sup>some burning before fracture</sup> facing 270gms. Diam 290mm 18%. Abrasive, orange-brown fabric with traces cream slip. Inclusions: fairly frequent & frequent, ill-sorted, mostly quartz, few opaque black and red-brown material. A few quartz & 1 red-brown inclusion gits survive. die 1

Faverdale, Darlington [FAV 04 Unstratified 2K]

L facing. two joining sherds including spout & 1 B.B. Sherd which should belong, 220gms 125gms. Diam 240mm, 23% Base 10.5mm. Burnt outside & PTO Dimples but not deeply impressed. die 1

inside. Abrasive, same fabric as 1K but fired to a drab buff with thick blackish core to near the surface. Probably fired almost entirely in a reducing atmosphere. Interactions gnt:

## ANAVS

Corbridge [AH. 59 ~~Dra. B. 9~~<sup>✓</sup>] red-brown fabric with grey core and cream slip. B

Binchester [BIN M2; See KAS Pl. XLIX no. 15 + P. 153<sup>V.P.</sup>; Durham DC 9]  
 r. facing, hard, orange-brown fabric with buff core; white + brown (s.s.)  
 grit. Δ A

Binchester [BIN M10; See KAS. Pl. XLIX; Durham DC 7]; hard, red fabric  
 with grey core and cream slip; r. facing. <sup>no. no. 10</sup> C ~~E~~

Binchester [BIN M9; See KAS. Pl. XLIX; Durham DC 6] r. facing; soft,  
 red-brown fabric with cream slip. B

~~Binchester~~ <sup>Provenance uncertain</sup>  
~~Corbridge~~ [no. no.; Durham KD 7] red fabric with thick grey core and  
 cream slip; white and brown grit. B

ANAS

Coleridge [BV/64 M501 422K] flange fragment. Hard, pale,  
orange-brown fabric fused to creamy buff at surface; moderate, quartz  
and v. occasional grey inclusions, usually all tiny, occasionally larger.<sup>Δ</sup>

Corbridge [S. 101; 51/47; ⑤ 1); 119K] hard, orange fabric with buff slip, red in parts; 1 or 2 grey grits; l. facing. A

Corbridge [U.S. 41; 256K] slightly rough, orange-buff fabric with cream slip. Type 1A? ? 15 4/15: AA+XXXI's 239. A

Corbridge [7.5.36; N. 8]K internal bldg. of Forum [IA] S106; ⑤ f/xi/17 266K] orangy-pink fabric with cream-buff slip; medium + small, r/b, grey, grits. Type 1Ai rim. A

Corbridge [IA], S110, ⑤ e)/xi, 47; 245K] l. facing; slightly sandy fabric, buff core to pink outside; very sparse grey grits. A

Corbridge [S 109; IA], 10/6/36; 248K] r. facing; N. of W. internal buildings of Forum; slightly sandy, hard buff fabric, cream slip. Approx Type 1Ai A

ANAVS

? a different part: Fabric different DIE D

Corbridge [10] XXXIII 1911; S. 105; (5) n)/RT 47; 263K] dark grey core to

orangy buff fabric; no slip; much tiny r/b, grey grit to b.b;

stamped diagonally

D

Catterick [1959 <sup>or 2</sup> J II (19) (446) 10K] hard, gritty orange fabric with ~~dark~~

greyish core; much tiny grit in fabric - which is similar to that of MITIVI.

flange fragment. p. 340, MS 4 ~~192~~ Phase 3

D

Kirkby Thore [Plaskett Gillbanks Bequest; 27.26; 1926; 27.26/70; Tullie House 8K]

hard, pink fabric with grey core; cream slip; much, tiny to medium, brown

& grey grit to b.b.

Different di:

G.

ia + 1b on p 84  
nos ~~62~~ p 84

Corlisle, Bank Street [CW<sup>2</sup> XVII p. 161, ~~111~~ 112;  $\phi$  1892, 95 + 96; Tullie House 26K]

Stamped each side of spout; hard, pink fabric with grey core and cream slip; much, white, brown and grey grit to b. b; apparently crosses in bottom border. F

Housesteads [~~the~~ French N/W gate (Extension) <sup>not seen. E.B.B's drawing.</sup> E 30; Durham 9K] soft tan. This has plentiful grit - Binchert, example has none. in Anau's folder p. 1. Coloured fabric with cream slip; no grit on piece. H. 32. Six. ✓ C ~~E~~

Catterick [<sup>445</sup> 1959 H. IX ② S. Wader. 24K] hard brownish pink fabric, fine textured with cream slip; flange + part of bead only. Phase 6-7 B

Corbridge [DN 54; in 1963 at Newcastle 35K] brick red fabric with dk grey core; hard; cream slip; ANAVS twice close together. B

2.4K MS44 Phasoba -7 (see p. 46)

- Colbridge [s. 305; ⑤ t/xi, 47; 246K] l. facing; dark grey core to pink,  
 with cream slip; medium to smallish, r/b, white, grey grit; Type IA ii. B
- Colbridge [①; no. no.; 242K] dark greenish grey core to pink  
 fabric, with cream slip; largish to tiny grits, r/b, black, grey, whitish,  
 to c.  $\frac{1}{4}$  in b. b. b. Type IA ii. B
- Colbridge [vs 40 ..... ? ⑤ u/xi, 47 ①; 257K] r. facing; hard, grey core  
 to brick, colour, slightly orangy buff surface. B
- Colbridge [1952; Between Temples I + II; 295K] l. facing; grey core  
 to orange-reddish fabric; with cream slip, 2 stamps together; medium to  
 small, r/b, black, grey, grits; some missing. B

Corbridge [S. 152; 217K] dark grey core to brickish pink; flange fragment;  
buff slip. F

Corbridge [HL 60 Seen at Durham <sup>1965</sup> 16K] r. facing; twice together.  
red-brown fabric with grey core & cream slip. Sketch. C

Binchester [9K At Durham 1963. EB (1). Trench N of w. gate (extension);  
soft tan, cream slip; n. g. 0 ANAVS]. A C

Corbridge [S107 214K Site] r. fac. Hard orange-brown  
with thick black core & cream slip. Seen 1974 apparently  
for first time. B

Corbridge [Temple III + Site XI; 1952; 296K; HA 52; FB 686.] r. facing;

hard, dark grey core changing to reddish orange, with cream slip; prolific,<sup>B</sup>

r/b., grey, black grits to c.  $\frac{1}{4}$  in. b.b.b.  $\Delta A / \text{no. } \frac{1}{2}$  slip; on 295K

Corbridge [Site XI VII 5/4/56. <sup>(1963 at Newcastle 3K)</sup> top soil + all levels above mason's chippings.

C.E. 56; 294K] L. facing; approximates to 295K in shape. <sup>few grits; burnt.</sup>  $\Delta A / \text{no. } \frac{1}{2}$

Corbridge [AE 56, same layers; 298K] r. facing; hard grey core to <sup>wh. flint, brown + grey grit.</sup> pink fabric, with cream slip, type  $\Delta A / \text{no. } \frac{1}{2}$  but head higher than flange. <sup>slip</sup>  $\Delta A / \text{no. } \frac{1}{2}$

Chesters [1819/2041; 4K] r. facing; red-brown fabric with cream slip;

large, brown + black(?) grit. Restored. 1 stamp each side of spout.<sup>B</sup>

Chesters [2486/3796; 35K] Die B. no. rubbing; hard, red fabric with grey core, cream slip; brown grit.<sup>B</sup>

ANAVS  
Cambridge [425K] v. fac. ? B

Cambridge [404K] v. fac. ? B

rubbed in 1998

Corbridge [s. 391; Analysis 20; ⑤ h/xi, 47; 273K] dark bluish,

blackish grey to orange fabric, with cream slip; sparsish, largish to medium, r/b, grey gits. B

Corbridge [I 11.7.38; s. of site 40.7. found by T. Baty; 270K] r. facing. dark grey core changing to orangy pink. Nearest to IA ii in shape. B

Corbridge [s. 7, 51, I 10, Drawn ⑤ i/xi, 47; 277K] r. facing; brick red fabric with grey core and cream slip; hard; small, white and large, brown sandstone gits, 1 B; A (check with ...). B

Corbridge [us 38; I 13; ⑤ o/xi, 47; 264K] r. facing; dark grey core to orangy buff fabric with cream slip; few r/b + black gits. B

ANAVS AA4 XXXIII (1955) p 159, fig 5, 2 stamps from Valthungfelling. DIE B  
Benwell. P. 161.

Corbridge [no. s. no. XII; c 6/4; b III; 382K] soft, brick red fabric with  
cream slip; abundant, medium to large, white, brown grit, starting

1 1/2 in. below rim. B  
Corbridge [no. s. no; 1947 (46) XII B below Level a 30/7/47 II; 267K] r. facing;  
dark grey core changing to buff and then brick red; cream buff slip.

Corbridge [u.s. 36; ? AS; 14 IB; 269K] L. facing; grey core changing to  
orange, with cream slip; few grits visible, most worn away. I think the  
mortarium drawn for IB(ii). B


Corbridge [s 31; IB; 5 p/xi, 47; 268K] L. facing; greyish buff core,  
(dark grey in flange) to orangy pink, with cream slip; prolific large to  
medium, & some smaller, r/b, grey, whitish, blackish grits to c. 3/4 b. b. b. B

Corbridge [s 21; 57;  $\overline{113}$ ]; (5) s/ $\pi$  47; 265K;] r-facing; dark grey  
core to orangy colour, cream slip. B

Corbridge [s 4  $\square$  x1 N (5) r/ $\pi$ , 47; 241K] L-facing; blackish grey  
core with bluish tinge changing to orange, tiny white granules in it,  
cream slip. B

Corbridge [ $\overline{113}$ ] s 321 (5) K/ $\pi$ , 47; 259K] r-facing; black-grey core  
changing to orangy brown, with cream slip; no grit survives. B

Corbridge [ $\overline{113}$ ], s 392, E. area N.E. S. 45; 244K] r-facing; blue  
blackish core changing to brick pink; almost red; with a cream slip B

Corbridge [309K; no nos.?] 1 stamp each side of spout; probably pinkish cream  
fabric; restored whole; much, large to small, r/b, grey grit. D=11ins. 

ANAVS<sup>or</sup> ANANVS  
ANANVS

Chester [2434/3744 ; 36K] Die B; no rubbing; red-brown fabric with grey core and cream slip. B

Chester [2428/3738 ; 37K] red-brown fabric with grey core and cream slip. (8) B

Chester [2485/3795 ; 2481/3791 joining ; 38K] Die A; buff, sandy fabric with sparse, brown grit. A

Bewell [in S.P.'s store at Newcastle. 10K] Gilliam type. 258; r-facing; orange-buff fabric with greyish buff core and cream slip; some white grit. A  
? = AA4 IV (1927) 196, no 2  
here

Halter [1927. Simpson. Vallum Filling 1927; in S.P.'s store. Newcastle 15K] r-facing, hard; pink-brown with blackish core; cream slip; no near spot to draw. B

London Hill [L.H. 1946 (108); Hunterian M. 88K] r. facing; flange & bead only,

drab yellowish grey core to pink; probably had slip, now gone but low 2 signs of it. *Sketch* B

Camelon [FX 233; NMA 48K] r. facing; orange fabric with thin drab core with cream slip, much, brown + grey + black(?) grit to c. 1 1/2 b. b. b. b. *Sketch*

Newstead [D. 266, fig. 35, no. 20; <sup>NMA mentioned</sup> FRA 1472; VII. 15. 65; NMA 124K]; l. facing; sandy, red fabric with grey core and cream slip; no grit on fabric. B

Cramond [no name - Huntley House.] Yellowish salmon. pink with medium grey core. Thick mixture of large + small, rounded white + more angular brown, ranging from light to dk brown. *Sketch* *Revid's book.* 2 stamps. B

Camelon [42] CAM 75 HK Site A. 23k] flange fragment. Orange-brown fabric (2.5YR 6/6) with thick drab brown and drab grey core, moderate inclusions + ill-sorted quartz, sparse red-brown and <sup>rare</sup> black fragments, traces of cream slip, no titivation grit survivors. B

Also see no 479 unmarked Site C Spout and flange fragment with dangles. No stamp and unlikely to belong to the above.

ANCORAETVS or ANCORRETVS

Rickwillow Road, Ely [sent by Bob Atkins Feb. 2002 (D. Mackvett) EPW

1112 (26) Phase 8 1K] 245gms Drain 400mm 8.5%

Very hard, greyish white fabric with thick slightly darker core;  
Inclusions: fairly frequent, tiny, much almost sand-sized,  
mostly quartz with moderate, small to medium quartz and  
occasional red-brown, black (probably slag) material and  
rare large white probably quartz. Buff-cream slip.

Titivation: possibly had very little but has been very heavily  
worn. mostly black slag, 1 pale brown, 2 quartz.





Prokumlaw Rd., Ely

ANCORAETVS or ANCORRETVS

Godmanchester [6K. PL 516:11 W. Green] Sandy cream inside +  
 inside surface; pinky brown outside surface; purplish brown  
 slip? but overfired perhaps; tiny black grits. 2 very small  
 neat holes on underside beneath stamp; 2 similar ones  
 but more widely spaced <sup>out</sup> in side just below spat? Purpose unknown.  
 Origin expected to be Upper Neave Valley like Uediacus etc.

Gochmanchester      Hunts  
Painfold Lane      side  
Mansio      pits



7

PL 516-11

ANCOR AETVS & ANCORIRETVS

Parish of Roxton

TL 139549. Roxton Road West, north-east of Roxton,  
Beds, Timby et al. 2007, Site 1b. p. 74-5 and fig. 4.7  
Enclosure 11.2 in context 1445, ~~is~~ a recut in Ditch  
1203, p 242, Fig. 8.10 no. 14 profile and  
stamp.

Timby, J, Richard Brown, et al. 2007 Settlement  
on the Bedfordshire Claylands. Archaeology  
along the A421 Great Barford Bypass

ANDIL cf. CANDIDUS

B.M. M. 2772

ANTU[

See

]STANA - incomplete ;

~~VERECUNDVS F of VIRECUNDVS~~

~~British bronze.~~

~~v. large med.~~

~~(1) Wroxeter (ii, <sup>p. 469</sup> 2007, f 17<sup>no</sup>, 40); <sup>Type 149</sup> Gaul (CIL XII, 5685, 41),  
N. Pompieque (Bull. Soc. Hist. Comp. tome 2); VERECUND FEC~~

Wroxeter [I, fig. 116 no 15 + p. 68] frag.

Wilderspool [Kendrick 11.68; 63K] on v. small fragment; soft, slightly sandy, pink fabric with cream slip; flange only.

APRIL 15


London Guildhall Amphitheatre SE92 (22637) Con 15223

Pd4 (AD120-160 Masony Amph) 507K ] L facing 235gms

Diam 280mm. 14% Bunt or fired to grey throughout

but grey everywhere. Inclusions: packed with moderately well-sorted quartz with rare large ? slag black ~~in~~

Texture:  $e^{3/4}$  inch with out grit or scoring: below that rough scoring combined with flint & quartz small to smallish; both grit & scoring worn away in lower half of bowl. Ver region fabric



APRIL 15

Inside St. Paul's Cathedral [GM307. Not far from S. C. Wren's kiln

Kiln: (Illustration no 13, 523K) stamped Apollon on both sides. Patch of burning on flange. Flavian sport as Frey 1972 fig. 110, 370 + 106, 230 but sides both the same in this pot except (side shorter back to front measurement. Flange smooth, but conc. scoring on inside upto bottom of bead. Diam. 26 cms. 88% Greyish-cream all over surface & throughout the fabric.

Inclusions: moderately well sorted, frequent at x20 mostly quartz, few blk & red-brown & rare larger red-brown. The whole in the centre looks like accident than wear. Inclusion: flint & quartz

APRILIS

FOUND IN LONDON

Cury's Hospital

London [MA. 2735 Guildhall M. 15K] r. facing; broken fragment of

stamp on other side of spout survives; sandy, greyish cream fabric; flange & spout only; shape may have been like a hefty MARINVS SOLVVS but a bit shallower. heavy. *Vellutaria* fabric undoubtedly B

London [CIL. VII 134, 15 (amphora) over Coll. Ant. 1, 149. CRS M. R. London p. 89; M. 2773; British M. 51K] r. facing;

diagonal; slightly sandy, greyish cream fabric; lvs 2 whitish grit on fragment. Sketch Ad. Vellutaria fabric - CRS London. D

Colchester [14.61 Queen St. Excavation. See other card. 573K] A

r. facing

APRILIS

(? Fabric  
summa b) Albinus in Mercerside H (Richborough),

Baylham House, Coddanham, Suffolk TM 118528 7K ] l. fac.

Stamped along - apparently a slightly curved stamp? Bright orange-brown fabric quite heavily tempered with mostly fine quartz, trans. wh. & flint grit; no "tril." - grit a piece. Two deep grooves below bead. Flange incomplete.

APRILIS

20

Smeltshaw [St Stephen Green; Ken Hill, Areal Site 59. 219.950;

33K] greyish buff fabric with creamy buff surface; small white  
grit; Stamp faint.

Colchester [408K <sup>no. no.</sup>] creamy fabric; 1 or 2 black and white grits; diagonal  
stamp. l. facing <sup>Spout almost a trail.</sup> ~~probably R. Colchester p. 97; it is a 9; old find~~ E

Colchester [279K; 87K.30 A. Union] cream fabric; 1 brown and 1 grey grit; l. facing  
<sup>C. + R. M. R. f 931, 25; ~~prob.~~ I think not.</sup> approx. 370K.; hospital in pencil = 421K. A

Colchester M [171.33; 343K.] pink-orange, slightly sandy fabric; tiny, white,  
+ black grits; stamp battered; v. facing; no form quoted. A

Colchester [294K, Playhouse Site. 135.29.] buff, smooth fabric, surface slightly  
greyish; v. few, dark grits, v. facing. A

APRILIS

33K Snettisham

4

APRILIS

4081K Colchester facing

XXX APRILIS XXX

277K Colchester

APRILIS

Colchester [P5634 1.81 D1892 T290 S18] some accretion.  
heavy wider rim than S19.

Colchester [P3332 BKC T223 T260 S19] Land r. facing.  
sketch. Δ

Colchester [P5635 1.81 B1739 T280 S20] Land r. facing.  
look quite like Ver.

APRILIS

Colchester [R Colchester p. 97 'APRILIS.F'  
Technical College; ~~1880~~ or 2980 '14; May 3; 443K] cream fabric;

white, red-brown, grey gills; 1 stamp each side of spout B.F 34/38. C

Colchester [CE.M.R. 1935-7 p. 39; probably from the Union.  
~~240~~ 35; 430K.] grey and drab fabric, black in parts, pres. burnt.

no rubbing; stamp broken; die as 279K. A

Colchester [Hospital no. no. 421K] creamy-pink, slightly sandy fabric; small  
diagonal, broken stamp; not rubbed; probably join 279K Big stamp. A

Colchester, Town Walls; [Roman Colchester, fig 23, B. no 10+10 on p. 56.] not seen;

'hard yellow-buff, with sparse large white grit; upper rampart; read

"APRILIS OF (?)"; ~~dated late first century.~~ Die probably as 443K. See other card. 543K. ΔC

[? Colchester, Insula 9 p. 94; APRILIS.F on f. 195; not drawn - not known  
whether seen or not.] ~~Probably~~ = ~~408K~~ 443K. ? at least

VAPRIUSE

443K Colchester, Va.

1966 - Six seen. 5 hawks

APRIL 15

Scole, Norfolk. [2K 1007 SCL 117] r. facing. In fine-textured

deep  
cream fabric with thick pink core; abundant grit to  
"about  $\frac{3}{4}$ " below top of bead. (c  $\frac{1}{2}$ " b.b. bead). Mostly pebbly  
quartz-like grit, one or two red-brown; + some grey  
probably flint. Dr = 30cms. Stamp slightly diagonal. A

Colchester [now in the Dept. of History, University of Exeter] l. facing

YZ + l. facing. (On pot CATWODUN VM 195. B). Heavily  
worn. Hooked rim reminiscent of 5TK BM. In very drab

cream fabric tempered with quite a lot of grit; grey flint,  
white translucent white + red-brown tint grit.

APR 1950

CHECK

ARA (Kraai)

Caerleon [C'59; JF 3; D1; (D5) G. Boon] fine-textured cream fabric with brown and white grits in the fabric; abundant white and a few brown, medium to small lenticular grits to c.  $\frac{1}{2}$  below top of head, worn away in lower half of vessel. Traces of red-brown slip on outside of body which is also heavily pitted.

[ASVAR] (B) Nothing to do with name. Graffito on Drag. 27 (Flavian). Berichten van de Rijksdienst voor het Oudheidkundig Bodemonderzoek <sup>1954</sup> P. 44; Jahrgang 8, (1954-8).

and 2 DARD One potter or ARDSI = V...  
Two?

Heicester [20K; Nr. Town Wall; 860 an old number.] hard, whitish grey fabric;

sparse grey and brown grit; [horizontal grooving for spout. A

Heicester [41K. West Bridge area; 316-1953]; buff grey core, patchy purple, brown,

and buff surface; small mortar. A B

Cardinock [Cw. XLVII p. 118, no. 1. Tullie House 39K] l. facing; cream fabric;

with buff core and slip; abundant, largest to smallest grey, brown,

white & black grit to bear b. b; unstratified; read ARD [ A

Holditch [HN. 7 ② 1; 4K] stamp fragmentary; soft, finely textured creamy

buff fabric with reddish flecks of grit in it; 1/2 b grit survives on piece;

1 grey grit embedded in underside of flange; die as 20K Heicester, A


ARDLA

2015 Leicester 17

ARL <sup>D or B</sup> -  
ret.

Woodbury, outside Axminster [WDY '81 30 1K] slightly burnt; <sup>0.29</sup>/<sub>30</sub>

hard, sl. granular greyish cream. 10xR 8/3 with orange-brown core in flange. Superficially like Ver. region but inclusions smaller - probably mostly quartz with some dark, blackish. r. facing  $\Delta$ .  
More inclusions than first thought. Probably Ver. region.



Woodbury, outside Axminster


ARDUS A?

(Resid.)

YORK [1989. 24 71807 / 3150 (Context AD 140+) SM21

126K] r. fac. Dv. 27. Three joining sherds. Bunt before fracture. Well-worn. Hard cream.

Inclusions: fairly frequent, mostly quartz with some black iron slag <sup>Not well sorted</sup>. Inclusions: blackish 3-4 mm. Brownish-buff slip.



20910 . and 21  
Grantham M [IK; ? find place] slightly sandy, cream fabric, with buff cream surface; medium to large, white, brown, & black grit.

Holditch, Staffs [H N 6③ 4; 10K] flange fragment; fine-cream fabric with buff slip; tiny grits in fabric.

ARDSA

Hoditch [HI 14 ③ 5; 8K] flange fragment; soft, fine-textured buff-orange

fabric with r/b +ophile grits in it; upper surface + near surface, cream; die as HIK Heider. B

Mangidunum [not published Nottingham Univ. M.] greyish cream

with r/b + grey tw. grit in fabric - v. small pieces. slip distinctly orange but paler underneath flange; no tinturation grit.

L. facing; has been misstamped + restamped afterwards.

Form like BEVALVS.

ARD2A

Think about ARDRA & J ... ARDRA


Littlechester [20K. Hats] facing: Very hard, drabish  
cream fabric, heavily quilted; white & grey interwoven quilt; surface  
greyish except just near spout.

DVR'DS

? Little chest,  
01-17 alternative

Winchester [40K 75 QI (46) 4.] Quite deep hooded rim  
 had in fine cream fabric <sup>with moderate + ill sorted, quartz, a little black, rare v/b</sup> ~~heavily tempered~~ with fine grit;  
 deep cream slip surviving under flange; grit is <sup>all or</sup> mostly  
 white quartz-like (almost opaque); ~~few v-b. + few white~~  
~~Apert~~ well-worn. ~~Dr. 29 cm~~ Dr. 34 cm ? This potter

Castleford [(686) CAS 81 S10 L472 (1575) 47k] ~~Burnt~~ or overfired  
 to grey throughout, fairly <sup>fine</sup> ~~coarse~~ textured, moderate inclusions  
 of quartz, sparse red-brown and <sup>rather more</sup> black ~~fragments~~ <sub>v-b</sub>. Trituration  
 grit included greyish ~~flint~~ <sup>flint</sup> or quartz? Dr. 26 cm. Very hard  
 stamped twice close together. Dr. 28/30



VRDS Initial mark = end mark, probably a space filler. ? = ARDSA

Derby Racecourse [DRC 74 III (6) 50] may be part of same vessel as (44) but does not join. 35K] Cream fabric, heavily tempered with fine grit; (44) has red-brown and quartz-like grit. Surface is rough because of added grit.

Chesterton

Waternewton [Kate's Cabin Farm site no. 3; E. Greenfield; CH

7463; M123] stamped each side of spout; hard, buff fabric with orangish slip; one or two gits only on fragment - brown & black.

Littlechester [Brought Brassington 1965 (E) Derby N.] white fabric with yellowish slip, bunt in parts; red-brown git with some white ones; fabric tempered with red-brown git. rubricus material

Little Chester [43K DL C 79 DCA join<sup>g</sup>, AGC, AAS, EXP] <sup>Dr. 31</sup>


The whole rim of vessel not stamped once on one side and twice on the other side. Well-worn. Hard, greyish-cream <sup>fabric</sup>, fairly fine-textured with ~~fine~~ ill-sorted, quartz, red-brown <sub>p-to</sub> & sandstone & darker brown slag; git

similar and brownish - butt slips.

AR111T X

Welwyn cemetery (Tony Rook Drg no. 300. Sct 03 (5) 11K)

Land n. facing. typical early 2 spont. 405 gms  
Diameter 300 mm  $\approx 26\%$  Fabric: greyish. cream with  
some pink in the core; probably a cream slip, fired to  
buff in parts & to a brownish-grey newsprint n. facing.  
Inclusions: frequent but not as packed as it can be in VRW;  
tiny or medium-sized, mostly quartz but more red-brown  
than often in VRW. interstratified: mostly flint,  
some quartz, fewer red-brown. s. ph.  
occasional <sup>large</sup> n-b sandstone inclusions.



Ewell, Surrey [rubbing + drawing sent by S.S.F. (Findv?) to E.B. in 1951]

Identification certain + rubbing sent back to S.S.F. Tracing of drawing kept. Stamped each side of spout. X =  D v.?? 36  
 T.14 L.2 [519]

Highgate Wood [HW 68; 364. 1K] Will be l-facing; sandy greyish cream fabric + slip; slightly burnt. middle die badly impressed; grey flint, small <sup>inh.</sup> pit <sup>some quartz</sup> fair amount. Abundant inclusions, mainly quartz, rare red brown

Baldock, Brewery Field 1968 (no acc. no assigned)

Ketchworth Museum. Sandy brownish buff fabric with very thick orange-pink core. r-facing. fragmentary. Spout shallow.

AR 11 NT X

Baldock [TT/GT 286 4K] in sandy greyish cream with pink core.

Enfield, Lincoln Road, Mddx. [A3 F 32 11K] granular, <sup>Beant.</sup> cream buff margins, grey surfaces; grey + white flint grits.

Cow Roast, North Church. (CR 74 (37) 19J L85 (36) 7K)

Hard cream fabric with grey core.

Braughing [inf. C. Partridge BR. 72 A AU 17. 14K]

Granular ~~grey~~ pinkish fabric fixed to greyish cream at surfaces + packed with tempering - qty + red-brown - tempering unusual; only 3 grits surviving 2 black (?iron) + 1 white  
95.

AREN TVS

Pd. 6 OA 11

London, Basinghall Street (BA2 05 <492> 2108 802K)

Lt r. facing. 340gms Diam. 340mm 19% worn  
VRW fabric: buff-cream with <sup>pale</sup> grey core; inclusions: packed  
with quartz f, rare o/b, rare opaque black. Tituration:  
flint, quartz, rare red/brown. Finger depressions  
for making spout. Hit quit starts c 4cms below bead.

ARINI  
B  
BSE  
London [1937.434 Guildhall M. 21K] r. facing; sandy, very slightly

pinkish, grey fabric with drab buff surface burnt in parts; largish to small, good amount, r/b, white, black, grey grit to c.  $\frac{1}{2}$  in. b. b. b.;  
D = c. 12 ins.

London [Guildhall M. 129K] L. facing; sandy, cream-buff fabric with orange surface; grey grit.

London [1930.105 Guildhall M. 145K] r. facing; sandy, orangy buff fabric; medium to small, r/b, grey grit to c.  $\frac{1}{2}$  b. b. b. D =  $9\frac{1}{2}$  ins.

London (?) [CRS. British M. 8K] L. facing; slightly sandy, greyish cream fabric with buff exterior; few, medium + small, grey, brownish grits.

ARIINTFX

honda\* [BM. CRS unregistered remainder. 146K] l. facing

weyuth cream. drawing in book.

Brockley Hill [TLMAS 19, pt. i p. 72, M15 read as MARINVS; E3. Sull. 53;

Harrow 25K] slightly sandy, grey changing to pink; surface darkened in parts;

Great Chesterford [Cambridge M;] rather rough, orange-yellow fabric with pinkish tinge below surface, and buff core; little grit visible, small, brown &

Venulamun [212K sent by J. Jeffery; surface] sandy, brownish buff fabric; poorly made; flange to bead only; "surface find, by the modern roadside, E. of the Roman Theatre".

Venulamun [51.3/ Newcastle. 6K J.P.G.] sandy, orange-brown fabric; grey surface; perhaps discoloured slip; old find.

ARGENTUS? 1973 + 1974 | and BH House 2000

Brockley Hill [BH73 T.C. MS 29 260K] flange frag rather

weathered in greyish cream granular fabric with brownish  
tinge in core. TLHAS 27 (1976) MS 2

Brockley Hill [BH 74 T.C. MS 29/30 340K] flange frag.  
in greyish cream with buff slip. AR[... stamped  
twice close together. The letters fit Argentes but are much clearer  
than usual. TLHAS 27 (1976) MS 3

Brockley Hill House [Alex Smith TLHAS 59 (2008)  
Oxford Unit BH100 Context 152 p111 3<sup>4</sup>]

359K] l. facing 2 stamps next to each other so close as to look  
like a 2 line stamp. Spout early @ type plan A and photos  
VRW. 545g. Diam 440 mm. 20% packed with quite well sorted P70

quartz (transparent and large amount (? 25%) brown quartz) with  
opaque red-brown and rare black + grey. Fine and d range  
AVRW. Int cont: only c. 1 flint out surviving. Surface cream  
but fabric peachy cream throughout up to surface. Very slight  
singling. S

- Brockley Hill [190K BH.66 nr. T.C. M11] overfired throughout.  
to blackish grey; white + black flint grits. THMAS 27 (1976)  
MS1 p 211 A
- Brockley Hill [MS4 BH72 CT1(2) 192K] l. facing overfired  
throughout to dark grey London Arch. 1973 A
- Brockley Hill [BH 72 CT1(3) MS3 191K] r. facing. over-  
fired throughout to grey; fabric harder than normal  
& heavily gritted in clay. do. A
- Brockley Hill [BH 72 CT1 K2F1 MS1. 193K] r. facing  
overfired. partly dark grey + brownish cream. do sketch.
- Brockley Hill [BH 72 CT1 K2F1 MS2 195K] r. facing  
Overfired throughout to dark grey throughout. Waste crack through  
dark flint grits; one white (do)

AR III I-X ~ AR II NFX ~ AR II N (Arenthum).

TB + TA join in.

Holme Chase, Bucks [HC 65 etc. R.W. Giffiths, 112, Whaddon Way,

Bletchley, Bucks.] Sandy, cream fabric with buff slip; l. facing  $\Delta$   
Ventrarium [60 G XV ① / 1 251K] v. facing. Coarse grained  
drab, cream fabric with buff slip; much grit worn away;  
dark grey + white flint grit + debris. D = 11" <sup>Waster cracks</sup> <sub>under face of</sub>

Ventrarium [57 W II ⑮ / 1 261K] Sandy, creamy buff  
fabric with buff slip; burnt in parts; most of grit worn away; one  
or two grey + whitish flint + grits survive. D = 10. 263K is  
fairly certainly <sup>probably flint or carbon</sup> part of same ventrarium but does not join. <sup>NO</sup>

Ventrarium [60 G XV ① / 1 273K] v. facing. Sandy greyish ~~red~~  
fabric with ~~greenish~~ buff slip; grey-black + white flint grit + brown.  
worn or damaged. waste cracks under face.

Holme Chase - Probably an X at the end. Reading ARINT-~~X~~ is probably  
complete. Letters are insufficiently joined to be certain  
beyond doubt of RT or X; though the R seems quite clear  
in some or others it could be B. F could perhaps be  
F

AREATPA / ARENPA / AREALPA ?

Vendarnium [58 · B ⊕ 165 K] r. facing, sandy, buff fabric with

orangy buff slip; few smallish + small brown, black grits.

Richborough [iv p. 251; no. 35; 72; 77 K] outer ditch, clay filling; sandy, orange fabric with purple exterior (? slip over fired); flange of bead only, letters very coarsely cut, + style + fabric appears to be MIDDIX / HERTS. type Variant B.F. 34/38; misread VISINI [in report.

London [Bank of England no. 3.1.1] r. facing stamp broken vessel nearly complete. D = 10 1/2" Δ

Vendarnium [Ver. 57. TXI ⊕ 229 K] l. facing. Sandy, greyish cream.

fabric with buff slip; burnt in parts; grit worn away. Note faint diagonal perhaps giving A!PA over end of stamp probably.

MR 11111

Venulanium [57 W II (15) / 1 263K.] Hard, sandy greyish cream fabric with traces of pinkish brown slip; few sparse red-brown, white (flint?) + dk grey grits survive.

Venulanium [58 D VIII (6) / 1 <sup>258K</sup>~~277K~~] <sup>YES</sup> Robustly but not certainly this potter. Material v. similar to 261K + 263K <sup>if not</sup>. Hard greyish buff fabric; cream slip; red-brown + white grit. dk grey: top of flange.

Folly Lane, St. Albans [A91/c BJ D (14) <sup>Dr. 42 (12%)</sup> Midden dump 7K] r-facing. <sup>slightly</sup> Worn. Encompasses cream fabric. Mostly pale brown ~~pieces~~ with a skin of cream. <sup>20x</sup> Inclusions: abundant tiny quartz inclusions with rare black + red-brown. No slip apparent

Intervation: Wam. v. little snows, tiny fragments mostly flint,  
some quartz, rare orange-brown.

Venlamium [Car Park A.VI.7 (28) 114K] hard, coarse, sandy, buff fabric with red-brown core; small and medium, white and brown grit.

Venlamium [Car Park A.VI.3 (40) 112K] fabric like 111K.

Venlamium [Car Park A.V (45) (47) 111K] coarse, sandy, orange-brown fabric, burnt; white to grey grit.

Venlamium [1931, V.A.B. 7B-1. Pie House 102K] gritty, grey fabric, mistired; hard, sandy fabric.

Venlamium [1958. BIV (3a); 144K] L. facing. sandy, drab, brownish grey fabric and surface; latter a little paler and more orangey brown in parts; some, black, r/b, + grey medium - small grits (of flint) survive. A.

# ARINTUS

Staines [Y10 QR RS 75 A 4 8 . 14K] granular

brownish fabric.

Staines [CAD 77; A70 (20) 37K] r. facing. Granular,  
orange-buff fabric with drab dark grey core; surface  
discoloured to muddy dark brown & red-brown.

ABINT-X

Baldeck [5F | EL 158; 16K] flange fragment, In hard

brownish fabric, grey in parts, Venulanium fabric.

Radlett [1959 ~~the~~ Pit. Rubbing sent by S.A. Pistles]

<sup>Northchurch Berks</sup>  
Low Roast [S.P. 957101; 2K] L. facing. CR 73 <sup>100%</sup> 21F(9) L4 [E]

[4] Either <sup>✓</sup> overfired throughout or burnt throughout to a bluish grey with slip discoloured to <sup>grey</sup> a muddy brown. A few bits of flint grit. △

Broughing (Information J. Warbis, 161, Rathcoble Gardens, Hornsey,

London N.8) Photographs & drawing sent April 1974 no 7

Hertford M. ~~4K~~ 4K



✓

MARINVS

Brockley Hill [L MAS xi, ii, p. 181, fig 4, no. M5 + p. 183; 1951; 76K] almost

worn away; sandy buff fabric; very worn all over, fragment of flange.

Brockley Hill [L MAS 19, pt 1, p. 71; G=C6;  $\Delta$ ; ~~D5/D9~~. Harrow 18K

L. ARRIUS ~~CAI VDS~~ CAPIT[ ] / LV[ ] V. F

ALL are Die I

London [SHW 56. St. Smithin's Ho; Walbrook. 305K 9H]

stamp diagonal r. facing; scoring + grit on flange; scoring inside but mostly worn away. Greyish cream fabric; white, grey, orange-brown + translucent whitish.

London [SHW 56 9H 306K] flange only; usual type but different vessel. greyish white fabric; burnt.

London [P. Tyers. 9PO 75. From a pre-Boudiccan level. Context

12163. Access. no. 4775] Complete profile with

~~stamp~~; spout broken off. Heavily pitted, greyish creamy fabric with pink core. Gut + concentric scoring on flange.

L. ARRIVS CAP. L. CAPITE. i. ARRIVS CAPIT(?)  
~~L. ARRIVS CAP. L. CAPITE.~~ (COG)  
ALL are die 1 today

Wall [W7/2. B. Round] stamp slightly diagonal. Sandy, off-white fabric with buff slip; flint & quartz-like grit.

Wickham Kennels, Braughing [brought by Adrian Haverest; HA 29 FW ③] returned to Claire Halpin Hertfordshire Unit 31.5.97] Dr. 30 Mostly greyish-cream but with some extremely thin bands of pinkish brown in centre of fabric. Packed with quartz sub rounded (with rare orange-brown fill-sorted). Very little of inside survives and covered with a white encrustation which goes over the rim. Slip fired to brassy brown on upper surfaces

but only cream under flange. Flint + quartz gut a  
layer surface flange & will have had concentric scoring  
though it is not very evident on sheerd. Will also have  
had it on inside but mostly obscured. ~~Revised~~

WARRINS VAPIT [O. // LVGV DV - VDV V] See  
ALL are Die 1 CAPIT(0)<sup>3</sup>

London [no. no. Guildhall M. 20K] sandy, greyish cream fabric; internal

scoring; coarse; grey to orange-buff surface; yellow accretion under  
bead; small, black, grey to b.b. and some grit on flange; bright orange  
on part of outside to purple in parts; cracking under flange; D = c. 12 ins.

<sup>Site of Pewsters' Hall, Lime St.</sup>  
London [1936-196 Guildhall M. 105K] r. facing; hole in bottom; sandy,  
buff fabric; some, grey + blackish grit; most of grit worn away; D = 13 ins.

variant B.F. 38. Scoring top + inside; heavy little, deep flange.

<sup>B.F.</sup>  
London, [1928-78 Guildhall M. 168K] sandy fabric; pink zone to dirty cream;  
very few, white, r/b, medium grit near bead; surface blackened in parts;

1 stamp each side spout, some grit on flange. D = 12 ins. B.F. 38 nearest.  
Stamps v. clear. dots after 1 + R. Some grit on top.

~~WARRIOR~~ ~~WARRIOR~~ DV L. ARRIUS ~~CAPIVS~~ → L. ARRIUS CAPI(T)G)  
Awh are Die I CAPITL LVGV DV F

London, Bank of England [1928/7/13/6; British M. 31K] stamped each side

of spout; slightly sandy, pink fabric to cream near surface; surface brownish buff, grey in parts; very well worn; grit gone below c. 1" b.b.b; bottom worn out; smallish, grey + black + brown, (flint probably) grit in the inch, on head and quite a lot on flange; D =  $10\frac{3}{4}$ ; a rather narrow BF. 38.

London [Bank of England no. 315] stamped each side; sandy, greyish fabric; scoring inside and on flange; completely hole in bottom through wear. D =  $11\frac{1}{2}$ ". BF. 38.

London [ $\frac{1}{2}$  vessel with spout + 1 surring, 2 line stamp. In Dove Collection now in Company Offices in Cloudsley St. NI but will probably go to GH.

~~CARRISAL~~ L. ARRIVS CA | ~~EVDFE~~ CAPIT~~X~~  
L. ARRIVS CAPIT(6) | LUGUDV-F

Northwich r-facing 4K

Sandy greyish cream fabric

with brownish slip; grit on the flange; worn very smooth. Die 1

Deanshanger, Northants [FG XV(52) 5K] heavily burnt & heavily worn. Concentric grooving inside & a flange combined with the grit (flint, quartz & black ? ironstone).

Granular greyish cream with pink core, packed with quartz tempering. Pt. E. 33

Die 1

L. ARRIVS CAPIT [?]

See CAPIT (0?)


Die 2

Bloomberg Site [K9K29]

991K]

Bloomberg Site [K717]

927k



199A

? 10.1.7.

Leicester [51K Welles St; 444.1956; LAST. xxxiii, 61] hard buff fabric;

brown + white gut; Attius Marivoid shape.

Little Chester [GW 1960 L. lacing; friable fabric; misfired, surface  
grey + fabric? grey to buff. L.P. 5. 7

MASOR(?) - cf. AMSOR of RAHS

ASSAR → CASSARIVS

---


))

ASILA? retro

Worcester, The Flint [Repat April 2014  
Context 8662 Rec no. JE 4229 18K] Flange

fraguent, Period 6. [Rec. 4715 <sup>with spout</sup> could be same vessel  $\frac{9}{2}$  73g]

FF 15 gm. Fine textured orange brown fabric with cream slip, inclusions; moderate tiny to small quartz; random occasional black slag(?) ill-sorted but large & largeish spout same fabric.



Hamby St., Dröitwich [NGR SO 9025 6341  
HWCM 681 Irena heutowicz Hereford & Worcester

County Council 681-171 <sup>5K</sup> (7) ] 3 joining fragments. Slightly burnt;  
 very worn - only about 4 tetravalent gills survive. Hard, fine-textured  
 Rare, quartz (transparent) & rarer red-brown inclusions at X10. Ill-  
 sorted. White slip. Dr. 27µm. A few <sup>quartz + red-brown</sup> gills embedded into outside of  
 orange-brown fabric. Roman Dröitwich 2006 fig 39, no. 24  
 Wool, Dorset (Ray Farrer), and on CD Montana Catalogue  
 171; ?CG44; P4 (post Roman)

Wynfrith, Dorset [in Atomic Energy R. E. pipeline 1959; Dorset Proceedings  
; sent by R. Farrar] stamped twice about 1 in apart;  
fine, hard, brownish-orange fabric, surface brownish buff; cream or  
light-coloured slip - only traces remain; inside very smooth; one small  
white grit on fragment.

Droitwich Bays Meadow, Worcs. [DBM 71 IV (31) 4k] l. facing. <sup>\* Fairly hard</sup> ~~Soft~~  
Micaceous, orange <sup>brown</sup> fabric (SYR 6/6), sparse inclusions tiny quartz  
large ill-sorted brownish (? iron-rich) and greenish-black fragments. Trituration grit: quartz and  
brownish sandstone, traces of cream slip. Worn. Dr. 28cm  
Stamped twice fairly close together. Phase 2 mid @ to 3rd c.  
P TO

upside  
down



pebbles  
'd

o  
o  
o  
o

Roman Dorswich: Dordleshill  
Fort, Bays Meadow Vella,  
and roadside settlement  
Ed. Derek Hurst.

CBA Res Rep 146  
2006

p. 156 fig 104, no. 2  
and p 157, no. 2  
— wrong.

~~West~~, Dorset. Winfillh.  
(Farrer)

← Proc Dorset Natl Hist &  
Arch Soc vol 84 1963 P J  
Fowler

J, AS, H, NE

St. John's

ASILA

Warcester

Warcester

[WCH 101591 140

etc. 6

PTO for neg. sherds

(2 joining);

1 other sherd, probably the right facing stamp.

[H.K.] fragments of both stamps: 32.5 gms Diam

c 280 23%. Reddish-brown fabric with good

traces of cream slip. Inclusions: fairly frequent,

mostly fine, with some larger (but still smallish),

apparently mostly black (? slag), quartz, rare

red-brown material. Intertwining: white &

pinkish quartz, pale red-brown sandstone, red-brown (? slag), probably quartz sandstone. Some wear. Part of sp out survives - projects unusually

WCH 101591 1406 Rec 727 and 729 <sup>?? l. facing</sup> 4 sherds  
2 of which (Rec 727) join + are bagged together.

WCH 101591 1409 Rec 728. 1 flange fragment  
probably the right facing stamp.

WCH 101591 1407 Rec 726 ..

→ S1K1 Sidbury is an area of Worcester

Worcester ~~Sidbury~~ Worcester

Sidbury, ~~Worcester~~ [WS 76 1497 (P4-95) (30)] 4K <sup>Very smooth</sup> | Slightly

micaceous, v. fine-textured, orange-brown fabric, tiny inclusions  
of quartz, occasional hard red-brown <sup>(probably iron)</sup> fragments, and  
plant remains. Trituration grit quartz, <sup>rare</sup> red-brown, and  
fragments of brownish sandstone; thick cream slip. Dr. 25 cms.

CRS double-stamped, 2 joining body sherds, 1 base piece and 3  
sherds of same vessel, some slightly burnt. V. hard

sub-phase 5-1 3rd century p21 in report  
Darlington & Evans 1992.

A.T

See A. ...  
of ...  
for P. Weirham

D.H. Potter

York [13#6 2 III brought by A. B. ...] Hand, tile-red fabric; possibly has  
a light brown slip; fabric slightly micaceous; no texturation quit but  
1 small wh. quit in fabric + a large hole in flange fabric where  
a large quit has been embedded. A may have vertical as well as  
horizontal bar but a unevenness in this region of flange - probably  
the bar is there. AT [seems most likely reading but AJ is not  
impossible.

break.



Yoke (from H. Bowes.)

ATCIR TITVS


Brockley Hill [BH 72 CT1 K2 Fu MS 17 + MS 18 198K]

Two part, not joining of one vessel with waste crack through it piece of clay adhering. It has been used in building the kiln. Overfired completely to blackish grey; (dk bluish grey really; burnt brown colour at spot; white & grey flint grit. (In structure of kiln & of its products).

②

①


ANCIR TITVS or ATCIR TITVS



MS 17 v. 1 p. 10  
198K Knockley Hill.

ATEPAC [IVS] (VRW) <sup>needs to be</sup> ? <sup>Atepaname</sup> ? 110/120 - 150 A  
<sup>retro</sup>  
London, 10 Gresham St Group A context [267] Accession

no. <703> <sup>MS12 Fig 26</sup> <sup>Period 5</sup> 6.5-7K r. facing some wear. Has the rounded  
keying depressions typical of the Venetian region.  
Fabric at fine end of VRW. 2 sheds 410g Diameter <sup>max</sup> 340  
Profile with distal bead can be closely matched in some  
material made at Lincoln Technical College Kilm



ATEPAK  - see Biley for derivation.

Vendaniium [V Pit 6 (not a waster) AJ xi <sup>P. 280</sup> ~~P. 280~~, 15K] Pit 6; pinkish,

slightly sandy, buff fabric; fairly sparse, medium and large, white, red, brown, grey grit.

Hampden Mills, <sup>M. Oxney, Nr. Watford</sup> Oxney, Nr. Watford [St. A + Hert. Archit. & Arch. Soc. Trans.

1961 Fig 2 no. 2 & p. 82 no. 2] "Montanius of hard cream ware, with a flattened bead rising above the rim. Stamped ATE! (ret.) impressed vertically downwards. This is the stamp of the potter who signed himself ATEPO on a pot from Vendaniium (Pit VI) Fig. 31 - no 38?"

Hedgerkey kiln-site, Bucks (letter to Jones 11.V.63  
Hampden Mills, Oxney nr. Watford)



RI/A

The  
little lines of depression round each side of  
each stone (see rubbings (light)) must have been  
raised in die by clay squeezed out from making  
letters - not ~~probably~~ properly clean before  
baking.

ATEPA [CIVS or ...] This path ... as  
certainly <sup>highly</sup> some reading,  
Great Chesterford [1948 WELL 2] Flange fragment in cream fabric

with v. thick brownish core; sandy. Fabric undistinguished.

Staines [Elmsleigh 210, (265) 42K] Granular greyish  
cream fabric with pink core; buff slip; quartz tempering  
fine version. ? brownish slip. Dr. ? Dental head. L. piece.

Hedgeley, Bucks [M. V. Jones] [63. Aylesbury M.] l. facy  
 Light ~~to brown~~ <sup>to brown</sup> sandy. [buff fabric with brick coloured core; gut worn away  
 in lower half; large to small flint grit - wh., grey, <sup>occasionally</sup> reddish brown; one or two stuck in surface in lower half  
 on outside of vessel; one or two colourless grits which are  
 probably not flint. In the die the letters were poked out so as to  
 create a ridge of clay on each side which make grooves along  
 side the letter in the stamp. D = 11" traces of brown slip  
 no doubt meant to be buff.

Southwell, Notts [SCS X12 388 3.K.] L facing 300gms  
 Diameter 290mm. 26% Three joining sherds. <sup>Fine-textured,</sup> L cream fabric  
 with fine granular fracture; remains of a pale  
 brownish <sup>cream</sup> (ochre) slip. Fairly frequent to frequent, sand-  
 sized to tiny, quartz and red-brown material with  
 some very slight brownish-ochre staining inside the  
 fabric. Inturation grit: worn away except for about  
 9-10, mixed, quartz, red-brown siltstone and black (? slag).  
 Condition (i) very heavily worn; ii extra added to form  
 spout has fallen off exposing its cutting across the

Krombert Dore 1998, p. 160.

rim, which was made to keep it into place. Report

to I. Rowlandson March 2013,

⑤ φ Δ

ATEPACIUS 2  
Abbey St/ Marks Rd.

Technical College  
in immediate vicinity Kils. Unid.

Lincoln, Technical College, Next to Kils. site [2002.453

LCB 02 (012) City of Lincoln Arch. Unit 97K] FF

in hard, dead white fabric; slip fired to purple-grey.  
Probably a waste. Inclusions: moderate, tiny to small,  
quartz, red-brown and black material.

ATEPAC 2 + check Scotland

Lincoln.

Castleford [799] CAS 83 [15] 556 [322] . 39K] l. facing

slightly micaceous, greyish-cream fabric / moderate inclusions  
quartz mesh  
haematite stained quartz, sparse red-brown and tiny  
black fragments. No biturbation grit survives. Half of a <sup>circled</sup> punch hole  
survives. No keying for extra clay, or spout. Self coloured  
inclusions can be seen in surface of fabric.

Lincoln College, Abbey St / Monk's Road [LE02 2 002 453

~~(012) 97K] City of Lincoln Unit sent by H. Darling /  
B. Precious, r. facing stamped twice close together  
with coin fabric.~~

## ATEPACIUS 2

Winterton, Lincs [11K now no. no. \_\_\_\_\_] sandy, cream fabric with pinkish <sup>yellow</sup> slip; abundant very untidy <sup>+ chunky</sup> grit; <sup>huge</sup> large grey to medium, grey, brown white to red brown grit.

Roxby, Lincs, [11K now R/ARI \_\_\_\_\_] l. facing. Flange frequent. Cream fabric with darker slip; an earlier attempt at stamping <sup>is</sup> smoothed; 1 large <sup>+ a few</sup> small red-brown, and grey grits on flange.

York [124K SM 6 1989.21 2168] stamped twice close together.

Dr. 48 cans. 2 large joining sherds. Very hard cream fabric. Inclusions: fairly frequent quartz, moderate orange- and red-brown. Mostly smallest inclusions but all rather randomly dispersed and not well-sorted. Trituration worn away entirely in lower half. Very

heavily worn. Quartz, transparent & pinkish, with small  
proportions of dark red. ? haematite, dark red slag, sandstone.  
Yellowish-cream slip. A Lincoln variant fabric.  
Context is 130 +

(A) TERACI Q? see ATEPAC.

Lancaster Trans. of L.S.C. Antiq. S. xxiv, 1906 p 54. ] <sup>? 2 check</sup> NOT SEEN in Museum.  
Found The Stoney Institute, Lancaster. - Read as ATEPAC by Watkin.

SATV ( $B_2$  - Cambridge)


Cambridge S117, 121/2, 332/3, 368, 383:

Newstead (p. 266, 25) - SV

Division so far according to  $B_2$

ATEPACIUS 3 joining fragments SF6752 9  
L. facing 72K Union

Ribchester [RB 89 Context 18 joins RB 89 Context 25  
V. facing 6310 69K] Dr. 26 69K = 3 joining fragments. Well-  
worn. There should be about  $\frac{1}{3}$  of vessel - 2 modern breaks  
Slightly pearly surface. Creamy buff fabric  
with brownish tones in part. Core greyish buff but  
pinkish in base. Self coloured slip. Inclusions:  
moderate, tiny to medium, not well-sorted, quartz  
& red-brown. Turbation: quartz, probably flint,  
red-brown. 69K fragmentary & identifiable only:  
it joins. Fabric 65



ATEPAC. Q - ATRACILUS

of ATRACIL (the ...)

Lincoln [Technical College Kiln 1936; 7K] greyish core to cream near surfaces,  
buff slip varying in shade. 1 white grit, 1 pinky white grit.

Lancaster [Watkins R. Lancs. p 187; found in making Rly Station 1849/50. <sup>not seen</sup>

Lancaster [Watkin p. 187 do.] ATEPAC mentioned also Trans. L.C. Ant. S. XXIV 1906  
p. 54, The Stoney Institute. <sup>not seen</sup>

Lincoln [Temperance Place. Information M. Darling 18.8.1980  
apparently missing. See file.




Technical College Kilm, Lincoln 77K 1/2  
1986.

ATEPAC [...]

2

Winter ton, [TW/VV (\$)] ( Archive 74 joins archive 91, xw/AEN.

No. 92 xw/AEN ~~is~~ in spot of same vessel not joining. 14K] probably left-facing. Porosity, cream fabric inclusions: moderate, ill-sorted quartz, some opaque red-brown, rare black staining. Dr. 29cm. No tentation survives.



ATEPACIUS 2

WINCOLN


Castleford [712] CAS 81 S10 L453 /1406 51k] FF;

effect: deep - impressed stamp. <sup>Hard,</sup> <sup>with slightly brown-cream sand</sup> Fine, cream fabric, ~~fine~~ some  
~~ill-sorted, ill-sorted quartz,~~ <sup>and</sup> <sup>pale</sup> ~~of~~ <sup>of</sup> Quartz (large <sup>over</sup> ~~3~~ <sup>2</sup> mm) red-brown fragments.  
<sup>fine</sup> inclusions (largest trace up to 3 mm)  
 No trituration grit survives; orange-brown slip, overfired  
 to grey on underside.

712 CAS 81 SIO L453

1406

break



Castleford 51k

ATPACIV(s) 3 56 on each sherd [3]

Corbridge | 3.352 94K + 216K, [2 joining sherds] l. facing.

Micaceous; slightly sandy-textured, brownish-pink fabric with greyish-cream core. Surface somewhat smoothed. A few minor small patches of brown which could be slip. Small patch of black. Inclusions: sand-sized. Interstitial grid: medium + small ~~sized~~, red-brown sandstone quartz but most have fallen out. Hatching is reminiscent of hieroglyph 4K. Illustrated atypically xxvi (1948) <sup>no. 3</sup> stamp only



ATPACIVS ~~4~~ ? some previous H-H. H-H

Different die  
Probably H-H

<sup>138-40</sup> Leicester [4K; ~~857~~] <sup>1964</sup> Bond St; ~~1866~~ hard, buff fabric; medium and large grit

(flat) black and brown. cf. DOBALLUC

A

Cambridge [AA<sup>4</sup> XXVI, 1948; S 352 [3] 56; 216K] pink buff fabric

B

~~Leicester 4K, L. facing~~

gilt fabric undoubtedly Hartshill - Manduessed in type (1964).

There is no ATPACIVS from Poltross, Biscan



Leicester 4. 10. 7

ATTICVS AFEC/KANAB ~~BO~~ BON

Colchester [information + scan from Steve Benfield<sup>d</sup> 20/4/2016

Colchester M. Found in an extra-mural site at St. John's Abbey and excavated by CAG (Colchester Archaeological Group). A sherd flake from rim. Off-white, sandy fabric. (no rubbing)

ATTICVS·FEC/KANABIS·BON Temporary cord BONN

Trier [Pfehl 2002] He does not appear to know of any other stamps of this potter, but mentions several other mortarium stamps - not sure all are in my index; certainly some are not.

\* Von Bonn nach Trier: Ein mortarium of Atticus aus den KANABAE (Legion) by Stefan F. Pfehl in Trier Zeitschrift für Geschichte und Kunst des Trierer Landes und seiner Nachbargebiete. 65. Jahrgang 2002  
Illustration 93, Abb. 1.



ATTICUS I SEC / KANAB I B B O N N

B O N N

Ventanium [D 86 MB 316K] r. facing, stamped along  
IRS. Small bits of <sup>black</sup> accretion in places, on vessel surfaces &  
fractures. Cream fabric with very thick pink core;  
fairly frequent, ill-sorted, inclusions of sub-rounded  
quartz (up to 4 mm) and orange-brown, rock  
fragments (2 mm), rare black material, No. 10  
grit survives. Buff-cream slip or fused darker at  
surfaces. Diam c 490 mm (Niblett, Manning, &  
Saunders 2006, p 136-7 and fig 38, no. 7) Residual  
in rubble used as make-up in the later (3) - phase 9-10  
PTD

Probably derived from ~~derived~~ destroyed bath-house in  
Insula III. Associated with Antonine to mid ③  
material.

Note on petrology by D F Williams p. 137.

ATTICUS & FEC | KANA B~~ASE~~. BON  
15

Arensburg [Leiden<sup>IK</sup> Museum, CIL XIII, 10006, 148, AR 637  
+ & L stamps, both impressed along the flange  
[Ref. Hoffmeyer, p. 129, 6 plus

The Artisii.

Grater

(Secundus (not in Britain))

Sabinus

See Continental Cards for distribution.

PRIMVS (C. IC. ARTIVS PRIMVS)

~~Wob. xel. ex [1914, t. 3, no. 1, p. 60]~~

~~London [CIL VII 1334, 41 CRS. R. London p. 89] <sup>Illustr.</sup> <sup>check</sup> NOT seen <sup>? see the card!</sup> Reading doubtful.  
(Chivepost M)~~

~~Engiswald [CIL VIII, 1006, 41]~~ ✓

~~Vienna [CIL II, 5625, 34. 16K; 17K; 18K]~~ ✓

(G. ATISIVS) GRATVS Sep: <sup>Continental pot do</sup> would have been made at Colchester


Colchester [St. Mary's, (COLEM 2001. 64) Area G.

SF 1977 ?? K] 2 joining shards (break modern)  
<sup>across the rim</sup> L-facing stamp <sup>& beginning of r. facing stamp</sup> (Boudiccan demolition,  
other pot <sup>many</sup> pre-Hovian, Period 1). Faint cracks  
in fabric in and under flange <sup>and</sup> round spout  
probably result from being in Boudiccan demolition  
rather than being a waste. Discolouration in  
fabric probably <sup>caused by</sup> demolition <sup>context</sup>. Greenish-cream, slightly  
greyish in parts. Fine-textured fabric, inclusions  
included qtz, black & red brown but too tiny to be clearly  
distinguished at X20. Inclusion quartz, with some black

<sup>14</sup> # Should it be analyzed? <sup>Q111em 2.36</sup> This form was made  
at Colchester but never with this classic Aoste  
spont. 1.75gms Draw 280mm 17% There is a  
definite, thin red layer ~~below~~ just below the inside  
surface which is cream.

London, Bow Bells House [Context 1683 Acc. <1067> BBB05; 8.33K]

r. facing across. Pd 2. Diameter not possible. ?c 300 mm or less. Very fine-textured cream fabric with smooth surface. Inclusions: extremely tiny black, fewer red-brown and quartz. Moderate amount, with rare largish black, red-brown + quartz inclusions. Inclusions: a few quartz curvilinear. 40 gms. A



20 miles south-east of the Kentish Knock Lightship, or 40 miles

due east of the North Foreland [Heavington Spa Mus;] PSAL

2; XIII p. 107, 1890<sup>Arch</sup> Dredged up by a trawler. D =  $9\frac{3}{4}$ ' +  
 depth  $3\frac{1}{8}$ '. Misread as G ATISIVS GRATVS (no stop). Spout  
 broken & fraction rubbed down to a smooth surface; found in  
 about 12 fathoms of water. Arch. J. XLVII p: 234; VCN. III,  
 Kent p. 162; The Antiquary vol. 23 Jan/June p. 10.  
 (see note book); Information G.W. - The whole pot is stained  
 brown but original surface shows in bits as cream. No  
 gilt is visible; some marine encrustation. letter 1.12.61.  
 Bought in London by donor.

G. ATISIUS GRATVS

Attributed  
reference correct

A

Topsham [T/33; Rougemouthib., Exeter; Proc. Devon Arch. Soc. III. (1937), 16. figs,

no. 1] Bushe-Fox 50; l. facing; fine, creamy peach fabric with cream surface; micaceous; white grit - much of it glassy in appearance,

to b. b. stamp worn. D = Found by T. B. Payne in the Park  
stratified junction of Quay St & Lower Quay Street, Exeter, Devon, England, one v. faint.  
Gloucester [A 10,009 114 / 1960-6 26K] A mortarium in fire -  
Assoc. pottery pre-Flu. & Flu. Samian.

Textured, drab brownish-grey fabric with possible traces of a thick cream slip; there is a very little very fine quartz, red-brown + black tempering; the small-sized interstition grit is mostly quartz with a few blackish + red-brown grits. Probably subjected to abnormal conditions to produce the unusual colouring; not certain its burning. A B Fox 50. Flange broken l. facing

G. ATISIVS GRATVS see G. ATISIVS.

FOUND IN LONDON

Byck persbunny Ho. Wailbrook Stream. pale fine brownish cream  
London [19530 Guildhall M. 1K] L. facing; drab cream-buff fabric with

very smooth surface; smallish, quartz like grit very near to b. b. slight  
burning on parts of surface. D = c. 11 1/2 ins; B.F. 50 <sup>at bottom of flange</sup> well turned in A  
London [1937.69 Guildhall M. 78K] L. facing, smooth, buff fabric with  
a ? slip, discoloured brown; inside pitted; a few, grey, v/b, grits  
survive; D = c. 8 ins. BF 50 very small + thin; v. like 29K C  
closed in at bottom of flange.

G. ATISIVS [ GRATVS OR SABINVS

AOSTO

G ATISIVS

Bucklersbury House, Walbrook [1955; in private possession E.G. Abbas

London file

rubbing from N. Look to E. Birley] G. ATISIVS; almost certainly from same die as that found at Glanum, St. Rémy. <sup>Die</sup> GH IK Die A

Usk [Arch. J. xxxv p. 293; 311.78; 31K.N.M.W] shape v. v. similar to 30K;

+ facing; soft, cream, buff fabric with tinged pink in parts; abundant, small, whitish & grey gills to head; 1 large; B.F. 50; G. ATISIVS only <sup>Die</sup> A

~~Fishbourne [New die drawings, probably inaccurate & fits no die yet known for either <sup>Die</sup> B or C]~~

~~or Ennals FB 6/6 (8) also FB 61/6 (14) & 9 and FB 6/6 (14) 46~~

Canterbury [M IV 80 (624) 188 47K] r. Facing slightly micaceous, <sup>very</sup> <sup>B</sup>

fine-textured, <sup>pale</sup> ~~peachy~~ brown fabric with v. little <sup>very very</sup> tiny qty temper & occ. ill-sorted <sup>of</sup> red-brown inclusions; <sup>small</sup> <sup>black</sup> <sup>back</sup> <sup>wh.</sup> <sup>transp.</sup> <sup>qtz.</sup>

Corbridge [AA<sup>4</sup> XLVI p. 175, no. 2; AA<sup>B</sup> VIII, 1911 excus. p. 35, no. 112 f. 9, p. 115; M100; 281K1K]

very fine, cream fabric and drab cream surface on top; tiny and small grey inconspicuous grit; cheesewire d. ✓ B

Carlton [Sca Silurum, J.R. Kee, p. 42; pl. 23; figs. 1-11; VII, 1334 no. 45; 31.78; 30KNMW]

l. facing; compact, smooth buff fabric; not much grit; worn; flutlike, whitish & grey ✓ F

Carlton [ref. as above; 31.78; 31KNMW] appears to be a different vessel

from 30K; r. facing; soft, cream buff fabric with tinge of pink in parts; prolific, small, whitish, grey grits to bead; one large; B.F. 50.


Wroxeter [D. Arkinson, Rowley House] unstamped portion of B.F. 50. could be GRATVS.

G.F. 15:15

Not certain it is A.T. 15:11, treat separately

Fishbourne [FB 61/6 (8) / FB 61/6 (14) 40 / FB 61/6 (14) 40 Mus]

New die r. facing diagonal. stamp faint.



G. ATTIVS MARINVS

4 names; 2 FEELTS

Radlett [FEELT<sup>o</sup> 8K; Proc. Soc. Ant. 1898 2s. xvii p261. + St. Albans Arch. & A. Soc.

Trans. vol i pt iii n.s. p176-84] sandy pinkish cream fabric; slight traces of slip burnt orange; sparse gnt, mostly missing, a few on flange.

A waster though probably usable.

Bii

Leicester [2K; 847, <sup>of number</sup> Blackfriars, Leicester.] yellowish buff; small + medium brown gnt.

Bi

Leicester [7K 219] counterstamp of G.A.M. hard, yellow-buff; brown and grey, medium-sized gnt. (≠ to 2K, 19K or 29K).

Bii

Leicester [19K; 5.6.189; 1889; St. Nicholas] slightly sandy, yellow-buff; medium brown gnt, small also. Is not part of 2K. See C.V.I.D.A. - could be this.

10 at house to all together.

Bii

9. ATTIVUS MARINUS

Rosk. suggests ~~late~~ <sup>late</sup> ~~to~~ <sup>to</sup> ~~early~~ <sup>early</sup> ~~2~~ <sup>2</sup>  
 Wilcote, Oxon. <sup>The</sup> R-B Roadside Settlement at Wilcote, Oxon.

737 on p. r. (KK)

Exc. 1990-92 A.R. Hands. BAR But Ser. 232 1993

fig. 61, no. 579 and p. 110] L. facing. <sup>ill-sorted</sup> NOT the most granular fabric. Greyish-buff fabric, abundant inclusions: most quartz, rare orange, ~~red-brown~~ <sup>blackish + ? flint</sup>. Slip overfired to grey. <sup>rare red-brown</sup> IRW Interstratification: flint, quartz. PTO <sup>1" b.b.b.</sup> PTO

Dr. 3 ~~1/2~~ <sup>26%</sup> Spout wide nearest to 3G. 655gms. Slip discoloured to grey.

hereafter, Bonhairs have A.168.1993.2008 (247) 340K]

Dr 30 cms. (facing FE CIT + tiny part of name on r. facing. Shattered by a pick A.168.1993 240 belongs out does not join. Fine textured, slightly pinkish cream fabric, <sup>PTO</sup> with slightly brownish streaks. Inclusions: moderate, tiny quartz,

(rarer r-brass topaque white. No tintuation  
survives - Leicester 340K )

(Wilcote continued: definitely VRW1 Spont  
definitely later than c AD 90. Best date c AD 90-  
110. (Stamp abraded) Even c 80/90/100 as optimum  
date. Profile similar to Colchester 9AM's; ~~6AM's~~

8

G. ATTUS MARINUS

Dragonby, Humbers [277-DR-70-AD-Y 9K] FF. burnt. Hard,  
 fine-textured, drab cream fabric with pink core. Moderate,  
 quartz, r-brown and rare black inclusions. Appears to have  
 a brownish-orange slip. s. Dr. c. 29 Δ

(277) - TPQ end d (2)

M

Gonalston, Notts [Tarmac Hovingham Quary TMH 0509HNH  
 3K Trent & Peak] FF. Some dots showing below middle bar. L. fac.  
 presumed. Fabric cream fine-textured. Interior discoloured to  
 pale brown. Inclusions few, mostly orange-brown small &  
 few quartz. Softish-surface slightly powdery. 40g. Δ  
 Diam uncertain c. 30 cells. M

G. ATTIVUS MARINUS

✓  
Hereceter [ATT. 1975. 5488 T F 79 (777) (731) 269K] ATT. 1975. 5490


(2 fragments)  
F 17 I (446) ← part of same pot, does not join. r. facing Dr. 3 lines

Hard cream fabric with thick pink core. Inclusions: fairly frequent, ill-sorted but mostly smallish; quartz, red-brown & rare black

Interstratification: mixed, quartz, brown ss, red-brown and grey ss. Well-worn. Second sherd slightly burnt. Spontaneous <sup>type</sup> variant <sup>needs photo</sup>

Hereceter [A39<sup>+</sup>. 1988. 8488 F6 (2) 270K] Flange fragment.

different pot <sup>same</sup>. Hard cream fabric; inclusions: <sup>moderate</sup> fairly frequent, ill-sorted, mostly quartz, rare red-brown & black. F&CIT clear!



G. ATIVS MARINUS

Leicester. [29K; 32'16 Redcross St. 3 2. 1916; ] counterstamp only. Bii

Warrington M. [<sup>28K</sup> no prov.; probably Wilderspod; 342'13; r. facing] soft, cream fabric; B;  
medium to large, red-brown & grey gits, occasionally on flange; worn very smooth.

Wilderspod [70'99; 39K; l. <sup>part</sup> facing] smooth cream fabric with brown buff  
slip; largish to medium, grey, black, brown gits to b. b. Typical rim. Not  
part of others. FEET stamp only. Bii

High Cross [Chance find in road works; J. Pickering. ] 1 name stamp  
and the border of a counterstamp, both from same vessel; fine, creamy  
white fabric, browned (? tile) & white, medium to small git; ~~sp~~ some  
internal scoring. Bii


G. ATTIVS MARINVS

heicester [302~~3~~ 1971 (210) 164K] would be l-facing. Slightly pinkish surface <sup>37</sup> rather drab cream otherwise; tempered with good amount of quartz; not hard but not soft. Grit mostly quartz but a little red-brown + dark brown grit intertempering; intertemperation grit mostly quartz grit. Dr. 36cms. Δ not bad.

heicester [205) 302 1971 166K 166K] r-facing. Top broken from spout in part. Finger marks like Bradley Hill / Radlett farspout. This + 164K shows dots clearly. Cream fabric with pink core + cream to buff slip, purple-grey patches. Tempered with quartz, red-brown. Int. grit the same up to beada praaguet Dr. = c. 37cms.

G. ATTIVUS MARINUS

- Colchester Mus. [3870. 19 ; 406K] counterstamp only; overfired fabric; pale cream-buff surface changing to dark grey and red-pink core; flake only. A ii
- London [G.H.; 116K] counterstamp only; sandy, slightly pinkish cream fabric; blackened in patches inside; 1 red-brown and 1 black grit; flange broken; no number. Z13 Radlett certainly. A ii
- Leicester [Gallowtree Gate 116. 1962/148. 113K] stamp and counterstamp; latter very clearly impressed <sup>cream with slightly pinkish tinge; large to small, wh. r/b and grey grit.</sup> B i tii
- Leicester [116. 1962. 74; 114K] both stamps. no rubbing. B i tii
- Leicester [93' 1962. 115K] RECIT only. no rubbing. B ii

N.B. 113K Counterstamp clear shows dots in border  and  
fine lines in letter-panel  . Also at end of panel 

GATTIUS MARINUS

joins 2 pieces 1969 I (51) s. Dv. 29 cm.

Leicester [164-1969 U/S 152K] hard cream fabric with brownish orange  
to surface; a little at 2 + 0/b. temper.

core; quartz-like + pink brown (stone) grit; cream slip. Δ  
very smooth on outside body sharp facets as if instrument (knife) used.  
Counterstamp. Dots + diagonal marks show in border.

Wildenpool [67 (6) F. 1.0. Unstratified 9.1.K.] v-facing flange  
flaring above bead but section incomplete. F&C [1]  
in cream fabric but pink throughout upto upper surface.

All dots + lines in stamp very clear + fresh.

London [12 845M (Hayer Collection) 9K Merseyside County Museum]  
fragment; die worn. Cream fabric fine, with pink core.  
v. thin indeed + flaring v. high. CHECK if possible

G. ATTIVS MARINUS.

Colchester Museum [Rep. 1937 p 39 no 6636; 287K.] hard, smoothish, v. sl.

~~pinkish cream fabric, some~~

High Cross [1955 2ii +

n.s.



Slack [YAT Part 101; Pt 1 8 vol x XVI p 70 no 9] on rim no. 12 p 68; white to pale buff fabric; red  
? black grit up to rim. 7:1 n.1

Wall Museum [Oct. 1927 8K] <sup>potish</sup> pale buff fabric with darker buff surface

probably a dip; moderate, medium-large & medium, white, black & brown to near b. & b. B<sub>i</sub>

Leicester [p 215 + p 216 f. 58 no. II a, b, c] <sup>GR 77X/10K/101K</sup> <sup>B, B<sub>ii</sub></sup> another fragmentary) hard, rather coarse fabric

ranges from dirty whiteto reddish buff in some cases with cream or unberslip; grit  
coarser variegated occurs also inside fabric. B<sub>i</sub> / B<sub>ii</sub> / B<sub>iii</sub> / B<sub>iv</sub>



keiserster.



G. ATTIVS MARINVS.

Not published

slightly micaceous  
off-white or pale

Leicester [A77 1975] I (688) (791) 228k] R. facing. Cream fabric,

with pinkish core; moderate inclusions of quartz, red-brown and black <sup>streaky</sup> fragments are common. Trituration grit <sup>mixed</sup> soft red-brown fragments and quartz. die 5

Leicester, Causeway Lane [A1. 1991 (2914) 17708 ; (2150) 17705 + (2914) 17708 M012; 323K] r. fac. Basically fine textured cream fabric with pale brownish pink core. Slightly more than moderate, ill-sorted inclusions: quartz + orange-brown material. Dr. 25 cans. Possibly a slightly darker slip. Trituration: mixed, quartz, quartz clusters (s.s), red-brown ss, rare black. There is a deliberate fine combing but not as deep as V.R. Region + little if any



break

Leicester 228k r. fac.  
77 1975 I (688) 791

deeper than on flange. Bore clear. burnt.

G. ATTIVUS MARINUS

<sup>102K</sup>  
Leicester [p.163 & p.164 f. 44 no.2]; hard buff ware, pinkish core Bi

~~Leicester M [note 155 - name folder S. P. 18 EB, M15, 52K] G. ATT. MARINUS not seen~~

Leicester [p.163 & p.164 f. 44 no.3]; light buff ware. 103K Bi

Leicester M [G. ATT. MARINUS not seen. information D. Clarke; M11; 60K] n.s.


Grainsby, Lincoln [1K GR (A); Arch. & A. Soc. of the County of Lincoln; Arch. notes

for the year 1955, D. Petch, fig 1, no. 6; A-TF/263988]; buff fabric with thin orange core; <sup>orange buff</sup> slip; fine textured but with particles of sand. large Bi

medium/small gits <sup>grey</sup> red/brown, white & black, moderate amount sparsely to b/b.

Wall [Site Museum 9K] slightly sandy, brittle, brown-buff fabric with pinkish


tinge with tiny gits in fabric and on surface; prolific, large & medium white, brown, black gits, internal surface torn by gits. Bi



(1/4)

VITA  
|||||  
|||||

R




Leicester.

(1/4)

VITA  
|||||  
|||||

3



out.

Grainsby nr. Lincoln.

1/2 K.

→ Do a rubbing

Templeborough [W. V. Wade 1948; Rotherham M.] counterstamp only; white

nineclaw: reading from outside; trace of (possibly) ... Bii  
 'CHECK SOURCE of manufacture  
Leicester [Rubbing from D. Clarke; M15; 52K] <sup>PTO</sup> name and counterstamp; c. half  
 survives; fabric dirty, not Midland but as whole resembles BH/R in being granular

pinkish cream with pale buff slip; traces of burning in part; most of gut worn away; greyish brown  
Holditch, Staffs [J. Charlton. KK] buff-brown self-coloured fabric; no gut

survives; sketch  
 R349 1960 Church have see overcard Bi  
Rodester [found by workman; information J. E. Critchlow & rubbings] 5K

'4 sizable pieces' with stamp each side of spout. <sup>PTO</sup> Bi and Bii

Melandra Castle Miss M. Daniel, Cromford, 24, Fauvel Road,  
 Glessop, Derbyshire. (J. R. Dockerill, Darhnam)

~~Suggested dating~~

AD 90/100/110/110-125.

contd.

Roceter Church has from notebook, Hard cream fabric,  
buff slip, rough scoring; tinturation black, brown, grey  
& whitish. Flange rising above bead. 5K

hereafter 52K - The Colchester stamp - was it

being used at Radlet? Probably not - should  
needs to be compared with the Albion at Colchester  
considered to be local - fabric is granular but not  
source of that is not 100% certain. (2017) <sup>found</sup> like VRW.

Urbandra C. See letter to J-P in 9.AM folder.

Stamp now lost.

~~Brockley Hill [BH 73 TC MS28 257K] facing greyish buff~~

~~with brownish slip.~~

Brockley Hill [BH 73 TC MS54 256K] granular greyish buff fabric with dark grey <sup>upper</sup> surface. Castle R. pottery Mon B H, Mddx, 1966 + 1972-1974, Trans LMAS 27 (1976) p 213 MS4 Unfortunately I appear to have drawn the stamp as a complete stamp.

Tripantium [Sc. SF 34. 9K] flange & bead; hard cream fabric containing gritty particles; pale buff slip.

Ashley, Northants [SP. 788917. ASH 66 J (7) 2K. Steven J.

Taylor 18, St. Johns Court, Warrick. Fragmented both stamps; 5 fragments in all, one of them burnt. Hard, coarsish cream fabric & slip, buff at spout. Heavily gutted fabric but only one indeterminate trituration grit.

~~Robby Radlett fabric~~ Midland - not late - dots in border dec.

Brockley Hill [West Kiln Ditch S.A. Castle] Castle & Warbis' Bi

Excavations on Field No. 157, Brockley Hill (Sulloniaca?) Middlesex

TLMAS 24(1973) 103, fig 7, M18

PTO

Brockley Hill stamp - almost certainly this was not sent because of the size of the piece or it was found late and information but apparently no rubbing was sent. It is undoubtedly a second mention from B.H.

G. ATTIVUS MARINUS

Billingsgate Dumps [Information from Ted Connell]

B-G 128 1979 K] assumed to be L. Facing - Flange

fragment. Mainly ginger brown (Munsell 2.5YR

6/10 (described as light red); oxidised to

greyish cream at surface (skin of greyish -

cream. A <sup>strip</sup> which is fired to reddish-


brown just beyond stamp. Fabric granular.

Inclusions: frequent, not well sorted quartz

with few, tiny to small, black & red-brown.

Finger depression underneath stamp: 80gms

Diameter  $\leq 340$ mm. 8% die 2.1 VRW



G. ATTIVS MARINVS

A

*[Faint, illegible handwriting]*



w. 141' 01 (21) 7  
Stamps on opposite sides of spout.

drawn by W.B. Good

G. ATTIVUS MARINUS

Rocedex, Northfield [95K 50gms (5)  
RONO1 v/s archive no (16) name stamp

this does not join rest but can be assumed to be the right-facing stamp.

Other sherds archive (96) (5 sherds but breaks may be modern) arch. (183)  
RONO1 8070 405gms  
F 816-04 (joining 9183)

counterstamp FECIT L. facing.

Arch. (15) RONO1 v/s 160gms joining arch 104  
RONO1 8104 55gms.

The 3 sets of sherds are all from same matrix.

Total weight 780gms. Dia. 280mm. 53%. Has had little if any use. Ruth Leary's fabric 12 with pre 140<sup>130</sup> iterations of it Arch. 96 burnt at one edge - after fracture. PTO

No sign of use. Some singing on 1 sherd  
(across)

There is rough but consistent concentric scoring. Very neatly finished base almost beginning to be a footing & exceptionally neat cheese wiring. Smooth, v. fine textured, ~~the~~ fabric, cream near surfaces with thick pink core; fabric ~~slightly~~ micaceous.

Inclusions: moderate, tiny to small, red-brown material, pinkish quartz, ~~very~~ rare black.

Coloration: small to large; only a moderate amount altogether; orange-brown sandstone, quartz (transparent and pinkish), rare black; well-mixed.

Very thin-walled vessel.

Namesamp could be new die? ?  
PECIT seems the same though.

S. ATTIVUS MARINUS

Coleshill [10K 1080 + 1095]  $\frac{3}{4}$  of vessel. both stamps.  
Riveted.. Cream fabric; red-brown, quartz + grey grits.

Sea Mills [2K F4020. 1965, I (11) ST 5512 7589] Flange  
fragment; fairly granular, brown buff fabric. Contains alot of quartz but  
not as much as B. Hill usually has. A Radlett product.

Northwich [65K CN(1)10.] L-facing. Attributed to S.A.M.  
Pinkish cream with some grey temper. A

Middlewich (Kinderton) 3277. 1977 Kiln of st. (7) 1980 [2K Middlewich  
library] Cream fabric with pink core; bright red-brown, brown +  
quartz inclusions.

G. ATTIVUS MARINUS

Annual site  
Malton [Injured Jockey Rehabilitation Centre (Code: 5.44.2011)]

Roman Pottery Assessment J. Evans & Phil Mills. Old  
Malton Road, Malton, N Yorks SE 79K7 72 27c.  
1 km from fort & adjacent onto Roman road  
leading from the fort. 22K]?? Lacing. 78gms Diam 240<sup>mm</sup>  
14% Flange fragment. Very hard, quite fine-textured  
buff fabric with some darker shade near surface in flange,  
possibly where approaching spout. Traces of self-coloured  
slip fired to darker colour on upper surface (almost orange-  
brown) in area of spout. Inclusions: fairly frequent to  
frequent, very ill-sorted, from minute (just over heat x20) P10

to Tiny and smallish, all randomly distributed:  
mostly transparent quartz with some pinkish  
some opaque orange-brown (mostly ~~sp~~ barely visible  
at X20); rare black material. No alteration  
qtz survives. On bag 5.44.2011 (054) (M13.1)  
Die 3.1 no. farther shed.

G. ATTIVUS MARINUS m. v. clear but dots in border are not clear.

Rocester [OPR 96 6 001 73K] L. facing ~~WEST~~ EAST. Midland  
but probably v. early. Form & spot reminiscent of ~~Rad~~  
Radlett & heavy tempering of qtz reminiscent.  
Dv. 4.3 cms. Oplu split in fabric. General appearance  
at fracture quite granular. Cream fabric with  
frequent but ill-sorted <sup>transp.</sup> quartz, few orange-brown  
& rare black wagner. Probably self-coloured.

Intervation: mostly worn away, mostly v. small  
quartz (viz at x20), few largish red-brown. May  
have had concentric scoring inside. Hoops as though  
trying to produce m. as at Radlett. Parts of stamp v. fresh.

9. ATTIVUS MARINVS

King Hall, Works SP44 4735 [9] joining sherds<sup>+</sup> LH 98  
1164/1 (2 sherds); 1164/2; 1164/10; ~~and~~ 1139/9 (4 sherds). M22  
1 K] Dv. 31.5 cms 41.5% r. facing. May never have  
been used. Very irregular, intermittent and carelessly  
made concentric scoring. 1075 g<sup>+</sup> g. Part of the  
flange is cream and this is clearly the colour intended,  
but much of the surface inside and out is grey. Some colour  
change has taken place after fragmentation because of  
the very clear colour change at one fracture especially.  
No wear on base. Fabric fairly hard for this pottery.

~~dark~~, buff-cream, slightly purker towards surfaces,  
but surfaces vary in colour from cream to grey and  
greyish orange-brown. Some of colour changes  
occurred after fracture. <sup>some being to pink</sup> May have had a slip  
but not covered. Inclusions: fairly frequent  
and ill-sorted; mostly quartz with some black (? some slag?).  
Inclusion grit: random small to largeish, upto top of bead  
in places; mostly quartz, some dk red s.s.; grey,  
black? slag, opaque white, quartz sandstone & flint.

G. ATTIVS MARINVS

Provenance <sup>England</sup> ~~unknown~~! <sup>locality unknown in Register - ? Colchester v. likely.</sup> A  
[FS 115; NMA.169K] r. facing; sandy, buff fabric; sketch.

Templeborough <sup>near</sup> [May, pl. xxxviii + p. 120 no. 1; Rotherham 19K] l. facing; hard,  
smooth, creamy, fine fabric with buff surface; very good amount, medium to  
small, white, black and brown grit to c. 1 in. b. b. but stragglers above; p=13 in  
read by May CATTIVS MARINVS. / B. i.

Templeborough [T/c/20; 3x.38; Rotherham M. 21K] l. facing; very badly worn  
recessed and stamp and broken; soft, orange pink fabric changing to cream  
very near surface; same type as 29K but has another spot <sup>n. i.</sup> not published.

Templeborough [R. P. Trenches S. side Staff(?) Rd; 1938; taken from large box;  
T/c/24; 5x.38; Rotherham M. 22K] r. facing; not part of 21K; fairly soft, cream  
fabric with some r/b grits on surface; type near 21K. n. i.

Wilderspool (Warr. Mus. 141'01 [7K]); creamy fabric with pinkish core; drab B


surface; no grit survives; [Striding 22 p 32 for ref. to G.A. Met. ...]

Wilderspool [1171, 16K not reproduced q. 715] <sup>off</sup> creamy buff fabric; grit sparse but B  
right up to & over rim; large small, r. brown, black, grey; buff outside & under flange. D = Bino

Wilderspool [Warr. M. 141'01 [21K]] <sup>cf also W. Ranney remains p 64 + 139'01</sup> + F.E.C.I.T. counterstamp; creamy coloured  
core, slightly darker surface <sup>slip</sup>; variable sized grit red & <sup>grey</sup> black rising v. B  
close to rim + occasional stray over. <sub>i + ii</sub>

Broughton Noe (Debyshire J. P.G. "F.E.C.I.T." only) [Jewry Wall p. 215] (not the same  
in Littlechester).

Venlamium [A.J. xx1, p 279 f. 3, p 280] A Bldg. [p. 72 T; 17K] pinkish, coarse,  
buff fabric; v. like CASTUS. Radlett fabric Ri



Ashley, Northants [ASH 66 J (13) 4k] Flange fragment,  
fragmentary stamp, different vessel from 2k. Pale <sup>brownish-cream</sup> yellowish-  
~~brown~~ (7.5YR 8/6), heavily fired, slightly darker color at  
the surface and slightly burnt. Frequent inclusions quartz.  
No tirtwaction grit survives. <sup>Could be little Chester.</sup> N

Bourne, [South St, Lincs. Inf. <sup>BSS 97 (424)</sup> Maggi Darling ~~rubbing~~ sketch.  
No tubulation cuts survive. 2k. Diam 290mm 11% <sup>10</sup>/<sub>100</sub>g M  
n. facing name stamp. 3 joining sherds. Hard fine textured  
fabric, cream with <sup>thin layers</sup> ~~shades~~ of brown in it, very moderate  
inclusions, quartz with rare red-brown and black material. <sup>P10</sup>  
Brownish cream slip. Typical M-H fabric but hard & fine <sup>early</sup> (2)

At least 3 dots inside upper part of border,  
Borne continued. letters very sharp and little dots in field  
visible on rubbing esp at top of lower line but also a few at top  
of upper line. Unlikely to show any poor impressions  
The top border ends <sup>at the beginning</sup> at the line of the dots <sup>but some</sup> viz later.  
bottom border broken so cannot see middle of border. ~~across~~

G. ATTIVUS MARINUS

Potter 45 — Hartshill + ? Mancetter

Hartshill [H60 (5B) 10 (38)  $\triangle$  ~~306~~] L: MH fabric 1 and

interstratification <sup>(MH)</sup> unit 3. Diameter 290 mm. 70 gms 5% mis

Recording type K4209. Drg no. P486.

~~3~~ (168) H60 (5) is believed to be from same pot  
but does not join.  $\triangle$

NB This is the only mortar ~~(MH)~~ S Attius Marinus found on the site.

## G. ATTIVS MARINVS

Little Chester (Darley Playing Field South (DPFS) AMAI  
Context 11113 =  $\text{E}_i$  post 120. Fill of possible architectural  
cut for structure, later used as a domestic pit, BF  
#485, 61K] FECLT #1200. L. facing, but of  
additional spongy clay has flaked, wt 1235g  
Diam 290mm, 10% / A white fabric, slightly rough  
to the touch. Fairly frequent to frequent inclusions  
consisting mostly of small to medium-sized quartz  
with some red-brown and probably other rocks.  
The inclusions are mostly red-brown with occasional  
quartz and black gnt. no indication of use on sherd, d. 4.3

G. Attino Marcus

Little Chester, Darley Playing Field South (DPFS):

[AMAR <sup>Context</sup> (10153) BIF 839 60K] <sup>(early 2')</sup> context: N-S ditch immediately W  
of Ryknield Street within views] 60K l. facing. Wt 4 Dpms  
Diam.  $\approx$  290 mm.  $\approx$  4%. Cream fabric with sandwich  
core, very pale brownish with greyish-cream inner core.  
Frequent, ill-sorted inclusions, mostly small to medium and  
mostly quartz with rare black and red-brown  
material. Broken too high for tinteration gub. Almost  
complete stamp, reading FEET 7 NETS. d. 403

G. ATTIVS MARINVS


~~Little Cherty~~

## GATTING MARINUS

Blackfriars  
 Leicester [WAA 14 BFL A 646 343K] 55g  $\leq$  300mm 4%

Hard cream fabric (to a thickness of 2-3mm at the surface);  
 core up to 9mm thick in parts. Core similar to Munsell  
 5YR 7/4. Inclusions: frequent, mostly small to  
 tiny: quartz (transparent & rose) + opaque red-brown  
 (with rare black) + some quartz sandstone? Also,  
 rare larger black (slag) + red-brown. ~~possibly~~  
 Intertaxation grit: only one certain on small sherd  
 - quartz sandstone. The surface slip is <sup>dark buff, but is</sup> dark brown  
 in places probably because in the spout area.

Very clearly not VRW despite being frequent <sup>inclusions</sup> MH 1 d33



# 9. ATTIVS MARINUS

Little Chester (Darley Playing Field South - AMA3 (30158 in context)) unstratified. BF2663 Darby Mus 2015-21, 62K) l. facing. FEClT retro. WC-590gms D<sub>100</sub> 340.  $\mu$  22% Self-colored, hard, fairly fine textured, cream fabric. Inclusions ill-sorted, but mostly so tiny that they are only visible at x20 magnification; they consist mostly of quartz with some red-brown material. The plentiful & ill-sorted, ~~textured~~ grit is mainly in lower half of bowl and consists of quartz, at least 2 kinds of sandstone & some black material with occasional quartz sandstone to


There is some slight cracking where body meets flange  
The stamp is an excellent impression from the earliest  
die ~~used~~ of SAH used in the midlands. It could  
be a die used at Radlett or B. Hill.

Dec 3.1

F. ATTIUS MARINUS

Walton-le-Dale [WDA6 Dvq 585. 3001-7365 67K] r. facing  
counterstamp. Six sherds joining counted as 2 because  
rest of breaks are modern. Powdery surface. Cream fabric  
with self-colored slip. Pink core. Inclusions; moderate,  
ill-sorted, quartz, red-brown material, blackish? slag  
& rare rather spread out white pellets (Cu or -reactive).  
Worn heavily. Interstratification up to bottom of head: large  
& small quartz, red-brown, grey, flint. A little  
very curious scoring on inside. 1010 gms Diam 33cms  
37%.

d. 4:1



G. ATTIVUS MARINUS

Dies 5 and 6

R. Leary July 2005

Barton St, Manchester (64) Contest 790 18K Pd 3 Phase 3. Small


fragment very close to spout. Drawn but not true profile. r. facing.  
Cream fabric, sc or self-c. slip. Inclusions: fairly frequent to  
frequent, tiny to small, mostly transparent + pinkish quartz,  
few orange-brown and black. Inclusions show in surface.  
under magnification. Two quartz + 1 black testulation  
grits survive. Part of lower letters + border of FZCIT stamp  
survives. die 6

~~Seal type [SCAE (64)] stamp should be l. facing.~~  
~~upper part of letters + border of FZCIT stamp.~~

G. ATTIVS MARINVS

Lancaster [Mitchell's Brewery Jerry Evans <sup>sent</sup> 9/2002; <sup>year.</sup>];

L99/109 4322 35K] L. facing. Diam 290 mm 13%  
125g Hard, cream self-coloured or s-c slip. Inclusions visible  
at x20: fairly frequent, ill-sorted, transparent and pinkish  
quartz, rare opaque red-brown and black material.  
Interturbation grit was extended up to top of bead. What survives  
is smallest to medium sized, mixture of quartz, red-brown  
sandstone & rare dense black. Rob 19/H



G. ATTIVS MARINVS

B

Lincoln [Watertower 1910 "Westgate" written on piece, 13K] FEEL on one side of spout, name on other. rather sandy, coarsish cream fabric with buff slip (shade varying); large to smallish red/brown, black, and white grits to near <sup>white grit only translucent</sup> Lincoln [Monk's Rd 14K] smooth, (slightly pinkish) cream fabric; medium and small red/brown grits up to head, 1 or 2 fragments on flange. Broken st. <sup>translucent</sup> Caerleon [Sea Silurians, J. Fa. Lee p. 42, p. 23; fig. sub iii. 1856 p. 77 tab. 2, fig. 4; CIL VII, 1334, 12; 31.78; 29K N.M.W] sandy, cream-buff fabric with buff surface; some flint grit. B.F. 58; read by Lee p. 42 as GATTIVS MANSINVS. Check source

A



9. ATTIVUS MARINUS

Colchester [P3187 M103371 T<sub>2</sub> 202 S21] r. facing sketch.

A

Colchester [P5617 1.81 A346 S22] IRS Big hook. T1 [.]

does not fit other pieces from Colchester die.

A

G. ATTIVUS MARINUS

Mag, Fig 7 no 5

May 1935 ~~55~~ R.C.E.M. 1935-7 p. 39.

Colchester M [~~R.C.E.M. 1935-7 p. 39~~; 660'36; 287K] hard, smooth, sh, but

with tiny gits in fabric; v. slightly pinkish, cream to greyish cream surface. A


Colchester M [~~475~~; 662'27; 338K] cream, <sup>smooth, hard</sup> slightly sandy fabric;

moderate, small to medium, red, grey, black, white gits. Stamp and corner of another next to it. Approx. B-F 58 but head lower. A

Baqinton [B. Hall Pit; 7K [B.A. Stanley] "hard, pinky fabric; few gits of gravel". FCCIT stamp only. In Coventry Museum. Bii

Baqinton [B. Hall Grounds. 8KB A. Stanley sends information.

Coventry Museum] "cream, soft, fabric, almost vesicular; few git holes". Bii Bii



287K + 338K Escheater Mils.

Brough-on-Noe [counterstamp. J.P.G.] Under the rampart of the Bii

IVIVS VERVS fort + dates to pre. A.D. 125. Also with one of earliest b. b. cooking pots like that at Chesterholm before deserted.

Elack [YAS. XXI, p. 163; Pl. XVI, no. 31; Skipton Museum] r. facing; <sup>Check Drawing source</sup> buff fabric with orange-brown core to very near surface; discoloured to dark grey on outside; good amount, large to small, red, grey + brown grit to near b. b.; the grey is flint probably. Ci  
 Mammoth, <sup>Red Lion 161</sup> [Monmouth School; information G. Boon Nival. Die Ai <sup>Found by walkman 1963.</sup>

a rubbing sent. Found 1961 <sup>1/5</sup> seen 1994 Greyish-cream fabric with abundant quartz inclusions. Venlavin region fabric but the

time version. Tinturation v. heavily worn - all surface gone  
to 1 cm b.b.b. Very little remaining above that point - flint,  
quartz & ? iron slag. L-facing. Dv. 32. Surface overfired  
to darker color; ~~tiny~~ <sup>small</sup> patches of vitrification around spout.  
Spout not like Flavian Albinoid spouts. Differs from Witcote  
spout but not by a vast amount. Approx. D Spt. 3.  
Inclusions much as Witcote but latter has a few red-  
brown ? slag inclusions.

G. ATTIVUS MARINUS

Templeborough [p. 12 no. 1 + pl. xxxviii, no. 1]

Gerleyn <sup>Caerleon Museum. CIL VII 234, 12.</sup> Neca, p. 42, tab. 23, f. 1 + Arch. Camb. III 1856 p. 77, tab. 2, fig. 4] as Colchester,

Elstach [VAT, <sup>xxi</sup> p. 163, no. 31 + fig. XVI; <sup>about 1923</sup> St. Ives Winton Museum]

35 C

Melandra C. [pl. Via Derby Arch. J. <sup>f. v, no 62.</sup> LXI x p. 25 fig. 5, no. 62; 7K] <sup>Buxton 1</sup> v. smooth, soft, <sup>5384</sup> very slightly creamish with brownish buff slip; large to small brown + grey guts to top of b.

B

Godmanchester [unpublished, <sup>The</sup> Norris Museum St. Ives]; reddish brown.

? n. s.

The Broadway, St. Ives, Cambs PE27 5BX  
01480 497314

VITTA . J  
MIIAM

TEMPLETSBO ROUGH (1)

VITTA . J  
MIIAM


(14) Godmanchester

Y.

? VITTAIS  
?VVIIRAM

(15) EBLACK

→ NOT THE STAMP  
I rubbed at Skipton M.  
etched by T. May?



G. ATTIVUS MARINUS

Castleford [no 456 CAS 80 S10 L054 64K] l. facing  
corner, borders only; dots survive. Nos. 565-6 from same pot  
Different vessel from no. 34K. Quite hard, rather brittle <sup>cream</sup> fabric.

fairly frequent, ill-sorted quartz + r-b + rare black inclusions  
Probably has slip, ~~is~~ orange-brown. Inclusions: sandstone +  
quartz. little wear. Dv. 33cm.

Ribchester [RB89 context 54 SF 6909 67K] r. facing. Dies  
Dv. 30cm. Cream fabric rather brownish streaks in  
fabric. Inclusions: ill-sorted but small, moderate +  
at X 20; mostly transparent + pinkish quartz; some  
opaque orange-brown, rare black? slag. Inclusions:  
quartz, red brown; sandstone

Border probably G.A. *trium* *arsinilar*.

Highgate Wood [HW 68 370 4K] Burnt; greyish with tinges, pink in core;

Staines [16K QK 76 B4 11] Flange fragment is fairly fine cream fabric. Too damaged to draw properly. Fabric finer than the rest. v. fragmentary top of first TD of ATTIVUS + border.

Wildespool G.A. Mariner - one of these stamps is recorded  
in Trans. Hist. Soc. of Lancs. & Cheshire NS 22 (1906)  
p. 32 as from a refuse pit.

G. ATTIVS MARINVS

Colchester [Cat p. 259, 6]

<sup>pub 1945</sup>  
Ret Sawny Wall p. 215.  
Little Chester [Derby Mus 33 - '27; 1K.] complete; pale buff fabric; ? slip; <sup>Bi</sup>  
profile, med. H., blk, wh, red grits sparse nr. bead, to b; scoring; rim rises well above bd.

<sup>874. 56. 1. 38</sup>  
Radlett [V.C.H. Herts., 162 & St. Albans Ant. Soc. Trans. vol. 1, pt. 11, ns. p. 176-84]; rather sandy, <sup>7K</sup> <sup>no R</sup> <sup>D.C.</sup> Bi  
creamy pink fabric; typically Radlett; surface buff to orange, moderate fine & smallest grit black, wh, <sup>(flint prod.)</sup> brown, grey


<sup>E. Birley</sup>  
London [B. of E. 1929; & GH (mentioned by E. B. on list ~~but no reference to~~  
other references); 7 in E. B. London folder. <sup>Bi</sup>

York [old station file; private collection] N.G. Simpson & B<sup>2</sup>. flange rises above bead n. s.

(v)  
Colchester  
(Cat. fig. 7, 5)



Radlett  
no. 161.



Sketch. Derby Museum 33.27


9. ATTIVUS MARINUS

VRW


London [BBB05 Bow Bells House Context 1190; <916>]

Pa. 3. 820K] Flange fragment. 50 gms Diam 310 mm.

9% VRW Greyish-cream, brownish-cream thick core  
Surface a buff-cream slip fired to paleo-brown  
colour under flange. Die 3.1 As 7K Radlett 90-110



No 1, Poultry, London [Context 16739 Mus Acc. 4154 One 94 439K]  
 (facing). Intended to be greyish-cream but very heavily  
 burnt inside. <sup>Heavily</sup> Well-worn. Self-colored slip. Fabric pink  
 in parts <sup>near inner surface</sup> but may be due to burning. Frequent tiny to small,  
 fairly well-sorted quartz = fine end of Vev range. Few  
 interstitial grits survive, flint + quartz. 170g. Dm. 30cm. 10%



GATTUSO MARINUS


Northgate Kilns, London [MR995 Cont A1168 Acc (256)

566K] r fac (notspont) UNUSED 1600 g. Diam 32.5  
56% Dram base 12 cans. 3 joining sherds. Normal  
cream venetian eq. fabric. Inclusions: frequent moderately  
well-sorted, occasional red-brown, sometimes larger,  
Tinturation. Flint, quartz, red-brown material. Surface slip  
darker cream.

Coarseslip

The scoring inside is very broken, not as good as ~~the~~,  
& that is not of the early type

Seeley & Drummond Murray 2005, p 21, (P46), not drawn.




G. ATTIVUS MARINUS

London, 12-18 Moorgate, London EC2 [MGE 96 [1297] 1014] 418K

Graham Bruce AOC Archaeology Group 19.2.99] r. facing  
with deep finger impression under flange where stamp  
impressed. 370g. Diam 34cms. Heavily worn.

The finer end of fabric ~~and~~ and no sign of con. sc. on flange or inside.

Cream fabric fired to a brownish pink at the outside surface <sup>of bowl</sup>  
and ~~at~~ parts of interior. Very frequent, fairly well-sorted  
quartz inclusions with v v rare orange-brown & grey  
(? flint). Inclusions: tiny ~~to~~ small flint with some  
quartz, mostly worn away. (Radlett)



G. ATTIVS HARRINSVS

Leicester [316.1953/E Leicester 116K] counterstamp only. no  
rubbing; red surface. ? fabric 13 ii

Wildespool [80K. A4 E: (4)] J. Williams. r. facing. Hard cream fabric  
with darker slip; very edged/counterstamp - midland.

Wildespool [81K 66 /E 8/108] different vessel, probably l. facing. Fine  
softish cream fabric containing red-brown particles & grey; <sup>somewhat</sup> ~~slightly~~ abrasive  
to the touch; remains of buff slip; <sup>white</sup> ~~grey~~ flint & brown grits rather sparse  
(arguably to small). Very clear impression of counterstamp with dots showing  
& little diagonal lines above & below letters - early midland.

Manchester [D. Atkinson. 57. TR. S.N. end. B.B.L near cobbles; ~~ref~~  
counterstamp in old. Softish cream fabric with thick pinkness; fine sandy tempering in cream  
slip; red brown + grey grits.

Castleford [(725) CAS 81 S10 F494  $\triangle$  1587 .34k] c. facing FECIT.

l. facing G. AT. etc. Cream fabric, moderate <sup>to fairly frequent</sup> inclusions ill-sorted quartz, sparse red-brown and black fragments. Trituration grit reddish-brown sandstone and quartz. 4:2

Dr. 32 cms. Fabric B 3:1. Some lines scored by marine grits.

Rochester [RO 86 I 1228 53K] l. fac. Hard, cream fabric with some quartz and red-brown inclusions; perhaps with slightly darker cream slip. Dr. 3/4 cm FECIT - early use of die. Die 4:1. Trituration grit mostly quartz with some red-brown & w. occasional blackish grits. Spout type 2?

Esmonde Cleary & Ferris 1996, p. 67 no. 13 and fig. 30

G. ATTIVUS MARINUS

Chesterfield [VL98(31.61) 8K] r. facing diam. 28 cms. 22%

Cream fabric with moderate to fairly frequent inclusions, very fine & small <sup>(x20)</sup>, mostly quartz with some orange-brown ill-sorted inclusions scarcely visible without lens. Scars = slips.

Intertaxia: up to 5 cm below top of bead & odd one above that line. A background of fine and small <sup>(a little pinkish)</sup> quartz & black material & some red-brown sandstone. Larger grits mostly red-brown sandstone with rare quartz. Fabric hard and fine textured. 440g letter sharply cut & dots & III, clear in stamp. Not published

G. ATTIVUS MARINUS

Taddington [TD 81 325/2 (on pot) Warrick M] P.B. 1-A-B 8'  
[TD 81 (71) No. 64 SK] L-facing FECT. Fabric greyish  
(on bag label)

but fused to cream at surface; fine quartz & ool dark grey  
& red inclusions; trituration unusual - right up to top of bed  
& occasionally over it - quartz, o/b, blackish. Dr. 36 cms.

Castleford [595] CAS 80 S10 N27. [68] - 36k] r-facing. Die B.  
Yellowish-cream fabric, moderate inclusions ill-sorted quartz  
and sparse orange-brown fragments. Quartz temper sometimes stuck  
together in lumps. Trituration - grit - quartz + brown sandstone.  
where is it? Dr. 32 cms. Not checked 3.2.93

G. ATTIVUS MARINUS

Probably both 19-H

Little Chester [DLC 79 ARC + DLC 79 HFF + DLC HFFH] 49K

Dr. 31 cms. Hard white fabric with moderate amount of quartz  
(whitish + rose); cream to cream-buff slip; red-brown  
tinturation (?? later) l. facing. FELT.

Little Chester [DLC 80 HYK] probably <sup>SOK</sup> l. facing. Dr. 33.5  
slightly bent; some striations plus quartz, o/brown; <sup>tinturation:</sup> blackish  
fabric slightly micaceous; hard, creamy white fabric  
with some quartz inclusions. Corner of stamp probably  
S. AN as Fecit.

G. ATTIVUS MARINUS (prob. - lly B - at least 2 runs)  
Probably both H-H but EXN could be L. Chest.

Little Chester [DLC 80 ACM] 47K 29cun. Hard cream fabric with

very thick pink core; fabric, slightly micaceous with a fair amount of very fine quartz (transp. + rose), few r/b and blk inclusions; pinkish-buff slip; truncation cont quartz, p/b sandstone and other red-brown particles. <sup>Probably i. packing</sup> Some rough striations. Name.

Little Chester [DLC 79 <sup>+ EMC</sup> EXN] <sup>48K</sup> 484 v. facing.] very hard, pale buff fabric with ~~transp~~-pinkish core; a great deal of tiny temper, (Dr. 53) mostly quartz with very ool black and r/b; truncation mostly quartz with very ool r/b cont. Brownish-buff slip. v. facing. <sup>NAME</sup>

1 flint?

6. ATTIVS MARINUS

Venlaminum [58 E V (5) / 2. 262K] flange fragment.

Sandy & pale brown with salmon pink core. Butt slip.

Clearly a Radlett type fabric.

Venlaminum. [57. Z I (12) / 5 260K] flange fragment. Burnt.

Surface various shades of buff and pink & grey of core grey. Radlett type fabric undoubtedly.

Some changes made Jan 1990:

~~G. ATTIVS MARINVS~~ new die sequence (DEC. 86.)

OLD DIE 1 A namestamp = DIE 1  
" " 1 B FECIT = DIE 2 } Colcheste

OLD DIE 2 A namestamp = DIE 3  
" " 2 B FECIT = DIE 4 } 

3.1	3.2	3.3
4.1	4.2	4.3

Radlett, M-Hartshill  
? Little Chester

OLD DIE 3 A namestamp = DIE 5  
" " 3 B FECIT = DIE 6 } ??

4. ATTIVS MAR INVS

handoff A156, Yorksey Lock

Torksey <sup>locks</sup> hincs [Ian Rowlandson · L.T.L.E 15 519 1K]

l. facing, Diameter 310mm. 29% 490gm. Some wear  
Orange-brown fabric with some dirty cream in "core" in  
flange & underneath spout; a thin wedge in body in <sup>centre</sup> "core"  
and possibly a few tiny areas at surface. Traces survive  
on spout & on exterior of a matt, orange-brown slip.  
Surface & stamp slightly abraded, some fine  
cracking in surface in, under and around flange.  
Inclusions; fairly frequent to frequent, mostly quartz  
with red-brown & black material. Inclusions/git:  
P 10

Lots, ill-sorted & well mixed, red-brown and other sandstones, various sorts of quartz, quartz sandstone. few black rocks, few probable cream clay pellets. 1 streak of cream clay showing in surface ~~is~~ underneath. Inturation grit 1 Fe ci stamp dk.

S. ATTIVUS MARINUS

WAL (E2) 11

see packing list

Wallsend [WSP100 noSF context E02:11 loc - phase VS 44K] L. fac.

Incomplete nu-section. 50g. Dam? Heavily over-fired.  
orange-brown fabric at surface, the rest reduced to dark  
grey with pale grey core; slip discoloured to brownish-buff.  
Fairly frequent, ill-sorted but a background of v tiny to small,  
quartz, black, brown to red-brown inclusions. Titulation: quartz,  
brown sandstone and black material. <sup>only 2 or 4 grains as they'd.</sup> F of counterstamp. Border  
in pristine state.

S. ATTIVUS MARINUS

Reminds me of Genic. lis

Near Pocklington [sent by Gillian S. Baker, The Lodge, West Green,

Pocklington, York Feb 16 1973] b. facing sandy orange-brown

fabric with greyish core (thin merging) with traces of mat red-brown

slip; <sup>chert-like</sup> white soft + <sup>sandstone</sup> red-brown grit + quartz-like grit - all surviving

in fabric. Not quite like Little Chester. ? kind Cii Δ

see 44K wall section

SE 88780852

Scunthorpe [SCAE (664) Int. M. Darling IK] stamp should be

(. facing. Upper <sup>edge</sup> letters and border of ECIT stamp 600gms.  
 Diam 300 mm 32% some wear. Hardish, self-colored  
 brownish-pink (Munsell 7.75 YR 8/4) with pinker core  
 & creamier patches on surface of flange. Inclusions:  
 frequent, ill-sorted, mixed, tiny to smallish, pinkish  
 and transparent quartz, some red-brown and black  
 material and black smears in fabric, rare white & v  
 rare blue material. Inclusions appear on all surfaces  
 & make it feel slightly abrasive. Int. grit: smallest  
 to medium, red-brown sandstone, pinkish transparent  
 and white quartz, rare black & cream material.

Barton-on-Humber [brought by B. Whitwell E.A. 67.40. P/P.] Ci

l. facing. Hard, cream fabric, containing grit; with yellow slip; medium to small flint grit (apparently all flint, some of it pinkish). Lincolnshire

History & Archaeology (Arch. l. Notes for 1968) vol. T, no. 4, 1969, 105

Melincroft Castle [MSL 66 B] D 11K] r. facing. Fine cream fabric

with darker cream slip; grey grit - several fragments. <sup>Peter Welton ✓</sup> \$6

Manchester [46] <sup>Roman Manchester June 1974, figs. 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100</sup> Mc. 72 2 (80) fairly fine-textured

cream fabric; slightly darker slip l. facing. 11K **DB**

Manchester [ditto Mitre Yard 1974] Cream fabric with thick pink

core with buff slip; worn. Grit varies from tiny to monstrous size. white quartz, red-brown (some ? haematite + some ? sandstone; few grey  
(? flint), few white opaque. Δ

~~Coleshill [works 1080 + 1095  
K. Scott. 10.10.78] Almost complete~~

~~mortarium with lead repairs in a "ditch feature"~~

~~Warrick H. UK(n)~~

Melandra [80 XXII J. P. Wild.] Dr. s For dating evidence see

~~J.P. Wild's letter 14/7/80 To be checked~~ <sup>to see if joins</sup> HEL 66 [B] D (P.W. 1981) Die 5

<sup>14/7/80</sup>  
J.P. Wild letter 'Deposited at some point between Trajanic  
rebuild & the fort's abandonment in c AD 140'. Hard  
drab cream fabric; inclusions: moderate to fairly frequent, P10  
small to medium-sized, consisting mainly of quartz with  
some red-brown & black material. Interstratified grit: fairly frequent,  
ill-sorted, is mixed: quartz, red-brown & black rock; shell; a

in north face (outside) the fort ditch

Light brown, including fractures  
quartz sandstone; All surfaces covered with drab grey sil.  
Clean deposit, Diam 360 10% + 6% 310 gms + 75 gms

Antiquated retro

Brampton

Brampton [P9/10 DS 101 (2) NFK Norwich M. 124K]

Fairly fine-textured peach-brown fabric with some a little fine quartz tempennig; surface smooth; 1 trituration grit survives. Dr. 33cms.

Wisbech by-pass, Fengate Road Pit H (2) - early (3) rubbing  
description and profile sent by Tony Gregory. (not seen, rubbing poor but appears to be this stamp).



Creek

0

ATIMZ ?GRATINUS cat down?

MANCETTER/HARTSHILL  
creamy-white fabric with pink  
foxes

Manchuresdum [1063] ①9 W71 ⑧27] Fine-textured, very moderate,  
tiny & small quartz, often slightly pinkish and less common red-brown  
(refined-pot)  
r. facing. Tituration gut; abundant, angular re-fired pot. Unusual  
projecting spot. X-ray - ? gratinus. Dr. 30.5 cms.

Manchesdum [1064] ⑧ W71 ⑧⑧.4] Softish, fine-textured, cream fabric,  
very moderate small quartz inclusions and black specks & larger black  
possibly all iron compounds. No tituration survives.

(19) 1218 17

Mancty. 1063

n face



6

ATREX

Colchester [no. no. Oxford Rd, August 1931, 437K] red fabric and surface;  
some, small, white + dark girts to bead; outside part and under flange  
bright orange cream? D no more than 10 ins. r. facing. Scratch.  
Hard. Source unknown; fine scoring as well as small girt

ATREX<sup>oc</sup>

43716 Colchester  $\frac{1}{2}$   $\frac{1}{2}$

ATRICMS


Intonation: white, grey, black + red brown.  
 Brownish cream with fine tempering.

Caistor-by-Norwich [Norfolk A. xxvi. Pt. ii p. 213 no. 21] buff clay + surface; <sup>see so</sup> ~~not seen~~. + A

Colchester <sup>M</sup> [May 4, 197; 169.33 on pot. if same one. Laver Coll. 334K] pinky cream, A  
 slightly sandy fabric, a little white and brown grit in fragments.

Colchester <sup>M</sup> [4636.23 or 4630.23; 422K] buff, hard, roughish fabric; milling;  
 medium, whitish + black grit to b.b. B.F. 58; r. facing. A

Colchester <sup>M</sup>. [Laver Coll. 4482, 23] rather coarse cream fabric; no grit survives.  
 v. approx. B.F. 66. May 1930, p. 239 and Text-fig. 7, no. 4  
 on p. 241.



ATC: — (3) Shallowish thick looks...

ATRICIVS

C. S. Chester [P7562 181 E663 S131] probably right f.


Brownish-tuff with some quartz inclusions.

ATTI [—

Gaston Slack [WE 249 ~~EV~~] Il-facing. V. Rigby.

Bunt; incomplete v. section. Hard, bright orange-brown fabric with much fine quartz temper; traces thin cream slip; little Intaration grit, quartz & red-brown; probably northern. 4

Welton, Humber side [Red Mockey Mc 5 ca 405]



Venlanium [1954 K.VII T(7); 16K] L. facing; sandy, creamy pink fabric

and surface; abundant, r/b, black, white, grey grits, largish to tiny  
to b. b. A. Joins 1959 K.VII +; top of flange heavily scored and very  
heavily pitted flange - small, white, r/b, grey (almost black) D = 16 1/2"  
London [Liverpool M] Merseyside County Museum. 8K.

17.7.1902.49 Bennett Collection. Burnt white  
bowl; very well worn. Stamped only once; projecting  
spout; early. Crumpled, pinkish cream fabric so  
far as I can see; red-brown, black, white & grey  
grits worn away entirely in bottom 2/3 rds.

~~COLCHESTER~~ATTICVS. FEC. KANA BI. BONColchester See Continental cardsVembancium " " "

ATTILIVS

Brockley Hill [82K BH. 68 K.D. (P), D. in (Castle's list)] sandy, cream fabric | <sup>with sl. pinker core</sup>  
with creamy buff slip surviving in parts; 1 flint grit, above bead.  
Heard. D = c. 12 1/2" Δ




Brookley Hill BH68 82V  
KDD①

Newstead [p. 266, fig. 35, no. 1; FRA 1453; N.M.A. 109K] hard, dark red  
fabric with grey core; blue black surface, probably burnt; Flange  
fragment. CIL XII, 5685, 6.  
? same pottery as at Carlisle??

ATTIVS

Carlsbad Millenium excavations [CAR99 MIL Tr. 2 (555)

254K] Lfacing 575 gm. 240mm. 39% Technically  
a waster. Overfired and distated. <sup>Usable</sup> Some cracking  
under flange. Little use. Extremely hard (near  
scratched, orange-brown skin with very thick  
blackish, well defused to core coming through  
to surface in places. Buff slip. Indurcous:  
moderate, ill sorted, random quartz. 9 sherds  
all breaks modern. Distal bead.



ATTIVUS - MATT ATTIVUS

incomplete

Milecastle 49 [79/B; Tullie Ho. 22K] L-facing; orange fabric with <sup>brunish-grey</sup> greyish core and

trans  
[cream slip; few inclusions quartz red - (1)  
grey and brown; CW<sup>2</sup> LII p. 33 no. 21 read as MATT  
by I.P.G. Fabric softish much softer than CAR BOKLAE

1994 October 12th seen at heeds. Inclusions: moderate to  
fairly frequent, almost all <sup>trans</sup> quartz, rare blackish  
slag. Dr. 27 cm.

~~MATT~~ [...] (net)

See Abergavenny stamp

Mile castles 79 [CW<sup>2</sup> h11 p 33 no 21] orange fabric with grey brown  
TW core + cream slip, the quilt is small, multi-coloured  
& well worn. [described as typical H/A. cf.

MC. 50 no 96 A.D. 128-197; Balmunloy  
Pl. xli. no 19. A.D. 142-197.

Birdswald no 1 alley deposit  
Turris no 1. A.D. 22-8.

Die as

R BIVSII

Corbridge S309

Corbridge S328

Corbridge S338

Boskwellhaugh (Hant. Mus.)

ATTIVS CRESCES

London Bow Bells Home [Acc (16) Context 211 Pd 3 OA9

814K] L facing assumed. 1070 gms Dr 460mm. 17% Hard,  
Self-coloured, cream <sup>tabic</sup> pink with pink core at basal angle &  
spreading up, thinning  $\frac{2}{3}$  up side. Inclusions: fairly  
frequent, tiny to medium-sized, mostly quartz with a  
few black & red brown material & perhaps a few flint.

Inclusions: fairly frequent, vari-sized, though though  
mostly medium & smaller; transparent, opaque & pinkish  
quartz with hackly fracture, flint, occasional quartz  
sandstone & mica. Traces of a light but not continuous

concentric scoring. Frange smooth. Some wear in bottom.

Decorative stamps, placed above & below name stamp.  
E. Anglia. Probably Baylham, Suffolk

G. ATTIVUS CRESCES.

See CRESCENS + T.M 88  
See trademark 88, P. 200  
0/6

Colchester M [MOSK no. no.] hard, very smooth, surface red, orange fabric.

few red-brown, whitish, black gills. L. facing of. Stamp complete  
but end not impressed.

VITA

CRESCERE

4558 Colchester M. L. facing

CRESCEUS w. Snettisham

FK

Ingoldisthorpe, [Not 6 FK 1989 in Norwicher K. Lynn H] C. facing

Information D. Gurney . 1515 SNT 018 . Discoloured . friable .

Worn . Fine-textured , <sup>brownish</sup> clean / abric surface drab, brownish .

Very moderate , mostly small <sup>opaque</sup> stony quartz , fewer red-brown & black ,

± ? flint inclusions with rare large ones . Tituration grit :

little survives includes flint and quartz . Dr. 31. <sup>grit</sup> ~~is~~ slightly

shaler than Bayham House examples . Δ . Worn . (D. Gurney)

FRIL-CRIST, 2001, p 61 no 33, - fig 35, no 33 .



1515 SNT 018 l fac.

CRESCENS. . . CRESCUARIVS or CRESCENTIS

? In Coddenhams Parrot Tiles NEW. of Ipswich (SE. WESTPETER'S)

Baylham district [Ipswich M. S. J.] nearly complete, reconstructed, stamped diagonally; hard sandy buff fabric, little worn but base gone; fine crushed flint (?); some larger grits apparently rubbed out; grit inside, up to bead, a little on rim, & some in fabric; said by West to be from a Flavian level.

Baylham district House [BJ/GP SE  $\triangle$  70] Found in a kiln. N. Loughlin  
Fine cream fabric; qtz & flint temp. <sup>accidentally</sup>; large flint grit in fabric has caused a crack in bead. Stamp ~~somewhat~~ diagonal.

bK △

Probably made at Baylham  
which side stamps - is it part of earlier find? No.

- 1) Check up on whether typed  
 or by hand, if possible a  
 Neils piece of which side  
 stamps
- 2) Check on how close  
 all pieces of  
 Crescents are
- 3) Get sample



ATO NOTA ??? Sivapattinam Fabric Co. (Camel) Inc. In  
A@see

Invesk [77] 1977. 15NK Pub. no. 32] 9. Thomas. Barut; Smoothed

fabric; fine-textured cream with probably a fair amount of very finely  
fragmented quartz and red-brown inclusions, trituration quartz  
(transparent), black and red s.s.; slightly micaceous; (48)  
(body shed) also part of it is but not joining; a tiny fragment  
joining with no. number. A second die

Camelot [2] CAM 75 Ex. Site A [47] 8k] FF. Cream fabric.  
fine textured, <sup>possibly r.tac.</sup> moderate at X20 but extremely <sup>r and facing.</sup> tiny; occasional large but <sup>see over</sup> tiny quartz and orange-brown  
fragments. No trituration grit survives. <sup>Probably</sup> the other  
stamp from 74/75 and 72/73 which all join.

AR (Site A. Ploughsoil) See report. PTO

Camelot contd.

② in r/forestamp. (75) in L. facing. Finer textured than Aesico

(Woodward), but same sort of inclusions but latter bigger & probably more.

Inclusions: small to large, angular to rounded, quartz (rounded), red-brown sandstone, pale brown material, with fewer black

2 joins 125, 72, 344, 275, 328, 73-75.

Same vessel 234/345; 557-8, 327.

Could have a slightly darker slip than body colour.

No keying whatsoever for extra clay to adhere to.

Form & test pit identical to Aesico (Woodward).

ATO @TA

<sup>lines</sup>

Owmbly [Information R. Petrin fieldwalking ? to Scunthorpe M]

l-facring. Yellowish-cream fabric with some tiny, orange-brown inclusions with 1 or 2 large ones  
Inclusion grit: only about 4 surviving = quartz, red-brown (s-s), ? flint. Fragment weathered very yellowish-cream slip. Seen at Hull Art meeting 1996

J. 21. sandy, almost off-white fabric, cream slip.

~~Yorkshire~~ Mus. [38K] white pipeclay and white slip, white, brown grit of grey

~~grit~~ grit; stamp unreadable but the stamp & the rim-form suggests a Lincolnshire origin. A CIL VII, 1331, 136 USL(O)

Mus. K 327. A TO? ret. w. OTA Dr. = c. 30cm

Bishopthorpe, York [R. Perrin, 1973 ISI 11005] Flange

fragment from a typically S. Carlton type mortarium cleft under the flange - small. Off-white fabric containing a lot of grit, red-brown, transparent quartz, grey translucent and sparkling mica particles.

IT preserved. 91K



listed as amphora in CIL. & as found at  
York. Mus. Catalogue no. K 327. This  
is not a pot but stamp is recognizable  
from dx interpretation. USL©

Peter 1981 (Skeldergate & Bishophill), p. 84, no 400  
not illustrated.

AVLIVS

no. 223 CHE/NF'64  $\Delta$  II (5a5)

Chester [Nun's Field (NF) TR 6 1st. E. Extension. 50K] brownish pink fabric; thin  
drab cream core petering out in body; cream slip; abundant, smallest and  
small red-brown, grey grit, well-mixed. Stamp probably ends in V  
- there is a suggestion of the end of the panel. See R.P.F. for similar  
stamp and product. Sample taken  $\Delta$  v. facing.



039

50K Chester. r.facing.

N/DII X retrograde or VIDII X

Alchester [A421.479.M21 KA521] These numbers are on the bags, the  
numbers on the pot are A421 891 479 (sic) <sup>Oxford Unit</sup> sent by Jerry  
Evans end of Jan 1998 ] L-facing. Shallow horned spout -  
early second century. Stamp fragmentary. ~~Orange~~ - cream  
<sup>skinny bit</sup> fabric with ~~on~~ outside, rest including inner & upper surfaces  
is pale orange-brown (5YR 7/8). Inclusions: abundant, quartz,  
sub-rounded, generally well-sorted. Self-coloured.  
Inclusions: included quartz, flint & rare purple (?haematite)  
smallish, few only, surviving just below bead. High break  
Diam 35cms. 355g.

Sandy Beds (381 SA/C; stamp from D. Johnston.) (l. facing; sandy fabric intended to be cream with v. thick pinkish core almost to surface, and buff slip; but inside surface & inner half of fabric is burnt black. Die has rocked over curve so that outer part of stamp is not quite in line with rest and there are  $\parallel$  twisting marks in the clay. There may have been a slight attempt at 'beading' the distal end of the flange further from the spout because it survives where added clay has broken away.

AVDEX or VIDEX QK 76

Staines [17K Y90.137] r. facing. Frag. impression

Granular, pale brownish fabric; slip darker.

Staines [CAD 77 + (177) 30K] r. facing. Granular pale brown fabric with grey core & buff slip. (Saturninus-like spot).

VIDEX (or VIDEEX) vet

Staines [QRS 76 B 5 (12) (338) K. Cronch] overfired throughout.  
Saturninus like spout. Flint & red-brown grit. Greyish  
cream fabric. Dr. = c. 27 cms. 2IK

Orpington [Kent small site near Orpington vill a. <sup>(not published)</sup> Δ  
19.7.94. JP 104 SAO-93-65 1K] stamped each side  
Dr. 28. Bunt. Head well-worn. Surface slightly granular.

Brownish fabric (sl. dirty pale brown) with thin grey core <sup>surface pale brown</sup>  
<sub>where not obscured by burning</sub>  
Inclusions: very frequent quartz generally well sorted but with  
some variation. It may be the finer fabric but or bits could  
be smaller. Fabric is softer than Ver. fabric usually is. No slip.  
Interruption grit: mostly worn away but a few flint, quartz & ? red-brown  
slag.


Int quit - ill-sorted.

## VIDEX

Brockley Hill [BH 66 m. T.C. [M5] 188K] Granular orange-brown fabric with thin grey core; tiny white grit. Stamped twice close together. A

Brockley Hill [BH '66 m. T.C. [M7] 187K] r. facing. Stamped twice close together, Orange-brown towards outside but rest of surface dark grey; a few flint white & black grit; probably never much. A

Brockley Hill [BH '66 m. T.C. [M6] 189K] l. facing. Blackish grey granular grit with much white grit in fabric; a few white flint grits on fabric piece. Stamped twice close together. A



BH 166 write C. M. 71  
187K Brockley Hill

Hambleton Villa, Bucks. [Arch. 71 p. 188, fig. 19, no 4; 10K.] L. facing; sandy,

buff fabric with grey core; large to tiny, sparse, black + grey grits to near

b. b. BF. 46/58. At least 11 ft or below D ? V.

Sandy Beds (E381 SA/c; stamp from D. Johnston) L. facing

sandy fabric; intended to be cream with pinkish core almost

to surface but inside surface + inner half fabric is burnt.

Stamp has <sup>been</sup> ~~been~~ <sup>rocked over</sup> ~~been~~ badly applied so that outer part of stamp

is not quite in line with rest and there are all twisting

marks in the clay. There may have been a slight attempt

at beading further from spout because it survives <sup>where</sup> under

added clay has broken away.

Carlisle, The lanes [82 LEL A (419) (216) 153K] l. facing.


Dr. 25cms. Fine-textured <sup>sl.</sup> brownish-cream (7.5YR 8/4) with orange-pink core (5YR 7/6) Appears to have a brownish-buff slip. Inclusions: sparse, ill-sorted, ~~most~~ quartz, rare opaque red-brown. Tituration: mostly quartz, some red-brown sandstone.

Carlisle, The lanes [82 LEL A (119) (369) joins LEL A (84) (404) <sup>5/2</sup>

154K] r. facing & joining sherds altogether. Fine textured; pale brownish buff fabric (7.5YR 8/6). Inclusions: very moderate, ill-sorted, mostly quartz <sup>with</sup> some red brown ss. Tituration grit: quartz, clusters quartz grains, red-brown sandstone. IRS slightly brownish, buff slip. Dr.  $\approx$  36cms.

AUSTINUS

Maypat [Maypat, Cumbria: A Roman Fort and its  
Garrison, M. G. Jarrett, CtW extra series XXII  
(1976) fig 13, no. 29 'cream ware with very pale  
orange core, brown and white quartz grits.  
Not seen



AUSTINUS

Maryport <sup>M66 DBex DD.</sup> [1966. A. Birley] r. facing; buff-red fabric with buff core; brown and white angular and, rounder, small + medium grit. Stamp faint. Sketch. B


Stamp seen at Cardiff could perhaps be this. Desc<sup>n</sup>.  
+ skeleton DOE notebook.

Soft, fine cream fabric with orange core; brownish slip; red-brown grey grits large to medium sb.  
ALL 'ONE' - checked on rubbings

AUSTINVS

/check

Vindolanda 2 10789 + 9725 die C



AVSTINUS (Link with 'Caltrop' of other desc. Wilderpool (?) + Cardine  
from Wilderpool) [See also uncertain ne Middlewich or Kidderminster] Region.

Birdswood [CW<sup>2</sup> L, p. 58 no. 8 + fig. 1, no. 8; In J.P.G.'s store at Newcastle

12K] From Vallum ditch filling (dated to latter half of Hadrian's reign),  
nr. S.W. Angle of camp 1929; 1; Fabric: unusual, <sup>hard</sup> - softish cream with  
reddish layer just inside + buff core; white, brown + grey gut, silk s. A  
Not much gap before went out of use + time of filling.

NB. E.B. + J.P.G. quote Lancaster this is a misreading of L + C XXIV, p. 54,  
nos. 8079 + Pl. 3. 8v 9; E.B. quotes Kivke by Thore a loose leaves but this is assignable.

[1963 . S. 9 - wooden die - red fabric, cream slip ; S. 124  
pale buff fabric, brown + white gut on piece ; S. 14  
orange-brown fabric with cream slip.]

AVSTINVS <sup>B</sup> <sup>Prumpt</sup> construction at earlier.

II (Ant) J.P.G. thinks - Ant. w (4) zero level  
III (4th C) " (4) "

Cordoncok [CW<sup>2</sup> XLVII p. 116 no. 54; Tullio. Ho. 38K] L-facing; 25.1946

orange-brown fabric with buff slip; brown, grey gits; same general

type as 37K

Cordoncok [CW<sup>2</sup> XLVII p. 118 no. 2; S.W. Angle (1); 88/1947.6; Tullio. Ho. 58K]

stamped each side of spat; orange fabric with buff slip; very abundant, large to small, mostly brown, some grey, 1 or 2 black + 1 or 2 white gits to b. b; horizontal grain-marks; no stamp; on subsoil. S.W. Angle. Primary probably J.P.G.

Amble side [CW<sup>2</sup> XV p. 52 + p. 45 no. 6] red clay, buff slip, red and grey gits, 7 in. diam. Stamp, FABSTINIVMANV. South gateway; Armitt library

Ribchester [R1B 78 BAH 1 42K] fine <sup>pink -</sup> orange-brown fabric containing quartz, dark grey grit + some red-brown tempering; traces of cream slip surviving mainly in stamp; quartz + few v-begits. Dm. 28 cms. Casting - probably wooden die. The lump in  $\Lambda$   $\Delta$  in top line is a quartz grit; 1 of bottom  $\Lambda$  goes down to bottom line.



11T2VΛ

Ribchester

AVSTINUS

Landaster [LB 88 6812 261/315/6 28K] FF Tan  
coloured fabric [Munsell 5YR 7/6 'reddish yellow'] with  
pink-brown core [Munsell 2.5YR 6/6 'light red']  
Fabric not hard. Fine textured. Traces of cream slip. horizontal  
striations in the stamp. Inclusions: few, random, ill-  
sorted quartz, red-brown. 20g. I ~~R~~

AVSTINVS | FECIT (retro)

Watercreek [MB/W 11K. Kendall M] r. facing. SK. very near

spot + difficult flange may be lower further round. Soft,  
fairly fine-textured fabric. Traces of cream slip. horizontal  
grain-marks in stamp. Slightly pimply surface; g/s,  
r/b (s.s.) + black tintation. Pr. 2 locs. As in W. Dale SK. I

AVSTINVS

Lancaster

Raneglass [LV 75 A I 46] <sup>24K</sup> r. facing. Quite hard but fine -

textured, orange-brown fabric with buff slip. Fabric contains some qty + other kind of grit; no int<sup>n</sup>. grit on fabric. Neatly moulded spout, broken.

Walton-le-dale, Lancs. <sup>(19)</sup> [WD 82 1022 (192). 5k] <sup>fine-textured, bright orange fabric</sup>  
(5YR 6/8), inclusions angular [quartz, ill-sorted, slightly micaceous. No titration survives. (Fabric 31) occ' red-brown inclusions].  
Pr. impossible. Pr.  $\leq 27$ .

F

AUSTINUS

Carbridge [B1 67 M505 423K] hard, fine-textured, very pale brown fabric fired almost to cream at the surface, with brownish slip; fairly ill-sorted, quartz, red-brown and occasional black inclusions. Dv. 22cms. Inclusions: transparent + milky quartz, red-brown sandstone, blackish and possibly flint grits. A

Corbridge [AA<sup>4</sup> XXVI p.175, no.4; S9, EA 13 [4]; 362K] hard, brick red, slightly sandy fabric, with cream slip. B

Corbridge [AA<sup>4</sup> XXVI p.175, no.4; S 124, 1911 [4]; 363K] r-facing; slightly sandy, yellowish buff fabric; small white, grey, brown grit. Probably used for original drawing. D

Corbridge [AA<sup>4</sup> XXVI p.175; S 14; 56; [4]; 364K] sandy, orange-brown, with cream slip; sparse, small + medium brown, sandstone, + white grit. B

Chesters [2436/3747; 19K] red-brown fabric; cream slip; medium + large, brown + white grit; Near 4. A. D B

Austrian

Attributed

Carbonite, The houses [CAR 82 B (73) <sup>287</sup> OGL 158K] FF Hard, very  
fine-textured, orange-brown fabric (2.5 YR 6/8) with cream slip.  
Inclusions: 3 quartz + 1 red-brown barely visible at X20. Stamp frequently

295

75K

Carlisle, Blackfriars Street [CAR 78 BLA 296 B 615] l. facing

About  $\frac{3}{4}$  of worn mortarium. Slashing for keying spout partly exposed - looks just parallel. Spout survives. Very hard,  $\Delta$  dark red-brown fabric with fair amount of tempering, mostly quartz; but almost worn away in bottom despite being so dense & hard. Has been good amount of white quartz, red-brown & black. Other nos. 268 DD63; 269 B376; 295 B600<sup>all join</sup>. Cream slip. Dr. 31  $\Delta$


Carlisle, Blackfriars Street [CAR 78 BLA B 615 300] 76K; l. facing <sup>Dr. 32</sup> Hard, fine-textured, buff & pale orange-b. fabric streaked buff-cream slip. Worn. Quartz & sandstone trituration, with odd black grit.  $\Delta$

AUSTINVS

Butchergate, Carlisle [seen in store at Dr group meeting (Cubboings)]

Complete mortar in

D



Carlisle, Blackfriars Street [CAR 78 BLA B 634 P 28] 355

joining B + 124 77K ] <sup>Dr. 32</sup> l. facing. Hard, fine-textured, buff (deep buff) but in no way red, with thin pink core in parts. A good amount of quartz tempering. Brownish buff slip. <sup>A</sup>  
Quartz, sandstone & black interstratification, some of it covered with slip. <sup>D</sup>

Carlisle, Blackfriars Street [CAR 78 BLA B 631 P 3] 78K

r. facing. Very hard, orangy buff fabric, fine-textured, with ~~the~~ paler buff at surface & thin grey core; deep buff slip; A. quartz tempering; good amount sandstone, white quartz

356

 Dr. c. 37

Caliste [CW<sup>2</sup> XVII, Plate XVII, 3b + 3c; OM. 448 + p. 84. May] 8

I hope give 3a + 6 as OM. 448 but the drawings correspond only with b + c being from the one vessel; (particularly as 3a is from a different die; 6 YK. Tullie House Museum. B

Caliste [CW<sup>2</sup> XVII, Pl. XVII probably 3a. Tullie House Museum. 68K. no. no. on vessel. (see May). A

Caliste ? [32-21. Provenance unknown. Tullie House M. 89K. A

Caliste [CW<sup>2</sup> LXIV p. 30 no 5 + fig 6 no. 5.] Assigned by J. P. G. to AUSTINUS.

Border of stamp. Red fabric with blue core in thickest part of the rim + a cream slip; multicoloured grit, mainly reddish-brown + opaque whitish grey. Ginner's marks w on it.

Carlisle [Sewerage Works 1857; ~~See ed<sup>2</sup> xvii p. 196~~; ~~see~~ Tullie House 12K]

stamped each side of spout; hard, orange-brown fabric with buff slip; much, black, grey, white and brown grit to near b.b., some of white appears to be chalk. A

Fidenbridge, Carlisle [From City Surveyor; 51-1931; Tullie Ho. 10K] l-facing. pinkish brown fabric with buff slip; abundant, white, brown, black, grey, largish to small grit to b.b.; D = 1.0 ins, horizontal grain-marks. B

Carlisle [Tullie Ho. Gardens 26.8.1957; 97.1957; 37K] stamped twice on each side of spout; hard, orange fabric with cream slip; much, brown, white & grey, large to small grits; worn, to c.  $\frac{3}{4}$ " b. b.; D = c. 1.3 ins. S.P.G. in Hadrianic-Antoine deposit. C

Carlisle, Blackfriars Street [CAR 78 BLA B (107) P 10] 79K;

[354] fine-textured <sup>orangey</sup> buff fabric with paler surface + drab greyish-cream core. Deep buff slip. Quartz tempering. quartz + red-brown interstratification gut. Dr. c 32 A C

Carlisle, Blackfriars Street [CAR 78 BLA A (157) P 18] [350] 80K]

Hard, orange-brown fabric fairly fine-textured; quartz tempering; sandstone + quartz gut. Fabric seems definitely different from both the red + the fine buff. IR 3 but A 176 + 301 or 307 prob. same vessel.

AUSTINVS (S) J

Kinderton [Middlewich M. 2K] brick red fabric; small, medium & large, white,

red-brown grit, including sandstone; 1 stamp each side of spout.

J ~~Q~~  
J ~~Q~~



2K. Kinderton (Middlewich, M).

lenses 2, Carlisle

Body of samianlike <sup>fabricslip</sup> ~~metastasis~~ with <sup>inclusion:</sup> quartz and

galena. Presumed Carlisle

Is herd ? as Blackfars 242 Feb 611 + O P nos 540-41

sample of cream/white with chunks in it not apparently

Cranbeck (gut-worm away) CAR 79 KLAB (732) 

Birdsward [420/3901 5 59K] r. facing. Hard orange-brown  
 (2.5YR 6/6) with redder core (2.5YR 5/8): moderate, mostly  
 small quartz, + opaque black (less) + some much larger opaque  
 black (? iron slag), occasional pale ? ss. Very thin cream slip,  
 fabric shows through. Inclusion grit: qtz, clusters  
 of quartz grains; sandstone. Dv. 32cms wide ✓ B

Birdsward [420, 4222/6 60K] Different vessel. Fabric not as  
 hard as above. Orange-brown fabric, surface slightly paler  
 traces of thin cream slip. Some widely dispersed quartz  
 and fewer black (? iron slag) inclusions. No tubular surface  
 Dv. 35cms. B.

AUSTINUS

J Dieck

? may have been used?

SMOOTH flange

Walton-le-Dale [WD96 Drq. 448. 3110 9024 32K] facing

235g Dr. 33 15%. Thin cream slip! Fine-textured, reddish-brown [Munsell 2.5YR 5/6 'red']. Inclusions: few, random, <sup>(varnish)</sup> opaque cream, red-brown and quartz.

Interventions: mostly quartz, few red-brown ss, opaque black quartz sandstone, flecks of mica or feldspar.

Walton-le-Dale [WD96 Drq 468. 3109 / <sup>SEE 3H</sup> 9014 / 23 35K 33K]

195g Dr. 33 cms 10%. Tiny trace of cream slip. Reddish-brown fabric [Munsell 2.5YR 6/6 'light red'], with <sup>slts</sup> <sub>2-3</sub> brown surface skin.

Inclusions: Fine textured, few, <sup>10</sup> random inclusions, ill-sorted, opaque cream, quartz, flecks of

mica or feldspar; few black + red-brown, Titanation:  
quartz, red-brown, very few black. ~~X~~J

AVSTINUS

Stanwix [Vallum Filling 1933; c. M. 69.1934; Tullie Ho. 14K] flange fragment,

stamped twice; fine, softish cream fabric; looks like a midland fabric. D

how ~~Borrow~~ <sup>Arrow</sup> Bridge [1950 Exc 67]; Kendal Mus.] r. facing; stamped twice

close together; hard, pale buff fabric with a darker surface; ? slip;

much, v. unevenly dispersed, large to small grit right to b. b; stamps

in poor condition. D

Ambleside [Crw<sup>2</sup> XV p. 56 fig. 28 and p. 45, no. 26 where read as


FAUSTINI MANU. Armit hibrary 5K] "South gateway". r. facing. Red-

brown fabric with pale buff slip; largest medium red-brown, white

grit; (also p. 57, no. 2 for further reference). A


How Borrow Bridge  
EE Burley C+W NS XLVII 1948 (offprint in  
folder. Cumbria, (old Westmoreland))

Wallend [WSP 242 SF 1459 Context E14:28 loc 10 phase 2  
 WALE14 28/1459 on pot 20K] Dr. 28 cm. 14% 145g.  
 Softish, fine-textured tan coloured fabric (Munsell 5YR  
 6/6 "reddish-yellow") with few? slag (black), rare orange-b  
 brown mat'l and rare tiny quartz inclusions; ill-sorted small  
 and tiny, and random. Inclusions: plentiful, smallish to medium-sized  
 very mixed; mostly quartz (transparent & pinkish), black slag,  
 possibly also black material, quartz sandstone, red-brown sandstone  
 Traces of red-brown slip on top of flange & down to 4 mm below  
 top of bead, could have been in straight line. J ~~X~~  
 ? a lacquer slip



AUSTINVS

Stanwix, vicus [Ian Caruana 'Observations in the vicus of  
Stanwix Roman Fort on the site of the Miles MacLure  
Hall 1986 (NY 400569) in Trans. C+W Antiq &  
Arch. Soc. vol C (2000), 55-78. p 66, fig. 5



AUSTINUS p. 10 JOINS: 33K | 34K | 35K ~~35~~

Notes: 4ms etc as 32K in fac

Walton-le-Dale [WD 96 3104 | 8318? 34K JOINS


WD 96 Dg. 450 3109 | 9723 35K] L. facing. Diagonal  
slashing to key clay added for sport. Traces of cream  
slip. Technically a water-hole infabric, but may  
have been used - not certain. Stamped twice close  
together on right side and on left side 35K & 33K.  
Has curious appearance of having a layer added  
on inside. Intuition: quartz, red-brown ss.  
34K 443g. 15% | Some wear  
35K 665g Dr. 36 cms 24% | Stamped twice close  
33K 235g 9% | together on each side  
& sport.

33-35K Looks likely to have been used. Slip  
definitely gone - need base perhaps for certainty

Camden [3K 2002-042-17<sup>3</sup> (CE02-106a)] l. Facing.

55g 5% Rim-skerd in bright, orange-brown fabric with some dense black in the core which is exposed on the internal surface. There is a left facing stamp with clear traces of white slip on stamp. Different profile in body to 2K. Fabric fine-textured.

Inclusions: frequent, sand-sized w/ tiny/small quartz & black; a few larger black on this skerd.  
Interaction gnt: 3-4 survive, quartz & black.



AVSTINVS

Carviden [2K Falkirk Mus] r. facing.  $\Delta$  Die B (S) Diam 30 mm 24%

2002-042-037 (CE02-107) 3 joining sherds with r. facing stamp. All discoloured on inside to greyish-berige with one area to blackish (probably burning). JOINS

2002-042-~~112~~<sup>112</sup> (CE02-106a) <sup>large</sup> base sherd and  
2002-042-150 (CE02-106a) small base sherd.

NOT Joining:

2002-042-112 CE02-106a on bag (106a on sherd) 65% <sup>5%</sup>

2002-042-112 Flange fragment with diagonal slashes. This sherd joins flange fragment 2002-42-64. Weights of all sherds attributed 02K 560g. P<sub>170</sub>

Fine textured, orange-brown fabric. Inclusions: some  
random, minute to small, quartz & few black.  
Intertaxation: well mixed, vari-sized, quartzes,  
sandstones, quartz sand stone, black rock &  
others. Mainly in bottom of vessel but some stay  
up to head. Traces of cream slip underneath  
flange but the stamp is covered with matt,  
red-brown slip; there is another patch  
elsewhere on flange upper side. All  
sherds abraded through but the non joining  
number is not discoloured - ? discoloration after  
fracture.

Strageath [82 G I (1) 13K] large fragment. black with cream slip. Sketch. B

Camelon [23] no label, possibly Price (colln? 19k] r-facing die D S  
 Hard; orange to brown fabric (2.5YR 5/6), <sup>very well fired.</sup> ~~Heavily worn~~ inclusions ill-sorted quartz  
 and sparse blackish fragments. Trituration grit mostly pinky-red to pale orange sandstones with some quartz; thick cream slip. <sup>Dr. 32cm</sup> Hackly fracture  
 Dr. 32cm

Camelon [34] CAM 76 CS site A. 22k] fragmentary stamp. Brownish-orange fabric (5YR 6/8), <sup>fairly sparse</sup> moderate inclusions of ill-sorted, angular quartz and sparse brownish-black fragments. Trituration grit <sup>rather</sup> mainly reddish-brown sandstone with some quartz; Cream slip. B  
 Dr. 26cms. Gilt right up to top of bead

Cramond [Alan Rae, Dr. Eastnor, School Brae, Cramond, Edinburgh 4.]

CR 57; 26<sup>hard</sup> ②; buff-brown fabric; white + brown grit (fines; l. facing) DA

Cramond [CR 57 26<sup>fine, soft</sup> ②; do;] probably AVSTINVS; red-brown fabric;  
white + brown grit, large <sup>red-</sup> <sup>fines, sparse</sup> remains of cream slip. Die uncertain. AA

Newstead [NMA. (II 1965; packed in collar). XCIX museum numbering.]

hard, pink fabric with thick buff core but very near surface changing  
to cream. Grit in fabric. 1 grey grit. B

Tassie'sholm <sup>(Milton)</sup> [Hunterian M. F. 1962.40.] pale orange-brown fabric with dark  
grey core. Darker orange-brown slip. (Also in E.B.B.'s folder. A)

Now called MILTON

Dunrodeer [Dumfries & Galloway - N. H. & A. S. F. 1938.55; 93K]

Kurterian. M. [1938; N.E. Corner; friable orangy buff fabric with pink-brown grey grit; few survive; surface orange; scored slightly on flange by stamp. 1/11:] B

Abnethy [PSAS. XXV p. 393; NMA; FX 231; 50K] flange broken; soft, orange fabric, cream slip; very few, ? brown grits survive. B

Munich [PSAS. LXIII p. 528; NMA 91.12; 1930.227; 82K] v. facing; soft pink fabric, sketch. Macdonald p. 456. B

Newstead [unpublished. no. no. NMA. 138K] orange brown fabric with cream slip; medium & large, grey and brown grit; v. facing. A✓

Balmuirdy [pl. xl, B. 18 + p. 78; F. 1922.324; 21K] r-facing; orange-red

fabric with pale buff slip; white + grey gut to b. b, most gone. D

Balmuirdy [pl. xl. B. 17 + p. 78; F. 1922.325; 24K Hunterian M.] soft, orange fabric, slip almost gone; worn; like Balmuirdy type 17. A

Balmuirdy [<sup>Macdonald p. 456.</sup> pl. xl, B. 18 + p. 78; F. 1922.325; Hunterian M. 32K] l-facing soft orange fabric with traces of slip.; grey, white + 1 or 2 brown gut; probably type 17. A

Bar Hill [<sup>Macdonald p. 456.</sup> p. 70; F. 1936.482; Hunterian M. 58K] pale buff fabric, pinkish in parts; buff fabric with pink buff changing to pink ~~to~~ core. B mixed, medium + small, brown, white, black, grey gut; orangy buff slip. D = 12 in; 1 stamp each side spout; horizontal marks in stamp.

Birens [<sup>6th. series</sup> P.S. AS LXXII, p. 331, fig. 34, no. 1; FP. no. no.; NMA. 158.K] l. facing;

sandy, buff fabric with orange (? brown) ? B

Camelon [unregistered; NMA. 54.K] soft, pink fabric with <sup>concord</sup> cream slip; grey, brown grit to c. 1/2 b.b.b.; near 46K but bigger. B

Carzield [Dept. of Arch. Durham in 1959; 1955; 2141] red-brown fabric with cream slip. A.A. Now in Dumps M. 2/41 cz '55 B

Tassiesholm (Milton) 14 April 47 Information + rubbing from B<sub>2</sub>; Scotland folder; stamped twice (Info - 5 - from E. Bentley). A

Rough Castle red-brown fabric; no grit. NMA; AE [<sup>4.</sup>BRH rubbing]. B

Carzield [Dumps M.] <sup>Trans of Dumfriesshire & Galloway N. P. + Ant. S. XXIV</sup> pale buff fabric; made up into whole vessel; brown, black, grey, large to smallest grit to near head. D=11mm. ? a slip; stamped each side. D

Carzield XXIV - The Pottery from the Roman Fort at Carzield  
by E. Birley + J. P. Gittam p. 2-11 fig 2 no. 11-17 p. 7.  
~~J.P.G.~~ (Pottery from 1939 Exc<sup>n</sup>.) No find places.

AVITOR misreading - see AVTIOR See  
(AVTIOR):

DVTIO (cf. AVITOR)

VIA TOR

? Hadrianic? (PE)

(i) Chesters (no. 2488); red/buff fabric/cream wash.

Cardunach (1943, CW 2 xlvii p 118);

Slacks (p 70 no 1 'AVITOR'), no 1. Too doubtful.

'doubtful of AVITOR + ANTONIUS, read by E.B. as AVITOR or DVTIO



76.  
OVTIP

Caistor by Norwich [6K; 1431-33, 152-929. Pit under Hypocaust I; unpublished]

brownish orange fabric & surface; prolific white, red-brown, occasional, medium sized grit.

Caistor by Norwich [59K Norf. Arch xxv Pt II, p211 R.7] 4. (c)] pinky brownish buff core changing to buff surface; medium-sized, good amount black, white, red-brown grits to lead. r. facing, brownish cream with pink core; grey, black & red-brown grit.

AXI

Hardknor - ? MAXI CW <sup>2</sup> XXI p. 36 r no. 22 .

DL5 / LDB

Walton-le-Dale [Pickering AA 57.??] SST