

3

Colchester [Sheepen Kilns, C332WS (77); 207K] drab, hard, pale buff fabric; cracked all under rim; good amount white, black, drk brown, grey, medium to largish grit to c. 1/4" b.b. b. r. facing. D = 13 1/2 - 14 ins.

Colchester [kilns C33 CWS (95) 208K]; fairly certainly from same vessel; hard, (but with small fissures in fabric, drab buff; surface of both 207K & 208K cream I think, but with reddish staining all over; few white, grey grits to b.b. l. facing. D = 13 1/2 - 14 ins.

Colchester [Union 168.33; 353K] cream fabric flange and bead; little medium, white, brown grit upto bead; end of flange broken. A sketch in book.

Colchester Kilns 1959; [146.60; 473K] softish cream fabric with some grit in fabric; fabric a little croded. From Kilns (?)



20 YK Colchester.

BARO.

Blanches Kilus [1959; 147.60; 442K] n. facing; softish creamy buff

fabric with grit in it and a good deal on the flange; much, medium
and small grey, red-brown and white grit to bead. From Kilus (?)

BARO


York [SM19. 1974.5. 18.19 VII 1964] 105K] stamped along.

Dir. 25cms. 2 pieces joining. Form almost identical with Ilkley one. Slightly sandy cream fabric with pink core. Inclusions:

^{mostly transpl, some pinkish.}
ill-sorted quartz with few red-brown (opaque). Interstices:

ill-sorted quartz, some red-brown? sandstone; orange-brown sandstone. Buff-cream slip. Context Residual,

Bowes, Durham [S.21. 9^KAK] l. facing stamped along



BARO

Ribchester [77 EB 5 36K] (facing sp. surface. Soft creamy pink

fabric with salmon pink core & cream inner core; much qty tempering
qtz + red-brown ^(haematite) inclusions - some of it missing. Does not look
like a Colchester fabric; also a pale brown? diorite qtz. Same
fabric as the Ilkley mortarium. Dr. 29 cms.

Ilkley [1896 A 27.58/30~~F~~/32. 17K] 2 pieces carrying parts
of both stamps. Bright orange-brown fabric with quartz ^{tr. 6} tempering;
rather chewy fabric. Dr. 28 cms. Surface cream - probably fired to
cream ~~is not~~ too thick for a slip: haematite, ? diorite & quartz
qtz. ? ?

BARC

*

Yorkshire Museum [usk] pinkish ~~buff~~ fabric, hard^d sandy [like amphora]; large

& medium red-brown & white ^{& grey} gilt up to rim; but worn away over most

of surface. l. facing. ~~Letter~~ BARO with part of an other letter following

as possibly BARO. The fabric could just possibly be Colchester,

but the gilt is odd. well-worn. D.v. = 3 @ curis. Δ



18x. Yorkshire U.

BDT (John Dare says mortar is identical with Bellicus)

AA⁴ XXVIII, Destruct in deposit; fig. 10, no. 105.

Corbridge [AA⁴ XXVI, p. 176 no. 6; (106) XII A'47, 59; 6K] soft cream fabric with slight tinge of pink; surface burnt in part drab buff; large to small, r/b, grey, blackish grits to c. 1 in. b. b. b.

Corbridge [AA⁴ XXVI, p. 176 no. 6; (106) XII A'47, 60; 4K] cream fabric with pale cream buff surface; some, large to medium, r/b, grey grits.

Corbridge [AA⁴ XXVI p. 176 no. 6; XII A; 6/47 (106) Analysis (10); 8K] fine, cream fabric with grey, orange-brown grits in fabric; smallish, r/b, grey, black, grits to c. 1/2 in. b. b. b.

Corbridge [S 325 (6); AA⁴ XXVI p. 176, no. 6; 341K] sandy fawn fabric with red-brown core; with cream slip; brown and white, medium & large grits.

1963. Fabric re-examined.

As s.ATV + qnt also (but well mixed) - Pale buff slip.

All in same fabric.

BDT ? reader q.

Corbridge [AA⁴ xxvi p.176 no.6; S 337 (6); 342K no rubbing BD-] sandy, pinkish; grey core, but burnt or misfired.

Corbridge [AA⁴ xxvi p.176 no.6; 1 more than published; S113 (6) 340K] sandy, whitish fabric with yellowish tinge; smooth surface, patchy orange brown - purplish; large + medium, brown + white grit; quartz + sandstone like A.6.

Corbridge [AA⁴ xxvi p.176 no.6; S67 (6); 343K] sandy, buff-white fabric; quartz + brown (ss.) grit; medium to large. Piece from which A.6 made.

Corbridge [AA⁴ xxvi p.176 no.6; US45 (6) 344K] slightly sandy, pinkish white fabric; medium + large, brown, white grit; sandstone + quartz.

Rough Castle [Unregistered; NMA. 44K] v. fading; 2 large joining Δ

fragments; ^{Drawing} grey creamy core to buff fabric; medium brown + grey grit.

Munnills [PSAS 64.94.2; NMA 86K] 94.2; 1930; 2.55; soft; cream

fabric with light grey core; moderate, brown + grey grit to head.

Newstead [NMA. (VI 1945 in boxes in cellar)] Unstamped. i BE o: Fine,

cream fabric with salmon pink core. Sketch of section no. 7.

Croy Hill [③ LAK ④ 906] 1K] ^{CR 77} ^{Smooth} Soft, Fine, cream fabric, sparse (small to large)

inclusions of quartz and red-brown fragments. Titration grit
knobby quartz / sandstone and red-brown fragments. Dr. 25cms. Surface v. smooth PTO

(NB. Inveravan - 3 fragments, unstamped form in their Phase 2. Worn)

NBS Dimples in spout.

at Cambridge
Fabric Re-examine d 1963 ÷ Cream, finish fabric; traces of
tiny v/f. grit in fabric; slightly darker slip; red-brown,
+ translucent white, and grey grit, medium + small-
sized; sometimes grey core. $\frac{3}{4}$ in this fabric.

Other fabric - brownish pink with thick cream slip;
sometimes grey core. Some grit. S. 143; S 388;
S. 144; s. 138 (no slip); S. 146; U.S. 6 (no slip); S. 145.


Coay Hill Softish in nature of fabric. It is in good condition
silky, fine textured fabric

BELICVS

FK = Falkirk Museum.

Mum. vils (2003-047-197) joins 2003-047-037 (MM03-38); same
MM03-08 (195gms) on pot 120gms

pot as 2003-067-002 (60gms) MM03-38 [FK] L. facing Cream
fabric with grey core in flange, slightly rough to the touch; there was
probably a darker cream slip. Inclusions: moderate to fairly
frequent, mostly sub-rounded minute to tiny quartz and
opaque red-brown and black material combined with
some ill-sorted, larger red-brown and rare black material.
Interstratification: well-mixed and concentrated in the
lower half of the material, thinning out upwards from
the half-way point. Condition: well worn. Diam 280mm
13% (stp) + 6% Total weight 375gms.



BETHICUS

Corbridge [AA⁴xxvi p. 176, no. 5; S 376 [5]; ②, d/xi, 47; 234K] r. facing;
 very compact, fine grained, smooth, thick, grey core to pale buff
 fabric; prolific, r/b, grey, black; smallish, evenly dispersed, thinning
 to b.b; type as whole one drawn. △

Corbridge [AA⁴xxvi p. 176, no. 5; S 145, xxx, [5] ②, i/xii, 47; 235K] thick
 pink, salmon coloured, core changing to buff very close to surfaces; r/b,
 grey, gits to c. 1 in b. top of b. Type S iii fits exactly.

Corbridge [AA⁴xxvi p. 176, no. 5; S 349; [5]; ②, j/xii, 47; 236K] r. facing; dark
 grey core to pale buff fabric; medium, good amount, r/b, grey,
 black gits; orangy buff surface; Type 229K.

BEHLICVS

Corbridge [AA⁺ XXVIII p. 193, fig 10. no 94 + p. 197, 94.
AA⁺ XXVI p. 176, no. 5; 5/47 XIA 81 (94) 51; 2K] L. facing; smooth,

fine fabric, buff with pink core; some smallish, r/b, grey, grits to nr. b. b.
Type as whole drawing, but this piece fragmentary.

Corbridge [AA⁺ XXVI p. 176, no. 5; 248; no. 111K] L. facing; grey core changing
to buff with pinkish tinge; small + largish, grey grit; broken + badly
impressed.

Corbridge [AA⁺ XXVI p. 176, no. 5; 51 US. 33; 2 m/XII, 47; 218K] hard, compact;
dark grey core changing to greyish buff. Δ

Corbridge [AA⁺ XXVI p. 176 no. 5; 2 b/XI, 47; 5346 51; 229K] grey core to
buff fabric with orange surface; 1 stamp each side of spout; prolific, grey, r/b,
black grits to c. 1/2 b. b. b. D = 11 ins. A.

BEHNICVS

Colbridge [AA⁴ xxvi p. 176 no. 5; S. 148 xxx [5], (2) / xi, 47; in] ELL [0.; 230K] thick

cream core tending to pink near surface; few gints survive; l. facing.

Type 5iv; very rough and broken.

Colbridge [AA⁴ xxvi p. 176 no. 5; US 5; (2) x / xi, 47; 1908; [5]; 231K] grey core to buff fabric, with orangy surface; prolific, r/b, grey, black, gints to b. b. ^{sketch}

Colbridge [AA⁴ xxvi p. 176 no. 5; (2) K / xi, 47, [5], US. 6; 232K]; grey core changing to orangy buff fabric; hard; sparsish, grey & black, large to medium gints; very close to 5iv in Rept.

Colbridge [AA⁴ xxvi p. 176 no. 5; S. 147; xxx [5] (2) / xi, 47; 233K] lightish grey grey core to cream fabric; surface pink; some r/b & grey gints. Approx.

Type 5ii, broken.

BEHICVS

FIND OUT ALL numbers relevant to Dist^o,
dep.

Corbridge [S.143 xxx [5] ② h/xii, 47; 250K; AA⁴ xxvi;] l. facing; pinkish
orange fabric; with tiny buff core in flange; surface buff, could be slip;
prolific, smallish, grey, r/b, black grit; Type as 229K.

Corbridge [AA⁴ xxvi; S.141, xxx [5]; 129S; ② g/xii, 47; 251K] r. facing;
roughly scored internally; grey core to cream fabric; cream buff surface;
much r/b, black, grey to c. 3/4 to top b; D = 12 ins; Type as whole vessel
drawn.

Corbridge [AA⁴ xxvi; S.138 xxx [5]; ② f/xi, 47; 252K] r. facing; blackened
on flange; brick red surface; blackened on part of outside. Type 229K
prolific, black, grey, r/b, largish to smallish grit. ? whole.

BRUENS NB DORE Feb. 1992 says identical with BDT

Cambridge [CR 63. Seen at Durham 1963. 6K] i > [BE 0 no rubbing.

hard, creamy buff fabric with translucent, brown to grey grit. Side x1
North end. Disturbed layer containing rubble. Sketch.

Cambridge [CR 63. Seen at Durham 1963 7K] i > [BE 0. maybe
part of 6K.

Cambridge [AAS 7. At Durham 1963; 32K] flange fragment; hard cream
fabric.

Cambridge [YR - * 405K] BE [no 7.

Cambridge Information SPG Letter 19 August 1969 found that year NS

BRAR, V. 20

Ribchester [Museum. "Inclay of furnace"] flange fragment; pink-buff fabric
D = 2.9"

merging to greyish white at surfaces. Stamp may be whole.
^{with} Bannaventa [Whilton Lodge; Northampton Mus. D.3 1956/7; 10K] creamy buff, hard,
no. 240; Edwin D. Bailey; Fig. VII, no. 53. ^{Journal of the Northants Nat. H. Soc. + Field Club. xxxiii June 1957, no. 260}
Sandy ware, sparse, large and medium brown grit.

Voxeter [Site Mus. Unpublished. M145; 107K] hard whitish fabric; a little small
grey grit; below 1st floor B.2, S. wing.

High Cross [Chance find in roadworks. S. Pickering; information +
rubbing G.W.] brownish cream fabric; "no grit on fragment".

Rochester [Denstone College; B.69]; ³⁵³ ^{18K} "cream ware with large, red + white grits".

q.w L. facing Cream fabric with inky grey core. Rises in centre
bottom; tintation brown, black, white + greyish 1RS

out
RAP/6 in.

Ribchester

27

out
BAR

DB 1956/7 10K x 10K
Bannaventa (Northampton)


Corbridge [AA¹ XVI, nos; S. 156, [5] x IE; 1911; ② u. / xiv, 47; 244K] pink core but greyish cream to outside, cream to inside; flange buff fabric, pale purplish pink to brown in flange. Nr. Type 5v; no rubbing ^{on} [8] in.

Corbridge [do.; S. 380 [5] ① r. / xii, 47; 245K] pallid cream fabric with buff surface; prolific, r/b, grey, black, small, girt to c. $\frac{3}{4}$ in. b. b. b; D = 11 $\frac{1}{2}$ in. Type as whole vessel drawn; no rubbing ^{on} [8] i.

Corbridge [do.; E. area N.E. [5] S. 77; ② c. / xi, 47; 246K] r. facing; very slightly pinkish, cream fabric; much girt worn away; cream surface; faint, worn stamp; no rubbing ^{the} [8] i; grey, r/b, largish to small girt surviving to c. $\frac{1}{2}$ in. b. b. b. Type as 5w approx.

BENWELLS (corrected by a letter from J.S. 1967).
Great Chesters at Corbridge Site M.

~~Corbridge~~ ¹⁹⁵⁷ [G.C. 1951/5. AA^{xvii} p.176 no.5; 292K] L-facing; sootish,

grey core changing to pale buff fabric; r/b, grey, grits.  no. sketch

Corbridge [1958; BP 58; 405K 19th. Jan] N. <sup>and
flange</sup> range Room 1, W. side;

"central third, further cutting back, mainly in clay"; large piece of flange
with edge of very faint stamp.

Chesters [2431/3742 ; 24K] hard, buff-reddish fabric; medium + small,
brown + white grit. no rubbing.

Benwell ^{Newcastle} [P.G. 9K] ^{EA High tunnel} stamped each side; Brown, white + grey grit. — much [△]

Corbridge [Seen at Durham 1963; 0063; 1963 2K] l-facing  |

no. rubbing. buff fabric with grey core; much, brown, grey, white + red-brown
grit. [Site XLIV Trench II End end, outside circular feature, in dirty filling

+ debris near surface.

BERKLEYS 29 London exx. from Site XXX (B²)

London [A⁴xvi p. 176, no. 5; 15 v. 36] (2) w/xii, #7; 237K] r. facing

pinkish cream fabric with buff surface; profile, r/b, grey, good amount, medium to largeish; no rubbing @ EB in.

London [A⁴xvi p. 176 nos. 5, 388, 15]; XIw, N; 238K] v. facing; slightly

rough, orange fabric with little grits in it, cream near surface; profile, r/b, some black, whitish grey grits to c. 1 in. b. b. Type

as whole drawn one. of FC [in list]

London [A⁴xvi p. 176 nos. 5, 32, 157, xvi, 2 v/xii, #7; 239K] l. facing;

grey core changing to cream, medium, grey, r/b grits; ? mistered; appears Type 5iii; no rubbing. @ EB K: ^{only}

BELVICUS

Corbridge [do; S 140 xxx [5]; 247K] l. facing; grey core to cream fabric;

no grits visible; Type 5v.

Corbridge [do; S 334 [5] xxx S/M. 137; ② g/r, 47; 248K] l. facing; thick grey core to reddish orange fabric near surface; surface buff to orange; large to medium, grey, black grit to c. 1 1/2 in; surface discoloured purple inside to 1/3 way along flange + some on outside - ? due to stacking in kiln. D = 12 ins;

Corbridge [do; [5]; 1914 BS 34; ② v/xii, 47; 249K] r. facing; pale grey core to yellow ochre colour; surface brownish buff in parts; pale, dirty buff in others; 1 or 2 r/b. grits. D = 10 ins. Type approx. 5iii/ii.

Corbridge [AA⁹ xxvi nos; S 149 xxx, 15]; 240K] r-facing; drab greyish cream core changing to cream surface; surface brownish buff in parts; grit, grey & r/b; no rubbing. ^{end} 8K;

Corbridge [AA⁴ xxvi nos; S 398, 27; 1911; 5] ② n/xii, 47; 241K] L-facing; reddish pink core to cream buff near surface; surface brownish buff; some grey grit; broken flange; approx. type 5iv ^{made} 8K in no rubbing.

Corbridge [AA⁹ xxvi nos; 5]; ② n/xii, 47; 242K] fabric as above ^{241K} but orange surface; r/b, white, grey, medium grits; no rubbing; worn ^{at} 8K;

Corbridge [AA⁴ xxvi nos; S 146; xxx; ② q/xi, 47; 243K] L-facing; fabric as 241K but surface buff; prolific r/b, grey, blackish smoky to medium to c. 1/2 in. b.b.b. Type as 229K ^{back} 8K in. no rubbing.

NOTE dimples in ends of spout

Corbridge [A⁴xxxv; 5144 xxx; ② a/xi, 47, 5], 253K] L-facing; buff core to

light orange pink fabric, yellow buff surface; pritic grey, r/b,
black, medium, 5 c. 1/2 in. b. b. b. D = 11 ins. Type 5iii.

Corbridge [Do. 5381 5] xxx; ② c/xiii, 47, 254K] r-facing; brickish

orange core to pale buff fabric; pritic, black, r/b, grey, swallow to

medium, 5 c. 1/2 in. b. b. b. Type 5v.

Corbridge [19 NR IIIA 5/47; 110K] worn or badly impressed, black,

pink core to buff fabric; few grey r/b pits.

Corbridge [Ac 57; Durham. KD4 135L] no marking] red brown fabric with grey

core + red purple slip; medium white brown rounded pit. Buttons

rest ~ end.

B 1111

see BALUS

Waxeter [WB (44) 25. 48K Site 1966] r. facing. westwardland

fabri. Hard, cream fabric with very thick pink core + buff slip;
whitish brown spot. Some burning inside + on bead - D = A



W. J. P.

W. J. P.

W. J. P. (WB (44) 25)

BELLUS

Wroxeter [WB (44) 25 (52) J. Evans 148K] r. facing. Dr. 26cm.


Hard, cream fabric but pale brownish-orange except for skin.

cream to buff-cream slip - colour varies. Inclusions: fairly frequent,

ill-sorted, mostly quartz including slightly brownish, few opaque


red-brown. Interactions: quartz & opaque red-brown (? haematite

sl. burnt.



W. roxeter [Rowley Ho. F9. K16] dark, grey core changing to brick red fabric, some greyish ^{patches} staining on surface, perhaps a lighter slip but not obvious. Large and medium, white (? quartz) reddish brown grit.

[Seen 1963. Hard, red fabric with pale, thin grey core in flange and cream slip (though surface mostly pink). Pimply surface. Stamp had been surf-smoothed out and re-impressed which probably accounts for the additives in it. Cnt - brown (s.s.) and white, pebbly grit; NB. Note similarity to Rhaetan morhana.



B IIII-1

W. MIDLANDS. D

1912, F. 16 no. 21 + p. 68.

Wroxeter [87K Site Mus. M21] pink-orange core to buff orange; prolific

cream; hard + dark buff slip;

large & medium white + red-brown ^{black} glint, some missing & much sparser
near head; bright orange brown slip; white is crystalline, brown

maybe ss... D = 12 1/2"

□□□□□□□□

1. $\int \frac{1}{x^2} dx$

2. $\int \frac{1}{x^3} dx$

3. $\int \frac{1}{x^4} dx$

B11NY

BELLS

Watlington M. [probably wilderspool: 68'029; 6K] orange, soft fabric
changing to cream; r. facing; flange + head. needs drawing;
Wilderspool [85K Δ ①] r. facing. V. Hard, pale buff fabric with very large
amount of gritty material included; buff orange slip (translucent pinkish, red-
brown + grey grit); red-brown, grey + white grit medium to small to b.



© W. 68'029




RIL VS X net
C

Incomplete

Wroxeter [WB (47) 17 147 K. 1966. Site] r. facing. Hard, cream,

fabric, tempered with fine grit; orange buff chips; abundant,
small to large white, browns, transparent. D = Δ
West midland fabric.



ask
sp

Moxela WB. (47) 17

B11P)

3-7 King St.

Fabric of iron-slaggerit (impure)
from N. France
fine,

London [1931.244 Guildhall M. 235K] r. facing, smooth surface; hard,
pale brownish

cream ~~buff~~ fabric with pinkish tinge in core, changing to dark grey
very near surfaces, possibly due to firing conditions; internal
scoring; medium to tiny, black, white, grey grits to b. but only
stragglers above c. $\frac{1}{2}$ in. b. b. b. scoring inside only.

Colchester [NMA; Edinburgh FS10; 173K] r. facing; thick, yellow-cream fabric;
medium & small, grey & white grit inside & on rim. ^{Cut in a} out of
the flange and concentric scoring on flange & inside.

BILICEDO?

Gld Winterringham [8K. \triangle 61 ES/DY 96.] v. facing.

Neat little stamp, top of h. damaged. Very slightly sandy, off-white fabric with slightly orange slip; a little red-brown, grey, crystalline grit is preserved by accident in the flange. Fabric typical of Sault Carbon type.

BIRIA (N, VA etc) sometimes described as BIRN CATTERICK
Binchester [BIN/H Hoopell Collⁿ. (not published in Vinona. ^{BINCHETER})
K.A. Steer in The Archaeology of Roman Durham 1938
p 128 (unpublished) described there as 'sandy-brown
material, variant of Wrox 1912, fig 19, no 86. ~~see~~ Plate
XLIX, no. 2. Jerry Evans found pot ^{Southern Ravine, M} ^{Whitton Park} ? 36K
Facing stamp assumed because of position of stamp.
245g. Dr. 25cm 86% Heavily worn. Traces of cream
slip. V. very slight burning. Fairly fine-textured,
orange/brown fabric with thick dark grey core;
changes in colour well-defined; ^{mostly odd temp} few inclusions; quartz,
^{fewer larger} ^{fewer} ~~dark~~ red-brown and black opaque. ^{inclusions} ^{quartz} ^{quartz}
and red-brown sandstone, smallish. Slip thin where survives
on outside.

Softer than Anceus: inclusion also slightly different.

This fabric has been compared with Anceus (WallSEND/17K
WSP 549 WF 98 5688 and is definitely not the same fabric.

BISSO → see ABISSO F. under ABISSO

~~i) Jayton Thorpe (Norf. Arch. xxiii pt. ii, c 13)
Bisso F (nt.)~~



(1)

BOLLVS

See MOTTIVS BOLLVS

CANDIDUS

① CANDIDUS (net)

(Margidulum (Ant. 2 4/44; 11/41 38))

BOV.

BENWELL

CLAY DIE

Fragment of alleged die for mortarium [A A⁴ or Pl. XXXIII, 2
+ p. 169] Missing: ~~not~~ unlikely

= 1K?

HERRING BONE
COLCHESTER

2 stamps from Die M in Colchester Mus. 1 from Kiln site, one
from unknown local find spot. 143K (Kilns)
274K. (97.56)

^e
+ 19K; ~~169~~; 182? ; 264 (1026.57)

BONOVVS

Wroxeter [Rowley Ho. E. 10; p. 279 + p. 298 & 9, Fig 47 no. 14; 28K] hard, smooth,
creamy buff, buff slip; prolific, small & medium, hard black grit. See 9W's letter.
Yorkshire Mus. [20K] white pipeclay with cream slip; large black (flint?)

grit.
Mandeville [Burm. A.S. LIII, Pl xxvii + p 184] 5K. Firm. Mus. 205.56. Hard, buff-brown
fabric with greyish surface; very few large and medium ^{dark brown} black grits. D=c. 10 1/2 ms. ^{Involow a waste.}

Leicester [R.T. 9] sent by K.M. Kenyon to B²; not seen.

Hartshill [High School, Warwick, Walters] information from S. Webster.
cream fabric; rubbing and drawing.



BONOX

Wicket (Rowley Ho) 0. 29K 2

BONOX

20K Yorkshire Mas.

BONOX

Mancetter 3 (2)

NB. see NOX Bar Hill.: Assigned by B².

ALBINVS

Venulamium [57. z I. 26; 5K] r-facing; very dark grey core changing

to cream near surface; sandy; surface cream but top of flange buff; internal scoring; tiny to medium, black, r/b, grey gnts, muds, to b. b.

Ulk [see, Isca pl. 21, 5; + Pl. 23, 13; ^{? as ALBINVS "E. LVND} Isca. in PSA 2, 4, 10, p. 22. 1; CIL VII 1354 + 5 (b); 1862; 31-78/119; found while building a Jail; 110K NMW] whole except hole in base; pinkish sandy fabric, surface has creamy buff tinge; worn; internal scoring; largest small, mixed gnt; white, brown, red brown + black to head below c. 2 in s; gnt worn almost wholly away; outside of spout gone; some cracking under flange; D=13% ALBINVS (left) and ENAVIA (right).

BONOXVS


Leicester [A295.1973.1961.I (03) M012 242k] Flange fragment,

fragmentary stamp, joins another FF. Cream fabric, moderate inclusions of quartz, sparse red-brown fragments (upto 2mm).

No trituration grit survives.

Leicester, Causeway lane A1.1991 (522) 17704 M04?]

Flange fragment. Very fine textured white fabric, slightly micaceous; sparse, tiny? pale orange-brown + quartz with rare large sandstone or quartz. Stamp very badly impressed. Either a new die or misimpressed in some way so that the N has got suppressed ~~AE 1973~~ in some way. Dr. 30cr



BONOVUS

YOK [YORKM 2003.303 1038] M2 145K] (facing . Die^S

Quite hard fabric (red to cream at the surface, with rest of body slightly pinkish cream. Quite well-worn. Inclusions: moderate to fairly frequent, not well sorted, mostly sub-rounded, transparent & pinkish quartz with rare opaque orange-brown. Inclusion: few in upper half, only red-brown surviving.

Surface in upper half appears to have wear marks. 380 gms
Diam 310 mm. 24% Spent probably Type 3-photo

Cdeshill [6K slightly sandy cream fabric; red-brown grit. $\triangle 1102$]

GH-JM.

Roxeter [RO 87 III 1689 48K] IRS. Buff-brown, hard, fine-textured fabric fixed to cream at surface; a little quartz & occasional darker including red-brown tinteration grit. Has had an unusual orange-brown slip lateral diameter ≤ 26 cms.

York [SM26 1990.21 2175 Fab
M14 115K] Very fine-textured, cream fabric with very few, v. tiny inclusions: quartz, orange-brown, black. Dr. 29 cms. 2 sherds not joining. 3 cream slip die 1. Fabric v. smooth. Well worn: tinteration - little survivors - blackish. $\pm \leq 2$ red-brown. Context: ves ideal Monaghan 1997 fig 372,

BONOXVS

Chester [AG 75 VI (40) 71K] flange fragment. Very hard,
drab cream fabric with pink core. Inclusions: moderate, small to
tiny, transparent quartz + opaque black, perhaps burnt. Stamp
very faint + broken but looks similar to me. Not entirely certain

18K


Rocaster [G. Webster 1961; seen by B.R.H.] RC 931. Only fragment

of stamp; slightly sandy. Pale buff fabric with orange buff slip; dark brown gut w.b.b.; flange broken; gut largest to median.

Wall [w. 691. H. 17. 25K Greenfield 1964] flange fragment. Hard, cream fabric with pale buff slip; contains something gut in fabric.

Caves Inn, Tripontium [At Hinkley Grammar School] r. facing ^{25K} Hard brownish cream fabric + cream slip; cracked between head + flange; core brownish. Dr. = 13" 8.

Castleford [13K H. Bowes] r. facing; WMM 72. hard, fine cream fabric with pink core; fine dark gut in the fabric.



25K Fingerprint

Die B

BONOKUS

DIE 3

Groffe Quarry

Naneatai - near coin hoard by Arbouny t'lang SP 361 895 K. Scott

found by Nick

BONOX



SP361895

BONOVUS

Perin 1990, fig. 136, 15~~6~~3

York, Tanner Row [1981. ¹²R I 1386 266 .98k] probably k. fac.

Slightly micaceous, fairly fine-textured, cream fabric, ^{with pink} core, discoloured to 'dirty' cream at the surface (waterlogged deposit). Moderate inclusions of quartz, translucent and opaque, often iron stained, sparse orange-brown fragments. Trituration grit included red-brown fragments, some hard fragments and some iron compounds, possibly greyish and bluish flint fragments also. Worn. Dr. 3.2 cm. Buff-brown surface may be a slip but possibly discoloured firing effect. Dr. 3.2 cm.

Δ Stamp on this rim appears to be slightly larger than other stamps - could this be? rim shape. Has been treated as ^{recpt.}

BONOXUS

SCOTLAND

DRAW THIS

Newstead [NMA (iii) 1965 packed in cellophane]. l-facing; half of
p87; hard, cream fabric; red/brown gilt; buff slip. Close sketch. no?

BOVEDO

Worked at ECG IN HARSH (traced in N. France)

To ind EHC 1537 [AT] 11038 (84+85)

Eignhough [EH86 BC 1535] [A] 11038 Sample 401K [w. facing

diagonally impressed; ^{probably} The die has either slipped ^{is}

or been impressed twice. Slightly micaceous, softish

cream fabric, with dark grey, pale grey and deep pink

in the core; both the dark grey and the deep pink come

through the parts of the surface. The cream and pink are

surface skin only in parts (sometimes as little as 2 mm

thick), few, random inclusions consisting of quartz

opaque black, pale sandstone and average brown

in colour. Soft - coloured. Most of the interstratification is

p to

worn away but it was probably all tiny to small, mostly
quartz with some black and some red-brown and pale
brown ss. ^{definite} traces of concentric scoring surfaces on the
inside. Worn? Diam. 340 mm. Δ

Hanson 2007

BORIEDO (misread by Walters) See Evreux envelope.

Histor. Soc. L.C. N^o. xvii

NO See other card Thompson and

Ribchester [M2774; Clk VII, B34, no. 15, ~~found on Ribchester~~ in 1796; Watkins

R. hands, p. 161; Whitaker, Whalley ed. II, 1818, p. 28, tab. 2; British M. 4K

see Walters for other References. Townley Coll; stamped diagonally; v. facing;

vessel ^{cream} white, 1 stamp only; ~~seems to be buff~~ but surface discoloured grey; ^{+ grit} ^{except just below head}

grit worn away in most of it; rilling ⁵⁰ on rim faint, worn away inside; ^{Drawn 1993.}

brown, grey, black grit seen; B.F. 14 | 18; $D = 12\frac{3}{4}$ in. ^{no. 143}

Castleford [29K 2 pieces from S2 L7 in Phase I + 1 piece from ^{stamped along.}

S2 L5 F 236 (Phase III). (4)] Well-worn mortarium in fine,

wear fabric; Intustion grit is worn away ^{quartz, chiefly packed} over most of

interior but tiny translucent white & pink together with a few red-b & grey survive in common with regular concentric scoring just below bead.

Castleton continued
Fabric micaceous: random, v. ill-sorted opaque red-brown material including
slivers of red-brown material. Smooth surface. 3 pieces not joining from a
deep notanum with deeply curved rim. The concentric scoring is deep
even & parallel in the 3 sunning grooves. The translucent pink tintation
? unusual. R. side of spout Dr. 29cm ~~Dr. 29cm~~

Rich et al.

(Ribchester eq. part of a hoard.

Write to Ben Edwards.

BORSEDO

Ribchester continued;

Boriedo from Ribchester hoard continued: micaceous.

grit on top of flange includes pinkish grit and transparent ^{quartz} and opaque red-brown, ~~flat~~ gold mica.

Inclusions: moderate: red-brown fawny prominent; galena;

These are embedded in the base and not necessarily in

fabric. May have iron slag. No sign of quartz inclusions;

probably a self-slowed slip. some grooving on the body

near where body joins flange. Note certain but I think C. may be

different. Information R. Jackson 25.1.95; "CIL has it

wrong. It was found with the hoard in ^{'a cube of} red sand' in the

gravel near the river but not in it or on shore


Red sand (Tanneley) probably means a box.

The hoard is mid/late C to early second d.

Do not know why calcium is low.

BORINIANVS? (382)

Elginhaugh [EH87 2BC 406] [BE] [16K] L + r fac. 2 joining
sherds. Dr. 345. Cream fabric, slightly yellowish. fairly
fine-textured: inclusions: frequent inclusion, v. tiny
mostly quartz, some orange-brown, few black, mica.
Darker cream slip. int gnt: very little of inside some
red brown surfaces. (Some large inclusions)



Archival no 1519

86±


Porite, Annetwell St. [SF71 C78 / 77 1100 132K] r. facing.

after fracture:

Burnt / Fine-textured, micaceous cream (almost brownish-cream) with tiny red-brown inclusions ^{Iron compounds (ferrous compounds)} & some thin, longitudinal cavities. buff-brown slip. Worn. Inclusion included quartz ^{iron} & sandstone, ^{occasional magnesian} L. Only back of spout survives but it is narrow & reminiscent of Arbinotypes. Flange form looks Flavian. (Fabric looks like ~~limestone~~ ^{interesting}). Dr. ~~32~~ 32. A. With 1519 makes all of vessel except for end of spout & flange by stamp. NB. This mortar was stamped only once. It was burnt after fracture. Stamped across rim. 7 joining pieces - complete except for end of spout & some flange. ^{some} Black v. hard girth? basalt, likely to be volcanic.

CAR 83 ANN A (1759) 1519
C 76/77 SF 71 1100

1519 = pot number
(care is lot.)



Carbite [Millennium site TRENCH 3 CAR 99 MIL (999) \triangle 819 255K]

r. facing. large portion of matarium barely used ^{inside} bottom
 only scuffed. In deposit dated ^{pd 3B} ~~AB87~~ ^{83-93/94} - pre 103/5.
 1720gms. Diam 35.5m 22+22% Smooth, fine-textured
 and micaceous, hard cream fabric with thick, well-
 defined pink core. Inclusions: moderate, ill-sorted but
 not jagged, opaque red-brown sandstone, gold mica,
 rare opaque black rock, very few quartz visible
 at x20. Inclusion grit: mixed, var-sized, red-
 brown (possibly igneous), quartz and limestone. There
^{is} ~~may~~ be a marginally darker ^{cream} slip. Never had many
 but only ppo

There are close wiping // marks an inside showing as
new. Occasionally deeper. Very little grit ever,
mostly in bottom


Only 1 stp survives ; complementary part missing
& sherds

Dear Ponce,

AN

You can read it BORINIA~~TE~~EC or BOR#NIM^UVEC
- retrograde of course.

Kay



B. RAE^{(ESTICVS} ~~LIBRARY~~ ^{see} TAESTIC-FI ~~LIBRARY~~

Wall [WL ⊕ J. Gould 1962] l. fading, slashing from
inside & outside for spout. ~~has~~ a few ~~red~~ brown & white
gits; hard, cream fabric with buff slip. D = 12".

Paternoster Sites, London 590K

FULL NAME OF POTTER IS BRAESTICVS but
the first part very rarely impressed.

— Long ~~the~~ ~~is~~ ~~re~~ ~~(~~ ~~0~~ ~~1~~ ~~0~~ ~~5~~ ~~)~~



Wall (+) J. Gould.

BRARVCO

check BRAPVCO as a possibility

Northwich [3K CN: RUNS] l. facing slight burning. Fine cream

fabric with some fine sandy particles.

A

Hereford [A. 302. 1971; I, II, IV. v/s 200K] Small incomplete
rim fragment.

Wall [WT|1|+ 49K] IR.S in fine-textured cream fabric
with red-brown and quartz inclusions.

Middle Littleton, S. Worcestershire [Found in field-walking & sent by
Ponce Watson, Vale Farm, Offenham, Evesham, Wores.

WR11 5 LW. 1K] ^{Stripped and close together} Marked 1A. Incomplete rim-section.

Hard 'creamy white' fabric with a fair amount of fine translucent
quartz & occasional black & rare r/b inclusions; ^{quartz, black &} r/b inclusions

BRARVCO

Alcester, Warwick [1976-7 I $\triangle 489$ $\circ 216$.45k] Hard, cream fabric
rather ill-sorted

with thin, pale grey core / inclusions of quartz and
occasional black (? slag) brownish-
rim red-brown fragments. No trituration. grit survives; cream

slip. R. facing, stamped twice close together. Dr. 31 cms.
traces of an ochre-coloured slip. worn. Slightly bent. slip

quite like Lincoln. Form = ? before AD 140. Midland.
AD 110 - 150 on Ruins

BRIC (os)

Mowsl

Wilderspool

Middlewich (Jersey Way, Middlewich; Project Code 10514,

JWN.12 21K] r-facing (spt does not survive). 3312/8659

- 1 piece originally and 3090/8392 not joining BS with
1 modern break. 306.3 + 14 1/4 g; Diam 340 15%

Orange-brown fabric with traces of ^{cream} can slip; thick
black core with fairly well-defined edges. Inclusions:
moderate to ^(traces of some white) heavy frequent, random, tiny to medium sized,
sub-^(traces of some white) rounded quartz & sparse, medium rounded black.

Inclusion gnt: medium sized, 1.55 mm quartz (some
poly crystalline), quartz sandstone, red-brown & other brown

Fabric hand with irregular fracture.

sandstone, black ? igneous.

Coarse concentric scoring - can't tell if originally continuous because pot well worn in use.

Outside ^{and base} greatly trimmed & smoothed. Base looks as though it was trimmed to be absolutely flat which is quite unusual.

BRICO(S)

P 10

Wilderspool [1898⁹ July (99) 45K; L. facing] ^{Hard} soft, fine textured, smooth fabric; dk grey core changing to orange¹; cream slips; low 2 greyish gnts; D=12-13 ins. horizontal marks in die, ^{very faint} slight tendency to "whitened" letters. 135'01

D=32 cms. Fabric tempered with sandy particles

Warrington R. R., T. May p. 64 two stamps recorded but one of these ~~cannot~~ now be found - ~~from waste~~ ^{possibly} at Stockton Heath.

Wilderspool [^{recently discovered} 'The Roman Fortification at Wilderspool'
Trans. of the Historic Soc. of Lancs & Ches for Year 1898
(publ.) Vol L; new series XIV p. 30 ~~appears~~
¹⁹⁰⁰
1899] ~~to record a third one.~~ is one of these.

OC 198

457x wilderspool C. facing.

7 1/2

May assume that he worked at S. Heath but
does not actually say his stamps were found
there.

BRCO

Sagontium [23.292 Blq. II, 5a; Floor 3; p. 150 no 2 and fig. 76,
no. 23; 61K] orange-brown fabric with grey core and cream
slip; largeish + medium; brown, white and grey
spots, quite a lot but unevenly spaced; D = c. 12 ins.
In the first firm flooring sealing post-holes of timber building st. ;
dated to just stone. . . . likely to belong to first half of
second century.

BRCO

Warrington M ^{P.T.O} [23K; 340.13.1] soft ^{ish} orange-pink fabric with cream slip; sparse ^{brush orange} ^{with gap} ^{27cms.}

white ^{few} & grey ^{leaves} girts to near b.b.; 1 stamp each side spout; D=c. 10cms.

Wildespool [24K; 1165; Keindicks] 1 stamp each side of spout; 1 facing rubbed; soft ^{ish, brown} orange fabric with cream slip; moderate, large & medium ^{red-}

brown, grey girts, stragglers to b.b.; ^{Some of the tempering in fabric.} well worn; D=10¹/₅. 25.6cms.

Warrington M. [no prov; probably Wildespool; 302'98.7; 64K r. facing] not the same vessel as 65K; soft orange fabric with grey core; cream slip. Flange only shape very like 24K, ^{Some tempering in fabric} but a different vessel. Close to 24K

Warrington M. [no prov; probably Wildespool; 302'98.6; 65K. r facing] R seems to be missing, or part of it; ^{a small} die damaged; soft orange fabric cream slip; few black girts. Similar to 24K but not identical. ^{tempering with brush-like girt.}

23K Warm, non-sandy particles in fabric for temperature.

BRIGIA Distribution suggests Newstead as most likely source.
more

Canelon [Falkirk Mus.] stamped each side spout; ^{v hard} orange-brown fabric with
cream slip; medium + large; white + brown grit. A

Newstead [FRA 1485; vii 5.77; NMA. 119K] soft, red-brown fabric with
cream slip; small + medium, white + brown grit. A

Newstead [FR ~~X~~; NMA. 133K] slightly sandy, red fabric with cream slip; ^{seen FR4}
medium-large, white + brown grit; about $\frac{1}{2}$ mortar survives. ^{the mortar is old} find

Canelon [NMA; 72K] r-facing; orange fabric; soft; with cream slip; worn;
few, black grits survive.

Hyne [PSAS ³⁵ ~~45~~ p. 184 NMA] 'SR' ref. = RR1 red-brown fabric
with smooth brown surface. A

See Canelon 72K; ?

Exc. ⁿ of the R. Camp at Lyne, Peebles^shire, D.

Christison (J. Anderson. 154-186
on rocks.

p. 184 S R retro. on mortar in hand red ware.

BRIGIA

Inveresk [M12 3/10-11 PPCM 51K] r. facing. Dia in 290m 27%

460gms. Well-worn. Very hard, orange-brown fabric with cream slip. Inclusions: moderate to fairly frequent, tiny to small, mostly rounded quartz with some black material.

Inturation: mixed, quartz, r/b sandstone, black material rock.

Well-worn

(5) Δ

Inveresk [M9 3 - Zone ^{PPCM} 6A 50NK] Different vessel. IRS 60g not as hard fired as above. Orange-brown fabric with cream slip. Inclusions: as above, size slightly more varied.


Inturation: 2-3, 2 quartz, 1 brownish-black pebbly rock.

Δ

BRIGIA Attributed

Camelon [40 CAM 77 AZ Site D, 24K] IRS. stamp very worn +
battered

feint. Brownish-orange fabric fired to paler orange-brown at
surface (7.5YR 6/6), moderate ^{to fairly frequent,} inclusions, ^{mostly} ^{moderately} fairly (well-sorted tiny
quartz. No vitrification grit survives; cream slip traces). Attributed
on strength of border and ^(see 133K New Zealand) ~~general similarity~~ fabric etc to 24K.
moderately hard.



24k Camelon (40) CAM 77AZ

BRIGIA

Camelon [⑦] 1976 Site A  21k] ^{And,} Pinkish-brown fabric (2.5YR 6/6)

^{thick} with drab grey core, moderate inclusions ^{white;} tiny quartz
and very sparse red-brown fragments. No tribulation grit
survives, traces of cream slip. Different vessel for 24k.
Core merges into pink-brown rather than sharp line. The border of
a second stamp survives \approx 1 cm away from the other.

BRUXSA

London [CRS. Ill. R. London p. 89; M 2775; Clk. vii, 1334, 16; Coll. Ant. i, p. 149; British Mus. IIIK] l. facing stamped along; compact, v. fine, ^{v. slightly} pinky cream fabric; surface probably drabbi^{sh} cream; v. dirty; medium + smallish, grey, white, black grit to b. b; grit on flange. One stamp only. Type as Q.VA S. (not SD)

BRVCCIVS

Silchester [May pl. ~~no. 15~~ A, no. 15 + p. 275; 20K] L-facing, slightly sandy, buff-cream fabric and surface, latter blackened in parts; grit worn away; probably not much on fragment.

Kinderton, Middlewich [IK Middlewich M.] sandy, buff fabric; red-brown grit, including tile.

Holditch, Staffs [H D 28 (3) Prof. Charlton] sandy, drab cream-buff fabric; blackened by bead; stamp broken and very worn.

Godmanchester [St. Ives Mus. 1903; 17.28] sandy, pinkish buff fabric; a little purplish to top of flange; fragment of flange only.

Wroxeter [iii. fig 3, no 57; M 135; 58K] sandy, buff fabric, orangish on parts of surface (? a slip) flange fragment.

BRUCCIOS

1989.33

- AG = 23-27 Moulsham St. 1975 33K

Chelmsford. [CHA 9 436 + A 9 323 (3) + A 9 3630 All join]

heavily worn; slightly burnt. Hard, v. drab cream fabric with pink
core; inclusions: frequent, tiny well-sorted, ^{or x20} smaller than usual, mostly quartz.


This is the finer fabric. Surface fairly smooth. Inclusions grit: flint,
rare opaque red-brown. D. 29cm Finer version.

Skaford Hoplands [Network Archaeology HOPS09 (129) 1K] n. fac.

Two joining flange fragments in VRW fabric varying in
in having 2 large long grits (1 in stamp + 1 in fabric)
could have had cream slip. The spout has fallen off and first
finger mark for spout section survives, 115gms D. 260m.

17% Ian Rowlandson 9/06/10

Dié 1



BRUCCIUS

Ribchester [R889 05 (Context) 5690^{SP} 66K] L-facing. burnt.

Dr. 32. Drab greyish cream packed with quartz inclusions, v. rare black + red-brown. Self-coloured slip.

Heavily worn + fracture high - little if any tubulation grit survives. Spout cut back + shallow + drooping + under than Albinus.

Caesar's Camp, Matthew Arnold School, Laleham, Surrey,
(old Mddx.) It formed part of a small collection of residual
^{Roman} pottery on what turned out to be a medieval earthwork
Cream at surface (not a slip) but fabric within
is more brownish in colour. Packed with moderately plto

well-sorted, quartz together with a considerable amount of opaque, reddish-brown material and rare large red-brown fragments. Fabric clearly attributable to VRW Itanqa ranan

^{code}
MAS 89 109A 60 grms Diam. c 330 mms
50% NGR: TQ 0529 7063.

S. Pelthorne Museum, 1 Elmleigh Rd, Staines
Middx TW18 4PM

BRVCCVS \subseteq AD 70-110 ~ 80-110

Highway type with

Corbridge [xxvi, p. 189 no. 46] RVCCVS [46]; 144K;] sandy, buff fabric with

pinkish tinge; misread as RVCCVS. Δ

Chesterholm [V 35 N*; Dept. of Arch. D.C. 16] coarse, buff fabric with red-brown core and surface. Δ

Northwich [B.D.G. Jones. 1K
BRVCCVS

Boxed Low Roast, North Church Herts [12K 592] (65) 22 M

Layer 149. Stamp diagonal. Granular cream fabric with pink core; possibly a slightly darker slip. Well-worn, few flint grits

border. [CIL VII 1334, 4, CRS, p. 15] W. R. London p. 89 —

"RVCCVS" - Not seen.

BRUCEUS

Rochester [74] OC R(3) burnt. Flange incomplete. Very sandy cream fabric with red-brown inclusions (few) & cream slip; very few small pits on piece; dark.

Rochester (1964 F. Sturdy RC V (1))^{11K} Coarse grained greyish cream with thin pink core. both stamps ^{for facing} D.v.c 32 d. A Δ

Wroster [S. Houghton R₃ W.W. 166K] flange only - could well be flange. greyish cream fabric. BRUCEUS; deep flange

Cirencester [S II 3 47K] flange fragment in granular greyish cream fabric.


Enfield, Lincoln Rd [Area 3 F 30 6K] Coarse, sandy, buff-pink fabric; burnt heavily; frag.

BRVCCIUS

214^D

Binchester [VIN 71 LX 214^D 27K] Joins VIN 71 JCB 693^D.

r. facing. Dr. 34. Granular cream fabric packed with abundant quartz. Fired is orange-brown on part of flange but not on outside. Intonation: most worn away but accretion on inside in patches. Certainly had no conc. scoring on top of flange or on inside.



Magiorinum [D. Neal 1221 18-2.35 1K] Upper half in one piece;
 grit worn away in lower half. Both stamps survive. Spout shallow
 - not called from Flu/Traj. + ? ② Granular greyish cream fabric
 but inner half of fabric fired pink + showing through surface
 cream skin in lower half; well packed with fairly regular sized
 transp. a whitish quartz and temper - v. rarely a blk w v/b grit;
 natural grit - ^{mainly} flint, v/b, quartz, black. Dr. ~~15~~ 30.5 Δ
Cirencester [SII 3. M174. 47K] FF. ^{Dr. 29cms.} Cream fabric (no Munsell equivalent)
 inclusions quartz and reddish-brown fragments upto 3mm.
 No trituration grit survives; possible traces of orange-brown slip.

Chesterholm [AA⁺ XV p.236 fig.5, no.56; V34 N.Low; Durham DC 13]

r-facing; coarse buff fabric with orange-cream surface. 4 in R pt.

Chesterholm [unpublished, may have been part of same vessel; Durham DC 14]
cream fabric with red-brown (?tile) inclusion; (B.R.M. - almost certainly not the same vessel)

Malton [LSM 69 (182) L.P. Wenham 13K] L-facing & whole of spout - broad
trough shallow. Hard, coarse & firm cream fabric tempered with fine gritty
particles; ^{cream} buff slip; white & grey flint, and red-brown trituration grits.
flange bent almost black throughout except for underside

D = c. 10" but difficult. Two attempts made at stamping - stamped Δ
over an initial attempt at stamping. Heavily worn. This

is definitely the finer version of Ver fabric. Dv. $\frac{c}{\text{cm}}$ 30

BRUCCIUS ~~Park St. Site~~

Towcester [TCW 76128 5K] flange fragment. Greyish cream fabric packed with quartz + v/b slip.

~~Ribchester~~

Ribchester [Ribchester quarry: RRG 80 061 50K] L-facing; granular greyish cream fabric, full of well-sorted quartz with few v/b inclusions; worn; not certain lamination? quartz; blackish. no gut on flange; shallow spout. Dv. ≤ 35 cms. First example of this die. Δ

Castleford [no 524 CAS 80 S10 L078 63K] Stamp-eroded. Δ

Join no 574 80 S10 L129 Flange fragment. Dv. 46 cms. Poorly impressed stamp.

Drab brownish cream fabric, not as granular as B4. 1-surface smoother. Inclusions: mainly qtz, rare o-b + blackish (? flint). No lamination visible on piece.



Riviera grandifolia

BRVNS

~~Chesteron, no. Pet. 1000, [Oct VII, 1334, 17; This is BRVNS]]~~

V98

Wilderspool [415'13; 53K.] could possibly be same pot as 9K but probably not.
B. F34; sandy gray fabric; fragment of flange.

BRUCCUS

Rochester [RO 86 I 1415 38K] r. facing; 3 joining fragments. well-worn. Dr. 30cms. Greyish-cream, granular fabric with apparently, a similar slip, fired to orange in region of spout. Packed with fairly well-sorted quartz with very occasional orange-brown & probably flint inclusions; inclusion gut consists of flint, quartz, ^{occasional} orange-brown and possibly occasional non slag. Die 3. Probable traces of vestigial internal scoring only. Δ
gut does not go with scoring.

BRVCIVS see DVRB.

Colbridge [^{S.111}xxvi p.177 no.7; ⑥ a/π, 47; 220K] T. facing; sandy, grey fabric;

B.F. 38

Colbridge [^{S.111}xxvi p.177 no.7; 345K; S.114 [21]]; coarse, sandy, orange fabric with brown surface; approx. 38 B.F. no grit.

Rocester [Rocester School; found ¹⁹¹³1915] ^{10K} sandy, cream ware?; fragmentary; information from G.W. See 'DVRB' ? part of same vessel. different vessel from 38K

Casham [not published; 27/vi/3] border only; flange fragment in cream fabric typical of BH/R.

Rocester [N. Staffs. F.C. xlix 1914-18 p.104 read as see 10K may be extra one DVRB

BRUCVS

Corbridge (2)

Wilderspool [M 136'01 May p 64]^{9K} heavy, sandy, pinkish buff fabric tending to red-
buff pink core. No grit discernible. ^{orange-}

Chesterholm [AA⁹ xv p 286 R 5, 56]; "hard, whitish buff; grit all worn away."

Wroreter [912 p 66, f 16 no 2]

Type 38; Pitt X with late S G ware 80-110.

Templeborough [xxviii no 2 misread upside down]

B.I.C.I. Fuel?

BRAND
(1/2) 7 W 136'01 [B]

BRAND
(1/2) Carbide

BRVC IVS — name cert. train

London

London [Guildhall M. 198K] 1 stamp each side of spout; "BOLSA V" on pot;

sandy, greyish cream fabric with surface varying from drab cream to buff and reddish brown; much medium, white, black, grey grit to c. 2 ins. b.b.b.; whole, save hole in bottom through wear; D = 11³/₁₆ ins; deep hook MELVS-like of 8K.

Venlanium [58 A IV (2) + A IV Rm. 7 (12); 149K] 1 stamp each side of spout. sandy, grey fabric ranging from almost cream to in flange to almost black in body; surface v. grey to cream, orange-buff in patches blackened towards head. ? by stacking. only 3 grey & v/b. grits survive. D = 12 ins. Δ.

BRUCCIVS

Alchester, Oxon [Not published; 4F1892 Ashmolean M. 75K] sandy,
slightly pinkish cream fabric + slip; no grit survives. B.F. 38; very sketchy

Corbridge [See Durham 5K. FW.63] sandy, orangy buff fabric;
very worn inside; no grit left; P-facing; Bache-Fox 38. D = 13"

Site x LIV Trench I West end. In clay immediately below
paving?

Caerleon [7. Access Baths 1964] Rubbing sent.

Brockley Hill [S. A. Castle] East Kiln Ditch. 93K

Brockley Hill [S. A. Castle. BH'7.0.T.1(4) 100K] very sandy orange - almost brown,
with thick grey core + slip discoloured to bluish grey; one or 2 flint grits.

BRUCIUS

London [12847 M. Merseyside County M. 15K.] Flange only.
greyish cream fabric.

BRUCCIVS

London (BBells House BB05. Context 7302 Acc <1337>

82.7K OA2 Pd 3) 145gms. Diam 32mm. 12%. Few joining
shards. Burnt, inside almost throughout. Stamp eroded.
Rockley Hill. VRW Surface worn heavily.

BRVECVS

London [SHW 54 303K GH] St Swithin's House, Wafbrook,
flange; Late Flange.


BRUCI

Brockley Hill House [Brockley Hill House BHNOO Oxon Unit.]

Alex Smith. Context 67 pm 755 374K } Hange fragment

4.5 gms. 5%. Orange-^{to brown} + greyish surface. Fracture
weathered. Packed with quartz, some red-brown &
blackish (? slag both).

Dieß



BRUCCIVS

13 published before Brockley Hill Home ~~is~~

Brockley Hill [BH 74 T.C. M.S 35 297K LM] granular

greyish cream fabric tempered with fine grit; white, grey, black
red-brown tiny & small tituration grit. Die 1

Brockley Hill House [Alex Smith Oxon Unit ^{BTH 100} Context 72 pmi. 832.360K] has to
be r. fac but spat does not survive. 635g. D. 320mm. 37%.

Thin skin (1-2mm thick) cream, rest brownish orange. Inclusions:
fine end of range VRW Very frequent almost entirely transparent
quartz, with rare opaque o/b, black and grey (? flint). But grit
not frequent in upper part but some ^{to small} tiny not well-sorted
flint, quartz, opaque blk (? flint), rare red-brown, not well
distributed. Slight burning on flange Die A 5

Brockley Hill [LMAS. xi ~~p. 181~~ p. 181 fig. 4, M1 + p. 183; U/S; 5K]

sandy, pinkish cream fabric; slightly diagonally; BF 34 ^{1/2} flange
only. Die 1

Brockley Hill [LMAS 19 pt. i, p. 71, M11; Harrow 3K] r. facing; sandy,
cream buff fabric; some cracking? water; moderate, unevenly
distributed, large to tiny, grey, black, white grits; D = 13 ins. ^{Die 1}

Brockley Hill [LMAS 19 pt. i p. 71, M11; Harrow 8K] r. facing; different vessel
from 3K; 2 joining pieces; hard, creamy buff fabric; nearest BF 38;
D = 13 1/2; Die 1

Brockley Hill [LMAS 19 pt. i p. 71; M11; Harrow 16K] very similar to 8K but
probably not part of it; flange fragment; creamy buff fabric burnt black on surface.

BRUCEIUS

Brockley Hill [ILMAS 19, pt. i; p. 71, 11; Harrow 17K] slightly sandy, cream

buff fabric; few, medium, black, white gnts; different vessel;
end of flange broken. Die 1

Brockley Hill [ILMAS 19, pt. i; p. 71, 11; Harrow 21K] flange fragment; slightly
sandy, cream fabric; orange on under-surface. Die 1

Brockley Hill [ILMAS 19, pt. i; p. 71, 11; Harrow 22K] assigned only; very slightly
sandy, cream fabric; few, small, black gnts. ~~not included~~

Brockley Hill [ILMAS Xns. pt. iii no. 10; p. 218] ~~not found~~ Appel bar

Brockley Hill [ILMAS (1951) Xns. pt. iii no. 9 on fig. 6, p. 211 + p. 218] ~~not found~~

Brockley Hill [ILMAS (1951) Xns. pt. iii no. 2 + p. 218] ~~not included~~
this one not certain

franklin-9

BRUCEUS 1973

Brockley Hill

Brockley Hill [B# 73 TC MS 46 251K] Page fragment; granula

cream fabric

Die 1

BRUCCINI'S

Accession

London, Cheapside [CDP04 <827> Context 728 856K]

Basal diameter 125-130mm.

4.25gms Diameter 270-300mm^c (15% of 300) + 6% Flange fragment. Burnt before fracture. One large rimsherd which joins a body sherd and base sherd (all breaks modern). The fragmentary stamp is on a flange fragment which does not join the other pieces, but it has a modern break on one side. It is likely to be from the same vessel. There is enough of this vessel to show that all the decoration had been worn away and that the heavy wear had resulted in a hole in the centre of the base. Fabric: pink to orange-brown but ^{dark} cream at parts of the surface & intended to be that colour.

Inclusions: packed with quartz and few red-brown and black
inclusions: none sawies except perc. 1 white quartz, 1 red-brown
and 1 grey? flint

BRVCCIVS

TPO

London, Chappside [CDP4 Accessⁿ 849.7 Context 15-33

861K] Flange fragment. 70g Diameter 29mm. 10%

Cr facing Fabric: v pale, brownish-tuff fabric with ? buff slip.

Inclusions: packed with quartz + rare red-brown and black material.

P10

Cheapside CDP04

Not sent to be checked said to be BRUCCIVS

Context 430 Acc <1831> <849> 862K

Context 728 Acc <628> <882> 863K

on excel.

Duntocher [Gough's handen IV, 103+pt. VI, 4; CIL. VII, 1334, 18; Macdonald p. 456;

note missing] See Over BRUSC. F ready.

~~ED~~

Mumills [K. Steer; 958; NMA 9K] flange fragment; hard, white fabric.

B

Newstead [p. 266, fig. 35, no. 3; FRA 1428; VII. 15. 10; NMA 141K] r. facing; cream fabric; medium flange; red-brown, black + white + grey grit.

C

Mumills [fig. ^{Macdonald p. 456} 94, no. 3; 1930-216A; 91.1; NMA 145K]; hard, cream with cream slip; black + brown grit to rim; l. facing.

A

Mumills [1930.216; NMA; 88K] r. facing; broken part, possibly part of 145K but I thought different: hard, white pipe clay, cream slip; medium to small brown, black, grey grit to b., sparser towards head. Sketch

A

Lawrence Keppie 'A Butanys XXXV (2004), p 213 fig 22
Duntochev.

Cramond [now Edinburgh] stamped each side of spout; hard cream with slip over grit; buff surface; small, medium and large, red-brown and white grit; vessel restored. A

Birrens [1962 (274) Huntarian M] Die C white fabric; dark brown grit; perhaps a cream slip. C

Mumills [FRB 807A NMA] Flake? could it be from same vessel as 9K which K. S. 10 is

BRUSCIUS

The Hive, Worcester [Context 6158 Rec no JE 3047 Pd 5
 19K] Wt 129 Diam 28 10% Hard cream fabric, self
 coloured; inclusions moderate, tiny transparent & pinkish
 quartz. v. rare large red-brown. Inclusion: (a) 2
 only survive, black + red-brown. Stamp retrograde. Has
 horizontal grain - ~~either~~ wooden die? new die A

York, Hungate [Context 54839. YORKM 2006 5201
 148K IRS. 28.5 gms. Hard, cream fabric
 self-coloured or with self-coloured slip. Moderate
 plus ^{tiny} inclusions range from ^{are extremely tiny} ~~smallest~~ / occasional
~~medium-sized~~, red-brown, quartz ~~trace~~ black ¹⁰

(clay pellets)
wear
quartz topaque

very occasional medium-sized black, & rare
material; no tinturation survives. Fabric fits date later
than AD 130. Broken too high

BRVSCIVS

Corbridge [BK67 M506. 75.2547 Site XIHQRS. 417k] DIE 5.

Hard, creamy-white fabric, fine-textured; moderate quartz inclusions with a few red-brown fragments. Trituration grit black and red-brown, hard, refined pottery. Worn. D. 27 cms.

BREUSCIVS or BRUCIVS

- white int - patches of rust.

E. 13 suggest last 1/4 of E & similarity to SILLUS

Corbridge [xxvi p. 177 no. 8; US. 53 ⑧; 346K] hard, white fabric with yellowish surface; red grit; badly impressed. E

Corbridge [xxvi p. 177 no. 8; US. 58. 347K] r. being; slightly sandy, white fabric, smooth, orange brown surface; no grit left. 2 other B

2 others like Bulby & Cotton P148"

Aldbrough [Rel. Iss. pl. xxviii / ill. vii 1334, 13a + (b) 5K] hard creamy white, purplish D

buff surface; a little black grit. 2 separate stamps on fragments of the same vessel.



9K + XXII p 376-7 Fig 1 + 2 vol Crypt School Grounds, Friar Orchard, r. facing
 Gloucester [B.G.A.S. IV, p 287-8 fig 6, 15], no 197.1; dirty white ware closely C

$D = 11\frac{1}{2}$ ins.
 resembling pipeclay, of very hard texture, sparse large ^{medium} black grit, ^{black centres} red/brown with.

Yorkshire Museum [45K] white pipeclay, brown-red angular grit is E

prolific.
 Wildsworth, Lincs. [3K. vol 6, Part I; 1955, fig 2, no. 8. 9 p. 61, Lincs. A + A. Soc. Repts + Pprs; Arch notes for Yr 1956] smooth and hard,

creamy buff fabric, with rather pale brownish buff slip, parts of surface of flange mushroom colour, parts of fabric burnt grey black; hard, medium-sized black grit, sparse on fragment. "from a site by R. Trent; where much R.B. pottery is ploughed up." C



BRUSCIUS

between Newark & Widnespool

A46 road widening scheme 2009 / Margidunum H9M09

303500 4K] 135g Dr. 310 mm. 13% Fabric: cream fabric

Inclusions: moderate, mostly fine, quartz, red-brown, rare

black, few ~~large~~ occasional larger ones. Only tan

bit of inside & 1 red-brown grit. It ought to be

facings judgment position. Die 6

Hartshill [Kiln 1963] 1K ✓ Probably l. facing; hard, cream fabric with pale buff slip; red-brown and brown angular grit; horizontal striation in stamp; D=13" Die 5 F

Hartshill [do. 2K ✓] Hard, fine-textured, cream fabric; buff slip; brown and red-brown grit; D=11". Striations also appear in border. F

Hartshill [do. 19K ✓] Cream fabric with tiny grit in body of fabric. F

Hartshill [do. 18K ✓] stamped twice together; stamps faint; hard F
cream fabric with tiny grits in it; three trituration grits - brown.

Hartshill [do. 3K ✓] Hard, fine cream fabric with buff slip; brown grit, rounded & obviously unworn. D=12". Die 6 G

of 1918 3 Kiln. S" 32699521

BRUSCIOS

Cobhill, Warks. [5K \triangle 1101 JM GH 78] stamped along. Very slightly
 singed in parts. Dr. 37cms. Buff slip.
 Cream fabric with a little grey + brown tempering.

A Die 7

Winterton [XW/AJS TN 1572 Archive no 100 17K] L facing. Dr. 30
 Slightly uncaecous, cream fabric. Inclusions: moderate ill-sorted
 pinkish quartz + occasional orange-brown + true black.
 2 blackish + 1 v/b tubular gouts survive.

Die 1

Wellton, Humberside (Rod Mackey MF' 146'iii 462 r. fac

Manduesedum [w ⑤ 6. $\triangle 137$ 1964] fine-textured, cream fabric; cream slip;
dark brown gnt. r-facing. A

Manduesedum [w ⑤ 1. $\triangle 13$ + $\triangle 78$ joining,] no rubbing - stamp as
 $\triangle 137$. Cream fabric + slip; dark brown gnt. A

Manduesedum [w ⑧ 6. $\triangle 172$] flange fragment. Friable, brownish
cream fabric, containing tiny particles. E

Manduesedum [w 65. \textcircled{V} 3. $\triangle 184$]

beave F

BRUSCIUS

Hibaldslöv [H1B 88 (386) 2K] Flange fragment. Fabric unusual

for M-H & micaceous like B. Carlton. Grey core + huge chunk
of fine grained grey material. Very fine-textured, very micaceous greyish-
cream fabric. Smooth. V. rare quartz + blk inclusions apart
from above-mentioned chunk.

Dié 7.

BRUSCI'S BRUSCI'S

FRA 1428

Newstead [p. 205, f. 35, III] "soft buff ware" FRA 1428

? Barchley Hill [Brockley Hill]

Wroster(?) [Arch. 88 (p. 222, 1)]; very seen by B².

Fith +

Unstratified

Dunthorpe [Gough's Camden IV, 103 + pl. v, 4 / CIL VII, 1334, 19]; BRVSC. F

Mumwells [see p. 116]

~~Corbridge (A) of 1907 site VI p. 67 BRVSC I~~

Naval
BRVSC

BRVSC

wronaten
F. 14, 1.

BRVSC

wronaten

BRUSCIUS

J.B. Whitwell

Archaeology, vol. 1, no. 1.

Frampton, west of Boston. [Arch. Notes 1964-5 p. 36 in Lincs. Hist. Soc. Trans. N. Boston] [Sent by Miss M. Vulich, 11th. Nov. 1964] Hard, creamy white

fabric containing tiny grit; fair amount red-brown grit. G

[TF/287435 - Fen Farm, Frampton Fen, Hubberts Bridge, Nr. Boston.]

Alcator [65. DI (25). 33K] 4 joining fragments; 1 other piece with same number & are probable DI 2a] Fine ^{hard to test} cream fabric and slip;

greenish grit. no. 68/66 in archive Few grit & v wave v/b inclusion of

Fisherwick [2K FW 68 2] XII ① Almost a quarter of vessel]

Creamy white fabric tempered with usually fine grit. Much red-brown grit

* Boston TS. Lincs. Archaeology Group 1965-6, 2-4.

E. Midland Archaeological Bulletin, no. 9, 1966, p. 14. TF 287435.

BREVSCIVS

Chesteron, nr. Peterborough [CIL, VII, 1334, no. 17; 65/4/8/9; British M. 33K] ^{It}

stamped each side; complete except a little of flange; fine, white fabric; abundant, red-brown + black, largish to smallish grit, much worn away; D = 8 1/10"; grit most worn in middle portion. B

Margidarium [SK 33499] Schola Ant. Dump. Notts U.M. A.S. 50V
p. 58 no. 49 fig. 6 no. 69; slightly sandy buff fabric; medium to large black grit

Attributed - not entirely certain. (NASO) "NASO" ?

~~Itley [Itley M. 33K] worn badly but can be assigned with reasonable certainty; cream fabric with medium to small red-brown grit to b. 6; a few grits also on top of flange.~~ B

BRUSCO S — ?

Downway, Worcester [HWCM 3899 1700 8 6K] Flange fragment

In hard cream fabric. Inclusions: moderate, pinkish & translucent quartz plus rare opaque red-brown. Obviously Man-H. End of stamp only survives i.e. border with red-brown slip. ? Die 3

Deanway
6K

BRUSCIUS

Clapham, Beds [CAP. 70 9. ③] rubbing H. Penquell.

BRUGCIUS

Newcastle [B690 3059 1K] r. facing. Dr. 28.5 cms. 7

joining sherds making up 4% of rim. All sherds covered in an ^{oamy} brown deposit. Hard cream fabric with few-
(some large) → rare orange-brown stained random, ill-sorted, quartz (some pebbly) inclusions (x20) with

Inkivation: mostly black with the odd red-brown one.

Spout Type: 4BBC (see drawing).

E

Aldbrough [13K unpub]. white pipe-clay; red-brown girt to bead
25K

Mancetter [Brim. Mus. 25K not seen. Brim. A. S. Trans. & Proc. for 1956, vol. 74 (1958) (p. 48 fig. 12 no. 81 + p. 47) no. 74] ^{retrograde} buff ^{hard cream fabric with} white fabric with

^{much from girt} fine black girts. ^{D=20'} Rubbing sent by A.O. 1963 §20/1/In Floor. ^{15 Rubbing of} Venlamium [1958 AIV Room 9 ①; 143K] r. facing. kosmooth, very fine white fabric; traces of very pale, pinkish buff slip, creamy on interior; r/b. & grey girts, rather sparse; smallish to c. 1/4 b. b. b.

High Cross [J. Pickering; 1958. Chance find in Road Works.] fragmentary; smooth, white fabric with 1 or 2 redbrown girts in fabric; no girt surfaces; assigned with fair certainty; stamp retrograde.

D

E


White moor Henge, Alrewas, Staffs [WHS 03 Area M F204

[2006] 1K [2]. Facing 335 gm. D. 35 mm 17%

burnt round upper ends edge of flange. Very hard, fine-textured, cream-faline with darker cream slip. Inclusions: moderate, sparadic, ill-sorted, quartz, red-brown

with rare cream spots. Tituration: mostly hard dark red-brown ^{rare} spots appearing darker surface, very rare quartz & possibly black rock. Weathering has given same deep cream color to all surfaces so wear diff. cut flanges but no

visible wear marks visible.



BRVSCIVS

Old Sleaford [D23^B 159] hard, fine, pipeclay fabric with cream slip; flange fragment only. A

Bainbridge? — ^(See Bainbridge envelope) likely to be BRVSCIVS. 1925; r. facing; fine, cream fabric; abundant large to smallest grit; red-brown, dark brown or orange brown; very few, v. unobtrusive white grits; ?

Manduesedun [1963 MANC.-63 T2 (2)]. Stamped twice together; fine-textured, slightly softish cream fabric; dark brown grit. Obviously unused but as only the very top of the unburnt shales it may not indicate a waste; buff slip, discoloured grey in parts; some of grit is a bead + flange; large vessel. F

BUDEA


Cartridge [US 50; 95K] end of stamp only; buff cream fabric with pink in core towards inside surface; cream-brown surface; large to smallish, red-brown, white and grey grit.

Cartridge [US 51; 168K] broken flange; cream fabric with pink-orange core; cream slip; abundant, red-brown, grey & whitish.

1963 Dimples in spot of BUDEA material].

Corbridge [xxvi, p. 177, no. 9; S. 103 ④; 336K] slightly sandy, buff fabric with
 orange surface; brown paint round stamp in border with ansae ^{no gut} 

Corbridge [xxvi, p. 177, no. 9; S. 369 ④ 56; 334K] sport with thumb mark in end.
 slightly sandy, white fabric; small black + white, + red-brown + grey grit;
 (black - some haematite); paint around stamp with closed ansae 

Corbridge [xxvi, p. 177, no. 9; S. 312 ④; 338K] broken double stamp; slightly
 sandy, white fabric; paint around stamp with ansae 

Corbridge [xxvii, p. 177, no. 9; S. 363 ④; 339K] sandy, whitish fabric with red-
 brown core; smoothed surface, patchy purplish and orange-brown
 medium + large grit; haematite; sandstone, + white; no. paint; Δ
 single stamp.

Bewcastle [P. Austin] Basically fine-textured cream fabric with much quartz and some red-brown (? sandstone) tempering, which makes the fabric slightly abrasive to the touch. The titration grit normally includes sandstone and milky quartz but the three sherds from Bewcastle are very fragmentary.

BVDEA (see RVDI)

(i) Newstead (265, f35, 26);

Corbridge & ex.

Zenwell? (AA4 IV; 169, no 3); — this is VITALIST IV

Ruin Wrox III. Inval. whitish buff trow. of fair sandstone; this is
the cr. r. k.



S. Newstead

92

()

()

Newstead [p. 266, fig. 35, no. 26; FRA 1479; v. 11. 15. 71; NMA 126K] slightly

sandy, white (dirty) fabric; burnt; no grit left.

Newstead. [not published; no. no. NMA 135K] cream fabric, as FRA
1479; ? same post.) pentagon post

BVCVS


Richborough [unpublished 6YK] l-facing; bright orange fabric with cream surface on top of outer part of flange; much, rather sporadic, smallish, grey, r/b, black grits to b. and well-scattered on flange; badly impressed,

Springhead [A.J. v.iii p.342 fig.4 + p.344 fig.3] Maidstone Mus. 2K; Watling St. at Springhead March 1922, W.F. Shelley; r-facing; fine, hard, pale buff fabric with v. thick pink core; hard, red, grey + white grit, largeish to tiny to head. △

Cerleon [Amphitheatre. Rubbing sent Dec. 1964 but not found.]

BUCVS ? Check place
No. 1 Boulton, London [ONE 94 Content 8184 Mus Acc no 3701 461K]

v. facing across flange. Spout + flange frag. 212g.
Fine-textured ^{crabs} cream fabric with few quartz + ? flint inclusions,
barely visible at x20 mag. v. rare orange-brown + v. rare
black, both o/b + black ill-sorted + probably larger. Fabric
appears to be brownish pink in parts + may have had a white
slip. Surface fine but slightly powdery.



Buccus

Fishbourne [FB/62/72] (9569. 3K] stamped along, probably l. facing & may be the only stamp on metarium. Stamp smoothed a bit in smoothing or scrubbing. Two pieces of same metarium but not joining. Fine-textured ^{slightly drab} ~~yellowish~~ cream fabric with salmon-pink core, contains v. little added grit. little of inside survives but grit seems to have been worn smooth below about $\frac{1}{4}$ " below bottom of head. Here & on top of flange grit is abundant, white, red-brown, grey. Some probably flint & rest quartz-like. Spant clear of grit - added afterwards. Grit probably applied after stamped - grit standing proud in stamp. Cumliffe 1971, fig 82, no. 4 & p 173

BVTR -

Not read thus: See uncertain & incomplete.

BRUCEVS / BRUCEVS

Chestholm ? BRUCEVS

B.V. TRI. O

721

Mancetter-Hartshill [① W71 ② 128] IRS. Fine-textured,

cream fabric; few inclusions 'rose' quartz and red-brown fragments. No tritvation grit survives. Dr. 28 cms.

Mancetter-Hartshill [⑦ W71 ② 58. ~~660~~] IRS. Fragmentary stamp.

Fabric overfined to grey. No tritvation grit survives. Dr. c. 28 cms.

Mancetter-Hartshill [① W71 ② 56. ~~653~~] IRS. Fragmentary stamp.

Fabric slightly overfined to greyish-white. No tritvation grit survives.

BV. TRIO ✓

C. fac.

for some pot.

Wroxeter [WB (63) + and WB (63) 4. 179K] two fragments ^{stamps} / not joining.

one a flange fragment. Hard white fabric with cream slip;
Mancetter - Hartshill. Slightly scuffed. Randomly dispersed 4'

ill-sorted, v. moderate quartz, mostly pinkish with pale soft orange? natural
iron compound. Dv. 25 cms.