

CAERLEON

?


CAERLEON STAMPS; used to be considered
'Legionary' - to be checked of

131

~~SECRET~~

~~REGISTRATION~~

Pavement [Newport 12K; House 18]. grey core changing to orange surfaces;
red-brown slip; white grit to c. $\frac{3}{4}$ in. below bead.



145, Newport, N.
a laundromat
Laundromat

A B II R ret.

CAERLEON

Gloucester [51/66 A.W. 14] 157 A. 8392] L. facing. Hard, thick red
fabric with traces of red-brown slip; abundant white quartz grit.
Dr. 52 cms Nostril poked into sunning sport end. Stamped twice A
close together. Die 1



A BIKR retrograde.

"LEGIONARY"

Die 1

Caerwent [Newport 25K] orange fabric, red slip - see other die ABHR

Caerleon [C 54; no no on fragment; 101K NMW] r-facing; stamped twice close together; usual fabric, brownish slip; white grit; good amount to c. $1\frac{1}{4}$ - $1\frac{1}{2}$ " b. b.; shape as 96 K. 54. 389A. P17


Caerwent (new) Die 1 Die 1



9118A ^{Quartz}
Bulmore, Caerleon [SF 216 76F/637 137K] Flange fragment

Fine textured, micaceous, orangy fabric. Inclusions: very rare, random, quartz and rarer red-brown material. Virtually no inclusions visible to naked eye. Noslip survives.

Die 1 ▲



RH8A

Grandon Bridge, Somerset

Knowle, Somerset; near Bowdrip, $\frac{1}{4}$ mile N.W. of Grandon Bridge on

banks of King Sedgemoor Drain [B.75; Bridgewater H] fine, brownish pink fabric with redder core; red-brown slip, mostly gone; no grit on fragment.

Die 2

Cirencester [A.154.3: A.C. 50 U.S. P.10; Cirencester H.] soft, brownish orange fabric; much white grit to $\frac{1}{3}$ " b.b.b; slip gone. 23K

Chalk

Die 2

Aylburton, Park Farm. Nr. Gloucester 1954-9. [Glou: M. no. 2218] villa? Fabric as mortaria at Caerleon but slip gone. Two fragments. Form has a distal bead. Possibly ABII R die 2

RH 2 A

LEGIONARY

Caerwent [Newport Mus. 26K] legionary ware. Die # 9

Wroxeter [E, 1912, fig. 1b, no. 2b; 124K; M 22] L. facing; orange brown fabric.
with reddish brown slip; no grit survives. Die 2



Иванъ Михаилъ Семеновъ

ABS retro DIE 1

28A

Aleman Kiln [AB 345/047 27K] L.facing. 1 sherd,
CR. Individual vessel. Dr. 29 6%. Discolored in
parts. Finger depression under rim under stamp.] 8'A Δ

Aleman Kiln [AB 345/~~047~~⁰⁶⁵ 28K] 1 sherd on handle of dish
or tray. Separate vessel and NOT a matavaun. 28A

Aleman Kiln [AB 345/047 ~~28K~~^{30K}] 1 sherd, complete rim
individual vessel Dr. 28 17% 28L. Type as
Manning 1993, pg 194, no. 13 (Caerleon)

Aleman Kiln [AB 345/047 32K] 1 sherd. CR. Type
as pg. 194, no. 18 Manning 1993. Stamp clearer
than rubbing. Slip dull. 28A Individual pot.

Conflated

Ter

IR relevant
on on + more
gather

Contra



28h Alkanit 20.5/665

AB345 retro DIE 2

28° A

Abernant kiln [AB 345/001 8K] L-facing IRS with distal
bead. Rotately individual vessel.

Abernant kiln [AB 345/014 19K] CR individual vessels

Dr. 25 cm. 7%

△

Abernant kiln [AB 345/024 21K] CR individual vessel △

Abernant Kiln [AB 345/003 22K] CR no rubbing. 4

Abernant kiln [AB 345/048 34/35K] CR individual vessel

Dr. 27 cm. 13%


A

Abernant kiln [AB 345/048 38K] FF

Confated

TC P

TOR



UAC

21K Agent 345/001
- 345/014

ABS retro. DIE 1

28°A

Abernant Kiln, near Caerleon [no. no. 1K] FF. individual vessel.

28[

Abernant Kiln, [AB 345 ⊕ 3K] FF. individual vessel
overfired to dark grey but core is red-brown.]8A

Abernant Kiln [AB 345/001 4K] 2 sherd^s. individual vessel
overfired to grey Dr. 25 5% 25% △

Abernant Kiln [AB 345/013 16K] 9 sherd^s, complete rim
individual vessel. Dr. 27cm. 16/0 Type as Manning 1993
fig. 194, no. F. r-facing 81A

Abernant Kiln [AB 345/013 17K] 1 sherd; CR; individual
vessel Dr. 26 30% probably right facing. 28[△

Summary: 8 different mataria and one other vessel
?tray or dish with handle.

All have distal bead on flange.

All have bead above flange, where bead exists.

Usually well above flange.

28A

LEGIONARY.

Caenwent [Newport Mus. 18K. T (148) 165.] brown fabric; dark red-brown slip; burnt or overfired. A Die I/1

Wroxeter [Field no. W.432] red-brown fabric with traces of slip; burnt; no grit on fragment. Die I

Caerleon [1954 At 20 in silt of lower culvert S.P; 26.7.54; N.W. 3K] ? the same die as the other. Fragmentary; r. facing; orange fabric; reddish brown slip; fair amount, medium, white grit to near top 1 bead; shape as N.W. 2K but bead lower. F.N.D.? ? Renamed ~~as 39K~~ [F.N.D.]



Newport Music
Showments.

28A

This is NOT Fig. 68, no. 37.

Grandon Bridge

Kingsale, Somerset [Bridgewater M. B. 75.] red-brown fabric with y-b.
slip; white grit. Die 2

Bath [W.S.P. 71 4K] Dr. 25 cm. Typical Caenon fabric
Walcot St., Exc^{hi} in Bath 1950-75 Edited by Barry Cunliffe 1979 Die 2^{DT}
106, fig 46, no. 52 and p. 105

Caenwent [40]

Die 2

'Walcot St, 1971' p.102-125 by Michael Owen.

28A

N-W, Fig. 68, no. 37.

Die 3

Shepton Mallet [SM 90 c1001 (E) Trench B. Sent by J. Evans 9K]

Dr. 31 cm. Hard, fine-textured, slightly micaceous reddish-brown fabric with thick dark blue-grey core. Random, rare inclusions, mostly quartz with fewer red-brown inclusions. All over red-brown slip but completely dull. Interraction grit all white quartz. Surface slightly blackened in one place.

Die 3-1

28X

Fig 68, no. 37

Coccoloma

28A

CÆRLEON TYPE
fig. 68, no. 37 Die 3

Caerleon [1954; 14.8.54; At 165-180 in yellow silt of road culvert]

NMW 1K] soft, orangy buff changing to reddish orange fairly near outside; slip not discernible; possibly patches; a little, white, translucent, small grit to near b. b.; low bead 54.389 A. P8 Δ Die 3.1

Caerleon [1954; 10.5.54; At 157 in silt of road culvert; NMW.8K]

usual fabric, 54.389 A. ? different die? Δ Die 3.2


Caerleon [Prysor Field III, The Finds of Pottery, p. 78, fig. 68, no. 37; Caerleon II]
Die 3.1

28% No 25 in report No 25 (illust)
No 25 (old no 76) No 25 (illust') Die 2
Carmarthen [CCS 18 253 34/73 1978 30K] L-facing. All grit worn away

Dr. = 28. Some slip surviving. Soft, micaceous, o-b fabric; fine-text.
Fabric all one shade. Inclusions very rare indeed. negligible one is qtz.

Carmarthen [CP 82 5871 33753 31K] L-facing. Dr. 26cm. Only tiny
patches of slip survive. Fabric as above. A little white grit
survives. Different vessel. no 27 in report die 1 ✓ ~~27~~


Carmarthen [CM 80 34 33691 32K] r. facing. Dr. 27. Different
vessel. Slip survives - dull. Softish, micaceous, fine-textured,
buff orange-brown with thick orange-red core: at x20 only VVV rare inclusion
visible ie qtz + 1 red. brown. no 26 in report Die 1
no 26 K



Probably fig 68, no. 37 but not fitting 100% ~~black~~ Carbon ABS
no 24 in Report

Carmarthen [CP83 v/s 33K] FF. No slip survives. Probably r.f.c.
Soft, fine, micaceous. Inclusions very very rare but some v/b
bits standing out on upper surface of flange. Dr. 28cm. Die 3.3
no dot between B and A and spacing there different.

Carmarthen [CP82 ~~5871~~ 33753 31K] L-facing. Dr. 26cm.
Only tiny patches of slip survive. Fabric as 30K (Dec 2). A
little white grit survives. Individual vessel. No 27 Die ~~2~~
Die 1



] / SC 1

CAERLEON TYPE.

~ 3r - 35

Caerleon [Prysg Field, The Finds of Pottery p. 78, fig. 68, no. 34; P. 36; 32.60; 29 F/CSE,

67K NMW] flange fragment; usual fabric; no slip survives; soft; flange beaded.

Caerleon [The Finds of Pottery p. 78, fig. 68, no. 32; 29; (P21); F78; 32.60; 74K

NMW] usual fabric, traces of slip; white grit; l. facing; shape like
18K Caerwent.

Caerleon [The Finds of Pottery p. 78, fig. 68, no. 35; NMW; 82K] drab grey core
to orange; traces of slips; shape near. 276.


Caerleon [The Finds of Pottery p. 78, fig. 68, no. 33; NMW. 93K; F85 (P35); 29,
32.60;] worn stamp, pinkish fabric, slip mostly gone; soft; no grit or fragm.

Bath [NPL 89-111/74] 16.K BAT RM 2001.61.1]

probably L facing. Fine-textured brown fabric with
red-brown slip ^{(orange brownish in fact).} heavily burnt. Inclusions:

v. moderate, tiny quartz with few red-brown & some
mica. Fabric probably discoloured by burning.

Intercalation: angular white quartz 240gms.
Diam. 310 m. 17% Outside moderately corrugated.
Well-worn.



Caerleon [Prysor Field iii, The Finds of Pottery, p. 78, fig. 68, no. 31; 27 PF +; 32-60; NMW. 83K] r. facing; usual fabric; no slip; 1 grit; mat no. 276.

Combeach [B76. Bridgewater M.; Dower 1937; Brick-pit] L. facing; white grit only;

Kenchester [HWCM 119; 51C Or. Mov. 2 (P419) Ditch BB 7K] about $\frac{3}{4}$ of vessel survives; slip gone; very soft, fine-textured orange-brown fabric; white grit surviving only in upper part; pitted below, where grit has fallen out. Traces of slip only. Dr. = 9 pieces.

~~YSC~~ also? see YSC


Nash-Williams ^{REGIONARY}
no. 47

Caerwent [Newport M. 8K] orange fabric with red-brown slip, white grit.
Profile near 276/8 but head not so high.

Caerleon [¹⁹⁵⁴ N.M.W. 2K. 16.8.54; At 165-180 in yellow silt of culvert (road)] compact
fabric; very orangey buff; reddish brown slip; white, medium small grit;
? burnt at one end; D = 10½ ins. 54.389 A.12

Caerleon [¹⁹⁵⁴ N.M.W. 5K. 13.8.54; At 165-180 in yellow silt of road culvert] L-facing;
very soft orange fabric to slightly paler colors near surfaces; slip gone;
Very tiny gritty tegmata in fabric; no internal grit; type as 1K.

Caerleon [Prysor Field iii, The Finds of Pottery p.78, fig. 68 no. 47; 32.60; b3 KNW]
dark, drab buff to drab orange, some splitting; texture like *VACASATUS* *BRARIATI*




'N86 IVSC

Nash-Williams no 47 UNLEGIONARY

Caerleon [A Lxx.v.111 p.186¹¹ f. 23 no 75] 2nd, described as legionary ware

Guildford [Prysq Field, Part 3, f. 68 no 47 + p. 79] - legionary ware 7(11)S

Bush Marsh [3K 917 BM 71 II ②] slightly burnt. Definitely Caerleon
Attributed to this die.



No.75.


Caerleon

✓

WCC IV SC Guest
Bulmore, Caerleon [SF120 76F/653 136K] ~~Nash Williams~~
Caerleon r. facing. Dian.

c. 30. Sample. Fine-textured, orange-brown (Munsell 2.5YR
6/8 'light red'). Inclusions: rare, random, ill-sorted smallish
~~frag~~ <sup>?
frag</sup> red-brown and ~~qtz~~ and some tiny ~~qtz~~, white quartz
infiltration.

△



ARSV or ATSV? (w. crossbar) ARW?

Caerulean + fine-textured very pale brown fabric with
greyish dove brown (pale) + white grit, "sintered" fabric!
local, but not ordinary Caerulean fabric no slip
discernible. Contains mica.



N-W no 49

Cardon [Prysq Field iii, The Finds of Pottery, p. 78, fig. 68, no. 49; (PB); 29 G(CW)]

S.; 32.60; 62K NMW] usual fabric; and slip; flange fragment.

Bash Marsh, Somerset [918 D10 joining V 17.] 2 joining frags.

1 quite heavily burnt; other with surface partly eroded.

Caerarthen [CP 82 5432 33/148 + CP 82 6139 38761 M2 29K]

5432 → 7 joining fragments incl. L. face stamp + all of spout.

6139 → r. facing does not quite join, probably same vessel.

Dv. 28 cms. Micaceous. O-b fabric with dark grey core in rim only, fading into thin greenish brown + probably becoming brown - not.

Softish but quite a lot of thin dark red-brown slips - white quartz - Intervallum grit. worn.

V2B n ASB ret or VSB

LEGIONARY.

Caerwent [Newport M. 6K.] orange fabric, red-brown slip; medium and large, white (? quartz) grit; fairly prolific up to bottom of bead; profile as 259/275 (bead higher than no. 259).

Caerwent [Newport M. 11K.; House VIII N 1909] fabric similar; profile as Jenkins' Field no. 113, but bead thicker and more rounded, outside broken. ^{intact}.

Caerleon [1954 NMW. 12K; At 20 in. silt of road culvert; 19.7.57] fragmentary end of flange; 1954; beaded end of flange; usual fabric.

Caerleon [1954 NMW. 13K; At 20-54 in. yellow silt of road culvert; 26.1.54] fragmentary end of beaded flange; compact, soft, orange (brownish); good, rib. slip; 54.389A. P.II.

Caerleon [N.W. 54.389A. P.10]. 130K




Pacemont [unclear] M. Am.

82A'


Sea Mills [Burst] Mus. 3K. F 3937. ST. 5512 7589

1965 I v/s very superficial burning; slip gone. Sl. micaceous
v/f fabric with few if any inclusions; wh. quartzite.

Bush Marsh (Hedge 919 BM 71, 1K) 2 joining fragments. Burnt
throughout to dark grey - slip blackish.




V9A Neskowin w/ Lorraine no. A3
2 joining sherds
Carmarthen [CP 83 8387 33781 + CP 83 8387 33782,
not joining] Ltr. Dr. 30 cm. No slip survives
Not far from rim. Usual fabric, v v rare v/b inclusion
? natural Fe² oxides; rare wh. cream bits. Abundant
white quartz tubulation grit.
Carmarthen [CP 87 v/s Several Cleavage 38K]
No slip - survives. Usual fabric but more ? natural
Fe² oxides visible. No tubulation grit except v
few wh. quartz. Rest worn away. Very heavy
wear. Dr. 30. 2 joining sherds + 1 BS.
This example: V9A 11.11 is no. on pot but not on labeling which is poor.



? Nash-Williams fig. 68, no. 13.

Carmarthen [CP 82 5550] 33° 7' S 41° K L. fac. usual hab.
no ship survivors. Dr. 24 cm.



See Nash-Williams fig. 68, no. 13 probably the same stamp.
Also Carmarthen 38K on with no. 13.

Carmarthen [CM 80 (168) 337] 2 42K] 1 R.S. Usual fabric
no slip or grit surface. Dr. 25.

Prysg Field no. 12

LEGIONARY.

Caerwent [Newport M. no 3K] pink-red fabric with red slip; medium,
white grit.

Cowbridge, Bears Barn [48 038 4021 7K] Fine-textured, pale brown
fabric with some sand-sized quartz + some larger red-brown inclusions
frare white. A B + R - - (rt) D. uncertain. A
TIR: no slip surviving!

KnowC_a



3K Paement
(Newport Rd.)

V. 91/1

Caerwent [Newport 27K] burnt grey core to brownish-pink surfaces; small fragment.

Caerleon [Ryng Field, The Finds of Pottery, p. 78, fig. 68 no. 13; F85, 29 (P12) 32, 60; 72K NMW] usual fabric; no slip survives; white grit; like no. 28M.

Caerleon [unpublished; as no. 13; S.F.; APM YT; 35.118 (C.15); 105K.NMW] flange and bit of bead; flange not beaded; no. 279 type but bead raised very little; light, orangey buff fabric with traces of light orangey brown slip.

Neath [early? concord; NMW. 27K] usual fabric; soft; slip does not survive; no grit on fragment.



278 Caloceras (Nepal)

Alternant Kiln [AB 345 ⊕ 2K] publication 15 Dr. 27 cm.

9.5%

Δ

Alternant kiln [AB 345/001 6K] publication 16 IRS

Alternant kiln [AB 345/047 23K] publication no. 17

Dr. 28 cm. 28%

Δ

23K Abenamt 3 1/4⁵/7, 1
rac facing v.



grain

6K Abenamt 3 45/100



o


2K Abenamt ⊕



Abernant Kiln [AB 345/065.40K] r. facing Dr. 29 18%

Illustration no. 21.





r. racing

i

o

345/065

40K Assessment

CAERLEON

Abernant Kiln [AB 345/017 47K] FF. Seen July 1997



47

Brach Abenait

AB 345 017

Abernant Kiln [AB 345/ See archive ~~#1-#6~~, 48-53
too fragmentary to identify, seen 7-97

Abernant Kiln [AB 345/ seen May 1998, See archive
for nos. 5, 7, 9, 11, 13, 15, 18, 20, 2⁴³⁶, 24, 25, 29, 37,
39, 41, 42, 43, 44, 45, 46. Stamps too
fragmentary for identification.

Only further work possible to help identification is to
check ALL of these for possible forms with the
rest & add spouts etc to see if will join other side.

Abernant kiln [AB 345/047 3IK] IRS Illustration no 18.

Δ

31K.abnormal 345/047



>
modification - 218.

Caerleon stamps Identifiable = future ?
Abernant Kiln [AB 345/001 10K] FF Publication no. 22.
fragmentsary stamp.
Abernant Kiln [AB 345/003 14K] FF Publication no. 23
Abernant Kiln [AB 345/047 26K] CR Publication no 24
got unusually finely broken. Δ

10K Abenamt
345/001



break

26K Abenamt
345/047

face pack

break

? break

?
break

14K Abenamt
345/003

P B 1 B%

Abernaut kiln [AB 345/003 12K] FF Publication no 20

Abernaut kiln [AB 345/048 33K] Publication no. 19 A

Dr. 29 cms. 9.5°

TOP?

3316 Altman: 345/048

L. 60c

0
1
2
3



bowl

TOP?

3216 Altman

345/003

0



bowl

DBM

10-18 London Bridge St,

London [Southwark, near London Bridge S&K Southwark]

Scutby Fiona Seeley. Site ~~LA~~ B97 Context 8 S

Fine-textured orange-brown fabric. Few mostly sand-sized
quartz inclusions, rare ? iron slag and soft white cream.
Red-brown slip. Intercalation grit: white quartz. Dr. c 28cmo.
120 grams.

Die B

MBC = DBM

CAERHEON TYPE

Caerleon [Prysg Field iii, The Finds Pottery p. 78, fig. 68, no. 40; C 29; G. 95 + P. 26,

32.60; 695+; NMW 9 & K] usual fabric and slip; white grit; moderate amount, worn, to near b. b.; similar to no. 279 but beaded flange.

Caerleon [Prysg Field iii, The Finds of Pottery p. 78, fig. 68, no. 41; 29; G. 39 S;

(P31) 81K N MW] usual fabric with good slip; no grit on fragment; neat no. 275.

Caerleon [Prysg Field iii, The Finds of Pottery p. 78, fig. 68, no. 42; 29; G. 39 S; (P32)
76K NMW] L. facing; usual fabric with brownish slip; white grits; similar
to no. 279 but beaded flange.

Caerleon [Prysg Field iii, The Finds of Pottery p. 78, fig. 68, no. 43; Caerleon Mus]
usual fabric.

~~D.B.W.~~ JBM news

CATERLEON

Westbury, Wilts [703 IK Devizes M.] softish but compact, fine orange fabric;

with very scant traces of the reddish slip; no grit survives; D = c. $1\frac{1}{2}$ ins.

Caeleon [1954; 54-78 in silt of culvert. S.P. 38.54; 20 K NMW] usual fabric; slip all gone; much hard, white, angular, smallish + few, medium grit; 1 or 2 darker to c. $\frac{1}{2}$ b.b.b; type as 2 K NHW. D = $9\frac{1}{2}$ ins. 54.389A. P14

Caeleon [17 K NMW.] 1954 flange fragment; usual fabric; prolific fine, white grit; some of it shiny; to c. $\frac{1}{4}$ in. b.b.b.; slip gone. 54.389A. P15

Caeleon [NMW. 33 K. Old finds] r. Facing; legionary fabric; slip gone; fairly similar to IK.

IR Westbury 703



M&C - DBM

CAERLEON TYPE

Caerleon [School Field; A6x; 35.118; c. 13; 108K NMW] facing;
usual fabric and slip; no grit on fragment; type as IK. (~~✓~~)

Caerwent [33K 9. Dunning

MBD - DBM

CAERLEON TYPE.

Caerleon [Prysg Field iii, The Finds of Pottery, p. 78, fig. 68, no. 44; 27; P.F. +; 32.60; 100K NMW] usual fabric, slip gone, soft, white grit; stamp worn; shape as 85K NMW.

Caerleon [Prysg Field iii, The Finds of Pottery, p. 78, fig. 68, no. 45; (P42); 27. P.F. +; 32.60; 99K NMW] r. facing; usual fabric & slip; white grit to c. $\frac{3}{4}$ b.b.b.; Type as 1K. B

Caerleon [C.54; At (18) in yellow silt of road culvert. 18. 8.64; 1954; compact, reddish orange fabric, rather soft; no grit; slip mostly gone; Type as 2K but head higher; 7K NMW.] 54. 399A. P16. (Die B.)

Caerleon [S.F. (11) A 158; 35.118; School Field; 104K NMW] usual fabric & slip; 1 white grit;

V94

CAERLEON TYPE.

Caerleon [Prysg Field, The Finds of Pottery p. 78, fig. 68, no. 14; 32.60; 29; (P22)

G. 39. S. a-b. 86K NMW] pinkish brown fabric; some trace of slip; much, white grit; like 275 but bead not so high

Caerleon [T. Trench 1. c-o. Top occupation in layer; 41K NMW] r. facing; usual fabric; slip gone; white, translucent, smallish grit to near b. b.

EN/118.

Nash-Williams no. 30

CAERLEON TYPE.

Caerleon [Vine Cottage Field; 1936; At +3'; in occupation and charcoal layer next below uppermost pink clay; SP 1 or latest p. S. P. 7.36; 42K; N MW] usual fabric; slip gone; shape as 260 but flange not so high.

Caerleon [Site Museum; Finds of Pottery p. 78, fig. 68, no. 30]

Roundbury, Dorchester [FC 2279 1248 P C 79G 4K] L. facing.

This appears to be from a different die from the Caerleon one but the reading is the same. ? montage.

Bulimore, Caerleon [75A/032 Δ 061 Drawing no. 137. 135K] Sample
tiny flakes of r/brown slip survives. Softish, powdery fabric.
fine-textured, ^{lightened} orange-brown fabric (Munsell 2.5 YR 6/8 light-red)

Inclusions: rare, random, ill-sorted, ~~fine~~⁺ smallish, red-brown
material + quartz. Interraction: white quartz △

R E A on A TF & E Nash - Williams no 19

CAERHEDON TYPE

Caerleon [Physg Field; The finds of pottery p. 78, fig. 68, no. 19] 28 T 32 (P II);
265!
61K NMW] usual fabric; white grit; shape very close to no. 257

Could be same obs 4

CAERLWYN No. 19

Waukegan, Illinois [v. Swan 14K] L. facing; hard, fine-textured

pinkish brown fabric with red-brown slips ^{iv} surfacing over outside &
on flange; slips not very good; abundant white quartz-like grit.
NB neat little sprout.

HVRs

— see Caerleon - Finds of Pottery no. 21; + Caerwent 22
BVAE

HVRs (nt) ~~Caerleon~~^{USK} (Arch. I. xxxv, 273 & ff) "Red ware"

DVER F

See no. 3 (similar)

CAERLEON TYPE

Nash-Williams no. 45

Caerleon [Prysor Field III, the Finds of Pottery p. 78, fig. 68, no. 48; Caerleon Site
Mus.]

BLN

- (1) *Wroxeter* (ii, 2001 f 17, p. 30); Type 126. ^{+ P 46.} ~~Wroxeter~~ letters barbed; forming right. Provenance possibly [615] ^{is in Wroxeter} ~~is in Wroxeter~~.
~~Wroxeter~~ ^[615] ~~Wroxeter~~ (inter. 68/027); creamy buff exterior, very pink core;
~~Wroxeter~~ [112, f 160021 + p. 68] Type 84.

'Type 126.'



30

200m
300m

- K A 30
E

DEAR I.
H.

CAERLEON TYPE.

Caerleon [Prysg Field; The Finds of Pottery p. 78, fig. 68, nos. 3 & 4 p. 77, 29; p. 27.

G. 39. S; p. 260; 97K NMW] legionary fabric; slip; white grit.

Caerleon [Prysg Field; The Finds of Pottery p. 78, fig. 68, no. 2 p. 77, Caerleon Mus].

JSCA2

CAERLEON TYPE.

Caerleon [Caerleon Mus., Prysor Field: The Finds of Pottery p.78, fig. 68 no. 4.] legionary ware

BRN

Caerleon [SBAA 48, p 77] may be on a Mortar.

C A

Wroxeter [1912, fig. 6 + pl. 8 no. 22] Type 66.

Wroxeter [1913, p. 47 no. 22 (3)] Type 54 in Pit ~~XXXII~~

Wroxeter [1913 p. 47 no. 22 (C)] Type 54

C/F

Wroxeter [1914, pl. 61 no. 22] Type 54 in Pit 70.

Wroxeter [1914, pl. 61 no. 22] Type 54 below pavement between sites V + VI

MCH M 63 Site V. Orange (burnt) dull
soil med. br. + wls. grit.

no. 20

Nash-Wilkens no 20

CAERLEON TYPE.

Pearson [32.60; C. 29; G. 36.5. P28]; Physq Field p. 78, fig. 68, no. 20,

94K NMW] usual fabric; much white of slip gone; no grit on
fragment. D = 14.1 in.

K 8 A

N-Williams no 38

CAERLEON TYPE

Caerleon (Caerleon Site Mus; Prysor Field iii; The Finds of Pottery, p. 78, fig. 6c,
no. 38].

Hydney, Glos. (Park Farm, Dr. C. Scott Garrett see letter) soft orange-
brown fabric, slip completely gone & stamp worn; no grit on
fragment.


East Aberthaw, South Glamorgan (repaired on two H. sell Glam fintext. q. 81)
Whitton Cross Roads near Barry, Glam. [information Vivien Bishop,
21, St. Cyres Rd., Penarth, Glam; discovered by Howard Thomas,
a porter in the N M W. See Bulletin of the Board of Celtic
Studies, Vol. XVIII 1958, Part IV ff. p. 293] S.T. O 81713;
red-brown fabric with red-brown slip; flange fragment.

Caerleon stamp

Nordic

Caerleon [31/100. Glam. Unit. 122K] IRS. C-facing. Normal

facing v strip



Probably Caerleon?
Same Shrepton flatlet.


Henley Wood, Yatton, Somerset [1964; E.G. M.3; 183; 578] very soft orange
fabric, slip gone; lumps to small white quartz grit, abundant.
Stamp very worn & unidentifiable. r. facing. The form can be
matched in Caerleon mataria but not on any the Shrepton flatlet
mataria. Probably from Caerleon. See Caerleon unidentified.

Scrub or Shrub? Check w/ S. Mallet. CAERLEON?
Sub.

Nettleton, Wilts. [E. Birley rubbing; "polished red ware"] 5/57/280

C. W. Kriestley Collection, Devizes Mus. Red-brown ship.
very slightly burnt; Brown w/ redder core. Flg & frag.
N. J. Wedlake, The Excavation of the Shrine of Apollo at Nettleton, Wiltshire, 1950-71 (1982) London. Rep't of Res. Comm.

of Soc. of Ants. of London no XL (Actually printed in Dorking)
Fig. 72, no. 24 on p. 173 + p. 74-




Nettleton, Wilts.
from E. Birley rubbing.

YACO

S-West W's 15.10.1971
CAGU 2051

Ceramic [Newport Mus. 1bK]. grey core changing to brick-orange; rather coarse; evenly distributed, very large, white opaque (pebbly look); red-brown slip. Generally similar in fabric & shape to Cassoleys but possibly another workshop making working in same tradition. Stamp also not really like theirs



V. III

see III. V

Caerleon: [C63 BH R⑥ NMW] Hard orange fabric w/ red -
brown slip + white grit.

111.V

'CAERLEON'

Chew Valley lake [cvl. RP 129. Rehtz]; probably badly burnt; chocolate brown - rather
brownish ochre in centre of fabric; very hard. Reading uncertain. Caerleon type

F 3773



Charterhouse-on-Mendips, Somerset [Taunton M.1K; A. 1055; VCH.]

Som. I p. 344 + Bath Field Club III, p. 341] soft, pinkish fabric with opaque white, medium + small + largish, moderate amount, to b.b. Surface or glaze slightly darker but the fabric is much pinker than Caerleon's fabric, the letters are rather coarsely formed + have no bases; letters are worn; there are slight indications that the vessel may have had a red-brown slip; D = c. 13½" probably 'Caerleon' product

Carmarthen [CM 81.2 33726 1011 35K] L. facing. 2 joining shards. Dr. 28. Half of a circular rivet-hole survives. No slip survives. Soft, fine-textured, micaceous, orange-brown - v. rare inclusions: r/b? natural Fe oxides. no. 31.

Seabrook pipeline, Avon levels. RSiles centered around ST5682
 Information sent by Paul Tyers. MAC 72 F174 lower black
 layer 1290g.] & 55% of rim + much of body. All breaks (shards)
 modern so there was more of it. L. facing. Dr. 32 cms.
 Fine-textured, micaceous orange-brown fabric with thin grey
 core; rare random quartz + other inclusions visible at x20. PTO

Seabrook cont'd

Intervetion grit - white quartz




Awan bowls (P. Tyers
Liac)

Fabric + stamp well preserved but only traces of slip survive behind bead. (from a layer cut into a surface that included pieces of TS Hadnanc a early Antoine)

Cerment [Newport M 7K.] orange-brown fabric with red-brown slip; medium, white grit to c. $\frac{1}{2}$ below head.

Cerment [Newport M. 15K. Ho. X VIII] orange-brown fabric with red-brown slip. Profile as [Jenkin's Field 1926] no. 115 but end of flange vertical and slightly bulging out.

Cerment [Newport M 20K.] orange-brown fabric, red-brown slip; medium, white grit to near bottom of head; profile as no 115 but end of flange normal [not turned or pointed].



15K Caement (Newport M.)



Caement 2001
(Newport M.)

LEGIONARY.

Caerwent [Newport M. 24K] legionary ware.



Newport M. 2000

V.I.C.I.


"LEGIONARY"

Caerwent [Newport 14K] legionary ware; burnt orange-brown fabric with slip.
Caerleon [Pysq Field fig 68 + p. 79 no 7] legionary ware. At Caerleon Museum.

Caerwent [Newport 21K; ① on label. no. 4 on back] orange-brown fabric
with red-brown slip. Profile like 14K. Flange fragment.

Catsgore [2 frags. from one vessel. Cat. F-468 no. 43. 1K]

1 stamp + part of other. Soft orange-brown fabric. All slip gone; white
quartz grit. Die no. 7.



R. L. Agurant.
(Newport M.)

Cannan (Newport, R.I.)

101X18

N-W. bl (ans), nos 8 & 9

Caerwent [Newport M. SK] usual fabric - pinkish red with red/brown slip; medium white, grit; moderate amount;

Caerleon [The Finds of Pottery; Prys sq Field, p. 48, fig. 68 no. 8; 27 P.F. p. 19; 32.60; 70K NMW] r-facing; soft "legionary" fabric; very red-brown; surface orangy, no slip survives; white grit;

Caerleon [The Finds of Pottery; Prys sq Field p. 78, fig. 68 no. 9; Caerleon Mus]


Caerleon [College Field; d. 1685; 102K NMW] r-facing; orangy pink fabric with tan-coloured slip; much white, medium to smallish grit to c. $\frac{1}{4}$ in b.b.b; near no. 275 in shape but bead not so high; much larger than most, probably collins; no bars on letters.



BtADI ret. nos. 8.9

Milk Street

Gaerlais [8.8-103-19 132K] no slip survives. The fabric with
red-brown inclusions all over. r. facing. D v. 29cm. Field wallings.
Newport M.



BLAD1 "

Caeleean.

Caeleean [C~~H~~ G.V.64. from Mrs. Murray Thrippland] "orange ware
with traces of darker orange slip - white grits". Rubbing sent.

UsK [4079. v 7.1(+ BW/ST+) 10K] fine soft orange-brown
fabric; traces of slip only ✓ ~~C. facings~~ wh. grit saturation

UsK [v 7.0 DDC(+) 9K] v. facing. fine pinkish brown
fabric with red-brown slip & white quartz grit; outside
surface brown. Beaded flange not quite complete +
upstanding bead. ✓ (There are 3 diff. great pots)

UsK [11077 + 11076] Drawing sent by Sabina Thompson 16K
oct. grit infuse (arrow) Qs. do not quite join across spout.
Caeleean - Arch. Cambrensis 1969 Fig. not drawn. p. 122 p. 1. Both slangs
survive; traces slip; finger marks on the outside; wh. grit grit

CAERLEON

Bar Hill [1936-483; Hunterian M...54.K] r.-facing; fine, pink fabric with
brown slip worn off in places but very well preserved for the most
part; abundant white grit; D = 15 ins.

Cowbridge, Bear Field (site 67) [Jomis 110.
1164] 67/631 [281 2K] L. fac. w.g.

Soft opaque pale cream inclusions (as in Kingholm Tinteration) Dr. 31 about.

Soft fine-textured fabric of usual kind. Slip all gone. A
likely to be from same due as the Bar Hill stamp.

116/67/631/981
DK Conv bridge
as Battall stamp

116/67/631/981
break.

CAERLEON.

Charterhouse-on-Mendip [FS.69 + FS.70; NMA 170K] | stamp each
side of spont.

%VOC

Bear Field, Cambridge [Site 67, 67/1348 A 241 223K 3K] L-facing

Fine-textured, micaceous, pale orange-brown (Mansell 5YR 6./6.)
with no inclusions visible at x10.

Caerleon: [54:389B-P12:131K]

Cowbridge, Bear Barn [48/043/026 ^{6K}] No slip surfaces. Soft, fine
textured orange-brown fabric with sparse, sand-sized quartz + rare
larger red-brown inclusions. No intercation grit surfaces. Dv. .98cm A.

Caerleon. [School Field, NMW 106K (C12) A PMU 35.118] Flange bead
like no 266 but no distal bead. Slip as 103K NMW.



A 24
67/13468 C. facinus
3K Bear Field 223
Coronado


% % C

Carmarthen [CM 81.2. 973] 33/25 / [1925] CM 81.2. 124) 33/34 27]

2 pieces joining - Dr. 31 cms. r. facing. Only traces of slip surviving.
Micaceous, fine textured, orange-brown with ^{thin} harsher slightly more
reddish core. Could be a different vessel from 28K

Carmarthen [CM 81.2. 1437] 33/33 28K

Dr. 32 cms. Fabric as above. No slip survives except by ^{thin} reddishness behind bead. Few white quartz ^{mini-} inclusions.



CAERLEON

A1

Myrtle Cottage, Caerleon. Rubbing sent. New die.

3918


LEGIONARY

N-W w. 21.

Caenwent [Newport M. 22 K] orange fabric with red-brown slip; small to medium white grit up to rim.


Caerleon [Pysg Field, The Finds of Pottery, p. 78, fig. 68, no. 21; 32:60; NMW; 65K] usual fabric; no grit on fragment; slip gone; ?near 287 shape.

Caerleon [The Finds of Pottery no. 81; 32:60; 66K NMW] This probably a fragment of 65K but it was not ascertained at the time; beaded flange.



Nash-Williams nos 5-6.

Caerleon [sent by Nigel Blackmore Royal Legionary Museum, Caerleon
28/2/02 · 141K] stamped twice close together. Very fine-
textured, orange-brown fabric pale in core; micaceous;
inclusions: few, sporadic, small to large, mostly red-brown but
some quartz. No sign of any of the slip. Titration: the usual
white quartz + perhaps mica. Diam c 350mm. 9% 260gms.



CAERLEON TYPE

NW no. 5 &c

Caerleon [Prysor Field, The Finds of Pottery p. 78, fig. 68, no. 5 + p. 77; type no.

234, probably this mortar; c. 29; G(CN)S (P8); 88K NMW]

usual fabric + slip.

Caerleon [Finds of Pottery p. 78, fig. 68, no. 6. Caerleon museum].

B.D.X.


N-W nos 24-26

LEGIONARY.

Caerwent [Newport 19K] legionary ware; white grit up to bottom bead. Profile as no. 275 but bead not as high and flange not as wide.
Caerleon [Prysg Field, Part III fig 68 + p 79 no 24-6; 3 exx] 32.60; NMW; 64 K] usual fabric; slip gone; white grit, very close to bead; near no. 26.6 in shape;

Caerleon [Prysg Field III The Finds of Pottery, p. 78, fig. 68 no. 24-6; 32.60 NMW; 7K] drabdish ochre core to brownish orange; beaded flange; no slip survives.

Caerleon [Prysg Field III, p. 78 fig. 68, no. 24-6; PF. 27+; P16]; 32.60; NMW; 84 K] ? burnt, drab grey core to orange near surface; few white grit. Shape near w. 26.6 but shorter.



49K [Newport MI]
Cement

CordLean [BN. M 2 - 4/s; NMW] flange fragment 'beginning wave'

?A BIR

B18V

CAERLEON.

Caerleon [CMG 64. Ms. L. Murray Threepland now] Description and rubbing sent. "Orange ware, with traces of darker orange slip." white grit. Arch. Cambrensis 1969 in The Hall, Caerleon, 1964: Exc^u a the site of the legionary Hospital by L. Murray Threepland 86-123 fig. 12, no. 4. & p. 122 no. 2.

PICA

CAERLEON TYPE

Caerleon [Rhysq Field, The Finds of Pottery, p. 78, fig. 68, no. 11; 32.60; P. 3, 69K]

NMW] dark drab, khaki core to drab pink; no slip survives; white grit.

B2A B71X0

X

I

(245)

F16

heicester [As no. 36 in Finds of Pottery. 366 A77. 1975.546] Grave IV 183K]

Flange fragment with distal bead. In I (245) fine orange-brown fabric, grey core & 1 tiny flake of red-brown slip surviving. Fabric contains streaks ^{calcareous material} quite a lot! Partially burnt - no slip surviving. Inclusions: ill-sorted flints almost as though it never had any. moderate, (?) chalk, definitely calcareous, fairly rare red-brown of quartz. Assigned - (fairly certain) A.


heicester [A 39. 1988 4974 799] F130. 200K] Flange fragment. Smooth, fine-textured. Color v. unusual? in cess pit?. Micaeous, buff-brown with yellowish patches. Rare quartz, rare v/lb; some tiny cream inclusions, perhaps calcareous. Different vessel. Surface polished but no signs of usual chip. Dr. 26cm.

LEGIONARY!

Kenchester [Woolhope Club, 1924-5 p. 42 no 3; Hereford Mus nos K] band,
orange fabric with red-brown slip. Flange fragment.

Gaerwen [Prysg Field, Part II fig 68 + p. 79 no 56] legionary fabric
7(39)s

Dolaucothi [5K Drawing stamp and ~~SD~~ information
P. Webster July 1996. Barn Jones Excavation
1972. Probably this stamp. Pot missing
Dolaucothi [Dol 72 Trench 1B Context ① 65 4]
Information P. Webster July 1996, B. Jones 1972
excavation]




Kontakt: 0171/
(4114)

Caerwent [Newport Mus. 9K] orange fabric; red-brown slip}

Caerleon [NMW. 6K 1954; 54-78 in silt of culvert] compact, reddish-orange; very reddish slip; white, length & small grits to near b.b. but mostly $\frac{1}{2}$ b.b.b.
D = c. 10 $\frac{1}{2}$ ins; Type as 276B (Finds of Pottery) - 54. 389 A. P. 7

Caerleon [Rhysq Field iii, The Finds of Pottery, p. 78, fig. 68 no. 36, (P 15), 29;
G. 39 S; 32.60; NMW; 80K] L-facing; usual fabric and slip;
near 25K & 18K Caerwent.




Caerleon no. 36. "B211x0"

Worcester [A40.1988.7203.1005] joining 8860(54) 301K probably L-facing.

Red-brown slip, not in good condition. Micaceous, red-brown fabric with moderate, v. ill-sorted & unevenly dispersed quartz inclusions; 3 quartz intercalated grits survives. Dr. ?? 30.

All 3 vessels different and all fabrics odd for Caerleon.



B VND

N.W. w.s 15-18

CAERLEON TYPE

Caerleon [Prysg Field, The Finds of Pottery, p. 78; fig. 68, no. 15; 29 G (CE) S; P 25;
32.60; 73 K NMW] stamp worn; Caerleon fabric, some slip; no grit on
fragment.

Caerleon [Prysg Field, The Finds of Pottery p. 78; fig. 68, no. 16; C 29; G. b. S (P 47)
32.60; 89 K NMW] usual fabric, no slip; white grit; similar to
no. 261 but flange not so high.

Caerleon [Prysg Field, The Finds of Pottery p. 78; fig. 68, no. 17; (P 45); 32.60; 27 P.F.
79 K NMW] usual fabric, no slip survives; shape as 25K Caerwent.

Caerleon [Prysg Field, The Finds of Pottery p. 78; fig. 68, no. 18; (P 50) P.F. + 27;
96 K NMW] L-facing; bright reddish orange fabric, more buff at surface; slight
traces of slip; white grit 15 b.b.

CAERLEON TYPE.
N.W. No. 15-18.

N.W. no.

Caerleon [NMW. 4K; 1954; 18. 8. 54. At 165-180 in yellow silt spread culvert]

compact, reddish orange fabric, surface slightly paler; traces of slip, mainly
in stamp; few, white grits or fragment; v. facing; type as 1K.

Caerleon [NMW 14K; 22.7.54; at 78 in silt of Road culvert] broken flange;
compact, soft, orange (brownish) fabric; good v/lb. slip; white grit; type as
2K N.M.W. 54. 389A · P5

Caerleon [At 165-180 in yellow silt of Road culvert; 18K NMW] slip gone
save infinitesimal amount; low 2 white grit; similar to 2K Caerleon but
splay out near break; 54. 389A · P6.

V.B.P. no. 39 Nash-Williams

'CAERLEON'

Caerleon [Newport]. 1K] Orange fabric with red slip; prolific, angular, medium to smallish, white grit to just below bead.

Caerleon [Prysg Field III, The Finds of Pottery p. 78, fig. 68, no. 39; 32.60;
29 (143) G. (c W) s; NMW 6.8 K] not drawn in Report + confused with no. 38; usual fabric; no slip survives; soft; shape as c. no. 275;

Chatterhouse-on-Mendips [Taunton 7. 3K; A: 1066] fabric redder in colour than the Shepton Mallett mortaria; grit white - probably same material as used at Shepton Mallet; laugish + medium grit. D = 11 1/2"

187A

Redwick, Mons. [1952-3. Cardiff M. sent by G.C.B.] Site described in BBCS XIV
George boom
(1952) 254-5. As no. 39 in Phys. Field.

V. BK no. 39

Cædmon [54.389A. P. 18. NTW] ^{BK} probably as no. 39.

Fragmentary no. 22 A'B(ω R) 1

FELICIO

cf. FELICIO ~~dissectarium~~

Ambleside [CJ XV p. 57 next to p. 43-21] soft sandy red clay, buff slip, quartz
grit. 6" Read FELICIO by B?; Misread in Rept.

D 180

Caerwent [Newport M. 10K] orange fabric, red-brown slip; small to medium, prolific grits, worn, to about $\frac{3}{4}$ ins. below top of bead. A
Caerwent [Newport M. 13K] same fabric; stamp broken; near 27 6/8 but bead probably not as high. A

Caerwent [Newport M. 14K] same fabric; prolific, small + medium, white grits, strays to top of bead. A

Wick Wood, Nettleton -
Nettleton-Wickwood [F b. 6195 B 7K. Bowls? Mrs]. Burnt

Caerleon; slightly burnt; slip gone. Not published.

Oldbury-on-Severn (Glos. ST. 6093. Sent by Mike Fulford 21.8.85)
 rubbing sent.



Not identified

Priddy, Somerset [Dr. Wells Museum] refacing. Softish fine grained
orange fabric, the red-brown slip has gone; white quartz grit

80293 nos 22-23.

CAERLEON TYPE

Caerleon [Physg Field, The Finds of Pottery, p. 78, fig. 68, no. 22; Caerleon Mus.]

Caerleon [The Finds of Pottery, p. 78, fig. 68, no. 23; 29 G.C.S. (P. 30); 32.60;
85K NMA] soft, pinky orange fabric; slip; medium to small, white grit

JESG

N - Williams 27-
w. 29

LEGIONARY

Caerwent [Newport M 23 K] orange fabric with red-brown slip; broken rim. Same general type of profile as 22 K 39 V 18

Gwent [Prysg Field Part II, fig. 68, + p. 79, 27-29. 3exx]


Gwent [Somerset VCH, I p. 292; at the time in ^{RIB 151} P.T.L. Museum.] S.B.

Bickspool, Bosherston, Pemb. [Bull. of Board of Celtic Studies v, 395] pot of a
woman standing on O.S.B.

Neath, S. Wales; Bulletin of Celtic Studies 13 fig. 5 no. 6; As fig. 68 no.

? 13 Prysg Field — ? ? ? S.B.; Cheek

Cirencester [51 K CIRBI J II (2) · M 88] Slip gone. soft, fine-text;
micaceous o-b. fabric; a few gr. white quartz interstices gr. to



DSBJS or]SEBSC'0 -]SEBISCO CAERLEON TYPE

15K NMW. 54.389B. P.10 N-Williams 27-29.

Caerleon [29.6.54; cutting Kh. pegs CD; latest occupation next above destroyed (!)

mosaic floor;] 2 stamps together; usual fabric; similar to 2K N.W.

Caerleon [Site Mus. Physg Field III, The Finds of Pottery, p.78, fig. 68, no. 27-28]
soft fabric; worn; light surface, like no. 27.60 without thickening in flange; (P 24)
here appears the patterned stamp missing. 29; G.5.5; 32.60.

Caerleon [(P 34) G(26) S; 32.60; NMW. 77K; The Finds of Pottery, Physg
Field III p.78, fig. 68., no. 29] flange fragment, slip good; flange
beaded. 54.389B. P.10.

Caerleon [35.118; S.F (School field); (16); NMW. 103K] L-facing
brownish orange fabric, with slip well preserved but very unusual,-
slightly metallic look about it and reddish brown with chocolate-like
tinge; white grits b. b. + large uphead; slight cracking under flange.

DSB

N.W. 003 27-29

CATERLEON TYPE

Caterleon [C14; School Field; A.P.M.V. 35.118; NMW. 107.K] r. facing

reddish orange fabric; dark reddish brown slip; 3 white grits;

Compton [VC H. Somerset p. 292 Haverfield. ^{is a} ~~piece~~ marked
SB1 on the lip, probably the same as a piece now in the
Bristol Museum which seems to read DSB?]. Bristol M.] 2K.

L. facing. F 791; brownish orange fabric with remains of
red-brown slip; may have been burnt; no grit on fragment;
bars on 1st letter + front of B. D = 13²


UsK [U70. EAX ① 8] 2 fragments with frag. stamps. ^{fine}
orange fabric. slip gone PF

GSB

N - Williams no 27-29

No provenance [bk. Bristol Mus. F6611] Slip gone.

Netleton, Wills [Wedlake 1982, fig. 105, no. 57] Not seen
Attribution certain



(not seen).

CAERLEON.

Wroxall Villa, Somerset ^{Arch.} Antiqu. & N. H. Soc. 115 or 105

p. 49, no. 6. Rim sherd mortarium; soft, red-brown; similar in form & fabric to CVL RP 129. Stamp similar to Caerleon, Princ Field 1927-9, p. 78; 31.

Q. SASER

Lincoln (A.J. x M. 3.254 (26) no 48); = "on a palisade in possession

of Mr. Allis. Sentence by Mr. Rossmilt & edit.

? ampliata

SV. 1321, 106,

CARRIAGE TYPE

DVR

Caerleon [1954
N.M.W. 16K.; cutting MN(W) + 26.6.54] usual fabric; slip fairly
good; much white grit; end of flange broken but seems like 263-4 [Finds of P.]
54.389 B. P. II.

C.A.2.2:1c

CAERLEON TYPE

Caerleon [Pysg Field; Finds of Pottery p.78, fig. 68 no. 10; 32.60; (P.37) 91KNMW]

L-facing; usual Caerleon fabric + slip; white grit to c. $\frac{1}{4}$ in b.b.

Caerleon [Pysg Field; Finds of Pottery p.78, fig. 68, no. 12; C. 29; 32.60;
87KNMW] n-facing; reddish orange fabric, harder than usual; red
slip; no grit on fragment; probably no. 260;

D.F.V.A.

? Imitation of Caerleon Stamps

Birdoswald [Alley; 31.1929; Tullie House 55K] broken; soft, orange fabric,
no slip left; flange only left; sketchy Caerleon type - stamp
check on Prysg Field no 3

incomplete stamp S-W. England-Shepton Mallet, Exeter area; Caerleon
of Caerleon type

Hayes Farm, Exeter, HF 87 403. Flange fragment

disclosed throughout & probably burnt. Has had orange-brown
surface. Matrix, now blackish, is soft. Fair quantity of random
ill-sorted, inclusions, mainly transparent & white quartz
with some opaque black & white material. Has distal
beach.



Hayes Farm
Exeter



Caerleon (unless there is a unidentified
same as "7K/108K/99" (local source))

Site 67

Bear Field) Cowbridge [185] 6.7/106.4/050 1K Flange fragment Br. 3cm
Munsell 2.5YR 5/8

Fine-textured, (heavily burnt) pale terra cotta with thick brown-
buff core, moderate to few ill-sorted, gravelly & varied
brown inclusions. Whitish quartz frituration. Slip gone. Color may
be altered by burning. It is a much harder texture than Caerleon
commonly is. Sample kept.



θ

67/1064/050
Bearfield, Cambridge 185
IK

Unidentified Caenlon.

Cowbridge, Bear Field [Site 67. (228^K) 67/1358 SK] usual fabric. Burnt
softish, fine st., micaceous etc. orange-brown (5YR 6/6), with
fairly frequent, ill sorted, other inclusions composed of natural
iron compounds. No slip surfaces. Burnt. No truncation
surfaces.

UV



5K Condridge

67/1358 A524 C

Prob R-Face


DW:IC

DI:AN

Bulmore, Caerleon [76F/600/A 201 SF201 139K] Broken stamp

from new die. Drawn 3 lions. Slip ^{Red/brown.} survives. Fine-textured, orange-brown fabric (Munsell 2.5 YR 5/6 'red') with ^{very thin} greyish core merging. Much of the red/b. slip survives.

Stamp may be ^{either} ~~one~~ way up




76F | b0C | 2.20 |

139K Bulmore, Caerleon
probably night forcing

Caerleon

Carmarthen [M 81.2 1045 33728 36v] FF. Some
slip. Some burning. Shades from off-white outside to slightly
redder at bottom. Fine-t., micaceous etc. Dr. \equiv 18cm



UU

Fragmentary but clear

Campanthen [CCS 18 (281) 34979 1978 (std no (102)) 40K] r, face
only 1 patch of sl. ip survives. IRS. Decor fabric + interior
grit. Normal diameters

white slipped

Unidentified

Usk [U70 Doh(3) HK] v. facing. heavily burnt round spout;
fine orange-brown fabric, thick pinkish core; traces of cream
slip; much white quartz grit. Apart from slip looks like
Caerleon product. D. ?25 SW/G5 Stamp no. 12.

RA ARC retro

Fig 68, no. 46

CREATION TYPE.

Caerleon [Prysg Field ii, inc Finds of Pottery p. 78, fig. 68, no. 46; (P39); C 23;

T 3 x 7; 32.60; 95K NMW] L.-facing; soft fabric, brownish slip;
white grit.

Caerleon [Prysg Field iii, p. 78^{as}, no. 46 but not published; (P13); 32.60;
75K NMW] stamp faint; soft fabric, some slip; white grit.


D9A1

Not Fig 68, no. 46

Caeleon

Carmarthen [M1
CP&G [5871] 35756 34K] L-facing

Dr. 29. Hardly any slip survives. Softw., micaceous,
probably worn. Virtually no inclusions at X20. 1 v/b showing
on top flange (softwh. ? natural Fe oxide). Some white qtz
trituration survives




Caerleon

J.

Caerleon Museum Gardens. (David Zienkiewicz CMG 83 (S2) label)

(27K] Fine-textured orange-brown fabric; remains of distinctly maroon-coloured slip, fairly matt, on inside. Small to medium translucent to whitish quartz grit. Dr. 94 cm.


'Pottery from excavations on the site of the Roman Legionary Museum, Caerleon 1983-5' J of Pottery Studies V (1992)
81-109 + Britannia XXIV



O —

Not thought to be Caerleon
fabric

Caerleon [U.D. C. 27; S.E by E II. ^{NNW} 119 K] stamped along; somewhat
coarse brownish pink fabric with bluish grey core, and cream slip;
mixed grit; r/b., white quartz-like, translucent pinkish & brownish;
Form as Camerton, 379. Made in S.W. England, ? Gloucs.
The other side of the fragment is a drab pinkish brown throughout.



LAI

UNCERTAIN
Incomplete

Coeruleon [A. Lxxviii p. 186-7 f. 23, no 7] red ware with white slip. ? Scars



•77

Caerlaver
on. 4

V.FV01 ((TOARVS 2))

Caerwent [Newport 2K.; D2/73.] purplish pink fabric where fractures
show; hard, angular, variegated size., white grit to c. 2 ins. below
bead; whole molar; 2 pairs of stamps, 1 pair each side of sept.
? slc (P)



Επανειδομένη (Επανειδομένη Μ. 2K)

E



5" x 3" GUIDE CARDS

TOLLIT & HARVEY LTD.
KING'S LYNN

British made

Ref: 4810

5 016196 048103 >

EIPHNA|EYTYX¹² GREEK STAMP
Check References etc
Risingham, Northumberland (Mrs d) Antiquities, Newcastle on
Tyne Mus Accession no. 1956.340A Found in 1857
Ephemeris Epigraphia 1887 vol VII, no. 1179 with
bibliography; Bonner Jahrbücher exvi, 1907 pp. 2
2 ff. figs 2, 4.

AA³ x~~VII~~ M.DCCCC XX p 110 no. 206 says
Habitancum (Risingham). It was in the collection
of Sir Robert Cotton, most of which came from
Risingham. p. 295 drawing in AA² XII, 1887,
p. 295-6. Pencil note 'Primary fort, no earlier' PTO

Translates as 'Happiness to weare' — needs check
than A.D. 175 M. Bishop 1993'

EIPHNAI EYTYXI GREEK STAMP See other card.

Probably is Risingham but was unmarked when I saw it.

Provenance unknown [it used to be thought to be from Risingham]

EE VII; 1179 ad C. n. 1334. 1335; Proc. of Newcastle Society of Antigs².

III p13; AA² XII p. 295; PSAN⁴ 6 p. 165 + ~~PSAN~~² AA³ XVII, 110 no. 206

Kings College Musen. Box 365 (11/2/3), 1956.55. A] very deeply cut-out letters, possibly a metal die used. Coarse + heavy like a Verecundoid anabasis; red-brown fabric thickly mixed with brown + white grit; possibly no additional titration grit. A.

Akhmin [cemetery dating 4-6th c. Die fröhchristlichen Alterthümer aus Achmin. Strasbourg. 1893. Förster (see his Reallexicon v. 940 fig. 652) (AKHMIM, Egyp)

EYTXVIC or WC
EIPHNE W

GREEK STAMP

Bought at Calymos [British Museum ~~ex~~ in Greek + Roman
56.8-26 258.6 K] E 194. Same form/fabric
as the Risingham ex.

Strasbourg, Salzmannsgasse [47245] stamped across
the rim. Very large vessel. Can't really see fabric
but Brenda M. Dickinson who reported on it
thought it was bricklike & pinky orange
with darker slip. No tinteration grit visible.
(An other example noted at Achmin-Stadt, Upper
ACH P TO

Egypt) Siebold, Bonn. Jahr c xvi, 1907,

pp. 1 ff. figs. 1, 3 with bibliography cited.

Hesperia xxxvi, 4, 1967 nos 160 & 161