

D

DC.VER

Middlewich [38°38' N of new sewer, 11K] Diam 28cm. L. facing.
worn in lower half. Fired cream at all surfaces but pink
in outer half of fabric; slightly powdery feel. Inclusions:
very ill-sorted, tiny to medium; fairly frequent;
transparent and pinkish quartz, opaque black;
red-brown silexite. Interraction: mostly gtz, some
black and red-brown. Slip fired & buff brown on
inside but cream on outside.

DC·VER

Ribchester [RB89 7354 74 60K] fragmentary stamp on one
small fragment which does not join the 2 other sherd^s from
same pot. Cream fairly fine textured. Inclusions, frequent:
mostly small to tiny but ill-sorted, mostly quartz with a few
orange-brown and rare black; Few random large inclusions,
probably accidental. Interruption: mostly quartz including
some pinkish and some ? greyish, few red-brown, rare
opaque black. Dr. 28 cms. Cacking under the flange
where turned down vertically.

DC·VER

Wroxeter [620 W.B. 78] I. Facing Very hard pale
brownish cream fabric with pink core, tempered ^{moderate, ill-} ~~with much~~
~~seized~~ ^{many greyish little red brown} fine grit; probably a slip but same color as fabric though
fired to orangy brown color; crack under flange;
interior grit - abundant originally but quite a lot missing.
mostly ^{white angular} grayish but with some r/b & blackish grits. D = 2³/₄ ins
West midland in every way. A

DC VFR

Wroxeter [1914, fig. 3, no. 48, p. 57 & p. 60; 111K; M128] hard, smooth orange brown fabric; white and brown medium grit. Ty. II 46 A

Wroxeter [Rowley's House; E26; p. 298 fig. 67, no. 89 = p. 299 & 279; 19K] A
Fine, cream fabric with buff slip and pimply surface; grit colourless, brown, black + grey; slip orangy in places. Most probably West Midland. D = 12. A. [3 or 4 un stamped fragments at site which were thought to be W. Midland imports + perhaps related to BF 26-30 are fairly certainly fragments of DC VFR]. Spt. v. shallow.

"In filling under original floor of East Room 2 i.e. before A.D. 130,

DC 21.1

Wroxeter [Rowley Ho. E 26; p 298 fig. 7 nos 4 + p 299 fig 79.; 19K] buff fabric, smooth,
hard surface, very pinkish in parts (?burning); prolific, smallish, medium +
small brown, grey, white gilt (?flint.) 2 stamps with spout between.

Wroxeter [~~1944~~ ^{Unpublished.} fig 3, nos 4 & 1257 + p 60; 48K] Buff fabric with orange slip;
prolific red/brown, white, black gilt up to c. $\frac{1}{4}$ " below b. of head; gilt worn 2 stamps.

Slack [YAJ pt. 101, vol. xxvi, p 70 no. 3] light brownish buff with reddish buff
surface, some gilt in fabric; varied sized red gilt up to rim, 2 in stamp.

Hereford Mus. [2K; 1803; [?]provenance] pinkish cream ware with tiny
varicoloured fragments in fabric; medium, opaque white, 1 red fragment, gilt
to c. $\frac{1}{2}$ " below head.

in D.R.V. out

Wroxeter (Rowley Ht.); 19K; 12
r-side.

VER

L-side. 19K

in EDG. out

48(?)K.
1.8 spout
Wroxeter.

D.R.V.

B.3. Slack

17

VER

Hereford Mus. 2803-A.K.

Q. D. VALENTIN'S see RATISER - same horizontal ridging for
spout.

Wroxeter [fig. 7, no. 2 + p 46] Type 66. Only 1 stamp published M78, 44K.

[M106, 41K]; orangy buff fabric with yellowish buff slip. Flange fragment.


[M78, 44K]; pink/orange fabric with ~~buff~~^{thin} slip. Medium sized white, +
~~black~~^{red} brown grit; grit worn, some missing; more prolific
in lower part getting scarcer to bead. Spout (45K) large.

[no. no. 45K] ~~Fabric as 44K~~; between 2nd + 3rd Floor; stamp badly
applied. on piece; horizontal ridging for keying of spout; D = 11 1/2".


Chester [no provenance, Box 115 165] pinkish brown fabric with buff core; no grit
survives. Stamp as Wrox. M106.



H78, 46K Worcester



M106, 41K Worcester



Worcester 46K — horizontal ridging

far keying sport as RATED).

These ridges are not slashed but shaped with instrument or with fingers on moving wheel — probably instrument not fingers.

Q.D. VALEN 5?

Wroxeter [WB ⑨2] 4 163K] (likely tube r. facing. some wear. Dr. 27cm.


Hard, fine-t, pink-brown fabric (2.5 YR 6/6). Inclusions: fairly frequent, small, mainly quartz, rare black (tiny). Green slip; no triangulation on sherd. my A

DAB:

Verulamium Region

Gadebridge Park Villa, Hemel Hempstead, Herts. [: 99; D. S. Neal

B1 | 12 | 69.] flange; r. facing. Somewhat abraded
surface; sandy, creamy buff. Joins H.H. 65 48/58 F 25
orange-brown, + grey, smaller grit rather sporadic



ndv
17

DAGOB! — DAGOBITVS + DAGOBIVS (HOLD) ETC

Stewart Rodd, Southampton [Plaisterum, Cotton & Gathercole p. 97,

fig. 21 no. 6 + p. 98 r.p.b. Southampton M.] Stamped along. Read as
DVC'ORI. In unusually fine thin littering. S.R. 31⁴. Very slightly sandy,
cream fabric with thick pink core (salmon), tempered with fine
grit - it has a friable look, but unlike Oxfordshire. There is
fine cracking at right angles across the flange all the way
round. Abundant tituration grit down to top of head, probably
all flint-grey & white, some large & medium but mostly
very tiny and crushed up together rather like the Wallis field
mortarium. D = c. 3½" looks like a waster. c. 1/4" neutron A
G.B. with similar profile to the stamp.



Pinkish buff patches on flange?
remnants of clay. ^{antimony} unknown

Southampton

Its purpose - probably at Richborough Rochester v. uncertain elsewhere.
The stamp is unusual in its small size, the spidery
lettering & its horizontal position - The fine grit in the
background produces an effect rather like a fine
sandpaper.

No agnion flange.

Probably local.

c. 55-90

DALIXIVS

Cameron [NMA. 64K] stamped along; huge & hefty; soft, cream fabric;
moderate, medium & small, brown, grey, black grit toward head;
worn;

Brookdale 1461 [13 # 75 146 + A longitudinal strip joining 1.] On

APPENDIX

DRAEES

Socie Architects of Canada 1999 162-163
Paul Wade 1998

Waterloo Street
burn. From Wood cut for the new bridge. West side of
hill quarries Mr. Burn flatback stone (thin). Outer surface
of quarry lime stone flatback stone (thin) thin. Quarry stone
differences below it. Cream light yellow thin thin thin
quarry lime stone flatback stone thin thin thin

DARES:

if *Aeneis* Bk V, 270 Mad T, 9

Hambleden Villa, Bucks. [Arch. 71, p. 188, fig. 19, no. 13; 16K; Aylesbury M.]

39' N of N.E. angle of Enclosure Wall. Fragmentary stamp on heavy sandy, grey fabric burnt to very dark grey in parts and on large part of surface. Some grit on surface - largish; small brown & grey grits inside. Sketch
London [Guildhall M.; Pl. A. 2545; 82K] L. facing; sandy, pink fabric changing to cream, surface smoothed; discoloured in places; largish to medium, r/b, grey, black grit; pitted where grit done; 10 bread and a few on top of flange. From 1913 excavation. Should be Verulamium fabric.

DARRIUS

See ~~CASPIRUS~~ OASTRIUS

BROCKLEY HILLMIDDLESEX

SATURNIN VS I	Exc. 1953 / 4 TLMAS (1956) p. 52, M. 17 / 8 Sull. 54.03;	Harrow 15K
FECL OF SATURNIN VS	1953 / 4 Exc. TLMAS (1956) p. 72 fig. 9; M. 9, Sull. 54.03;	Harrow 35K
SOLI VS	1952 Exc. TLMAS (1954) p. 275, fig. 8, W. 2, XI no. pt. III.	Hendon 23K
FECL	? FECI 1952 Exc. TLMAS (1954)	

DATICIUS & DEDICATUS

Box BS 14. 2

Twywell - Thrapston area, probably. [Northampton M. Acc.no.

D.33/56-7 "Charlton Pot": Provenance not known for certain. 9k; sandy, cream fabric with grey core. Inside worn; pale orange-brown grit and white; origin unknown - ? local. Probably a name stamp with border. Surface discoloured by burning in parts. L. facing. Fabric reminiscent of Vedicatus.

Chester [Grosvenor M. 48k] slightly sandy, white fabric; various yellowish, brown + white grits.

DEC M = 392K (?readina)

Corbridge MD 110 ?S. 345° not seen? no Y.S.B.

Artfully ~~decorated~~ ~~but~~ ~~not~~ ~~to~~ ~~the~~ ~~stage~~,
perhaps 5-10% after F₉ Uncertain

Long Bennington [50-LB.76 GB. 25] Cream fabric, abundant inclusions
quartz, red clay pellets and streaks. Tribulation grit quartz
red-brown haematite? and slag? Brown-orange slip.



Long Bennington
LB 76 GB 59 2k

DECANIO

Scotland.

Bar Hill [Macdonald p. 406; F. 1936.4.78; Hunterian 6.1K] fragment only;
~~brownish cream~~ with other surface.
pale buff, soft fabric; worn.

DELA. OF. C. ~~of DECANIO~~ of DECANIO DECANIO

Lancaster (Watkins, R. Lancs. p. 187); Check it Mayer collection one.

DECANIO

Probably hawkesbury but marked hondar in Mayer Collection.

[2843 M 18K Merseyside ~~Collec~~ County Museum]

Hard, pink-brown with cream slip; whitish quartz &
red-brown mostly but some grey & white. P TO

Walton-le-dale [WD 81 435 (87). 10K] ^{Free-textured; micaceous} Pale orange fabric
(5YR 6/6) with darker ^{pink} ~~orange~~ core, sparse inclusions
ill-sorted quartz and black ^{+ red-brown} ore fragments. No trituration
survives; cream slip. (Fabric 39) Dr. 27 cms.

Mayer Coll. contained some han caste material.

V.V. worn

Witlesspool [41°-3'02; 30K] f. stamp each side of spout, both faint; has
 abrasive marks; pinkish buff fabric, with pink core; red & black grit
 survives, only near bead. D. = just over 10 ins. ~~Restored~~. Complete D = 25¹/₂

Lobridge [^{Unpublished} M/46/2+; T.B. Wall Site 4; 76K]; slashed for addition of spout; hard, red
 fabric with buff slip; medium grits, grey, v. l., ^{white} brown to near bead. D = 10¹/₂ ins.

Hanover [J.C. xxiv, 1904, p. 54 no 3; 6K; Co-op. 18] r. facing; large portion;
 compact, very smooth, pale buff fabric with buff slip, brownish to purplish patches
 near spout due to firing; most of grit gone through heavy wear; striation
 marks; smooth, brown, black, whitish, smallish grits; just below bead.

Hanover [ditto; 6K] whole bowl; heavy striation; restored; hole in bottom; fairly smooth,
 pale brownish buff surface, cream in spout part of spout; few, brown white grey grits; ?slip:
 $D = 26 \text{ cm} = 10 \frac{3}{10}$ "

Lancaster [Trans. L. & C. Antig. S. xxiv p. 54, no. 3.] 2 other examples published; not found at Lancaster Museum. "On the ruins of four vessels of progressive size, apparently a 'nest'." J. R. Lidster took a plaster cast of one he handled in a job-lot offered by a dealer, Robert Clough.

From Railway excavation 1849?; sandy, reddish fabric in poor preservation; flange + bead - piece.

Ribchester 4 pieces Softish pinkish brown fabric; traces of white slip; red sandstone, grey flint, white crystalline grit.

DECANIO

Ribchester [RIB 78 BBY 2 46K]. L. facing. About a quarter,
m. in orange-brown fabric containing quartz + some r/b tempering. The basic
clay is a softish one but the tiny grains of quartz or sand make the surface
~~absor~~ abrasive to the touch; whit quartz + r/b + very occasional
black titration grit small to medium. Dr. 26.5 cm. Traces
of wh. or cream slip in angles of letters.

DECANIO TWO LINE STAMP

Ribchester [P. Webster, Greenside] Soft pinkish brown, fine
fabric containing fine sandy particles; red-brown, white
- few grits only or fragment traces of white slip
surviving only under flange. 27 cm.

Ribchester [RB 89 19 (context); SIF 6551 65K] Dr. 27.

stamp worn & perhaps not well impressed. Powdery.
Orange-brown fabric, powdery, with grey core which
merges into o/b. Inclusions: fairly fine textured;
v. moderate, ill-sorted, rounded, quartz, black & red-brown
only one quartz inclusions grit on small fragment. Softish.
Traces cream slip.

DECANIO

hancaster [LB 88 5720 195 33K] Utacing. Hard,
fairly fine textured fabric; probably had cream slip. Cream
fabric with pale pinkish core [Munsell 5YR 8/3 pink]
Well-worn. Inclusions: Fine-textured fabric. Very
moderate, almost invisible quartz; few r-brown ss + few
large + medium red-brown. 330g. Diam 33mm. 23.5%
Inturation: quartz, red-brown and rare black. Smooth
Fabric unusual for W + W (e) date. Its surface is fired
to cream, but fabric is the pale pinkish core within inner core of
cream.

DECANIO

Hancaster [h.B9.2 - 11659 - 7.30 - 34K] L-facing. Cream slip.


Smooth, very fine textured cream fabric, Cream slip.

Orange-brown, [Munsell 2.5YR 6/6 \leftrightarrow 'light red']

Inclusions: few, ill-sorted, quartz, black + red-brown.

Intercalation: quartz with few orange-brown sandstone.

90g. Diam. 290mm 9%. Worn.



DEG F

NB Form as early as AD 80

Carlisle Millennium Exc. [CAR00 MIL 5 7350 269K]


L + r facing. 900 gms Diam 280+ 44% Hand,
white, fabric with cream slip fired at brownish buff in
parts. Inclusions: fairly frequent, smallish to tiny, quartz,
orange-brown and less common black. Interspersed grit:
quartz, black, red-brown, grey (? quartz): small to
large. Appears to be combined with a coarse concentric
scoring. The scoring definitely there even if rough +
r little in upper part. At least 2 grooves scored a
flange too. Quite heavily worn. And faint
conc. scoring visible where clay for spout has come off.

NB

Has Ver characteristics (is profile + conc. scoring).

DECA

TYPE STAMPS.



DECIMA

see also DECUMA INVS

See AGESTICVS.

Corbridge [AA⁴ xxvi p. 189, no 47; S. 150 ~~xxxiv~~ ① c/xi/47; 133K] r.-facing.
 very compact, cream-white fabric with buff surface; some r/b, + black
 grits, sparse, survives. D=11½ ins.


Corbridge [AA⁴ xxvi p. 189, no 47; S. 335; 1911; ~~xxxiv~~, ① c/xii, 47; 134K]
 l.-facing; very compact, fine-grained, hard chalky fabric, much of grit
 worn away; large to small, r/b, and few white + grey grits, fair
 amount to vr. b.b. D=12 ins. "Cheesewired" base with great
 groove in middle of base. Sketch.

Corbridge [AA⁴ ~~xxvi~~ p. 189, no 47,

Attributed Decanurus Diec

Hardknott [815 Bag 18 H 68/11 10K] L.facing] E.P. [

Heavily burnt. Powdery, fine-textured pinkish fabric
fused to cream at surface. Inclusions: random, opaque
black (small), rare quartz & some red-brown inclusions.
Intercalation: included, quartz, sandstone. Dr. 25 cms.



DECANIVS

Caersws [CS18/361 13K] 2 joining sherd s. l. facing. (Hard, textured
pale, brownish cream with dark pale grey core (2.5 YR 8/4
cone: 10 YR 8/1); inclusions: sporadic, ill-sorted, quartz and
iron slag? May have a self-coloured slip. Intercrystalline grit:
frequent, relatively well-sorted, mostly transparent quartz with some
white + some pinkish, some red-brown sandstone + some haematite.
I.R. Dr. 96cm. Very smooth.

Die 6.

Caersws [CS18/203 3 joining sherd s. l. facing. Outside very
pitted. Smooth but powdery surface. Fine-textured, orangy buff
with sandwich core buff with pale grey centre (5 YR 7/6 outside;
2.5 YR 7/4 with cone 2.5 YR 7/2) Very sparse r-b slag +
self-coloured slip but tends to also orange-tinted-brown on outside

only - self-coloured on upper and inner surfaces. Groove below bead continues round under sport. Interruption grit; mixture of quartz & red-brown sandstone probably same slag. (Probably more sandstone than quartz. Dr. 28 cms Different vessel. i.e. 1. Patches of saffron-like orange-red/brown slip underneath flange

DECANIUS

Colbridge [S. 64 Site M & 92 K] r. facing; stamp broken and rest
 badly damaged; flange + spot only; Near enough to 55 T; hard
 buff fabric with thin pink core + red-brown to cream surface. E

Worcester [BW/M ; Worcester M. 9K] stamped DEC each side
 of spot; water cracks - fine - from back to front of spot;
 buff fabric with orangy slip; much white, brown + black grit.
 stamp complete. Die as Bindorwald (?).

D

C

Chester [55K Grosvenor M] Attributed.

~~1870^{ms}~~ [200, u 70 DAR ①, 12K] Off-white, softish fabric, some
 crudish white + brown grits. Mostly worn away; stamped b/t sides.

C




DECA. A

Wroxeter [1914, fig 3 no. 59, M 118, 42K] slightly sandy, creamy fabric with pale-buff slip; rather sparse, medium and large, white, red brown, black grit. Type 58 A

Wroxeter [Rowley no. E 16, 18K; not pub.] pink core changing to buffish cream, may have similar slip; prolific, varied sized, white, pinkish and brownish grit (sandstone) 1 stamp each side of spout. A

Wroxeter [Rowley no. E 16, 63, 24K] ^{unpub.} pinkish buff core changing to grey buff; pale buff surface with faintly pinkish tinge in places; prolific, varied sized red (sandstone), white (or pinkish white) grits up to bead. Rim Wrox. 58. 2 stamp. A

Wroxeter [Rowley no. E 2. P 20, 38K] coarse; greyish core changing to drab & greyish cream with orangish buff slip. Moderate amount, medium, brown & white grit. At 65 H.C. 130. A



DECA B

Wroxeter [i fig no 229 p.68; ii p. 47 no 22 (b) & (c); iii p. 61 no. 22]; 5 exs. (not seen)

[M10, K19] I, fig 16, no. 22; hard pinkish buff with some tile in fabric; light + dark brown grit.


[M 63, 20K]; site V. orange fabric changing to creamy buff on inside; pinky orange slip, rather reddish on outside, broken near spout; moderate amount of medium and small white and pinky white and black grit.

[M129, 21K] Pit 70 Buff with slip; flange fragment. III, p. 61, no. 22.

Wroxeter [913, fig. 17 no 45, M56, 31K] creamy to pale buff, hard fabric, buff slip, burnt in most parts to orange or black + red. II, fig. 17, no 45.

Wroxeter [Site Museum no. no. 114K.] sandy buff fabric, red-brown on rim; large brown + white grit. (III, p. 61 no 22, second mentioned?)

II, p. 47, no. 22, C (site V) CR not seen.



DECA

This thought to be DECA [i.e.] see drawing.


Wroxeter [fig. 3 fig. 7 no. 32 + pl. 6; M 14, 46 K] hard, buff: grey core with smooth winter surface; blackened on flange; white and brown + black grit. ^{be} Type 57 with slightly high

Wroxeter [1913, fig. 7 nos. 3 + pl. 6; M 51, 47 K] creamy buff, hard fabric with creamy slip; large, fairly prolific red-brown, white, black grits 1/2 - 3/4 from bead, stray st. ^{C Type 46}

Chester [Box 115; 18 K] hard, cream fabric with pinkish cream core (peach); medium grey and brown grit. Check A in folder. ^C

Chester. [Box ER; 29 K] slightly orangy buff with orange-brown slip; brown + grey grit. ^C

Wroxeter. [See this. 15 K M 74] pale buff fabric with buff slip. Rims frequent. Wroxeter [See this. 94 K 1973] pale buff fabric with buff slip; v. probably same mortar as 93 K.



DECANIUS

Wroxeter [M614 under channelled hypocaust Site VI; 123K] v. facing; roaster
crack through stamp but quite usalde; slightly sandy, dual cream fabric
with peach-coloured core; moderate, largish to medium, hard, whitish, +
brown (s.s.?) to near bl. ; orangy slip, very pale on outside; top of rim where
obscured by upper mortar purplish; v. close BF. 54 C D

Wroxeter [130K Site Hut; no M.no] stamp v. fragmentary; D, bottom (E(?)), +
spacing of border agree completely with DECANIUS; dual but fabric with
grey core; brownish buff surface; moderate amount black, grey grit to bl. to
BF. 54/58. The Reading uncertain but probably Illegible A.

Birdoswald F. [In S.P.G.'s store Newcastle.. Unmarked with label? Birdoswald. 21K] soft
cream fabric; multicoloured spout. Almost whole. PTO D

Shows a stamped piece in Bld. box no. -ark. A fine
brown cream; cream slip; white, brown, grey & black;
small grit.

DECANIVS

C.



Wroxeter [Site Mus. M 143, 99K] brownish buff fabric, orange-brownish surface; large and medium red-brown, white, black grit. C.

Wroxeter [Site Mus. M 94, 107K] Buff fabric and surface; flange broken and too near spout for good drawing. C.

Wroxeter [Site Mus. M 79, 98K] greyish white fabric; cream surface, fairly prolific, large + medium, white, red-brown, black grit. 1 stamp each side of spout; marked difference from fabric of others. C.

Wroxeter [Site Mus. M 67, 95K, Site vi]; hard, buff fabric with orange buff ^{surface}; large and medium, white, red-brown grit up to head. C.

Wroxeter [Rowley Ho. M 57, E 986; 44K] buff fabric, surface, large + medium, red-brown, white, black grit below head. 1 stamp each side of spout. Vessel complete or nearly so. C.



DECANIUS

— 15K

Alcester [Hughes, A.L.C. 61 T 1 XVII Pit 2] L. facing; (hard, fine-t.,
orange Munsell 2.5YR 6/8 no inclusions visible) more v.
red-brown fabric with buff slip; few large to small grits, brown & grey
quartz Dr. 2.8cm. + white grit. D = 11½". This is entirely different fabric from
the usual one - similar to the Wilderspool one (or West
midlands). Very worn.

A

Wroxeter [WB 50 70; 154K] (S) J Evans. L. facing. Hard, fine-textured (cream fabric;
medium-sized & small-sized red-brown & grey grit). Almost certainly
DECANIUS + die D. Could be same pot as 1891X Core galv. Dr. ? 24
Inclusions: few small quartz. Self-coloured or cream slip. Different pot.

GERANIUS

B

Birdoswald [D. Charlesworth] N-facing. Very ^{hard} brownish buff fabric, tempered with much dk & light grey & red-brown grit, with brownish slip, white & grey (flint), and red-brown, & quantity-like (white) to structure grit. D=12¹/₂". S. Gate topsoil

A.

Carmarthen [H6. ⑤1 m⑤1 69.] v. facing; softish cream fabric with pink core;

(D)



Büdewald (DC)

DiēB

Archaeo (39)

- ✓

die I (A)

Wroxeter [WC 77.C 600] 200k.G. Hey + Peter White] R. facing, CRS,

micaceous,

burnt slightly. Fine textured, orange-brown fabric, unusual
for this potter tiny inclusions of quartz just visible ($\times 20$).
+? more black
Included brown? ss.
No trituration grit survives, heavily worn, traces of cream
slip. Dr. 27 cm. This is a real orange-brown fabric with cream
slip. This vessel and Alcester 15K (Hughes) are the only
Known vessels of Decanius in this fabric.

DEC/ ?? DECANIVS n DECATVS etc.

Brecon [p. 246, no. 7; B. 25 M. N. cut across via Decumana. In S.E.

NMW. 50K] r.facing; buff fabric, surface dark, brownish buff, much, grey, whitish, small, grit. E

Wroxeter [1913 p. 45, fig. 17, no. 32 + p. 16.] Stamp not seen - now missing, but must be from above die rather than DECANVS (DEC)

Worcester [Marks' Spencer's Site] hard, cream fabric with some grit in it; buff slip; brown + grey grit. 5K E

Worcester [D. Atkinson unpublished W.P.D. 21.5 Kenyon] L.facing; hard, cream fabric with pink core; pale buff slip; black, brown + grey grit. Die as 50K Brecon

DECA.

A

Wroxeter [Site Museum no. no. 113K] coarse white fabric with fragments of tile in it; sandy.

A

Wroxeter [Site Museum. M146; 67K] buff fabric with drab buff slip; medium, black + white grit to wear head; D = dia. as 32K.

F

Alcester [AIC. 61 T, XVII Pit 2. L. facing. Hard, fine red-brown
H.V. higher, Birmingham) letter 15/3/61; red-bodily; buff
color-coated; mottling + drawing; few large to small grits = brown + grey + wh.

Worcester [H. Sander; letter 28/1/62; 8W(2)] probably L. facing; fine,
hard, ~~brownish~~ buff fabric with cream slip; inside surface
damaged + grit gone; stamp poorly impressed. D = c. 14".

E

* Thin in a real red-brown fabric.

DEC ANNS

1+2

Wroxeter [Site Mus. M147, 97K] buff fabric changing to orange with orange almost red surface; flange fragment.

C D

Wroxeter [Site Mus M31, 100K] buff fabric, orange surface cf. 96K for similar rim

C D

Wroxeter [Site Mus. Mus. M149, 96K] buff fabric; orange surface; large & medium prolific white, red-brown grit.


C

Wroxeter [Site Mus. M81, 102K] buff fabric; orange-red surface, blurred stamp of 96K for similar rim.

C

Wroxeter [Site Mus. no. no. 103K] cream buff fabric with moderate amount, large and medium, black, white, red-brown grit; much eroded; flange & stamp broken, ?like 97K.

C



Worster Spec. No. M 147, 97K.

? ? DECANIUS

Do not count

Wroxeter [WB 83 + 59 J. Evans. 247K] Dr. 31cms. Hard, deep
cream fabric with brownish slip. Inclusions: fairly frequent, ill-
sorted, mostly quartz some red-brown (not stag horn like). A close
border like Decanius d.s. p 30 3 no 13 + 18 ??

break



247K (57) Wroxeter WB (83) +

SF 57

hard die 5(E)

Wroxeter [WB 98 52. 188 k] CRS, slightly burnt. Cream fabric,
 with thin pinkish layer beneath the surface, moderate
 inclusions of quartz, sparse orange-brown fragments]. No
 titration grit survives, but a few quartz grits on
 the flange. Dr. 25 cm.
 p 303, no. 1b

Wroxeter [WB 88 IV 3] 230 K. Fragmentary. Burnt throughout. Hard Die 7
 - decupation possible. Some quartz titration. 65 J. Evans. Different vessel. Lfac.
 p 303, no 15

DECANINS

L.facing.

die 6(F)

Wroxeter [WB ⑥7 14. 189K] CRS. Fine-textured, cream

fabric, very few inclusions visible ($\times 20$), tiny ^{traces,} opaque white fragments and red-brown fragments. Trituration grit quartz, traces of a cream slip. Dr. 26⁵ cms.

~~probably~~ left facing. Different vessel. ④9 J Evans p. 303 no. 12

DECANIUS

Inclusions: some minute, few larger quartz
+ red-brown.

Wroxeter [WB 84 + 232 K] FF. very smooth ^{no. 815 ✓} J. Evans 92. v fine-textured,
hard, ^{cream fabric} very smooth. Different pot. D. 3. (92) J. Evans. p. p 30³, no 14

Wroxeter [WB 53 + 244 K] ... facing. J. Evans 93. Probably D. 3.

Hard, very pale creamy brown with paler core. Inclusions: fairly frequent,
quartz, rare orange-brown. No intercator survives. Dr. 30 cms. d 3?

Pale brownish slip. Different pot. p 303 no 11

NcT

239K WB 86 + 2 joining sherd

240K WB 12 + " — v. facing

241K WB 98 38 vv fragy

242K WB 83 +

243K WB 83 +

244K WB 53 +

245K WB 98 + ? edge Belemnite

246K

DIE CAN IVS?? Possibly - Does not fit the certain Die C.

Kinderton, Middlewich [Mr Middlewich M] hard, fine-grained buff fabric
with buff surface; abundant, white + grey, small, medium, large (quartzite?)
grit.

Wroxter [Dr J. G. W. Big S. & Baths] same die as above stamp.

DEC

CLEARING

Chester [Museum &c]: cream fabric.

~~7 NOV DECANO~~

Bart hill [Hunterian Mus]; — DECANO.

NO winter, good

N.B. Dies re-lettered.

A, B, (as before), D (DEC), C DECNI | E ~~DEC~~
E DECANIUS F DEC (plain border).

F

L. ATISIVS SECUNDVS cf SECUNDVS

C XII 5685. 5

C XII 5685. 38 : Annency


C XIII 10006. 12

C XIII 10006. 13 L. ATISIVS
SECUNDVS :: Lyon

Bontae nr. Vienne probably - ATISIVS SECUNDVS.

Same ligatures of NDV ..

1. P. Beekley
Decanis



? Decanis

G.W. Worcester

Bldg. s. of Bath's

c. LARFORD.

+ Worcester I, no 18.

DECANIVS

Raven glass [RV77 OC2 4K] Slightly abrasive probably due to added sand gritty particles some very fine; much transp. quartz + some in fabric; quartz + v/b grit; the v/b may well be haematite + are soft granular frag greyish cream. Cream fabric with pink in core near to inner surface. Phase 3. Residual W. Potter 1979, R. in north-west England, Fig 47, no 138 + p. 122.

DECANIVS

SE

Watlington M [68'09.4. no prov. probably Willespool. N.W.L. facing];
rather sandy; light grey core changing to reddish orange at surfaces; sparse,
white & red-brown grit to b.b.

B

Brecon Gaer [unpublished. B. 25. Ins. E; NMW. 51K] r.facing; drab
cream fabric with tiny grit, r/b. in it; much grey, r/b., and blackish
medium grit to near b.b.

C

Brecon Gaer [unpublished. B. 25; B. patch by intervallum road, W. gate with
31] NMW. 53K; r.facing; softish, cream buff fabric; grey grit;
stamp very worn; B.F. 58 but head lower. Probably DECANIVS -
too worn for reading to be clear.

C

DECANIUS Spout of 20K in a pushed up one sloping back in
noff¹⁰ profile.

Carmarthen [CM 81.2 1067 33533 20K] v. facing,

Dv. 26 Dv. adjusted. V. hard, overfired. 4 joining
shards. Fabric almost sintered. Brown buff with thick
mid-grey core. V. few inclusions, grey & black, apparent.
V. fine texture. Inclusions grit: mostly grey, some v/b
rare black. Right, half a sp. survives. (half was there in
New)

Carmarthen [CCS 18 385 30937 21K] (v. facing due
to no 18)

Different vessel. Stamp poorly impressed with plain
border like 6. 7 joining to other shard. (old no. 777)

Dv. 27a Inside mostly flaked or eroded away. Sandwich
See A for cross-clashing for added clay for spout.

fabrie brown-fuff surfaces with ~~some~~ salmon pink
+ internal brown-buff core. Soft, v. fine textured
few gr., black + rarer v-b inclusions visible. S-colored
intercations: quartz, black, v-b. Neuchâtel (Lb e6) (7)

20K 9. small wavy cracks transverse on head.

DECANIVS

Bardon St. Manchester [8 BAR03 Area 6 Context 54 17K] Flange

fragment. No 15 (ctx 554 joins) 12 (ctx 554 joins) 110A (ctx 54) joins; 3 body + base sherd in ⑯ are from same vessel; also nos 59 (ctx 922), 83 (ctx 54), 91 (ctx 54) and 119 (ctx 54) are from same vessel. All fragments suffer from accretion and discolouration. Body of fabric is brownish-orange, fired to cream on all surfaces, with some also silvery greyness beneath the cream. Inclusions: moderate to FF. grit-sorted, tiny to large, quartz, opaque black & red-brown. Interruption: mostly quartz, red-brown material, ? slag and a pale yellowish-brown material. Diam?

DECANIVS

mod to fairly frequent, qtz & orange-brown, mostly med. sized, occ. ill-sorted, rare large
large brown (clay)
in clumps

Alcester [65. H II 1.1 31K] Hard, creamy buff fabric containing
quartz sandstone + tot. v/b (hard)
grit; (buff slip; medium-sized, white, red brown and grey grit.
Burnt at outside of flange on top before fracture D = 1½" P/C

(38) S. Evans p302, no 9 facing. Hard. Slip fabric = cream

Wroxeter [WB 44] 25. 1966. (23K) sandy yellow sandstone
inclusion: fairly frequent, ill-sorted, rounded quartz, rare red-pink
buff. Body cream w/ small pieces of angular grit: no temperation
some quartz. Interlayer: one art. grey & iron-stained. Slip worn away inside
gilt surfaces. Scratch. See and rubbed B.M.I. Dr. 3 cm. Difficult

Gloucester [VC2 Bernard Reaves] Hard, creamy buff fabric w/ thick pink
core, and buff slip. Fabric tempered w/ added grit; red-brown,
white & grey interlayer grit. Partial compression. D = 1½" P/C

DECANIUS

Gloucester [46/74 III (452) 19K 10 fragments with (445) as well] stamped
 each side; poor impressions. Hard cream fabric with white,
 red-brown or grey titration grit. Carolyn Highway. C
 Seen 1975. ~~large~~ portion.

Archive (36) Wroxeter [WC 77 A 112 (227) 199k G. Hey + Peter White] FF
 Hard, fine textured cream fabric, few ^{small} ~~tiny~~ inclusions of
 quartz and orange-brown fragments. No titration grit survives
 no visible slip. Too fragmentary for dr. Different pot die 3.

Wroxeter [St Johnson via P. Ellis Jan/F. 2000 WC 79 (4) 253k]

modern break, 60g. Diam 27cm 8% hard cream fabric with
 tinged with pink near the underside. Ill-sorted, fairly frequent, random

inclusions: quartz, with ^{some} black slag-like & few orange-brown
buff - cream slips. no trituration survives. Probably
lacking.

Die 2

DEC . .

F

Wroxeter [1913, f. 17 no 33 + p 46, M. 66, 3.2K] greyish white fabric with buff surface; F
burnt purplish brown in parts; black + white and pinkish brown grit; Type 46.

Davies Coll. Found in Barn (?) Swan St in passage
Alcester, Warwick [Nov. 1921, 8K Warwick M. pencil writing on the pot, could not
read] under a tobacco shop.

drab cream fabric and surface; prolific, rather rounded pebbly grit, white,
red-brown (often), black (few), grey or greyish ab. c. $\frac{1}{2}$ - $\frac{3}{4}$ ins. l. b. b. ; r. facing. F
^{Die as above}

Penydarnen Park [Arch. Camb. 6 ser. vi, 3 (1906), pp. 193-208] no i P. Suggitt.

"Complete vessel; much restored; smooth buff fabric, remains of darker wash;
outside diam. $10\frac{1}{2}$ "; base $5\frac{3}{4}$ "; abundant, small, black + brown grit".

In Merthyr Museum. (grey flinty & some brown) F

DEC

M66. *Leucosoma*(?) *Brachy*?

DECANIVS

C

Pen-y-darnen Park [Arch. Camb., 6 ser., vi, 3 (1906), p. p. 193-208] P. Suggitt. 3

"Marl-cream... largish brown-black grit, partly scoured out. On public
display": Cyfarthfa Castle, Llanthryr. Check this? entered
? die time?; ? die C

DECANIVS.

C

Wroxeter [Dr. J. G. D. Bdg. s. 27. Bath] I feel sure this but not seen
of corresp. file for card & drawing.

Brecon [p. 24. b, no. 7.] buff mortar.

Wroxeter [Site Museum M.93; 116K] rather sandy, yellowish white fabric, smooth
surface, large white grit.

C

Shapwick, Dorset (R. Farrar to E. B. 1956) not in a dateable context; rubbing
hard, pale buff fabric containing brown + few grey grits; tataration grit
similar; few on fragment to top of bead. r. facing.

C

MOWS3

???? DECIMIUS

Middlewich [JWM12 6004/8712 22K] CR. Abraded.

Stamp too abraded for identification, but 2 lines
+ pair of verticals in lower line. DECIMIUS possible
but cannot be certain. WILDERSPOOL fairly certainly.

Hard, abrasive orange fabric with thin ochre core.
Inclusions moderate to fairly frequent, moderately well-
rounded tiny to small with occasionally medium,
subrounded quartz, occasional polycrystalline, sparse
small black. Only 3 tiny grits - appear to be
quartz sandstone. ~~5%~~ May have had a cream
clay but none surviving? 51% quartz 280mm 8%

DECIMITIUS

To small to tell if med


Walton-le-Dale [WD 96 Drg 489.289/80? 8, 31K] IRS

Orange-brown [Munsell 2.5YR 6/8 'light red'] with thick grey core [Munsell 10YR 6/1]. Inclusions: moderate to fairly frequent quartz, ill-sorted and frequent sand-sized quartz perhaps ^{the} in clay, making fabric slightly abrasive.

Also powdery. No titration survives. Dr. 28cm 7%

6.5g much sand-sized qtz possibly in clay. Tiny traces dolip

Lancaster [25K] L-facing orange-brown
cream slip.



DECW
2V IT

INHESIBLE

fine textured yellowish brown fabric with grey core; tempered by addⁿ.

Wilderspool [68'0 2.2; 72K] ~~very~~ slightly sandy, grey fabric; ? overpoured
of sandy material; cream slip. no grit or fragment.
no grit or fragment.

Warrington M. [68'02'5; no prov; presumably Wilderspool; 73K] soft, slightly
^{fine textured}
^{ochreous brown} sandy, orange fabric with red-orange core, grey in part of fabric nr. head;
^{traces} ^{grey} cream slip; ^{traces} ^{white} ^{Dv = c 36 cms.} plastic, medium to large, brown, grey grits to c. 1 in. b. b. b.

Wilderspool [285'13 May lot W] - previously Kendrick "Long Bank, Wilderspool"
^{sport like B.C. + brown} ^{brown} ^{by add "orange grey"}
18.69; 74 K. [Facing] thick grey core to red-orange; slightly sandy, cream
slip; moderate, large & small, brown, black, grey grits to c. 2 in. b. b. b.

Wilderspool [309'98.8 no prov. but in May collection; 75K] v. worn, like 76K.
but double led under sharply at end of flange; soft, red-orange, ^{fine textured} slightly
sandy fabric; cream slip, traces. like 72K but flange smaller & flange not per cd - 15 body
^{by addition of sand} ^{brown} sediment.



Restored Warrington A.M. 3-7

~~DECMITIVS~~ Pieces are all from different vessels. ~~Line G. 1312~~
CVI IT

1K

Walton-le-dale [Pickering 3K/3P] hard grey core changing to pink + buff surface

with buff cream slip; medium ^{hard} large white + brown grit.

Warrington M [86' 88; 1911. no prov. presumably Wilderspool; 69K] whole
^{1962 Wilderspool T. S. Downes.}
save for one fragment; ^{distorted} ^{by adding a segment} ^{brown} ^{in core +}
a waster but usable; sandy, orange fabric, grey in
part of base; ^{traces of} ^{slipping -} cream slip; large to medium, white, brown, black grits. D =
 $9\frac{4}{10}$ in s. 1 stamp each side of spout. Similar to 74K. ~~but~~. Dv. = 24.4 cms.

Warrington M [408' 13; no prov; presumably Wilderspool; 70K] hard, smooth
orange fabric with ^{thin} dark blue-grey core; cream slip; very sparse, large to
medium, red-brown, grey & black grits to c. t. in b.b.b. like 73K but different
^{broken}
Warrington M [418' 13 no prov; presumably Wilderspool 71K] hard, grey fabric; ^{badly} ^{scratches} ^{worn}
buff or cream slip; pinkish in parts; no grit on fragment. Similar to 73K but smaller. Dv. is 14K



walltonedale. 7 +

DECIMINUS

Manchester, So. Lazarus' Arches [04010 219 8 40K]

55gms 290mm 10% Fabric: fine-textured, orange-brown fabric with thin, pinker core; cream slip. Inclusions: fairly frequent, small and rounded quartz with rare red-brown & black material. No tertiaries survives - no interior

Manchester [04010 834 .1. 10 98 41K] 15gms. 4% flange frequent. Fabric identical with 40K except that the slip has gone on 41K + the stamp is more abraded than 40K. It is either from same vessel as 40K or an identical one.

DECIMINIS


Barton St, Manchester [41 Cxt 688 Pd 3 Phase 5 22K]

Diam 3.3. r. facing. Very heavy wear. Stamp abraded and probably poorly impressed. Bright orange-brown fabric with traces cream slip. Inclusions: frequent, sand-sized up to mm all, mostly quartz with some opaque black & red-brown material. Tint: mixed, quartz, quartz sandstone, red-brown and pale brown sandstone & hard grey material. Fabric slightly abrasive. Deasgate vicus, Manchester [Int Richard Clark. fig 9 no. M4 unpublished 26K]

DECIMUS

Dawgate vicus, Manchester [in] Rich Clark fig 9, M4 unpub

27K



INCOMPLETE DILCA - - - > retrograde or DILC1L low.

DILC1Y MINUS?

63K

lincoln

Lincoln [EB 121 East Bright 1966] 56K. Hard, cream fabric, quite heavily tempered with red-brown & grey grit and brownish buff slip. Fabric with fit with Lincolnshire but color differs from 54K. Fabric much harder than Winterton example. Flange frag.

YORK [SM 4 1990.28 3621 112K] l. facing 2 sherds

NOT joining. Hole central base of heavily worn matarium, Dr. 31cm. Cream fabric with brownish buff slip. Inclusions: fairly frequent tiny quartz with rare black; also some larger opaque red-brown material. Intercalation: quartz, red-brown material, rare black + probably sandstone. Well-worn. Context dated AD 100 +

wv
P
a

break

56K hin colm ERB 121

ATCA — ? or D11C11 [— Ltr.: Incomplete. ? Lincs


no 62a in archive + 65WJ/DC

Winterton, Lincs. [Roger Goodburn. MW/LV 11K] 1 flange fragment
+ 2 other fragments, none join.

+ 2 tiny frags. / Soft, cream fabric w/ pink core; quite heavily
tempered w/ a lot of slightly ^(and) ~~pinkish~~ transparent quartz &
occasional ~~rose~~ black. Ill-sorted.
a little v. b. opaque [Poor impression. Powdery-crumbly
Imitation: quartz, opaque red-brown, rare hard grey,
1 red clarity piece. Dr. c. 28.

long Bennington? 2K ?? Too fragmentary for certainty }

AT/mq - 11000 N



? as Lincoln product?
Incomplete.

Luminate one?

Lincoln, Potterford Plate [CP.A9.37] softish greyish cream fabric;
few, large grits survive - grey, white & r/b; flange
incomplete.

break

D

Lincoln
CP. A9.57

DECUMINA

See *uncertain*. Crivitge 155K

392K.

LOCCUS VIBIUS

~~Dobby Radcliffe~~

AESTICVS? ? ad DECVM? ? ad DECVM IN Fc Uncertain
LINCOLN

Corbridge [unpublished 392K S. 345;] coarse, white, slightly sandy fabric,
medium to large, white & pink grit, a little black & opaque white; ... (1963 - though
to be midland) A in Corbridge int.

~~DE R BR~~ DEISBIS (retrograde)

Brigstock, Northants. [Bag 43; BK 446; H. 3; E Greenfield

1961] slightly sandy texture; cream fabric with brownish
buff slip; moderate amount, large to small, black grit -
probably ironstone. D.C.C. 14's.



0

Brigstock, Northants

DEVALVS

See note

London [Basinghall St. BAZ05 <4> [60] Pd 2 Group II

810K] r and l facing. Burnt top of flange on facing side.
3300 gms Dr. 340mm. 100% Fabric VRW. Tint grit flat,
quartz & occasional red-brown material with traces of concentric
scoring. See report for details of heavy wear at hole in centre
base. No concentric scoring on flange.

Immediately below bead a 6mm wide clear band; below
that tinted after grit about 3 cms below the bottom of
the bead there is normal small tint grit combined with
concentric scoring. Below this point grit & concentric pto
scoring worn away in lower third as far extends into pink core

which would have left the base very thin.

DEVAUS

HONDON CHTRD

BSAE have for him; flange higher than bead a bit cruciform like.

hondon [Guildhall M. 1934.277; 98K] sandy, greyish white fabric, black

in body; internal scoring; small, black + white grit to bead. sketch.

hondon [Cll. R. hondon p. 89; CIL VII, 1334, 24(b)] DEVAI not seen

? hondon [no. no. hondon Mus. 16K] l. facing; one stamp only survives; cream fabric with orange pink core; worn; few grits survive. EVALVS is Lat. of Suggell. Sketch

hondon [1925. 20; 112, Fenchurch St.; Guildhall M. 252K] l. facing; creamy buff fabric. ? burnt in body; worn; a little grey + brown grit survives. form like Q. VA. \$ E normal form.

hondon [12850 M. 16K Merseyside County M.] granular,

orangey fabric with cream core; v. tiny flint + quartz grit, (opaque white), black, white, grey, red-brown. BFSO. Breaks under flange. Fingergrip

DEVAL VS.

Caster [Peterborough Mus. Axi xlvi, 14; CII. VII, 1334, 24] hard buff fabric; white
and brown grit.

Alcester, Warwick [12K Warwick Mus.] sandy, grey-buff fabric with
tiny, white, brown, black grits to bead. D = c. 11 ins.

Alcester, Warwick [13K Warwick Mus.] fabric as above. D = c. 11 ins.

Probably the same mortar as 12K.

Colchester [May f. no 9; 310.97; 317K] coarse, whitish grey; grit gone;
1 stamp each s. of spout. D = 12½ - 13". Approx. B-F 58 only; r. facing.

Maresfield, Sussex [SAC 1849 p. 173; CII. VII, 1334; no. 24c) not seen.

Margidunum [A.J. 1946 fig. 3, no 11] not seen.



Castor (Peterborough M.)

12K Alcester.

DEVIAT. LVS. ret.

Alchester, Oxon. [Not published; 4F 1892; Ashmolean M.76K] incized

Herts/Mddx. stamp; sandy greyish cream fabric w. few grits on fragment
brown & grey; buff slip. ▲

DEVALVS

→ Burcole SP 684 469
Towcester; Wood Burford Tow 1972] Woods. Sandy Crean
Fabric

fabric r-brown, white, transparent & dk. grey, A

lincoln (E. Bright, E.B. 121) Granular, cream with
pink core; 95% temper; depression under stamp p. Worn
vessel - body fragment. Flange fragment. 57K

DEVON VS

Colchester [P3340 BK C 75 J150 635K] L facing. IRS
greyish cream, granular. Frequent, small to medium (quartz)
inclusions. Only the skin c 2mm is greyish-cream, with thick
orange-brown core Munsell 5YR 7/6. Thin cream slip
fused to orange-brown in parts. Flange smooth i.e. noscoring
Inside there are indications of v. fine scoring but not
in normal way. Some tiny flint and quartz tinteration
gilt, very insignificant. Not very worn.

DEVALV'S

Fort

In F 51019

Brompton [Pentreheoling], staffs. [Sonia Allen PH5128A] 4K

2 flange fragments 115gms. Diam <350mm 9%
Hard, greyish-clean; packed with sub-rounded quartz
& rare red ironm frags. Some discolouration &
Somewhat battered. Not published Δ


DEVALVS] VANVS ret.

Venutinium [1939 Hard Courts **23**, -7.4K] Tracing from PCs welding] red buff;
mixed grit, much worn; v. faint impression across flange.

Venutinium [1933 A. vi. 3; 100 **5**; 45K] incised letters; yellowish buff
fabric;

Venutinium [59; X VIII **11** 179K] sandy, pink fabric with buff core
with orangey buff slip; medium to tiny, grey, white, brown & black grit
to b. b.; a few grits on flange.

Venutinium [Hertfordsh. Arch. vol 10 (1968) fig XIV, no. 1 on p. 34, p. 33-34.
in group sent by I. E. Anthony from pits and 2 kilns in
field beyond the S.E. Gate; 2 joining pieces; VG '64 **121** 2 joins V. & **IX**. 231K]
Tracing stamped along waste cracking under flange; inside spout turned in; faint cracking
Pit near Kiln II



Veniamin 1939. Hand Coats [2] 74K

at right angles over bead to inner part of flange; could perhaps be sold as second but crack under flange looks a bad one. Sandy cream fabric with fairly thick pink core; fabric contains a little finely fragmented grit. cream slip vv. pale buff
in places; some concentric grooving in inside near top, but lower interior has probably had some ware. Grit - mostly small & tiny but occasional larger fragment; white, red-brown, grey & a few translucent white. D = 12"

DEVALVS

Venelarium [58 B.T. 36 E; 183 K] flange fragment; sandy, cream fabric with cream slip; burnt grey in part.

Venelarium [59 B.I. 65; 192 K] sandy cream fabric with tiny grit in fabric with buff slip; abundant small tiny grey/brown + white tr. b. b.

Leicester [Jewry Wall fig. 58, no. 18 and p. 220 no. 18; L.T.P. 9.9; 75 K] stamped diagonally; sandy cream fabric; only one or two grey grits on fragment. P.B. suggests sobius as a possibility, but fits ~~the~~ stamp of DEVALVS perfectly.

DEVA RVS

Margidunum [AJ. xxiv p. 52, no. 11, fig. 2 no. 11 read as DEVA 1; 81K] L. facing
sandy, orangy buff fabric with buff slip; internal scoring; tiny,
white & greyish (flint - all probably) grit. D = 13½"

Venutium [C. VI. 7 N ~~44~~; 107K Ver. 1] slightly sandy, pinkish
buff fabric; small, grey & red (tile) grit. △.

Venutium [58 E ~~V~~ ⑤ / 1. 243K] flange fragment in sandy
cream w/ pinkish core & cream slip. Slightly diagonal.
Colchester Collection C. R. G. S. 590K.

Kelvedon, Essex, [rubbing W. Rodwell] Incuse stamp.

Venutium (SS / ME L21. Rubbing sent V. Righy.)

DEVALVS


EH 86

DEVALVS

Elginhaugh [86] + [87] not forming BC 1537 AK 11038

11K Diagonal ?? Lfac. Diam 290mm .230 + 75 gms

Flange smooth, NO conc. scoring. Cream fabric,
±? scoloured slip. Inclusions: frequent, tiny quartz.
Broken too high to show胎ware grit: only
have certain down to break poly carb bb.



Castledykes [1953 (54); Hunterian M. 101K] slightly sandy, cream fabric;
surface buff; few grey, brown, black grits;

DIALVS or DIALIS Symonds and Wade
Colchester [P3323 BKC(75) J258 T2 '115 S37] rand facing

Colchester [PL4993] 548 1.81 ^{T2102} B2321 S38]

DIAL

Colchester, Union [873.3 off Y8K; C.E.M.R. 1950-31 p.25] cream fabric and

surface with sl. pinkish tinge in fabric; red-brown grit; nearest B-F 58
but flange and head entirely on same level. ~~Notched but not deep.~~

Colchester, Union [167.33; 335K] cream fabric, no grit on fragment;
diagonal stamp; near B-F. 18, small but end of flange more turned down
and tapered. ~~Big~~ ~~notched~~ like Sevres. shallow & flatish

Colchester [from Ben Edwards via E.B] "hard, cream-buff fabric
& almost exactly B.F. 18 though no grits on the flange.
What few grits can be seen in the surviving fragment are white.
(Letter to nuttings 12th December 1960; to B.R.H.) Presently in his
possession



335K Colchester, Essex

② seen 1 ~~juvenile~~ hawk 167.33
1966

DURTVS' (E.B. tam in COERTIVTINVS) ✓

(1) DURTVS (ret) Margidunum (Ant-J. 4/44 f 4,30)
(M. 5,40 DURTVS (ret))

"COERTIVTINVS (E.B.)

DILITAS

DILITAS

DICCIA

Check on graffiti JRS xxxviii (1948)

p. 104 no. 27a 77

DIP

CaoTov [Artis,


PRASSO [

hondor [R.S. Coll. 1856; CII. vii, 1334, 40; Coll. Ant. i, pl. 50, 149; M2496;
British M.: 92 K] r: facing; 1 stamp only on vessel, large part of both sides survive;
hard, fine, cream fabric; few, small, black, grey grits - not obvious - b. b.;
surface greyish cream; flat-tinned type spout but built up underneath.

hondor

DIS | LDB

Wattle Syke, West Yorks. nr. Wetherby B TWO 7 Area A
(1708) Pot A. 1K Sintered; black with dark purple layers
just below the surfaces which enclose a black core. Has had
a cream slip. Inclusions: only ill-sorted quartz
visible. Intercalation: transparent and white quartz
quartz sandstone, few opaque black and red-brown
grns. Overfired completely. Undoubtedly a
water, must have been complete and usable.
65 gms 5% - ? left facing. Fit with being Walton
rather than Wilderspool. Very hard + smooth.
Contemp 3c residual. Published 2013



Wildenspool [66/132/5] Δ 87K] Fine-textured, reddish-orange fabric with cream slip.

Northwich [12K] Soft, orange-brown fabric with very slight traces of cream slip behind; softish brown tempering grit. Typical W. Ides wool product. V. poor impression¹⁹⁹¹. Almost complete?

Bewcastle (78.26:16 (17; 35; 34; 22 + 26)) P. Austin. Softish, fine-textured, bright orange-brown fabric; slightly micaceous, with a little sporadic quartz + sandstone tempering, mostly tiny but occasional particles 2mm. or more across; traces of a creamy slip; tempering grit mainly quartz with a little sandstone + black particles, ^{W. Ides} ~~post~~

DIS | LDB.

At least 6

Warrington M [no prov; but probably Wilderpool; 4ii'13; 35K] soft, orange fabric, with cream slip; 1 or 2 whitish grits on frequent ^{pub.} D = c. 10 ins.; type a ~~35~~³² K but bigger.

Wilderpool [1163; 36K; Kendrick] l. facing; soft orange fabric; slip + grit cannot be seen. D = 0.9 $\frac{1}{2}$ ins. No. ~~55~~³² K in shape; stamp almost worn away & probably never well impressed. Similar types to 32K diff. vessel.

Wilderpool [1169; 37K; Kendrick] l. facing soft orange fabric with cream slips; prolific smallish to tiny, grey, brown, whitish, grit to c. $\frac{1}{4}$ in. b.b.b. D = 11 - 11 $\frac{1}{2}$ ins.; broken & worn stamp; similar in shape to ~~55~~³² K but end of flange more inturned.

⁵¹² Chester [2427/3737; 26K] hard, red-brown; cream coloured slip; medium, white + brown grit. l. facing. L = c. 45, 843 - 90

These 8 stamps represent certainly 5 diff. vessels & probably 6 or 7 (Warrington M).

Stannix (Greenvy Bank; valium filling; 20.19-35; Tullie Ho. 16K) very hard, red-brown fabric with grey core in flange; cream slip; flange fragment; not part of the other 2 from this site.

Stannix (Greenvy Bank; valium filling; Tullie Ho. 17K] different vessel, very hard, orange fabric with pinkish ochre coloured core and white slip; fair amount of brown, translucent white, and grey grit to c. $3\frac{1}{4}$ ins.

D. Top. ♂ b; Scoring for spout - //./.

Birdoswald [1950. A. B. Unstrat. Newcastle in S.P.G's stow 7K] hard, red-brown fabric with thick black core; cream slip; white grit.


Birdoswald [Seen 1964. Cambridge. Found 1932] ② on piece. Soft, orange-brown fabric; & flange & head. (I think all slip gone).

DIS(LDB) Phase 5.1 (140-200) Buxton & Howard-Davis 2000

Ribchester [RB89.120 64K] L-facing. Soft, orange-brown fabric with reddish core; inclusions: moderate + mostly quartz, but only showing at x20. No ^{ill-sorted} ~~interruption~~ survival self-coloured slip. Dr. 25cms. Spont cut back as Wroxeter spouts

Ribchester [RB89.18 7769 57K Phase 5.1 (140-200)]
L-facing Dr. 29.5cms. Soft, powdery orange-brown fabric.
Inclusions: moderate, quartz + blackish, ill-sorted vis. at x20.
Interruption: mostly quartz (trans) ^{with} ~~softer~~ cream coloured rock, red-brown (?haematite), red-brown rock? ss. Cream slip. Spont in cut back reminiscent of Wroxeter spouts.

Buxton & Howard-Davis 2000



Ambleside [cw² xxi p. 56, fig. 26 + fig. 22 no. 20] red clay, buff slip; mixed grit twice on one mortar. D = 7½ ins.

Ambleside [unpublished, both vessels in the Armit Library.]

Ribchester [Site Museum] orange-brown fabric; cream slip. 11K

Walton-le-Dale [Trans. Hist. Soc. 8, 1-2 C, 109, - p. 40, fig. 16 no. 21 + p. 45] soft, orange-brown fabric with thin pink core, and cream slip; flange + head only.

Hardknott [cw² xxi p. 36 + no. 22]

Stannix [Greeny Bank; Vallum filling Exchs. 1934; 20-1935; Tullie Ho. 19K] r. facing; heavily burnt; pale pinky brown where color left; white slip; much translucent white + grey grit to c. 1 in. b.b.b.; sparse above.

DISILDB St. George's Crescent
Stanwix Info R Leung. Greenlane Archaeology

SG09 03 20K.] Assumed from position to be U-facing.
unmarked). Bright orange-brown with slight traces
of cream slip; inclusions: random, moderate, ill-
sorted, ~~some quartz~~, ^{and} some opaque black & perhaps
other material & perhaps grains too small to see with
lens. Intervening grit: mostly transparent quartz, & a
few other rocks, 1 white with grains in it; lev 2?
3 grained sandstone, occasional red-brown. Fabric
fairly fine textured. 150gms Dr. 200 mm 7% φG
(Notably Walton-le-Dale)

DISTLDB

Stanwix Info from R. Henry Greenblans

DIS LD B

Walton-le-Dale [WD96 not drawn. 1013 [8665 54K] IRS]

Traces cream slip. Inside half off-white [Munsell 2.5YR
5/8 'red']. Outside half tan [Munsell 5YR 6/6
'reddish yellow'] Inclusions: very moderate, ill-sorted.
tiny to small, quartz with ^{some sand-sized incls} few black reddish-brown.

Very fine-textured. Orientation: almost all quartz.
(+) noratt) on sherd. 65g. Worn

Walton-le-Dale [WD96 Drg 454.770/6299 [39K] will
be fl. facing. 330g Diam. 270mm 33%. Hard in good
state & good stamp. Some burning on flange. Fine-

Textured. Cream sh.p. Orange-brown fabric [Munsell
2.5 YR 5.8 'red'] Inclusions: few to moderate, ill-
sorted quartz with few black. Intercalation: almost
all quartz, ~~pass~~ rare red-brown sandstone. Fairly smooth
Packed up to bed.

DIST LDB

Walton-le-Dale [WD 96 Drg. 428.610 / ?? 6.6. - 38K] cracking
(upthrusts under rim). Traces cream slip. (widely)
Fine-textured, orange-brown [Munsell 2.5YR 6/8
'light red'], fired to tan near surface [Munsell 5 YR
6/6 'reddish-yellow']. Inclusions: quartz with rare
black, few, random, tiny ~~to~~^{but does some sand-sized} gravel. No alteration
available. 185g Diam. 40 mm. 10.5% probably
right facing.

JOINS 46K
Walton-le-Dale [WD 96 Drg 655, 293/76 30 52K] FF.
Traces cream slip. Fired to orange-brown core but to brown color
at surface; [Munsell 2.5YR 5/8 'red'] [Munsell 2.5YR 4/8
'red'] PTO

35g. Diam. ?300 mm b%. Appears to be somewhat
overfired - some sand-sized grains in fabric

DIS/LDB

JOINS 52K Modern break

Walton le Dale [WD 96 Drg 437.3036 / SI 97 46K] IRS.

Sog. Diam 340mm 7%. Partially impressed broken
stamp. On margin of being overfired. V. Hard, orange-
brown [Munsell 2.5YR 5/8 'red']. Cream slip traces,
Inclusions: moderate, ill-sorted, quartz with few black
+ red-brown sandstone. Fine textured.

Walton le Dale [WD 96. No drg/no. 1231 / 8/105, 56K] 2

joining sherds. Traces of cream slip. Edge of stamp only.
Burnt. Orange-brown [Munsell 2.5YR. 6/8 'light red'
with tan surface and cocoa brown core] [2.5YR 6/4
THIS IS OK! ATTRIBUTED STET PTA "light reddish-
brown"]

Inclusions: moderate, tiny quartz with few black. 225 g.
Diam 290 mm 22.5%. Interactions: probably all quartz as
sherd. Warm.

DIS | LD B

Walton-le-Dale [WD] 96 Dug H65, 3080 [9741 41K]

r. facing. 280g. Diam 48 cm. 12% Tan coloured fabric [Munsell 5 YR, 6/8]^{with purple core}. Powdered. Inclusions: fine-textured, few very tiny random quartz & red-brown.^{and few sand-sized} inclusions: very little sandries, quartz + black included.

Walton-le-Dale [WD] 96 Dug 433. 1522 [9644 42K]

likely to be r.facing but no obvious evidence. Slightly askew. 285g. Diam. 290 mm. 16.5% Fine-textured; no sign of slip. Orange brown [Munsell 5 YR 6/6 'reddish yellow']^{moderate} Inclusions: few ill-sorted quartz. Inturations:

mostly gray with some red-brown sandstone, and
paler brown ss, ?check mica or feldspar. Roughly
some wear.

DIS | LDB

Walton-le-Dale [WD96 Drg 434879] 49K 40g. IRS
4% It almost certainly joins 48K.

[WD96 Drg 436. 1048] 7445. ^{48K} 18g.

Diam 35 (9%). Overfired + technical waster. Very hard [smooth dark red fabric (Hunsell 10R 5/6 'red') ^{partly} reddish brown at surface, traces of cream slip. Inclusions: few random small quartz + very fine textured.

Walton-le-Dale [WD96 Drg 439 1154/8024 47K] FF.
Technical waster, heavily overfired, Fabric no 48 (49K).
Surface fired black with cream slip. ^{undiscerned} 35g Diam? 4% BTQ

-A section - Non-parallell w. determine inclusion

DIS[LDB] slightly prismatic pink tinged surface in places

Walton-le-Dale [WD 96] Drg 558 3001/9185.43K Position points

W.L. facing. Cream slip. 5 joining sherds. Hard
beige with greenish grey core. Discoloured & worn
inside [unusually 2.5% 6/2 'light brownish grey']

Probably used. Inclusions: fine textured; moderate,
irregularly shaped, few red-brown. Intercalation:
mostly quartz after black. 32.5g. Diam. 280mm.

25% mostly smoother than most at Wilderspool but often sand-sized incl.

Walton-le-Dale [WD 96 Drg 427.186/8854 55K] flake

Orange-brown with drab brown at and near surface.
Inclusions: few quartz (tiny). Fine textured. 8g.

DIS | WDB

Drg. 42

Walton-le-Dale [WID 96.716 | 3528 50K] Fine-textured,
orange-brown fabric [Munsell 2.5 YR 5/8 red'] with
pale brown surface and remains of cream slip.
few sand-sized.

Inclusions: very moderate, tiny quartz. No intumescion
survives. 90g. Diam. 320mm 8% Powder

Walton le Dale [WID 96 Drg 500. 1154 | 8074 : 45K] Broken
worn stamp. Fine-textured, traces of cream slip. Orange
-brown, fired to black [wear surface (v. thin dark layer) in parts of flange] [0/6 Munsell 2.5/R
6/8 'light red'] Inclusions: tiny quartz, rare black. No
intumescion available. 85g. Diam. 390mm. 6%.

DIS/LDB

Walton-le-Dale [WD96 Drg 528. 659/744.8.51K]

cream slip. Fine-textured, orange-brown fabric
[Munsell 2.5YR 5/8 'red'] inclusions; few quartz, rare
black. Surface lighter brown. 25g. Dr 26cm. 5.5%

Walton-le-Dale [WD96 Drg 460 1088/9609 44K] 180g

Diam. ? 32cm³⁶. 5%. Traces of green slip. Slightly powdery,
fine-textured orange-brown, 3 shades - inside top ~~light~~ buff
brown [Munsell 2.5YR 5/6 'red'] middle = orange-brown
[Munsell 10R 6/8 'light red'] outside $\frac{1}{2}$ brown [Munsell
2.5YR 5/6 but darker than inside $\frac{1}{3}$. Inclusions:
moderate, ill-sorted quartz, mica, some few red-brown, black +, ozo

pale sandstone. Trituration: mostly gritty, with few
red-brown, pale sandstone and very black. Stamp
Worn ✓

DIS(LDB)

1589?
different pot

Walton le Dale [WD 96] Irq. 426 799/7419 and 70K.
1589. Lt right facing. Modern breaks. Powdery
Traces of cream slip. Orange-brown [Munsell 5YR
6/6 'reddish yellow']. Inclusions; few to moderate
tiny quartz & rare large quartz & pale brown ss.
Intercalation: quartz, ^{few} sandstone & rare
black ~~possibly~~ worn. 435g Diam. 230 mm
57% breaks modern.

Walton le Dale [WD 96 not drawn. 799/7419 63K]
FF. Not part of 70K. Worn stamp. Fine-textured
no slip survivors. Orange-brown - similar to 70K but
PTD different vessel.

55g. Draw 24.0 on 15% Cannot be part of 70K
because it would mean having 2 stamps
on 1 side + only 1 on the other side.
Use 70K for form - not drawn separately.

DIS[LDB

Wattam-le-Dale [WD96 Avg 43K 729 | -7.411-4.0K] Lacing
buff cream slip. Waster. Fabric sintered. Red brown with
about 1-2mm at surface fired to black but slip remains
buff. Inclusions Moderate well-spaced tiny quartz
with rare larger quartz if ? black. Has also been
blackened on broken sections. No lamination
survives. 300g. Diam. 400mm 12% [lacing] fine

Wattam-le-Dale [WD96 Avg 46K. 158 | 917 9.53 K] textured
3 joining sherd. Powdery. No sign of slip. Orange-
brown fabric [Hunsell 2.5 YR 8/8 'light red'] surface
brownish ~~no~~ inclusions: few quartz, few black. PTO
moderate

Trituration: quartz - occasional quartz sandstone
205g. Diam. 280mm 21%

DIS/LDB.

403'13 DIS/LDB.
2 ~~in~~
1172 ~~conclusion~~

Warrington M [probably Wilderspool. 410'13; 14K] soft, orange fabric with cream slip, flange only.

Warrington M [probably Wilderspool 403'13; 15K] soft, orange fabric with cream slip; prolific, small, sharp, black, brown, whitish, grey grits to b.b.

Wilderspool [1172, 13th. June; 32K] 1 stamp each side of spout; soft orange fabric with cream slip with dab, pinky grey core; coarse wiling, prolific medium to smallish grey, brown, whitish grit to b.b. D = c. 12 in. cracking under flange

Warrington M. [33K. 405'13, not included in stamp; no prov., probably Wilderspool].
v. worn; soft buff-orange fabric with traces ^{of pinky} cream slip; flange & bead only. Similar to 32K Type

Warrington M. [34K. no prov.; probably Wilderspool; 302'98.12]; redorange to orange at surface; cream slip; D = c. 10 ins; flange only. Type similar 32K.



Restored.

DIS [LDB

? Walton

[area]

Tarraby, (1½ m. n. of Carlisle 2K. Britannia IX (1978) pl. 16, no 75

Ribchester Bathhouse [RIB 78 34 II, 144 52 K] retacing.
poor impression; orange-brown, fine textured, smooth fabric with
-some ill-sorted, random
few light v/f & grey inclusions; Traces of thin cream slip;
1 qtz tritulation grit surfaces. Dr. ~~25~~ cm 25.

Walton-le-dale [WD 81 000 (200). 7K] stamp on two IRS.

1. Facing. Orange ^{tan} fabric (5YR 6/8), sparse inclusions
quartz and glass fragments, micaceous. Tritulation grit
translucent quartz, red-brown haematite? or sandstone?
Cream slip. (Faint) + a few bluish spots. Dr. 33

hancaster [Trans. L & C. Antig. S. xxiv p. 54 no. 2; 4K] L. facing; hard, compact;
 blackish grey fabric with thick, pale buff slip; abundant, large to smallish, clustered,
 rather unsightly, white, grey, brown, black grits to c. 1 in. b. top b. to a few stragglers
 to top of bead; smooth fabric; chevronned bottom.

hancaster [Trans. L & C. Antig. S. xxiv p. 54, no. 2; not seen at hancaster, N.] ^{2 ex 4}
 mentioned
 Kirkham, W. Preston [Infn. J. Marshall, 22, Myrtle Drive, Kirkham; 1959; 3K]
 L. facing; fragmentary - part of topline + top D in bottom line; fine-textured, orangy
 brown fabric, rather harder than usual; surface more pinkish brown - possibly
 a surface slip; much, medium & small, brown, grey & blackish grits to
 c. $\frac{1}{4}$ " b. b. b.; sport badly made; some burning throughout in one part; D = 1 in.

DIS/LDB

hancaster [L.B.88.6703 6 26K] FF Hard orange-brown fabric [Munsell 2.5YR. 6 1/2 'bright red'] Inclusions: moderate ill-sorted, random quartz, few red-brown and black; tiny & small, fine textured. May have had slip. 90g Diam. 2.9cm 16%

hancaster [L.B.98.10886 583 27K] r. facing cream slip. Very hard, orange-brown fabric [Munsell 2.5YR 5/8 'red'] Hard darker at the inside edge. Inclusions: few, mostly very tiny, random quartz, rare black red-brown sandstone. Fine textured, intercalation: mostly quartz, few opaque black + pale brown sandstone. 310g. Diam 290mm PTO 23%

breaks lengthways under flange

DIS/LDB

Walton-le-Dale [WD 82 1361 (198) 144. 19k] probably l. fac
J. hard, ^{brown}


Dr. 31 cm., Orange [fabric (2.5 YR 5/8)], fires to paler orange
at surface; very fine, sparse quartz inclusions and
black fragments. Trituration grit quartz and red-brown
sandstone? and dark grey fragments; cream slip.

Burdoswald [420 204 58k] impression v. slightly diagonal
Hard, fine-textured, orange-brown (2.5 YR 6 1/8)
deep
some ill-sorted qtz, black (iron compound? slag), odd
fleck of galena. Self-colored. No trituration survivors.
Dr. not possible. W. P. Mott 1997, p 254-255 no 261

DIS/LDB

Deargate vicus, Manchester [Int Rich Clark fig 9 M4,
unpublished 28K - 30K

3 vessels SF 1275, 1285, 1293, 1417
at least 3 vessels ? 4 possibly.



DIS/LDB

3 vessels
in all

Ambleside [dw² xv p. 56, fig. 26 + p. 5th no. 3 + p. 43, no. 20 read as NSD.

B. Armit Library 8K]. Inside N. rampart, E. of gate. Orange-brown fabric with traces of grey core in flange; cream slip; D = 11". Stamp each side of spout. harrish & medium, red brown, colourless, grey + 1 or 2 black grits.

Ambleside [not published. Armit Library 7K] marked 31. orange-brown fabric with pale buff slip; abundant, small + tiny grit; colourless, a very few grey & red-brown, white (opaque) ones. D = 10½" l. facing.


Ambleside [rubbing sent by M. Burkitt March 1965; 17K] pink buff fabric with creamy buff slip; D = 9½"

Ribchester flange only. pink-brown fabric. P. Webster.
? = 15K + 22K?

Ribchester [RB89 102 6998 Phase 5.2. 56K] r-facing

Dr. 45. Eight joining sherd's making over a third of upper half of vessel. Well-worn, powdery pink-brown fabric with orange-brown core. Inclusions: moderate, ill-sorted, quartz, red-brown, cream, blackish. Fabric quite hard, difficult to break. Cream slip. Cracking under flange. - Infiltration: mostly quartz, some red brown - some probably ss.; cream rock; clusters quartz grains (ie = sandstone); some black.

Buxton + Howard-Davis 2000



DIVICTVS

York

translucent.

Yorkshire Museum [19K] orange-brown fabric, cream slip, small white
grit up to c. $\frac{1}{2}$ " from rim; stamped diagonally near spout; Type ~~as~~ ^A & PK " 1. facing
D = 11". well-worn

Yorkshire Museum [21] 2 stamps stamped diagonally near spout; orange
brown fabric with cream slip; 1 white (quartzite) grit, heavily worn.
 $3\frac{1}{2}$ cums. D = $12\frac{1}{2}$

Yorkshire Museum [26] DIV... stamped straight ^{over} on rim
from inside to outside rim near others but slightly heavier. Type ~~as~~ ^{21K}
[Tendency to grey core; grit wh. translucent trsh.] in facing across

No nibbing or drawing of 26K. transparent. flange'

These are all under amphorae cil vii 1331, 40; DIVIC K. 319, 320, 328.



DNC

Chesters [2441/3741; 28K] soft, sandy, red-brown fabric with cream
slip; sparse brown grit; no rutbing.

DNC N.B. Note similarity of stamp with those of CVSEC ^{STAMPS FROM SCOTLAND}

Balmuildy [x1, B.15 + p.78; F. 1922.331; Hunterian M. 28K] L.-facing;
slightly sandy, orange-pink fabric; -apit worn away; stamp worn,
on type 20.

DNC

Corbridge [AA⁴ xxvi, p. 179 no. 16; S. 130 (16); 186K] dark grey core to red-brown
fabric with cream slip; moderate, large to medium, red-brown, black, white
grit.

Corbridge [AA⁴ xxvi, p. 179, no. 16; no other no.; (16); 184K] L. facing; hard, brick-pink
fabric with buff slip; grit missing. D = 9½ ins.

Corbridge [AA⁴ xxvi, p. 179, no. 16, S. 155; XI E; (16); 188K] dark grey, almost black
core, changing to brick-pink; few r/b, grits surviving; cream slip.
Type approx. 16 in Report.


Corbridge [North of XII 6/47, complete; 283K unnumbered] 1 stp. each side of
a spout; probably pink fabric, almost red where it shows up through pale buff slip; some well-worn,
whitish, r/b brown, black, grey, large to small ones; much worn areas; D = 8 9/16 in.

[1963
Similar to 1962 in stamp border & lettering, fabric, grit (plus black or grey)
format.]

DOB ALL VS

Duxton [Copper Collage; Northampton Mus? 152; FA 1267] ^{11K.} Dirty greyish buff core to
slightly brownish buff surface with brownish buff slip; worn, varied-sized black
grit (some with reddish/brown centre), fairly prolific, up to bottom of bead. 2 stamps on
Tottenham Villa, Beds. [L. Matthews] "biscuit coloured fabric with reddish brown grain"
in effect, black grit + potter's name stamped boldly 3 times on each side.
^{See over}

Duxton [Northampton Mus? C.W.] ^{12 K.} 2 stamps. Hard cream fabric with
brownish tan ^{thin} slip. D = 1" ^{1/10"}. Top half complete. Copper Coll. V.
Verulamium [1957]. W.II (11); 25K.] 1 slip. each side of spout; hard cream
fabric with pale buff slip; abundant black or v. dk brown, red/brown,
large to small, hard, angular grits (?). 1 to c. $\frac{1}{2}$ in.
b.b. Not a warks. spout. Lindsay Rolfe. A



Totternhoe Villa: Redeposited. Bedo Arch. vol 20 (1992),
41-95. fig. 16, no. 174.

DOBAnhvs

Rough Castle [Maciver 58 J.C] parts of 2 worn stamps probably
from same mortarium; fine, cream fabric with pale buff slip; few,
black, + r/b, large to smallish grits to near b.b.; v. few; inside
worn.

DOCCAS ??

SEE DOCCAS

Colchester [P 3199 MD 3372 S 35]

Colchester [P 3191 MD 3373 S 36]


Check how many vessels?

DOCC AS ??

Colchester [P3200 MID3341 Tz 63 S'34]

DOCC AS

Billingsgate Dumps [B-G 128; 100] K from Ted
Carnell. Small fragment from from a flagge.
10gms VRW Granular pale brownish fabric
with untfied blackish-red surface. Inclusions;
frequent, quartz, not well sorted; few ill-
sorted red-brown and black material. d;
Too fragmentary to draw




DOCCAS

McSlog

Mickleton, Glos. [STRM 14 Content 16450 sent by Ed. &

IK VRW

200Gms Dr. 360mm 12% r. facing. 7 shards, all breaks modern. Cream fabric, perhaps self-coloured slip. In fracture, cream & pink streaks or layers. Inclusions: packed with not very well sorted, ^{sub rounded} quartz with few red-brown, & rare black inclusions; Only one titration grit survives, rose quartz. On stamp, around each letter Δ [d. 3] is incized - that does not show any rubbing, see ~~photo~~




DOCCAS

Worcester [Worcester Map 10K] ^{check} right facing probably.

Worn in lower ^{3/4} half. Buff slip. in chert flint grit.

V.R.W fabric upper border Die 3




DOCCAS

Lancaster [Jenny Evans 2002. Mitchell's Brewery L99/109/

4324. 36K] l.-facing more likely than r. To grns.

D_r c. 32.7% Very hard, cream fabric. Appears to have had a buff slip which is fired to grey in parts.

Inclusions vis. at x20: fairly frequent; very ill-sorted varying from to rare, large red-brown S.S., ^{orange-brown} and quartz to sand-sized. Mostly quartz (NO pinkish); includes red-brown material and opaque black. Interruption cmt: only 2 or three survive a small fragment but included quartz & opaque black & perhaps red-brown. Midland?



DOLL

DOCCAS?

Eg Eg 1:0

Mancetter [Birm Mus. 8K. A. Oswald's dig. v/s] soft, compact, cream

fabric, 1 or 2 grey grits on flange; flange fragment; l-facing. M

Mancetter [Birm. Mus. 9K. A. Oswald. v/s] probably a different
mortar; hard pinkish buff core changing to cream; buff slip, 1 v/b
grit on flange; flange fragment. Both 8K + 9K are Hartshill-
Mandeville. MM

Worcester [IA 24 (5) hei. 1965. 127K]. A midland product
but pink inside and more buff towards core, with cream
surface; grit gone... stamp broken. Early second rim?
probably. M

DOC
EEID

Burns V.C. + Monticello.

Die 3
Vernacular [1930 A. BG 1. pp. 72 + 88 [14]; 26K "Hadrianic layer"]

rather dense, slightly sandy, red fabric; purplish surface, no grit. B=12
mid - d F IND die
hanchester M [BG. 32; ? Bowling Green; 12K unpublished] r. facing; compact,
fine textured dirty cream fabric; cream surface; no grit inside. M
Ashchester Oxon. [Ant. J. IV p. 132, fig. 9 no. 8 + p. 131; Ashmolean M. 2 K] 1929.635.8
cream fabric with buff slip; B.F. 38 so far as can be seen. ? V? Engr. die 3-
NOT enough detail of fabric. ?

DOCC ASS 3

London [Saddlers Hall, 1956 - F. 25, OS 6. 311K 9H] r. [ac.
sandy, brownish pink fabric; red-brown & white grit
worn]

(mid 2)

London, Ironmonger Lane [A large group of 2nd Century
pottery from Ironmonger Lane, in the City of London: IRL 95,
context 58 by R. P. Symonds' in J. RPS vol 11, 21-38,
fig. 5, no. 99, & p. 38 described as illegible (2004) Die 2
fig. 100 in fig. 6 has a stamp, unsure if it's the same
stamp as another Robin thinks it is LUGD?]

DOCCAS - COINS ON DOLLARS

hondon card.

Reqs Ho: New Fish St. Hill

hondon [Guildhall M. 1932. 182; Y3K] flange fragment; sandy, pink die 1

fabric; l. facing. Misread as DORTA... (ret) by B². Verlani. Prob. 80+

hondon, have have [R.S. Coll. 1856; CIL VII, 1334, 25, "do... cited

by Walters; R. hondon p. 89 "DO..."; Coll. Ant. i, p. 149; read by Attributed die 1
Walter as DOCCIV within a border of hatched lines; seems likely

to be one referred to CIL, VII, 1331 (as amphora), 42; M 2480]; 131K

not seen at B.M. but surely this potter. National Fabric Collection

hondon [2-12, Gresham St.; A. 198; Pit I, 208K ^{4H 3081K} ~~Mardon 101~~] r. facing.

22974 Pit I. Sandy greyish buff fabric. Vermilion
fabric. Flavian - early Traj., v. early (?) die 1

DOCCAS

London, Basinghall St (BAZ 05 [2091] pt 6 OA II

803K) Flange frequent in greyish cream fabric.

Inclusions: abundant quartz. Fused to buff-brown
on flange, could be a slip. Normal VRW 60gus. (S)

Diam 330mm 6% VRW Ruffing mounted in Ring ^{file} do 1.

AC
Docc / EECIT

P Booth Tab 8.

Die 5?

Tiddington [WD 81 736/1 2 frags joining. Warwick M. 6K] Docc [very similar to docci in Die A but different. Fine textured cream fabric with quartz crystalline & red-brown ^{clay pellets} inclusions; red-brown & occasional quartz trituration. burnt Dr. 27^M A.P.B. cws. Fabric is Mancetter-Hartshill. Burnt.

Walton-le-Dale [WD 81 481.15k] 2 stamps, badly eroded, same die from either side of spout. Pinkish cream fabric (no Munsell equivalent), inclusions angular and sub-rounded quartz, ill-sorted and red clay pellets are common. No trituration grit survives. (Fabric 30) Fabric slightly abrasive. Flange fragment supplied. Mancetter - Hartshill. M

Doevers DOCCAS ~~Att~~ Diei + Corrige 1972a

Brockley Hill [B+1971 I. 126K] granular cream fabric w/ pink
core & cream slips; abundant grey & white flint grit, mostly tiny.
Large broken. Note slight but definite stroke in A. ^{mit Lacks} unrued.

Brockley Hill [B+71 TC 6x] 127K fragment probably from
a crest vessel. Sandy pinkish fabric containing tiny red-brown
grits.

Brockley Hill House [B+N00 Oxon Unit Context 15] prn: 211 361K
flange fragment r. facing 38g ?300mm 7% cream with
pink core. Incl. packed with quartz (trans) with rare red-brown
& 1 soft white containing transp. quartz. Brown slip (under
flange) cream on upper surface

Dock 11:

Brockley Hill [T.L.M.A.S. vol. 19 pt. i p. 71, M.7; Harrow 1K] l.-facing; sandy

pink fabric; slightly cream tinge on surface; abundant, white, brown,
grey, dark grey grit, medium to tiny to c. 2 b.b.b. die 1

Brockley Hill [T.L.M.A.S. 19, pt. i, p. 71, M.7; Harrow 2K] l.-facing; sandy,
pink fabric; slightly creamier tinge on top + inside surfaces; moderate
amount, large to small, white, grey, black grits b.b.; D = 13 ins;
cheese wired base; a waster crack - fairly certainly. die 1

Brockley Hill [T.L.M.A.S. 19 pt. i p. 71, M.7. Harrow 5K] flange fragment; a different
vessel from 1K & 2K; cream fabric. die 1

Brockley Hill [T.L.M.A.S. 19 pt. i p. 71; M.7 Harrow 20K 1/4]; D3, Sull. 54; flange fragment;
buff fabric, dark blackish purple surface; [FN.B. Only 3 in report] die 1

DOCCAS 1973 BROCKLEY HILL + 1974

Brockley Hill [BH 73 MS 36 254K] L. fabric granular pale

buff fabric with pink streaks in it; orangy buff slip. die 1

Brockley Hill [BH 73 T.C. MS 51 258K] border only. V. well-fired
brownish buff with tinged reddishness near at surface; reddish buff
slip. Discoloration prob. due to overfiring. Flint grey, sh. flock
grnt i few in outside die 1

Brockley Hill [BH 74 T.C. MS 27 290K] Pinkish brown fabric with
greyish cream; white & grey flint grit die 1

Brockley Hill [BH 74 T.C. MS 26 291K] Burnt throughout to
blackish grey; red. brown in much of fabric; ^{alittle} some accretion on flange
die 1

170 (1), Fig. 6

Leicester [Fawny Wall, fig. 58, no. 6 + p. 217; C 31] IS I M.S.

L.P. 38.1 - 3; 68K Leicester M.] hard, midland, creamy white fabric; pale buff slip; flange fragment, probably from a large, shallow 34-like bowl. M

Wroxeter [WB 83] 534 - 183k] Die 5 r. fac. and l. facing: on same vessel. Hard, cream fabric, inclusions quartz few ^{fine reddish} _{travertine} moderate and tiny red-brown fragments. Trituration grit quartz sandstone ^{little spherules} and red-brown fragments. Surface worn. Likely to be W. midland rather than Hanwell-Hartshill. Drawing by PR in drawer. Dr. 29cms. Yellowish slip. "M" Diet
Can't tell source PTO



longester J.W. nob. £31/5
L 38 1-3

183K Either H/M or Worcester. Sport + ship like Worcester. Fabric &
textured cut work fit H/M

DCCAS

ex JF 89

Die 6

104 N 916

Wroxeter [WB 98 183K] IRS, fragmentary stamp. Brownish-
Hand ^{moderate} ill-sorted; cream fabric, fine textured; few inclusions, of quartz and few
blackish iron slag fragments. Trituration grit incl. dead
quartz and iron slag; worn. Traces of pale ~~buff~~ ^{yellowish} slip. M
looks as though it is from a v. similar matassa to 183K.
Too fragmentary to draw.

D06C AS?

Roseite [R085-1095 33K] IRS. Cream fabric; some quartz
fr/lb inclusions; area on outside with thick mushroom brown
surface - looks too thick to be a slip but must be. Tinturation - tiny
& small quantity; & v. occasional r/lb & blackish grit upto b.b.
Some of quartz pinkish. Die 6?

△

Esmonde Cleary & Ferris 1996, 68 Not illustrated.

96 01

58 08

9
years

33K Rochester

DOCC AS

Highgate Wood [HW74 TSF1L1 [475|476] 11K] L.facing
Dv. 33cm. Granular greyish-cream fabric with brownish
streaks. Abundant inclusions: mostly quartz, rare &
sometimes larger red-brown inclusions. Intervening grit:
flint, some quartz, v. rare red-brown. Some wear.
Spout has lost end but NOT albinoid. Spout lansh. 2
large joining sherds. VRW

d.1

DOCC.AS or DOCC.V

Chester [Newgate site, Tobias - residual late C + early C levels^{4K}]; brownish red; c.

Wrox. Type 38. Appears identical with Rich. eq. VR/W dia. 1.

Richborough [IV p. 2 #9 no. 21] coarse brown (red fabric) cf. Wrox. 38.

[G.H. 1932-182]

Hoxne [B.M. Walters 2780 = VII 1331, & 2 "amphora"]

Hambleton Villa [A vol. 71, p. 188] cf. Wrox. 38






Chart
Newgate site
1935.



Sketch.
G.H. 1932-192.

Decr. IV S?

Fiddington [Stratford Mus. p 65 no 18; N. side of Goff-hinks 1924] sandy,
orange-buff fabric with grey-buff core, changing to cream-buff surface;
flange only, stamp worn. See other entry.]

Hambleden Villa, Bucks. [Arch. 71, p. 188, fig. 19, no. 3; 5K Aylesbury Mus.]
sandy greyish-white fabric; 1v. large brown grit probably accidental at
b.b., rest, small white and greyish; a very few on fragment, r. facing.

Richborough [iv. p. 249, no. 24; 35; 60K] sandy, red-brown fabric,
blackened on outside of flange (?firing); broken flange fragment; B.F.
34 but more inturned at bottom. Illustration. ✓ RMS did

London [hove have, R.S.Coll. 18516].


DOCCAS

Park St. Site

Towcester [TCW 76 129/1 6K] Flange fragment: in somewhat granular greyish cream fabric but with very fine finish & not as much quartz tempering as usual. Detail very clear - die fairly new when impressed. Id'd as probably made in Northants. (RW) About best impression seen

die 1

Staines [415] X10 (14) ^{QK} ~~thick~~ 76 B2 3 23K fragmentary.
Granular cream with pink core + reddish brown slips; much
quartz tempering ^{+ odd 1/2 grit.} border only. No tritⁿ. grit on fragment



DCCAS

48K

Cirencester [ED 1979 4/4/15. Watchin^g brief] Diameter c 27 cms.

Salmon pink throughout; abundant coarse & translucent quartz upto 0.5 mm; sparse rounded haematite upto 2 mm. Sparse angular grey & red flint upto 3 mm. (opaque type). (d, 1)

All information tritubing from Janet Richardson Ver.

Rosester [Int. M. Brassington 1985] record C more curved than usual.

sounds like Ver fabric

See Rosester envelope.

Tiddington [T. 179 stamp no. 18.1K] probably r-facing Dr. 29 cms;
granular frequent occasional

Cream fabric with pinkish core, [inclusions quartz and red-orange
fragments. No trituration grit survives. Orange-brown surface! possible deep cream slip.

P.B Fabric ? Made in Vendee Region.

Die 1

Daccas Daccas

Caersws [NMW]. Rubbing sent by S. Boon 1965. VRW see below.

Caersws [CS10/203 find no. 186. 9K] Die I. All of rim
sunning, including both stamps; one of them abraded.
Well worn & Dr. 30cm. Pale brownish-cream, granular
fabric with abundant, fairly well-sorted quartz. Hardly
any intention surfaces; it included flint + quartz. A.
With shallow spot. Surface ranges from pale cream/brown
to opaque reddish brown. VRW die I

DOCCAS

Rochester [RO 1093 32K] Cream fabric, may be marginally less
gritty than Ver. region fabric often is but it is fairly well packed
with quartz grit and occasional red-brown grit and ^{thin} streaks
of red-brown. Dr. c 30cms. VR NOT PUBLISHED ^{die 1} 4

Rochester [RO 86 II 1384 40K] 12 joining fragments; both L + r.
Stamps survive. $\frac{1}{2}$ to $\frac{2}{3}$ vessel. Shows use but not excessive wear.
Brownish fabric fixed to cream ^{at} surface; slip is brownish-yellow;
packed but appears to be less well sorted gritty than usual;
occasional re-d-brown inclusion; flint, quartz + occasional red-
brown trituration grit. Dr. 30cms. VR ^{tsanonde} Cleary T Fein ¹⁴ 64, no. 6. ^{Die 1.}

There are slight differences in spacing among some stamps
from die-type 1. ? a matrix used and more than one
die made. Or. due to curvature of rim. 32K Rochester is one
which differs (also Brockley Hill - K)


DOCCAS

Ribchester [RB 89 Context 285 SF. 7813 71K] Abat

30 joining sherds (²² + ¹² plastering fragments) making up a
 $\frac{2}{3}$ to $\frac{3}{4}$ of a mortarium which was probably worn to the
point where a plug fell out of the centre of the base.

Fragments of both stamps survive but at no point
is the flange fully preserved. Burnt. Dr. \approx 3cm.
buff-brown fabric with cream slip. Inclusions: frequent,
quartz (nothing else viz) but not packed as they can be -
giving the less granular fabric. Flange NOT scored.
+ probably not scored inside though v. heavily worn.
Interventions: flint, quartz, few r-b. VRW

Diel



Doxic AS 1914

Leicester [p. 116 f. 58 no. 64 p. 217] Frag. of a jug. Lookerum.

Brockley Hill [LMA 5.1956 vol. 19 pt. 1, p. 71 figs. 2 + 3 no. M7] 3 frags. with similar profiles.
2 in pinkish buff, the third in cream.




Ribchester [1914 G. P. N. 256 had pale 7 9/15 (207) brown
Museum] buff fabric with orange (slightly purplish) slip. Very
apparently only on top of flange & inside; pieces of lead and stone in fabric; small

white, grey grit; profuse but worn reaching almost to beads. D. 12 1/2".
Towcester Railway Station (Charmian Phillips contains)

Northampton Mus [probably Worcester (or Fleetwood) T. 5 K] sandy, yellow-buff fabric;
abundant white, brown, grey grit; patchy buff-brown-purple surface. B. H.

Cheltenham [Newstead Gallery]

Provenance confirmed by Charmian Phillips



DOC
EEID N.B. similarity of shape & fabric grit to Q.IV.CRES

Venitium [26K; 1930 A. bkg. I pp 72+88. 74] dull purple to red;

Hadianic layer on pink buff mⁱⁿ d. = 11½".

Templeborough [pl 20]: [3, 1916-17; 2K] flange only, hard, slightly coarse cream fabric with grits in it; few white v/b grits ^{NO} ^{CHECK} ^{P.T.O.} ^{drab} on top in fabric, top surface drab

Rossington Bridge [P.S. dump 1958] ^{36K} creamy white, fairly hard, smooth fabric with tan coloured buff; medium to large brown (sandstone), + white (?) grits; rather sparse right to b.b + incidental grits on top of rim outside; v. facing incompletely impressed. ^{DOCC!} ^{EE10°} A midland product. M

Aldchester (Oxon) [A.S. IX p131 fig. 9, no. 8] B.F. 74.



PS Templeborong (I saw the pot
but I can't find the nutting)

Leicester [43K AIR 39/9 Perry's West side of Hanvey Lane, 1939.

L-facing: sandy, Vermantium fabric; greyish. Probably
burnt. same die as Brockley Hill 83K V d.2

Brockley Hill [1975 Castle. N.G.R.C.T.Q.: 17394] flange

frag. B+C 75 T.C. in cream sandy fabric with pinkish
firing in parts. 351K d.2

Staines [BBS 69 B37 208~~8~~ 39K] Flange. Porched - well carved
cream no

greyish cream, pink core; pale ~~red~~ slip; slightly burnt.
Fair amount quartz & odd v/b & possibly flint tempering. Fairly
thin? version 30?

Roxeter [inf. Mr. Parassington 1985] missing supplied - second C
more carved than turned. Small, like v/c, h. Die 2 ~~Die 2~~



43 Kheistes. AR 39/9

DOC1 (WROKETTER)

Workshop serving
WROKETTER

Deansway, Worcester [HWCM 3899 12000 1K] r. facing & part of L. fac.

Dr. 30cm. Hard ^{buff-} cream fabric with thick ^{brownish-} pink core and surface or slip fired to brownish-orange. Inclusions, mixed & ill-sorted: shiny black ^{angular} with plate-like surface, quartz, ^{opaque} red-brown (sometimes large). Interruption grit: mixed translucent, white, pink & black quartz with some reddish iron (some at least seems to be r. sandstone), & rare black. Surface has had some wear. Typical Wrox. product.

CBA Res. Rep. 139, 2004 Iron Age & R-B pottery

by Victoria Bryant & J. Evans 281-338 p 263

Hfq 165 no. 8, Title "Excav at Deansway, Worcester"

1988-89. R-B small town to late medieval city by PJO

Hal Dalwood + Rachel Edward.

Kinderton, Middlewich [5K Middlewich M.] buff fabric with brick red core;
medium to large, white + brown [sandstone] grit.

Brecon Gaer [p. 247 no. 8, B25. Blq. A; pre-stone occupation with 18/31
NDER CIL LV 5 F; NMW 49K] r. facing; softish, cream, fairly fine
fabric, cream-buff surface; grey grits; B.F. 58.

Caersws [D. 20-526; NMW. 60K] 1 stamp each side spout; stamps
blurred + hardly impressed; cream-buff fabric, surface darker buff; prolific,
large to small, r/b. (?:); whitish + black grit; vessel white; B.F. 46/58
nearest; D = 10%.

Wall Town [WTN 17] 1. Walker] shape obvious imitation of B.F. 26/30 + variants;
fine, creamy buff fabric with some very small grit in it. 1960

DOCILIS I

or Staffs

Brecon [p. 247 no. 9, B25 T. area; NMW 54 K] hard, dark grey, somewhat coarse but not sandy, fabric, with brown core; internal scoring; slightly lumpy surface; good amount, white, black, smallish grits to near bead.
D = $11\frac{1}{2}$ - 12 ins.

Widenspool [May p. 64; 1150; 31 K] two stamps; very pale pinkish buff gritty fabric; plentiful white red + black small grit c.B.F. 58; D = $11\frac{1}{2}$.

Wroxeter [1861 Hawick Mus., Roxburgh, Whilton hedge Mus. seen BM 0.]

pretty coloured fabric with pink core; fine angular dark brown to grey grit in a band near rim only. See rim folder for nothing.

DOC1 [L15] II

Worcester [H. Sandon letter 28.1.62] L-tacing; ^{B.W. (2)} hard, buff fabric with some grit mixed in the body; orangy slip fired to purplish brown on this side of spout & on lower part of outside of body; much medium & small, white, black & red-brown grit to b.b.; (white is ?quartzite). D = 12".


Alcester [64 AA III 102 32K] Probably two pieces. Fabric varies from cream on upper surface of flange to bright pink elsewhere. Two faint cracks on flange. Grit probably white + r/b. Intended to be cream or buff. No trit. grit on stamped sherd. Dr. 28-30 cm.

DOCILIS I — Investigate possibility of being same
as in DOCILIS II.
yellowish grit in fabric.
Wroxeter [Rowley No. E25.20K] l-facing. buff
cream fabric with cream slip; brown
(s.s.) + dark grey.
purple on rim; yellowish inside; brown and white grit; B.F. 58. This is
probably the same as Shropshire A.S. Trans I, 338 + CIL VII, 1334, 26.
Wall Town [WTN ⑪ I. Walker¹⁹⁶⁹] fine creamy buff fabric with a little
grit in it; surface eroded, most grit gone, a few brown ones survive.
stamp v. faint due to erosion; stamp slightly diagonal.
Alcester [65 D II ②; D II ③ 1/4. 30K] l-facing. 3 large joining
pieces giving about half the vessel. Fairly fine creamy buff
fabric with buff slip discoloured to greyish colour near and
at spout. Some grit in fabric; medium & small, white, r/b
and grey grit, fairly abundant. D = 11"

DOCILIS I

Wroxeter [WB 84] 52 225K (38) J. Evans] main construction

FF. Hard fabric fired to cream at surface otherwise orangey pink
Inclusions: fairly frequent; ill-sorted, mostly quartz, rare black
fired-brain. Different vessel.




Probably Docilis T because of form!

Different vessel.

Wroxeter [WB 83 + 243K 58 J Evans] fragmentary stamp

Hard cream fabric; fairly frequent, ill-sorted mostly quartz
inclusions, few red-brown. Interruption & scarring to near b. of
bead: mostly quartz, rare red-brown. Yellowish buff clay. Dr. 28cm.

Str. v. v frag -



facing

Wroxeter [WB 90 204 191K] Hard, almost brownish cream fabric
fairly rare red-brown; ill-sorted.

with frequent quartz (?) inclusions included a lot of quartz + some opaque black material. Dr. 45 cm. Very slightly burnt; fired to pinkish orange colour. Different pot from 229K. Probably had scoring inside monolithic.

Wroxeter [WB 84 49 226K] v. facing. JF32. 123 J Evans. Dr. 28 cm.
At least 7 joining sherds + 1 odd fragment. Hard cream fabric.

Inclusions: fairly frequent, ill-sorted, mostly quartz, rare red-brown ss

Inclusions: mostly quartz, rare black trave red-brown - all smallish

Combined with rough concentric scoring upto b. of bead. None
a flange. This gritting seems typical for Doullis 1 + some
Vitallis at least with this rim form.

226 K Is this the same bowl as the one on show in the
new site Mus. It should not be 226 K but might be.
One on show is whole probably except for part of
flange on l. side. It is burnt. The right side
has all the sherds, the fragmentary stamp
and facing, where part of flange missing
bowl full of small bone (not coemation)
FIND Malcolm's drawing

Hard fine-textured,

Wroxeter [WB ⑨0 204. 191k] Flange fragment. [Cream fabric
229K]

Thick

with 1 pink layer on underside of flange; coarse-textured,
fairly frequent, mostly quartz, moderate inclusions of ill-sorted quartz and sparse red-
brown fragments. No trituration grit survives, fired to an
orange-buff colour at the surface.

red-pink
buff

Wroxeter [WB ⑨8 95 F890. 192k] IRS, r. facing, slightly ~~bassata~~.

Two vertical slashes as key marks for ~~spot~~. Hard,
buff-cream fabric, ^{moderate,} few inclusions of ^{well-sorted; mostly few} quartz, ^{yellowish} red-brown and
tiny black fragments. No trituration grit survives; ^{buff-}
brown slip. Dr. 30 cms. Different vessel.

DOC#LIS 1

King St. Civilian Site.

Middlewich Community Dig [Sent by R. Keary. c SJ 104663] Z05665

No. 133 (archive) 12588 Context 1217 Tr. 12 18K ~~set~~

L. facing 135g Dr. 300m 12% Hard, fine-textured
cream fabric with slightly pinkish tinge + with drab
pink cream core. Moderate to frequent, ill-sorted,
tiny small, black + ochre brown inclusions.

Inclusions: few survive, probably mostly quartz

Some singeing. (Context 1217 - see Name entry)
Midden deposit overlying clay floor

Wroxeter [1914 fig. 3, 47 + p. 60. Site Museum restored] stamped
each side of spout which is of West Midland type. Found in Pit 75.

Wroxeter [1914 fig. 3, 47 + p. 60] now lost. Found in a deposit under
the pavement between Sites V & VI "dating to the late first and early
second centuries.

Wroxeter [1914 fig. 3 no. 47 + p. 60] now lost. No reference to
find spot.

Wroxeter [D. Atkinson. In store at Library. Unpublished] fragmentary
worn; slightly diagonal; hard, creamy-buff, with some grit in it.

DOC.

WROXETER
W. MIDLANDS.
c. 100 - 140?

Wroxeter. [Atkinson f.47 p.298 no 9 + p.279; 15K] ^{E21}; orange-buff fabric, may have brownish buff slip, some reddish staining on flange (?burning); prolific small large, white & black grit in $\frac{1}{2}$ band under bead, more irregularly dispersed below. Room 2 in filling under original floor. Before c. A.D. 130

Leicester. [L.S.6 d.2 Ian Walker] hard fabric changing from grey to cream in small fragment possibly burnt or due to unusual conditions in the kiln. Rough exterior as if sandy; only 1 grit surviving. Reading uncertain but probably DOCI.

Brecon. [no 8.8:247] flat rimmed mortar ^{at 20x} "from a late first century deposit (co-i Building)"

Heronbridge. [cAS xx p.23 pl. XIV, no. 46] cream fabric with traces of brown paint.



Wyoester, (Rowley, Ho) 11575

Wroxeter [Bushe-Fox cont'd.] [M48, 14K]; buff brown fabric, purplish brown surface (overfired).

[M98, 15K] yellowish buff fabric, no slip(?)


[M 59, 16K] under level of op. sig. floor on s. side of Podium S.V.; yellowish buff fabric, no slip(?); abundant grit white + brown mainly; slashed lines inside.

[M 84, 17K] red brown fabric, black (burnt?) surface; a little white grit.

[M 110, 18K] yellowish buff, red brown surface slip; large, medium, + small grit including sandstone fragments.

[M152, 112K] seen 1958 B.R. n.

(61) Wroxeter [G.W. 1958 ⑧ + W.B. 1958 K] pale <sup>pale from
burning</sup> Dr. 27 at surface
slightly brownish pink fabric, fairly hard;
slightly darker surface, no grit or fragment, v. small excreted under flotage - r. facing



M59.16K WROXETER

DOC1. II

W.L. 1967

16

Wroxeter ~~25~~ exx. recorded by Bushe-Fox [i, fig 16 no 4 + pl 6 (2); ii p. 47 nos. (9);]
3


[M 12.6; 7K] buff fabric with orange buff slip, rather paler on the inside; largest medium, sparse grey and red/brown grit up to b. of bead.

[M 90; 10K] buff fabric with thick red core, surface patchy/brown, red, + black (? overfired); a little white and brown grit surviving up to bead almost

[M 9; 11K] T. Edward's Pit] Reddish brown with thick buff core; burnt surface but suggestion of cream slip; small white and brown grit.

[M 55 12K] Dark buff fabric, orange-brown surface slip; abundant white and a little brown grit.

[M 100? 13K] Buff with thick red core, orange brown surface .



wirecells

H.90 Slashed diagonally from knife?
for keying of sport.

A good deal of rim variation.

H59 + 110 L-facing. H90 v. facing;
H126 v. facing; H84 probably L.facing.

Wroxeter [WB 52] 22; 135K creamy buff fabric with pink core;
surface, probably slip; orange.

Wroxeter [1974 WB 86] 16. Dirty cream ware.

Wroxeter [WB 78] 1 167K r. facing A basically fine-textured
slightly pinkish-brownish cream with pale greyish core; tempered with mud
+ small pale white pellets. tiny grit; trituration grit - mostly quartz with a few
red-brown (? s.s.) + dark grits. D = 29 cms. (83) J. Evans. △

Wroxeter [WB 48] 65. 190K Flange fragment, fragmentary stamp
Pale Brownish-buff fabric, moderate inclusions fine quartz. No
trituration grit survives, red-brown slip on top of flange, could be
slip unusual - would pass as Rhaetian. Just there.

(40) J Evans

C. facing

slightly burnt,

Wroxeter [WB 98] 138. 196k] I.R.S., fragmentary stamp, left

Pale

facing. Brownish-buff. fabric, moderate + inclusions ^{fairly}
^{ill.} wet-softed; quartz ^{and} sparse brownish fragments. No trituration
 grit survives; pinky-brown slip. Different vessel to 190k.

Wroxeter [WB 55] 49 J. Fairer (55) 204k] Flange fragment in
 fine-textured, deep cream (almost brownish) fabric with pink core;
 some quartz inclusions and occasional quite large soft white
 pellets; occasional large red-brown inclusions; brownish cream
 patches on surface. Top flander (see 32k Alcato).



break

Wroxeter 196k

WB 98 138 d01

DOC 1

Wroxeter [WB 49] 122 : 935K] 4 pieces joining
heavily worn. Dr. 32 cms. Both stamps survive. Glue on one side - so
more sherd^s. Hard, yellowish-cream fabric. Pinkish-brown slip - browned
on part of flange. Inclusions: frequent, ill-sorted, mostly quartz, rare
red-brown. Integration: mostly quartz, few red-brown. A

Wroxeter [NB 86] 16 164K ⑧7 J Evans] Dr. 34 cms Hard, deep cream
yellow buff-cream fabric; sl. pinkish buff slip. Inclusions:
moderate +, ill-sorted, mostly quartz, rare red-brown.
Integration: mostly quartz, some red-brown s.s(?), ? slag? ^{rare?}
Fabric sl. micaceous. A

Wroxeter [WB ⑧ + ⑯ J. Evans 120K] r.-facing. Hard, pale brown fabric, fired darker at surface which is pinker ie. pinkish-brown. Inclusions: moderate +; ill-sorted, mostly quartz, rare red-brown. v. small curved under flange. Dr. 27. No trellisation survives.

Wroxeter [WB ⑧⑩ + ⑯ J. Evans 238K] FF l.-facing. Hard, fine-textured/cream fabric. Inclusions: moderate to fairly frequent, ill-sorted, quartz & ^{rare?} red-brown. Self-coloured. Dr. 29cm.

Wroxeter [WB ⑧⑯ + ⑯ J. Evans 236K] Hard cream fabric w/t thick pink core. Inclusions: moderate +, quartz, v. b + dark? cream buff slip fired to orange-brown on top outer half of flange. No trellisation survives. Dr. 26cm

Northwich [N. (Castle) Dairy] Z 31/35. No Cat no. 49K]

Off-white fabric with abundant quartz temper & a little red-b.
Sporadic, large to medium, hard pale v/b, black, glz,
sandstone v/b. Tripartite. Dr. 34. L-pac. stamp v.
faint.

~~Tiddington [ID 81 736/1 going BK Warwick-H] - Doc II~~ [very similar
to Doc II Die A but poss diff die - fine textured cream fabric with crystalline
& red brown inclusions; w/facet - edges quartz tripartite - green &
Die not otherwise recorded. Means probably = Doc II - fabric could well be M-H

DOC1. probably Doc 115 1

Wroxeter

Caerau [CR 90/19 4K] sent by Awdry Powys. r. facing. 5 joining
sherds + tiny flakes. (Three other body fragments? ^{? from open inclusions} part of vessel.
Buff-cream fabric? stained with brown possibly through fabric
hard and brownish buff slip intact; very moderate, not well
sorted quartz + iron slag inclusions. Interraction grit: small sized,
fairly frequent and snow. worn point mostly quartz, occasional black
slag. Dr. 36cm. Fired to buff-brown (sl. streaky)
throughout in area of spont + almost $\frac{1}{2}$ way round on
surviving side.

DOC:

January 10/355

3 large shards from 620/ likely to be same pot.
100-150

Caersws [cs 10/128 27 fragments, several joining. 2 flange frags.

have poorly preserved impressions] Dr. 33 cms. 5K. Soft, cream fabric, slightly pinkish with a lot of pink in top-sided core, probably more pink in some parts; 1 stamped fragment is brownish pink throughout surviving fabric. Some quartz, small, rounded with a little brown & black material; some of quartz pinkish. Occasional large? quartz, opaque white, rounded. No slip unless self coloured. Intercalation grit, a mixture of same grit which is in body, perhaps but not certainly with lower proportion of quartz. West midland - Taken to be At least 60% stamps

Published as 2 vessels: Not absolutely certain
but 1 stamp + 2 border fragments,

Carmarthen [CM 81.2 1571 1121 2276 2281 2697 33556
 14K]

Dv. = 29 cms. Slightly brittle texture. Fairly fine-textured. Moderate inclusions - definitely fewer than the illerates; cream except slightly brownish towards outside. Inclusions; quartz mostly, some r-b, probably s.s. Probably had a buff-brown slip. Heavily worn inside except at top; quartz mostly, some r-b. 8 joining sherds.

Carmarthen [CM 81.2 2061 2259 2281 33551 1571]

r-facing. Dv. = 29cm 4 joining sherds. Well worn. Hard, buff-brown fabric. Inclusions moderate: mostly quartz, illerated; rare r-b. Intercalation grit: mixture quartz; black (some vesicular) & some r-b. Some broken concentric scores at top.

His flanges are always smooth

Specimen T

Glan-y-Mor, Barry (Glam-Gwent Arch. Trust Ltd. 1980. Thought then
to be an oval base.] Hard, brownish-tuff fabric with a fair
amount of quartz + some red-brown + black tempering.
The abundant intercalation grit is of similar material, the
quartz again predominates. One stamp + frags of others.
Numerous numbers but 29/260 an surviving stamp. Dr. 31/32

0'54



Doc 1.

W. MIDLANDS.

Caerau, Breconshire [Carmarthen Mus. 2K] flange only; hard, buff fabric
with orangy buff.

Caerhun [AC. 1932, LXXXIX, f. 37 no. 10 or no. 30] pale buff; no grit preserved.
ante-dates stone fort. NOT seen at Hawddduo.

Chester [P31/2/2; 231/4 Box 115; CAS. XXX, Pl. xxv, 46, 47; Heronbridge 29K];
grey and brown grit. See also Wm. 16:2.

Castell Cennen [Carmarthen Mus. 1K. 31. 20.88 Roman Frontier in Wales,
Nash-Williams p. 62 footnote 1 where misread CCI] hard, peach coloured fabric
with orangy pink slip; grey grit, small, + smallish, good amount 15 c. 14. b. bb.

Caersws [CS10/557 7K] flange fragment. Fabric 2;
softish, basically fine textured with some, smallish but not
well-sorted quartz, red-brown & black inclusions.
Brownish-orange slip. Typical West midland fabric but
not as hard as it should be. In better condition than other
W. midland mortars at Caersws. Virtually certain ident
longhor [445-B 57/088 7K] Dr. 28cm. Hard, fine-textured, wa
fabric. Inclusions: moderate, ~~to fairly~~ well-dispersed,
quartz, red-brown ^{& black} slag-like material; mostly tiny but occasional large
grits, Intercalation grit: quartz, red ^{brown} & blackish: slag. Brownish-orange
slip.

Caerhun [Arch. Camb. LXXXIX fig. 37], no 89 on p. 79 et p. 45 no. 66;

Handedness] soft pink fabric; few greyish grits; l. facing

Caerhun [Arch. Camb. LXXXIX fig. 37, no. 8 on p. 79 + p. 44, no. 65;

z/143; Site F. 3; 924; buff fabric; brown, whitish & grey
grit.

Llanio [H. Jarrett; 19.IV.61; L061 AX; sent by J. Jeffery, letter 23.IV.61]

'hard, smooth buff fabric; section as Caerhun (Baillie-Reynolds
no. 40 with DOC stamp.'

Worcester (H. Sandars letter 28.II.62) l. facing; hard, buff fabric with
some grit mixed in the body; orangey slip fired to purple
brown round spout to lower part outside back body;

DOCEKLIS 30EL15

11K

d I

Many pot [RMS13 (10537) / 1099] probably (facing
20 grams. IRS in very hard, brick red fabric
except for a well-defined black layer (c 2mm's)
at inside and at upper part of flange. Thin
dark cream slip overall. Inclusions: moderate,
ill-sorted, but tiny to smallish, black, red-brown
and quartz. Interraction amt: few on small frag
transparent quartz (rare), mostly white (non-reactive)
(may have had other rocks) foot fragmentary d I

DOCILIS 3

red-brown fabric

Vindolanda [10324 and 10315 are on same mat/strin^{de} E

SF 10847 'to 102'

die B

9703, 9747, 8948

die D

not checked if any on same vessel so far
2-3 vessels

Doc 1

二

North

AiERB looseleaf

1914

Concordia [AA⁴ xxi p. 180, no. 18; US 62; 151, 61, Pit, 195K] thick, red-

pink core to buff to cream; sparsish, medium, r/b, grey. D ~~SC~~

Corbridge [AA⁴ xvi p. 180, no. 18; S. 120; 18; 196K] hard, brick red, very compact fabric; cream slip; prolific r/b, grey, medium grits. D

Chesters [2471/3782; 24K] L. facing, cream fabric with red-brown core,
softish; small + medium white and brown grit. D \$

Castle Crag, Borrowdale [Attributed to O.P.E.L. 15] D.O. no 9
Probable same die as most probably
certainly from Kinderton. Robert Lee made of

DOCC

xx

North-West.

- Rec'dt of
Carlisle, Scotch St., [Tullie House 32K] L-facing, corner of r.-facing stamp
survives; vessel made up; buff fabric apparently; large to smallish;
white, brown and grey grit, abundant in second 1" from b.b., all

completely worn away below; shape similar to 31.K. E


Carlisle [8.03 Crown + Mitre Hotel Site, English St. 41K.] L-facing D

Carlisle [Tullie House M. 72K] Assumed Carlisle - no
mark. D

~~Attributed~~ DIE K

Castile [2303] B (351) castle st 81 joins fragment? 23 68²⁰⁴⁸a

Hard, orange-brown fabric; fine-textured; moderate quartz-like & v. occ. black inclusions. Cream slip; quartz & red-brown inclusions agt... Border only survives. 105K.



DODGE LIS III

hawcaster [Mitchell's Brewery L99/109 4283. Jerry Evans 37K]

r. facing probably. fabric slightly powdery. It may have had a slip but no trace survives. Fairly fine-textured, orange-brown fabric. Inclusions vis. at x20: very ill-sorted, perhaps fairly frequent but most barely visible. Some few large orange-brown, ^{several to few pale brown s's} greyish, & black random. Interruption grit: frequent, very mixed, largely small-sized red-brown sandstone, quartz, (transparent & pinkish), & black ^{rock} material. Grit quite sharp on piece. I think it's Walton rather than W. Inclusions - some small to medium-sized and a few large P10 A

110gms . Draw 260mm . 11%

Carlisle Annetwell St. [89 ANN D (49) 503 143K] Probably ✓
slighty pinkish

r. facing. Fine textured fabric shading from buff at surface to
pink orange brown with bluish grey core. Could have a self-coloured
 slip. Inclusions: ^{moderate} _{with some} quartz, red-brown sandstone + black ~~ish~~? slate.
 Intergrit: included quartz & red-brown sandstone. D

Dr. 29.5 cms.

^{hues!}

Carlisle, The hauses [81 OGL A (308) 151K] ?L-facing. Dr. 31
 Hard, fine textured, bright orange-brown (5YR 6/8) with paler
 surface and traces of cream slip. Inclusions: very
 moderate, quartz, red-brown sandstone + iridescent flake
 Intergrit: angular quartz & red-brown sandstone. D

Cahide [Crown & Mitre Hotel; Pres. by H. T. Griffiths Esq. + A. G. O'May; 63,
Scotch St.; Sp. 21.10.; Tullie Ho. 9K] stamp fragmentary; hard, red,
fabric with cream slip; infiltration visible; some brown, grey and black
grit.

sketch

B

B

Cardenock [$cw^2 \times l vii$ p. 118 no. 3 a.; Tullie Ho. 40K] l. facing; orange-
brown fabric with buff slip; brown + grey grit, large to medium.

B

Cardenock [$cw^2 \times l vii$ p. 118 no. 3 b; Tullie Ho. 41K] soft, light, orange-brown
fabric with cream or buff slip; abundant, large to tiny, brown, grey grit
to b. b; South Rampart area (in subsoil).

B

Cardenock [$cw^2 \times l vii$ p. 118 no. 3; Tullie Ho. 44K] r. facing; same fabric
and grit; worn;

rough sketch

B

DOC1 Dic A North-West.

NB There are 2 Castlesteads in Cen. Eng.

Hadrian's Wall NY 5146.35

Castlesteads [13. 1946. 2; 1934 Excavations; Millie No. 24K] hard, brownish

pink fabric with grey core and cream slip; grey, brown and black grit. A
Warrington [presumably Wilderspool; 68' 02.8; 54K] slightly sandy fabric;
various shades of red + pink, cream slip; prolific, medium to small,
brown + grey grits to near b. b. D = c. 12^Y ins. A

HanCASTer [?? T. L & C. Ant. Soc. p. 54 no. 7 read DOC, probably not this stamp; 2K]
hard, brick-like, orangy red fabric with very slight traces of pale slip?; 1 or 2
quartz-like greyish grits near b. b.; smooth surface. A

HanCASTer Area [18; no. 32 on outside; see reference above; 13K] v. facing;
slight traces of stamp on other side of spout; hard, slightly buff, red-brown fabric;
abundant, white colourless, purplish, grey, small shiny grits, much worn at bottom; restored. A

Kate Hodgson & I.A.R. supplementary Rep. of the Cumberland
Excavations Committee for 1933-4; Excavations at Castlesteads
Town C.W. 2nd ser vol 34 159-165

Stanwix [Fort Area; Spring Excav. 1934; 71-1934-3; Stanwix School Yard;
 contemporary with roadway gravel; Tullie Ho. 18K] r.-facing; hard, buff
 fabric with darker buff slip; letter may have been made straight onto
 clay - for die overlapping on of clayon F and in border, though letters
 smoothed off; circ. D


Cardentnoch [cw² xlvii p. 118; no ③, Tullie Ho. 43K] orange-brown fabric
 with cream or buff slip; flange fragment. ~~X~~ = D

Cahirkie, Tullie House 1892 [cw² xvii, T.H.C. no. 5a+b; T.H. 1892, 74]
 "Clay, pale red" ~~not seen~~. stamped each side of spout. 70K.
 vessel not marked but the stamps appear to be those down. D

DOC EILIS

Hard Knott? [2K · Old rubbing is E.B.'s. Check any information
in E.B.'s files (none found 11.95) or in listing of Seminar Collection at
Durham. Hard, smooth, fine-textured, orange-brown
fabric. ^{Random} Some, ill-sorted, quartz, + rare brown ^{opaque} & black,
clear silt-size. Intercalations grit: quartz, red-brown sandstone
Dr. 25cm.

D'



Ravenglass [in RV76 D.S. 3 T. Potter] Two joining fragments in very hard fired, in fact, technically over-fired orange-brown fabric, fired to black at inner surface + a stain of black ^{and} on top of flange; thin buff slips; much wh. ^{and} trans. quartz; a little indeterminate grey grit.

Ravenglass [RV77 OM 21; 2K] v. faceted T. Potter. ^B ^{self-cof. pinkish} ^(+ no slip) ^{brownish} pink fabric with bluish grey core containing a good amount of grey grit to make it a little oatmeal-like in texture. Fabric is itself soft + shows brush marks readily. Trit grit may not be added but includes r/b, grey + white. Spont broken + v. shallow.

H stamp complete unless it has second ansate end. Dotted at bottom
as well as top.



DOCEILIS

D

Carlisle Millennium ex. [CAR00 MIL5 #26 2492 262K]

r.-facing. 240g Diam 190m. 48% Just normal facing
Fine-textured red-brown fabric with thin cream slip.

Some wear - slip worn away in lower half.
Inclusions: moderate to fairly frequent, minute to tiny, black
+ quartz. Trituration grit: ^{opaque} mostly, red-brown, pale brown,
black.

Carlisle Millennium ex. [CAR00 MIL5 5647 #28 266K]

? L.-facing. 50g. Some cracking under flange. Very hard,
fine-textured, red-brown fabric with cream slip. Inclusions:
minute to small mostly, rare larger red-brown + ?quartz; FF

PTD

Tort



266K Carlisle

Tortoise shell grit: large to small, red-brown (opaque);
quartz sandstone; quartz; opaque black; worn

Docci 3

Lenticle [PR81, Castle St. B (551) 2083 107K] r.fac. Hard orange-
brown fabric; moderate quartz; thin cream slip. Discolored.
Quartz black among tituration grit. L 

honest!

B


Burkitt, The hanes [CAR 81 OGH A 745] + 6 joining fragments 706
and a base 706 [52K] m. facing. Heavily worn. Hard, probably over-fired or ~~perhaps~~ more likely reduced in the firing. Inside + surface of the fabric is dark brown but then rapidly gives way to black or very near to black with brownish tinge; the core ($\frac{1}{3}$ of thickness) is a brown-red. The cream slip is discoloured. Inclusions: moderate, very ill-sorted, quartz angular + 2 different kinds. Probably some red-brown but difficult to see; 1 long straw still embedded in fabric. Interstices: angular transparent qtz, clusters of quartz grains, red-brown sandstone, grey-black? Dr. 25 cm

CIT

(hues)

Partake, The hanes [81 OGL A 718 155] r. facing Very hard,
fine textured, orange-brown fabric (2.5YR 5/6). Yellowish-buff slip.
Inclusions: sparse quartz + ?slag (blackish); occasional
small cavities in fabric. Intervening grit: quartz + red-brown
sandstone. Dr. 31 cms

J



155K Carlisle,
The hares

DOCC 1 E ??
Is this T₄9A??

North-West.

Birdoswald Turret [H. 13 (3); Tullie Ho. 31K] stamped each side of spont;
hard, dark orange fabric with dark buff slip; much, white, grey and
brown grit to b. b.

F

Cardewock [CW² xlvii no. 3]; Tullie House & bK] orange-brown fabric with
cream or buff slip; usual grit; flaked on flange; Specim. D

Ambleide [CW² xxI p. 16; fig. 3 no. 8 + Δ, + p. 19] Atmire library; "early
mortarium [8]: hard, red clay, buff slip, name DOCC in square panel;
almost certainly Hadrianic." North-east rampart of later fort.

The pottery belongs definitely to the second fort" Die E. 4K
4K Entered twice.

(1963) Teller note - O.S. 62 is cream with thick pink core.

DOC

Carlisle, Hanwell St. [CAR89 ANN D] 313 [738] 137K] r.facing.

Hard, fine-textured, orange-brown fabric; sparse, quartz +
r-b sandstone inclusions; no tint survives IRS (2.5YR 6/8)
traces of cream slip. Dr. c2b F

DOC:

For Description

North-West

20km west of Carlisle

Cardurnock [cw² XLVII p. 118 (3c); Tullie Ho. 42K] orange-brown fabric.

with cream or buff slip; little grit., brown and grey; badly
impressed;

C

Cardurnock [cw² XLVII p. 118 (3); 1st - North Rampart (1); Tullie Ho. 45K]

r. facing; same fabric and grit.

Sketch.

C

Birdoswald [420 (1593 + 57K) Hard, orange-brown fabric, paler
at surface; self-coloured; brown-buff core (7.5YR 7/6) :
(2.5YR 6/8)

moderate, ill-sorted, quartz, opaque r-b & rare black inclusions

Mineralization grit: ^{few} flakes of oolite; quartz; r-b sandstone,

B

Ambleside [Arnott Library 3K] Burnt; pinkish brown fabric with cream slip; medium, red-brown and grey grit; 2 pieces joining; D = 11" C

Ambleside [c+ w² XXI, fig. 3, facing p. 17, + p. 19] Arnott Library 4K "North-east rampart of later fort. The pottery belongs definitely to the second fort." L-facing; orange-brown fabric with redder core; cream slip; red-brown, coarser & white, medium & smallish grit E

Ambleside [not published 15K] pink fabric; stamp almost worn away A?
B Assigned only. ✓

Ambleside [1976 K. Buckitt] flange fragment. Very hard brick red fabric with drab cream slip; a little cracking under flange. 19K A

Doc C

Taylor 1991 Fig 303 no. 1

Carlisle [8] Castle St. B (555) 2077 106K] L. facing. Hard,
very fine-textured ^{red} orange-brown with v. little very tiny quartz
temper; cream slip. Mostly red sandstone but some quartz
intercalation. Very well made. Fabric differs quite a lot G.
from 107K. Slightly burnt: Some cracking under flange.

Carlisle [CAR 82 ANNA (1312) 1352 131K] Aunetwell St. Probably r. fac.
Very hard, almost sintered dark gingery brown fabric with quartz
inclusions (pebbly); thin cream or buff slip, so thin fabric shows
right through it. Intercalation: primary quartz, some sandstone,
occ. black. D=30 v. dense & heavy:
cm. C a

DOCC[~~E~~] IIS

Walton le Dale [WD96 drg 447. 770 / 9472 57K] FF
75g. Dr. 31 12% - 2 joining sherds. Burnt. Remains
of cream slipp. Powdery, soft orange-brown fabric [
Munsell 2.5 YR 6/6 'light red'], inclusions; sand-
sized, quartz. Tiny to small ^{mostly} _{few} Lgtz, (red-brown) & rare
black

L
Walton-le-Dale [WD96 drg 4 3 1. 2082 58K] L-facing.
Fine textured, ^{fine} ^{powdery} orange-brown fabric [Munsell 2.5 YR 5/6]
with paler surface. Inclusions: moderate ill-sorted quartz.
Inclusions: mainly quartz with some red-brown ss.
Powdery. May have had cream slipp but only slight possible traces.

P TO A

115g. 29cms 9%


DOCC or DOC1 F^E Doccius?

Chester (536) CRS 73/4 i ⑩ / 11 61K] in very hard,
ochre coloured fabric with orange-brown core + brownish buff slip
fired to dark grey on flange; tiny quartz (milky) in fabric.

Crook Street. Dr. said to be c. 155 mm by P.C. A-D

(184) Walton-le-Dale [WD 83 1362 ⑩ 18K] r. facing. Dr. 23 cms.
soil ^{brown} Orange fabric (5YR 6/8); fires to paler orange at surface;
inclusions quartz and red-brown fragments. Trituration
grit quartz, red-brown sandstone and 1 fragment white
feldspar. A

Walton-le-Dale [WD 96 drg. 429, 1001/75. 36K] r. facing
1.55 g. Dr. 31, 14% Traces of cream slip, cracking lengthways
under glaze. Powdery. Fine-textured, orange-brown
[Munsell 2.5 YR 6/8 'light red'] with thin pinker core
[Munsell 2.5 YR 6/4 'light reddish brown']. Inclusions:
few tiny to small, ill-s., quartz, red-brown and opaque cream
intrafibration: mostly quartz with some red-brown sandstone
and rare black(?). some sand-sized qtz but not much? in clay
DK use.



49.1965.6

Carkdale [Civic Centre Site v/c 93K] hard, orange brown fabric with

pink-brown core & traces of cream slip. Flange fragment. Gr

Carkdale [49.1965.2. Civic Centre site. 94K] complete but for pieces of flange; well-worn; creamy buff fabric with orange-brown core & dark buff slip; white, red-brown & grey titration. D

Carkdale [Civic Centre site 49.1965.6 95K] orange-brown fabric bent grey in parts. Flange fragment. B


Walton-le-dale [WD82 141 (ii). 4K] Pale brownish-orange fabric (7.5 YR 7/6), inclusions ill-sorted quartz, sparse red clay pellets and black one fragments. No titration survived. Traces of cream slip. (Fabric 39) Flange fragment. Smallish amount temper

Walton-le-Dale [WD 96 drg. 457 252 / 7707 37K]

position suggests (fac but no obvious evidence, 125g).

Dr. 30 cms 14% ^{probably traces of} No obvious slips discernible.

Powdery surface. Fine textured orange-brown [Munsell 7.5 YR
6/4 'light brown'] with thick powder core [Munsell 5 YR 5/4
'reddish brown']. Inclusions: few ^{medio} sand-sized quartz
barely visible, few random [largest] quartz, red brown
quartz sandstone. No trituration available. Fairly smooth.
No body surfaces



DOC 115 m

Birdoswald [In J. P. G's store, Newcastle 14K] r. facing; orange-brown
wlt redder core; cream slip; white + brown, smallish grit; flange
broken.

B

~~Moresby [CW² xlviii p. 65, no. 4 and fig 5, no. 4; In J. P. G.'s store; Newcastle 16K.] l. facing; hard, red-brown fabric wlt cream slip; J. P. G.
says large frequent coarse mica & micas sparse & large grit,
mostly brown, but mixed with grey & white. No close dating
evidence. — Gold's drawing gives only top of vessel. — Identified~~

^{DOC 12}
^{Die n.s.}
Birdoswald [Corstopitum M. in 1964. Old find.] Hard, brownish pink fabric
with cream slip. —

B

Doc 1 or Doc 1 (us) ? North-west England. DIE. G = D ✓

Old Penith [131-138. 7826404 8V] Slightly sandy, buff brown
near surface but mostly pink-brown with ^{thin} drab grey core; quartz
grey black & v/b tempering. No. tritn. survives. FABRIC 7. A.

Watercrook [W 80. E. 1 Pipeline 23K] L-facing worn. Slightly
powdery surface - brownish-pink fabric ~~with~~ deep cream surface,
deep surface brown & buff clay. ill-sorted; tintuation - a lot of v/b with
quartz, 1/6 inchum ill-sorted; dark brown inclusions;
a few white quartz & one or two black agts. Dr. 30 cms. D
abundant tempera ill-sorted

Newcastle, Shopford Bridge Die M. On streets of EBB. "
Never seen. "Presented by Scott. Builders Newcastle ton.
Die M


Old Find.

Carlisle [Fisher St. 509. 74K] two joining flakes with incomplete stamp p. 712 flange fragment probably from same vessel. Fine-text., hard, red-brown fabric with smooth surface; thick cream slip.

Carlisle [89 ANN D ^{Ameswell St} (287) 655 138K] r.-facing. Hard, very fine-textured, red-brown fabric (2.5 YR 5/6) with cream slip; sparse, small quartz, & fewer black inclusions. ^{Black mineral in} Int. weathering grit: quartz, red-brown sandstone & some haematite. Dr. ²⁵ 2.4cm.

Carlisle [The Lanes 1 82 OGL B (73) 302] 2 pieces joining with stamp; other fragments, not joining. 157K] r.-facing. Different vessel. Hard, orange-red-brown fabric (2.5 YR 6/8) with cream slip. Inclusions: ^{sparse quartz} P TO [&] sandstone

Inclusions: included quartz pebbles - Brown sandstone. Dr. 25 cms.



✓ Hard pink. cream slip;

Yorkshire [51K] (red-brown) fabric; abundant, large, brown, grey and white grit; Dr = 2.9cm sic c. 1500, 1331, 413000 "amphorae" probably this. C

Chester, Tullie House 1892 [72], Tullie Ho. 1K] r. facing; CW² xvii p. 196 no. 4 on no. 145; hard, haematite red-brown fabric with buff-slip; abundant, white, grey, brown and black, largest to small grits to b..b.; D = c. 12 is Maryport [CW² Cardeward, p. 189; rubbing B₂ 6K] "buff-biscuit self fabric; no grit in fragment; CW² v. p. 253; "amphora" (This is best rubbing) B

Hardwick [H/59/3; D. Charlesworth; seen] bag. Hard fine textured, compact, slightly pinkish red fabric with grey core in parts of flange, and a ^{cream} ~~pinkish~~ buff-slip; no grit or fragment, flange appears to have been drawn out and doubled back atop it itself, perhaps with object drinking bead. R T P Dr 28 D

Inclusions: some, spardic quartz, sparse opaque white
& black. (Fabric - Carlisle)

DOC 1 L 1 S 3

[B₂ 1 G, 120-160]
N.W.

CS. 43. 52 ①
Cardurnock (b) [Cw² xvii, p. 118 f. 11, 3a, b, c] red/buff fabric with cream wash,
grit mostly small and variegated but occasional large brown pieces.

Corbridge [S. 20 AH^x xxvi, p. 180, no 18] hard, brick-red with blue-grey
core, white surface slip.

Batmaddy [Hunterian Mus.],

Magnat [information to B. part H. Hoessman] buff-biscuit soft fabric; none on frag.

Chesters soft?

? Hardknott 1

B. 2 1 G Rubbing from Seminar Collⁿ at Darblay - see E.B. rubbing in
Pile - Provenance not known.

(Hardknott ?, here in Chancery)

Hardknott Unpubl. ? - B₂ Rubbing.)



L Cardurnock. (H)



18. Cambridge

AA⁴ xxvi p 180-18

DOCILIS (is not mentioned in
Campfield, Manport [TCWAAS series 1, US V, 1881,
(p 237 - 257)], p 253 - 254. Mistaken for an
amphora ^{s/20}~~handle~~. No drawing. JOCCEI read, but
full name suggested as DOCCEI. Findplace probably
NE of fort judging from plan.

DOCILIS I

? ?²
H/A

~~2~~ ? S.P.G.


Newstead [P.S. AS. 1949/50 v. 12, 7th] fabric hard brick red

with blue grey core and traces of white slip; grit brown and grey
Chestnut or tree.

I. Mortar (John

CW¹, XII, 264

(~~1949/50~~)
~~Camphfield~~ [CW, v, p. 253 +]; - ~~Test~~ ~~1~~ ~~2~~ ~~3~~ ~~4~~ ~~5~~ ~~6~~ ~~7~~ ~~8~~ ~~9~~ ~~10~~ ~~11~~ ~~12~~ ~~13~~ ~~14~~ ~~15~~ ~~16~~ ~~17~~ ~~18~~ ~~19~~ ~~20~~ ~~21~~ ~~22~~ ~~23~~ ~~24~~ ~~25~~ ~~26~~ ~~27~~ ~~28~~ ~~29~~ ~~30~~ ~~31~~ ~~32~~ ~~33~~ ~~34~~ ~~35~~ ~~36~~ ~~37~~ ~~38~~ ~~39~~ ~~40~~ ~~41~~ ~~42~~ ~~43~~ ~~44~~ ~~45~~ ~~46~~ ~~47~~ ~~48~~ ~~49~~ ~~50~~ ~~51~~ ~~52~~ ~~53~~ ~~54~~ ~~55~~ ~~56~~ ~~57~~ ~~58~~ ~~59~~ ~~60~~ ~~61~~ ~~62~~ ~~63~~ ~~64~~ ~~65~~ ~~66~~ ~~67~~ ~~68~~ ~~69~~ ~~70~~ ~~71~~ ~~72~~ ~~73~~ ~~74~~ ~~75~~ ~~76~~ ~~77~~ ~~78~~ ~~79~~ ~~80~~ ~~81~~ ~~82~~ ~~83~~ ~~84~~ ~~85~~ ~~86~~ ~~87~~ ~~88~~ ~~89~~ ~~90~~ ~~91~~ ~~92~~ ~~93~~ ~~94~~ ~~95~~ ~~96~~ ~~97~~ ~~98~~ ~~99~~ ~~100~~ ~~101~~ ~~102~~ ~~103~~ ~~104~~ ~~105~~ ~~106~~ ~~107~~ ~~108~~ ~~109~~ ~~110~~ ~~111~~ ~~112~~ ~~113~~ ~~114~~ ~~115~~ ~~116~~ ~~117~~ ~~118~~ ~~119~~ ~~120~~ ~~121~~ ~~122~~ ~~123~~ ~~124~~ ~~125~~ ~~126~~ ~~127~~ ~~128~~ ~~129~~ ~~130~~ ~~131~~ ~~132~~ ~~133~~ ~~134~~ ~~135~~ ~~136~~ ~~137~~ ~~138~~ ~~139~~ ~~140~~ ~~141~~ ~~142~~ ~~143~~ ~~144~~ ~~145~~ ~~146~~ ~~147~~ ~~148~~ ~~149~~ ~~150~~ ~~151~~ ~~152~~ ~~153~~ ~~154~~ ~~155~~ ~~156~~ ~~157~~ ~~158~~ ~~159~~ ~~160~~ ~~161~~ ~~162~~ ~~163~~ ~~164~~ ~~165~~ ~~166~~ ~~167~~ ~~168~~ ~~169~~ ~~170~~ ~~171~~ ~~172~~ ~~173~~ ~~174~~ ~~175~~ ~~176~~ ~~177~~ ~~178~~ ~~179~~ ~~180~~ ~~181~~ ~~182~~ ~~183~~ ~~184~~ ~~185~~ ~~186~~ ~~187~~ ~~188~~ ~~189~~ ~~190~~ ~~191~~ ~~192~~ ~~193~~ ~~194~~ ~~195~~ ~~196~~ ~~197~~ ~~198~~ ~~199~~ ~~200~~ ~~201~~ ~~202~~ ~~203~~ ~~204~~ ~~205~~ ~~206~~ ~~207~~ ~~208~~ ~~209~~ ~~210~~ ~~211~~ ~~212~~ ~~213~~ ~~214~~ ~~215~~ ~~216~~ ~~217~~ ~~218~~ ~~219~~ ~~220~~ ~~221~~ ~~222~~ ~~223~~ ~~224~~ ~~225~~ ~~226~~ ~~227~~ ~~228~~ ~~229~~ ~~230~~ ~~231~~ ~~232~~ ~~233~~ ~~234~~ ~~235~~ ~~236~~ ~~237~~ ~~238~~ ~~239~~ ~~240~~ ~~241~~ ~~242~~ ~~243~~ ~~244~~ ~~245~~ ~~246~~ ~~247~~ ~~248~~ ~~249~~ ~~250~~ ~~251~~ ~~252~~ ~~253~~ ~~254~~ ~~255~~ ~~256~~ ~~257~~ ~~258~~ ~~259~~ ~~260~~ ~~261~~ ~~262~~ ~~263~~ ~~264~~ ~~265~~ ~~266~~ ~~267~~ ~~268~~ ~~269~~ ~~270~~ ~~271~~ ~~272~~ ~~273~~ ~~274~~ ~~275~~ ~~276~~ ~~277~~ ~~278~~ ~~279~~ ~~280~~ ~~281~~ ~~282~~ ~~283~~ ~~284~~ ~~285~~ ~~286~~ ~~287~~ ~~288~~ ~~289~~ ~~290~~ ~~291~~ ~~292~~ ~~293~~ ~~294~~ ~~295~~ ~~296~~ ~~297~~ ~~298~~ ~~299~~ ~~300~~ ~~301~~ ~~302~~ ~~303~~ ~~304~~ ~~305~~ ~~306~~ ~~307~~ ~~308~~ ~~309~~ ~~310~~ ~~311~~ ~~312~~ ~~313~~ ~~314~~ ~~315~~ ~~316~~ ~~317~~ ~~318~~ ~~319~~ ~~320~~ ~~321~~ ~~322~~ ~~323~~ ~~324~~ ~~325~~ ~~326~~ ~~327~~ ~~328~~ ~~329~~ ~~330~~ ~~331~~ ~~332~~ ~~333~~ ~~334~~ ~~335~~ ~~336~~ ~~337~~ ~~338~~ ~~339~~ ~~340~~ ~~341~~ ~~342~~ ~~343~~ ~~344~~ ~~345~~ ~~346~~ ~~347~~ ~~348~~ ~~349~~ ~~350~~ ~~351~~ ~~352~~ ~~353~~ ~~354~~ ~~355~~ ~~356~~ ~~357~~ ~~358~~ ~~359~~ ~~360~~ ~~361~~ ~~362~~ ~~363~~ ~~364~~ ~~365~~ ~~366~~ ~~367~~ ~~368~~ ~~369~~ ~~370~~ ~~371~~ ~~372~~ ~~373~~ ~~374~~ ~~375~~ ~~376~~ ~~377~~ ~~378~~ ~~379~~ ~~380~~ ~~381~~ ~~382~~ ~~383~~ ~~384~~ ~~385~~ ~~386~~ ~~387~~ ~~388~~ ~~389~~ ~~390~~ ~~391~~ ~~392~~ ~~393~~ ~~394~~ ~~395~~ ~~396~~ ~~397~~ ~~398~~ ~~399~~ ~~400~~ ~~401~~ ~~402~~ ~~403~~ ~~404~~ ~~405~~ ~~406~~ ~~407~~ ~~408~~ ~~409~~ ~~410~~ ~~411~~ ~~412~~ ~~413~~ ~~414~~ ~~415~~ ~~416~~ ~~417~~ ~~418~~ ~~419~~ ~~420~~ ~~421~~ ~~422~~ ~~423~~ ~~424~~ ~~425~~ ~~426~~ ~~427~~ ~~428~~ ~~429~~ ~~430~~ ~~431~~ ~~432~~ ~~433~~ ~~434~~ ~~435~~ ~~436~~ ~~437~~ ~~438~~ ~~439~~ ~~440~~ ~~441~~ ~~442~~ ~~443~~ ~~444~~ ~~445~~ ~~446~~ ~~447~~ ~~448~~ ~~449~~ ~~450~~ ~~451~~ ~~452~~ ~~453~~ ~~454~~ ~~455~~ ~~456~~ ~~457~~ ~~458~~ ~~459~~ ~~460~~ ~~461~~ ~~462~~ ~~463~~ ~~464~~ ~~465~~ ~~466~~ ~~467~~ ~~468~~ ~~469~~ ~~470~~ ~~471~~ ~~472~~ ~~473~~ ~~474~~ ~~475~~ ~~476~~ ~~477~~ ~~478~~ ~~479~~ ~~480~~ ~~481~~ ~~482~~ ~~483~~ ~~484~~ ~~485~~ ~~486~~ ~~487~~ ~~488~~ ~~489~~ ~~490~~ ~~491~~ ~~492~~ ~~493~~ ~~494~~ ~~495~~ ~~496~~ ~~497~~ ~~498~~ ~~499~~ ~~500~~ ~~501~~ ~~502~~ ~~503~~ ~~504~~ ~~505~~ ~~506~~ ~~507~~ ~~508~~ ~~509~~ ~~510~~ ~~511~~ ~~512~~ ~~513~~ ~~514~~ ~~515~~ ~~516~~ ~~517~~ ~~518~~ ~~519~~ ~~520~~ ~~521~~ ~~522~~ ~~523~~ ~~524~~ ~~525~~ ~~526~~ ~~527~~ ~~528~~ ~~529~~ ~~530~~ ~~531~~ ~~532~~ ~~533~~ ~~534~~ ~~535~~ ~~536~~ ~~537~~ ~~538~~ ~~539~~ ~~540~~ ~~541~~ ~~542~~ ~~543~~ ~~544~~ ~~545~~ ~~546~~ ~~547~~ ~~548~~ ~~549~~ ~~550~~ ~~551~~ ~~552~~ ~~553~~ ~~554~~ ~~555~~ ~~556~~ ~~557~~ ~~558~~ ~~559~~ ~~560~~ ~~561~~ ~~562~~ ~~563~~ ~~564~~ ~~565~~ ~~566~~ ~~567~~ ~~568~~ ~~569~~ ~~570~~ ~~571~~ ~~572~~ ~~573~~ ~~574~~ ~~575~~ ~~576~~ ~~577~~ ~~578~~ ~~579~~ ~~580~~ ~~581~~ ~~582~~ ~~583~~ ~~584~~ ~~585~~ ~~586~~ ~~587~~ ~~588~~ ~~589~~ ~~590~~ ~~591~~ ~~592~~ ~~593~~ ~~594~~ ~~595~~ ~~596~~ ~~597~~ ~~598~~ ~~599~~ ~~600~~ ~~601~~ ~~602~~ ~~603~~ ~~604~~ ~~605~~ ~~606~~ ~~607~~ ~~608~~ ~~609~~ ~~610~~ ~~611~~ ~~612~~ ~~613~~ ~~614~~ ~~615~~ ~~616~~ ~~617~~ ~~618~~ ~~619~~ ~~620~~ ~~621~~ ~~622~~ ~~623~~ ~~624~~ ~~625~~ ~~626~~ ~~627~~ ~~628~~ ~~629~~ ~~630~~ ~~631~~ ~~632~~ ~~633~~ ~~634~~ ~~635~~ ~~636~~ ~~637~~ ~~638~~ ~~639~~ ~~640~~ ~~641~~ ~~642~~ ~~643~~ ~~644~~ ~~645~~ ~~646~~ ~~647~~ ~~648~~ ~~649~~ ~~650~~ ~~651~~ ~~652~~ ~~653~~ ~~654~~ ~~655~~ ~~656~~ ~~657~~ ~~658~~ ~~659~~ ~~660~~ ~~661~~ ~~662~~ ~~663~~ ~~664~~ ~~665~~ ~~666~~ ~~667~~ ~~668~~ ~~669~~ ~~670~~ ~~671~~ ~~672~~ ~~673~~ ~~674~~ ~~675~~ ~~676~~ ~~677~~ ~~678~~ ~~679~~ ~~680~~ ~~681~~ ~~682~~ ~~683~~ ~~684~~ ~~685~~ ~~686~~ ~~687~~ ~~688~~ ~~689~~ ~~690~~ ~~691~~ ~~692~~ ~~693~~ ~~694~~ ~~695~~ ~~696~~ ~~697~~ ~~698~~ ~~699~~ ~~700~~ ~~701~~ ~~702~~ ~~703~~ ~~704~~ ~~705~~ ~~706~~ ~~707~~ ~~708~~ ~~709~~ ~~710~~ ~~711~~ ~~712~~ ~~713~~ ~~714~~ ~~715~~ ~~716~~ ~~717~~ ~~718~~ ~~719~~ ~~720~~ ~~721~~ ~~722~~ ~~723~~ ~~724~~ ~~725~~ ~~726~~ ~~727~~ ~~728~~ ~~729~~ ~~730~~ ~~731~~ ~~732~~ ~~733~~ ~~734~~ ~~735~~ ~~736~~ ~~737~~ ~~738~~ ~~739~~ ~~740~~ ~~741~~ ~~742~~ ~~743~~ ~~744~~ ~~745~~ ~~746~~ ~~747~~ ~~748~~ ~~749~~ ~~750~~ ~~751~~ ~~752~~ ~~753~~ ~~754~~ ~~755~~ ~~756~~ ~~757~~ ~~758~~ ~~759~~ ~~760~~ ~~761~~ ~~762~~ ~~763~~ ~~764~~ ~~765~~ ~~766~~ ~~767~~ ~~768~~ ~~769~~ ~~770~~ ~~771~~ ~~772~~ ~~773~~ ~~774~~ ~~775~~ ~~776~~ ~~777~~ ~~778~~ ~~779~~ ~~780~~ ~~781~~ ~~782~~ ~~783~~ ~~784~~ ~~785~~ ~~786~~ ~~787~~ ~~788~~ ~~789~~ ~~790~~ ~~791~~ ~~792~~ ~~793~~ ~~794~~ ~~795~~ ~~796~~ ~~797~~ ~~798~~ ~~799~~ ~~800~~ ~~801~~ ~~802~~ ~~803~~ ~~804~~ ~~805~~ ~~806~~ ~~807~~ ~~808~~ ~~809~~ ~~810~~ ~~811~~ ~~812~~ ~~813~~ ~~814~~ ~~815~~ ~~816~~ ~~817~~ ~~818~~ ~~819~~ ~~820~~ ~~821~~ ~~822~~ ~~823~~ ~~824~~ ~~825~~ ~~826~~ ~~827~~ ~~828~~ ~~829~~ ~~830~~ ~~831~~ ~~832~~ ~~833~~ ~~834~~ ~~835~~ ~~836~~ ~~837~~ ~~838~~ ~~839~~ ~~840~~ ~~841~~ ~~842~~ ~~843~~ ~~844~~ ~~845~~ ~~846~~ ~~847~~ ~~848~~ ~~849~~ ~~850~~ ~~851~~ ~~852~~ ~~853~~ ~~854~~ ~~855~~ ~~856~~ ~~857~~ ~~858~~ ~~859~~ ~~860~~ ~~861~~ ~~862~~ ~~863~~ ~~864~~ ~~865~~ ~~866~~ ~~867~~ ~~868~~ ~~869~~ ~~870~~ ~~871~~ ~~872~~ ~~873~~ ~~874~~ ~~875~~ ~~876~~ ~~877~~ ~~878~~ ~~879~~ ~~880~~ ~~881~~ ~~882~~ ~~883~~ ~~884~~ ~~885~~ ~~886~~ ~~887~~ ~~888~~ ~~889~~ ~~890~~ ~~891~~ ~~892~~ ~~893~~ ~~894~~ ~~895~~ ~~896~~ ~~897~~ ~~898~~ ~~899~~ ~~900~~ ~~901~~ ~~902~~ ~~903~~ ~~904~~ ~~905~~ ~~906~~ ~~907~~ ~~908~~ ~~909~~ ~~910~~ ~~911~~ ~~912~~ ~~913~~ ~~914~~ ~~915~~ ~~916~~ ~~917~~ ~~918~~ ~~919~~ ~~920~~ ~~921~~ ~~922~~ ~~923~~ ~~924~~ ~~925~~ ~~926~~ ~~927~~ ~~928~~ ~~929~~ ~~930~~ ~~931~~ ~~932~~ ~~933~~ ~~934~~ ~~935~~ ~~936~~ ~~937~~ ~~938~~ ~~939~~ ~~940~~ ~~941~~ ~~942~~ ~~943~~ ~~944~~ ~~945~~ ~~946~~ ~~947~~ ~~948~~ ~~949~~ ~~950~~ ~~951~~ ~~952~~ ~~953~~ ~~954~~ ~~955~~ ~~956~~ ~~957~~ ~~958~~ ~~959~~ ~~960~~ ~~961~~ ~~962~~ ~~963~~ ~~964~~ ~~965~~ ~~966~~ ~~967~~ ~~968~~ ~~969~~ ~~970~~ ~~971~~ ~~972~~ ~~973~~ ~~974~~ ~~975~~ ~~976~~ ~~977~~ ~~978~~ ~~979~~ ~~980~~ ~~981~~ ~~982~~ ~~983~~ ~~984~~ ~~985~~ ~~986~~ ~~987~~ ~~988~~ ~~989~~ ~~990~~ ~~991~~ ~~992~~ ~~993~~ ~~994~~ ~~995~~ ~~996~~ ~~997~~ ~~998~~ ~~999~~ ~~1000~~ ~~1001~~ ~~1002~~ ~~1003~~ ~~1004~~ ~~1005~~ ~~1006~~ ~~1007~~ ~~1008~~ ~~1009~~ ~~1010~~ ~~1011~~ ~~1012~~ ~~1013~~ ~~1014~~ ~~1015~~ ~~1016~~ ~~1017~~ ~~1018~~ ~~1019~~ ~~1020~~ ~~1021~~ ~~1022~~ ~~1023~~ ~~1024~~ ~~1025~~ ~~1026~~ ~~1027~~ ~~1028~~ ~~1029~~ ~~1030~~ ~~1031~~ ~~1032~~ ~~1033~~ ~~1034~~ ~~1035~~ ~~1036~~ ~~1037~~ ~~1038~~ ~~1039~~ ~~1040~~ ~~1041~~ ~~1042~~ ~~1043~~ ~~1044~~ ~~1045~~ ~~1046~~ ~~1047~~ ~~1048~~ ~~1049~~ ~~1050~~ ~~1051~~ ~~1052~~ ~~1053~~ ~~1054~~ ~~1055~~ ~~1056~~ ~~1057~~ ~~1058~~ ~~1059~~ ~~1060~~ ~~1061~~ ~~1062~~ ~~1063~~ ~~1064~~ ~~1065~~ ~~1066~~ ~~1067~~ ~~1068~~ ~~1069~~ ~~1070~~ ~~1071~~ ~~1072~~ ~~1073~~ ~~1074~~ ~~1075~~ ~~1076~~ ~~1077~~ ~~1078~~ ~~1079~~ ~~1080~~ ~~1081~~ ~~1082~~ ~~1083~~ ~~1084~~ ~~1085~~ ~~1086~~ ~~1087~~ ~~1088~~ ~~1089~~ ~~1090~~ ~~1091~~ ~~1092~~ ~~1093~~ ~~1094~~ ~~1095~~ ~~1096~~ ~~1097~~ ~~1098~~ ~~1099~~ ~~1100~~ ~~1101~~ ~~1102~~ ~~1103~~ ~~1104~~ ~~1105~~ ~~1106~~ ~~1107~~ ~~1108~~ ~~1109~~ ~~1110~~ ~~1111~~ ~~1112~~ ~~1113~~ ~~1114~~ ~~1115~~ ~~1116~~ ~~1117~~ ~~1118~~ ~~1119~~ ~~1120~~ ~~1121~~ ~~1122~~ ~~1123~~ ~~1124~~ ~~1125~~ ~~1126~~ ~~1127~~ ~~1128~~ ~~1129~~ ~~1130~~ ~~1131~~ ~~1132~~ ~~1133~~ ~~1134~~ ~~1135~~ ~~1136~~ ~~1137~~ ~~1138~~ ~~1139~~ ~~1140~~ ~~1141~~ ~~1142~~ ~~1143~~ ~~1144~~ ~~1145~~ ~~1146~~ ~~1147~~ ~~1148~~ ~~1149~~ ~~1150~~ ~~1151~~ ~~1152~~ ~~1153~~ ~~1154~~ ~~1155~~ ~~1156~~ ~~1157~~ ~~1158~~ ~~1159~~ ~~1160~~ ~~1161~~ ~~1162~~ ~~1163~~ ~~1164~~ ~~1165~~ ~~1166~~ ~~1167~~ ~~1168~~ ~~1169~~ ~~1170~~ ~~1171~~ ~~1172~~ ~~1173~~ ~~1174~~ ~~1175~~ ~~1176~~ ~~1177~~ ~~1178~~ ~~1179~~ ~~1180~~ ~~1181~~ ~~1182~~ ~~1183~~ ~~1184~~ ~~1185~~ ~~1186~~ ~~1187~~ ~~1188~~ ~~1189~~ ~~1190~~ ~~1191~~ ~~1192~~ ~~1193~~ ~~1194~~ ~~1195~~ ~~1196~~ ~~1197~~ ~~1198~~ ~~1199~~ ~~1200~~ ~~1201~~ ~~1202~~ ~~1203~~ ~~1204~~ ~~1205~~ ~~1206~~ ~~1207~~ ~~1208~~ ~~1209~~ ~~1210~~ ~~1211~~ ~~1212~~ ~~1213~~ ~~1214~~ ~~1215~~ ~~1216~~ ~~1217~~ ~~1218~~ ~~1219~~ ~~1220~~ ~~1221~~ ~~1222~~ ~~1223~~ ~~1224~~ ~~1225~~ ~~1226~~ ~~1227~~ ~~1228~~ ~~1229~~ ~~1230~~ ~~1231~~ ~~1232~~ ~~1233~~ ~~1234~~ ~~1235~~ ~~1236~~ ~~1237~~ ~~1238~~ ~~1239~~ ~~1240~~ ~~1241~~ ~~1242~~ ~~1243~~ ~~1244~~ ~~1245~~ ~~1246~~ ~~1247~~ ~~1248~~ ~~1249~~ ~~1250~~ ~~1251~~ ~~1252~~ ~~1253~~ ~~1254~~ ~~1255~~ ~~1256~~ ~~1257~~ ~~1258~~ ~~1259~~ ~~1260~~ ~~1261~~ ~~1262~~ ~~1263~~ ~~1264~~ ~~1265~~ ~~1266~~ ~~1267~~ ~~1268~~ ~~1269~~ ~~1270~~ ~~1271~~ ~~1272~~ ~~1273~~ ~~1274~~ ~~1275~~ ~~1276~~ ~~1277~~ ~~1278~~ ~~1279~~ ~~1280~~ ~~1281~~ ~~1282~~ ~~1283~~ ~~1284~~ ~~1285~~ ~~1286~~ ~~1287~~ ~~1288~~ ~~1289~~ ~~1290~~ ~~1291~~ ~~1292~~ ~~1293~~ ~~1294~~ ~~1295~~ ~~1296~~ ~~1297~~ ~~1298~~ ~~1299~~ ~~1300~~ ~~1301~~ ~~1302~~ ~~1303~~ ~~1304~~ ~~1305~~ ~~1306~~ ~~1307~~ ~~1308~~ ~~1309~~ ~~1310~~



DOC1 or DOC21 III McCarthy 1990 fig 195, no. 10

Period 9a

Carlisle, Blackfriars St [357] CAR78BLA.B 515 P(36)

81K] Very hard, deep dark red fabric (1) with quartz
tempering & cream slip. Flange & head only. Dr. c. 27B.

Manyport [In the House 76.1958] ^{see Campfield} creamy fabric. 7K - B

Bowness on Solway [Potter, Romans in North-West England, 346 no


4 + 341, no. 33 + fig. 139 no. 33. Die uncertain ^{Aris and} B

Campfield (^{Adapted} CWV p. 253). Check this - may = Manyport
probably B

TK

Rodentia by Mayport Stamp

& this is it



No - Eric has Campfield &
another Mayport on card.
Check big loose leaves
& folders when found.

Montorium stamp from Campfield, Mayport 1956

Tullie House Museum, Acc. no. 76-1958

D. A. Welsby
Muncaster

DOEL 12

Trans C & Westmorland antiquarian
+ archaeological (Cw p. 64)

^{GSC}

Moresby [Cw² xx viii, p. 65, no 4 & fig. 5, no. 4] In JPGs store.

Newcastle 16 K] L-facing. hard, red-brown fabric with cream slip. JPG says he saw a larger fragment of same vessel & mentions sparse & large grit, mostly brown but mixed with grey & white. No close dating evidence - my drawing gives only top of vessel. I

Carlisle, Blackfriars Street [320] CAR 78 BLA D + 82 K

Very hard, dense, dark red fabric with fine quartz & red-brown (? ironstone or slag) tempering. Cream slip. Overfired in part. Dr. c. 52 cms. Flange only. A I

Castle Crag, Borrowdale Inked in rubbing from E.B.
probably O.K. Rubbing by E.B.B. I

DOCILIS 3 Fabric differs significantly from the other 2 from
Inveresk [PPCM 3 - Zone 8 M10 54 NK] L. facing 335g

Diameter 300 mm 18% Fabric differs M7 & H15.
Outside probably smoothed but fabric is ^{quite} granular.
Some holes in fabric. Pale brown fabric with slightly
greyish core. Inclusions: frequent, ill-sorted, mostly
quartz, with some black & rare red-brown. Intervaller
grit: mixed black and quartz, frequent. Well-
worn, & surface in lowest third ~~abraded~~ ^{eroded} inside,
rather than worn.

The matam has a ractian (purple) ship in bottom of head
over flange right.

DOCILIS 3

DIE 4

Inveresk [M7 3 - 7^{1/2} 5 PPCM 52 NK] v. facing 160g.

Diam 240m. 17% Orange-brown fabric with streaks
of cream clay. Cream slips. Inclusions: random,
moderate, ill-sorted. Fabric poorly mixed, v.
streaky sometimes cream v. thin. Inturcation: quartz,
red-brown sandstone, no black unless rare. scorched
/ burnt end of flange at spont area only. S DIE 4

Inveresk [M15 64 3 PPCM 53 NK] Likely to be (facing
60g. Diameter 230m. 17% Hard red-brown fabric, cream
slip. Inclusions: moderate, very ill-sorted, ^{fine-textured} quartz, black &
grey. Inturcation: quartz, black (blk) few survive
S Too high for ^{burnt} cream.

DOC 115 SG 3

STAMPS FROM N.W. ENGLAND
SCOTLAND,
B.C. + J.P.G.

Balmuidy [pl. x, unpublished F. 1922.31.6 Hunterian M. 12K] pale,
 $D =$

pinkish buff fabric; abundant grey & brown grit to b. b. D = 11 ins. G

Newstead [IAR; Dept. of A., Durham; PSAS 1949/50 p 34]
LXXXIV P 34 (1963) 31K + DC I

red fabric with grey core in flange; orange cream-slip; larger brown
& medium white, brown & black grit. Ant. T.S. A Impasto D

Barburgh Mill [David Rosevear.] Orange fabric with a cream slip + D
mixed grit. NOT = 250 N. Britannia V, 1974, 157, fig. 6 no 2023

Kirknewton (Beth Hanson) PSAS 110, 1978-80 p^{no 1} 300
edge of stp, attributed by J.P.G.

Fairly well made. A bell-shaped base, with a flat top, decorated with

DOC(E)ILIS at least! B6 top 2004, no. 10 scotland
Inveresk [FV #97 Hidden between military and 1st.civilian

28K] 40g. Diam. c 20cm. (6%) Fragmentary stamp
Softish, very fine-textured, orange-brown fabric (Munsell
5 YR 6/7 'reddish yellow') with unusual greyish brown
core (Munsell 5 YR 6/3 'light reddish brown') in upper
part of body, and fired to grey at uppermost rimmed
flange. There are traces of cream slip. Inclusions: (5)
ill-sorted, random quartz and some opaque black material

Inveresk [FV 461 Post-Roman 27K] 45g. Diam 27cm.
[7%]

Fine-textured cream fabric (Munsell 10 YR 8/3
'very pale brown'), slightly pinkish in parts; Inclusions:
moderate to fairly frequent, ill-sorted inclusions including PTO

1 large black grit (5 mm). The small fragment has
few opaque black and quartz \downarrow Intercrystalline grits.)

Bishop 2004, no. 40

Carzield [Dumfries M. no no.] r. fac. pink brown core (thick);
 rest cream, surface darker cream; red-brown + white grit.
 Thought to be Carzield. D

Carzield [Dumfries M. c. 1/64] Die D.

Inveresk [66 + 142] two no. 16 NK] L. facing; fine-textured, pink-brown
 fabric with cream-buff slip with some fine quartz tempering; trituration transp
 + milky quartz; red-brown s. s. of black. St. micaceous;
 either Carlisle area or Scotland. D

Docc D

Dr. 27 cms

Cameron [79] CAM 76 AQ Site A v/s 29K] Flange Fragment

Soft, durable cream fabric with thick brownish pink core; some inclusions: quartz, red-brown + blackish [23] CAM 76 A? v/s. CR

Cameron ? Docc D [67] 1977 D1 Topsoil CAM 77 A2 30K

Orange-brown fabric with traces of cream st. p; inclusions as above. flange fragment In Cameron enclosure

JONS Ser nos. 291, 212, Ser no 292 No doubt it is
DOCILIS 3 - difficult to nib; die not certain?

Cameron [Falkirk H 1972-64-166] U facing die D

Newstead [FRA 14.91; VII. 15.83; N.M.A. 132K] fragment only; cream fabric, smooth surface.

E

Camerdon [⑬ 1976 Site C 266 IIk] I. facing, die D. Cream PTO fabric with thick pale orange core inclusions of quartz on the surface; the fabric is rather fine textured but with moderate, sparse quartz and red-brown fragments. ~~one common~~ Trituration grit ^{pink & sand-sized (quartz)} quartz and red-brown fragments. Dr. 22 cm. TMS 12K D

Camerdon [⑭ CAM 76 PB Site A 190. 125] FF. with stamp and graffiti. Brownish-cream fabric with thick pale orange core, ^{pinkish} blockish inclusions quartz and red-brown fragments. No trituration grit survives, but some reddish-brown sandstone and quartz fragments on fringe. Dr. c. 22 ⑬ + ⑭ are pot.

501 ✓
13 ✓ 468 / 166 / 8 / 461 / 168 / 433 + 462

DOC(E)ILIS

Stamps at Fisher St - not entered
in catalog Die B.
front die

Cavendish, Fisher ST [FISH 044; 274K] L.Facing

See JRPS for all the stamps from
both dies

(NB Old fund 74K was from Fisher St)

DOC EILIS

Carlisle, Fisher St. [FISH 043; 280K] IRS. 15 gms. Fabric X 2;

Tiny part of top right hand corner of a stamp from die B. Has some coarse broken concentric grit on inside on small shard surviving (at top under bead) and deliberate concentric scoring/grooving on outside of body. Smallish to small, tabularian grit (red-brown ss, flk material trace quartz on shard packed together; in some places upto b. bead; grit larger than with finer con. sc. in Hellenic period. Only identified: id nature of site.

B

Carlisle, Fisher St [FISH 044; 274K] Uracin

DOINVS

73g shards.

PTO

Castleford [728] CAS 81 S10 L431 1485 35k r.facing. Cream
probably ~~was~~ as much as in Secondus. somewhat ill-sorted ~~flint~~
fabric, granular texture, abundant inclusions angular quartz
sparse red-brown fragments. Trituration grit quartz. Dr. 37 cms.
Heavily worn & burnt. Some accretion die B

Castleford [718] CAS 81 S10 L440 48k F.F. fragmentary stamp.
orange-brown fabric almost granular texture, frequent (above)
inclusions of quartz, sparse red-brown fragments. No
trituration grit survives, but a few flint fragments
on upper surface of flange, fired to darker orange-
brown at the surface or maybe a slip. die 4
PTO

35K

728 joins no 664 CAS⁸⁰/81 S10 L749 and no 669 CAS⁸⁰/81
S10 783 (431 et al) ALL join. Not joining but
probably from same pot are 3 joining body sherds L431
& 2 joining rim sherds.

48K Same pot as no. 688 CAS 81 S10 L414 joining no 646
CAS 81 S10 L700. Both stamps survive.

DONVS

(4)

Buxton M [13.K. no prov. probably local] coarse, orangy buff fabric to creamish buff surface but badly flaked, ^{reddish} a few medium black grits. B.

Buxton M [14.K. no prov. probably local; M. Holmes Collection V.10] sandy, grey cream fabric with ? buff surface; flange ^{thd.} only. Doinus type of BF 34. r. facing.

Castleshaw [M/c Museum; M.7, R.241, F.R.5] BF 34; l. facing; sandy, cream buff fabric with cream slip; small to medium white, brown grey grits; not many surviving to ur.b.
for Interim Report facing p. 27

D = c. 11½ ins. Found in the rampart of the inner fort July 27/08.

Mablethorpe, freshwater [32.55 Lincoln M. C.F. Campion's collection; provenance not entirely without doubt but water worn. D. Petch.] "white, sandy, v. hard fabric; surface cream to buff." Seeh again A April 2012. m. facing. Not water worn. Worn smooth. PTO

Packed with quartz (rounded) fairly well sorted with v. rare
orange-brown. Had a cream slip fired to brownish-buff near
spout. So heavily worn that v. few. tiny grits survive,
flint & quartz, rare orange-brown, (would also have
quartz). Diam. 320mm. 21% S A

D01NVS / name of a gypsum quarry

NOTES

Bantock [c SK 813488, near Newark, BAN T-05 167-104]

[K] IRS. Cream fabric with thick pinkish-brown core.
Inclusions: packed with moderately well-sorted quartz
grains. Triangular; only 1 flint grit survives. Note A
(Rural Settlement Context has pottery of late 1 - early 2 but
not further details)

DONVS

Camps

Tort Hill East [M13 THE AI(m)96 5046 3K] m. Sawtry.

Flange fragment, granular fabric grey either fired to grey
or burnt throughout. Reads from outside Die B.
Packed with quartz, rare opaque orange-brown.

Rocester [Esmonde Cleary and Fenn 1996 p 67, no. 8
13.83 and fig. 29, no. 8: mortarium with both stamps
never submitted for report. Check die B

Cripplegate Fatt, London [Mus Acc Site WO097 Context 152 615K]
L-facing - IRS. Drab greyish fabric with dark discoloured
slips. Packed with tiny almost entirely quartz with very rare
black red-brown material. No tubular or surviving. Counterstamped

POINUS

Castleford [no 985] Context 1073 SF 746 Joins. no 997 CAS 84. 15 V 1103
not joining (3 joining frags) - no 1023 CAS 84 15 V 1066 3rd.

Joinus no. 1000 CAS 84 15 1073. 53K C. facing.

Pale brown at surface but dark pink in thick areas at surface, in parts. Abundant inclusions: frequency as in KPK not as many as in Secondaries. Has had a slip - dark discoloured. All tubulation worn away except below bead.

Slight traces of concentric scoring may survive there. None on flange. Dr. £ 33cm B

Darbridge, Kirkham [Howard-Davis C & Buxton K, 2000] mentioned,
not published, KD94 277/1200 Phase 3.1. Rubbing test L.
H.W.L.

DOINVS

f B 246, 2 : - 120

DOINW (3)

31?

(Cinema 1936 E.B.)

? cont

Chester [sic honest] Box 50. Buff grey fabric with dark grey surface; a little black and white grit.


D

Park St Villa [Arch. 5, 192 p. 96]; buff ware

Wroxeter [Arch. 88, 1938 (p 222)];


Brockley Hill [Arch. 1928, vol. I, part III, p 270 (note);

Hereford [p 147 no 10 and p 214 f 95 C 4] buff with white and black grit



Mr. Chesterfield.

II from 7 1/2



DO DO

Park St., Arch. J 102 p. 96.



Wroxeter F. 14.2 Y

DOLINUS ED

(2)

Veniaminoff [Ver. 59. X II +; 168K] - facing most probably; sandy, muddy

coloured greyish brown fabric with dark grey surface, presumably a
slip mixture; inside discoloured in bands of brown, dark grey, &/ or brown;
a slight accidental glazing in parts (? water rising); much, white
(quartz), and some black, medium and small quartz tab. b; some
white grit stuck in outside of body; no fine but used thick.

Alcester [Mahany 66 U/S 23K] dented by finger under
stamp. Sandy orange-brown fabric containing some grit.
flue & bead fragment. Stamp incompletely impressed.
Depression under flange under stamp.

DOINVS D

Cambridge [RGSS II 26 SH/CJ. 13K] flange fragment in
orange-brown fabric coarsened by addition of much quartz;
dark reddish slips.

Bishops Stortford TL. 42.490220 [Int. C. Partridge 66 BS BWI.

" Hard pinkish-buff fabric with largeish inclusions of qtz & flint.

Magnovium Dropshot, Bucks [1659; 17-220Δ KK] flange fragment.
discoloured throughout to drab brownish-grey; granular
fabric, packed with quartz inclusions.

Wood Borcote [F205 Black Fill Layer III A154 3K] r-facing Ware
and completely discoloured to brownish grey but some brown shows
granular and packed with qtz inclusions. Dr. c. 30 cms

Foxholes Farm, Little Amwell, Herts. TL 3511. Skans. S. of Ware

[inf. Clive Partridge, A only ~~Doll.~~¹⁹⁸⁷, Feb. 1987 FHF 7566c+] flange fragment in 'hard, whitish fabric'. Conc. scoring & grit on surface of flange.

Coddenham, Suffolk n. Ipswich [not examined closely. Drawing supplied. D] Drawing sent by John Fletcher. CDD 019[-]; R.B site: from ditch filling c 180/190.] Dr. 29. 5/30cm.

Ht. 10.4 cm. Pale buff fabric, hard; heavily rounded, quartz grain filter, occasional larger (0.3mm), white quartz and sporadic reddish-brown inclusions interwoven; surviving ls small, crushed flat flat. 21.4
94

D.C.V.

(3)

Richborough [V; 108; area XVII/32; S.E.W. Gullies op. 19-21; Site Mus. 97 K]

on tiny flange; slightly sandy; core cream changing to pink and to cream again; surface cream under flange, top buff, burnt black round outer edge. SKetwin

Richborough [V; Pit 266; 12; Site Mus. 1921 K] l. facing; hole worn in bottom; other st.p. on r. side survives; almost whole; slightly sandy, cream-buff fabric; grey, and white grit.

Harrow's Cemetery, SAC lxvi p 48¹³, 134; hewes M. 1K 1 stamp each side of spout; almost whole; hole in bottom no doubt through wear; slightly sandy, probably brownish buff fabric; grit worn away to c. 1" b.b.b; medium sized, few black, grey, white grit; few on flange; BF. 34/38; D = 119/10^{not} ins. BLACK

DÖINVS

DÖINVS

(2)

Chester [Billings Coll. 223
K.C.A.S. XXVI p.33 no.3] creamy orange fabric, sandy.

A

Corbridge [S. 376 AA⁴ XXVI p.179 no.1] buff sandy fabric. Rim Type W. 38.


B

Wroxeter [1914, f.3, no 49]; T. 38

Fassocks [cemetry Sussex S.A. Clxvi p.48, no 134]: ?? Rim Went
black in air, p.57 like ear.
[If there is DÖINVS of this kind it is rather ^{black} than white; there is a DÖINVS]

High Cross [1955, H.C. 79, Greenfield ~~near~~] fairly smooth cream fabric; a very few
stray pieces of flint grit + white, ironstone grit. Hooked rim.

B



Alchester, Oxon. [Ant. J. IX p. 132 fig. 9, no. 9] Ashmolean M. 3K; 1929.636.

②] stamp diagonal; flange fragment; shape very similar to 1K but fabric different; dirty cream fabric with buff slip; burnt in parts; counterstamp only.

B

Alchester, Oxon. [Ant. J. IX p. 132 fig. 9, no. 10; Ashmolean M. 4K; 1929.637.11]

flange, broken, only; two pieces joining; could be part of 3K but fabric different; orangy throughout with slip on top of flange but turned grey by burning; brownish buff underneath; in Ant. J. drawn in reverse. B
hereafter; Guildhall Lane [355' 195^{b7}; 106K] (large flint grits in fabric) B

Pen Hafod, Llysteg [CAE. 17.181: n. 2. Janwell] Topsoil. Stamp broken & damaged fragment of flange & base. Sandy, brownish fabric with buff core; surface burnt over reddish; brownish slip. Q(A)

DOINGS

2K

Deansway, Worcester [H&WM 389 9 174 99 384] FF heavily

burnt to grey. Granular, packed with quartz inclusions. Die 1.
name becomes stamped from the outside. Probably v. facing.

Leicester [All & 1991 841 2404 305K] IRS. ^{1 certain} ~~House~~ fragments, none
~~House~~ joining. Greyish cream fabric with orange-brown s.l.p.
Abundant, fairly well-sorted quartz, v. rare red-brown (opaque)
inclusions. Intrusion grit: flint & quartz.

Cray Valley Sewer = correct site name.
Boxley, Kent [B. Philp sent 12.4.96 FCP - 95-19 1K] L fac^A

Dv. 39.5 cms All intrusion worn away. Perhaps slightly
burnt. Greyish-cream fabric inclusions abundant quartz
quartz not clearly defined at x10. fine end of range of fabric. D

D01NVS :

Kirkbride [Richard Bellhouse, 16, Lifts Lane, Kempsey,
Worcester WR5 3JN] Plaster cast? Die A. A ledge
of Intervallum road in the fort. On Gillam 240.

Tiddington [TR 82 457. 17K] die B. Dr. 28cm. Yellowish-cream fabric
quartz inclusions and red clay pellets. Trituration quartz and
flint. Fired to orange-brown at surface.

Cirencester [CIR 75 QI 128 M850. 55K] FF, stamp fragmentary.
die B? Cream fabric, inclusions quartz and red-brown
fragments. No trituration survives.

Dolans

(1)

Triportium [Cave's Inn. Rugby A.S. Sc. F61 19K] Two large pieces giving about half of rim. D = . Sandy, greyish cream. Small, red-brown, grey white grits; some traces of concentric scoring inside. Spout shallow; name stamp worn.

B. A

Wansborough, Wilts [B. Walters. WAN. R.C. 1970] flange fragment. 10K. Sandy greyish white fabric with white & dk. grey grits in surface; brownish buff slip.

B.

Easton Grey, Wilts [VCIT vol I, p. 68. JRS. XXIII, p. 205] not being sent by V. Swan. Found at White Walls & in the Malmesbury Museum. B Bedford, London Rd. [Bedford School Museum].

(4)

DOINVS.

33351 resp. dump.

Margidunum [not published; GK. Notts. Un. Mus.] L-facing; hard, sandy, buff fabric; internally scored; sparse, black + brown grit; stamp difficult.

Venlaunium [V F 24 + 13] ^{Arc. 24} ^{+ 24} misread as IVNIOF. 24K] hard, sandy, white fabric with small, black, brown + grey grit. B

Venlaunium [56 A xxv 7; 186K] flange fragment; sandy cream fabric with layer of pink in it; sketch in notebook.

Margidunum [AJ. xxv p. 52, no. 19 + fig. 3, no. 19 misread as MANIIRT. I; 19K] D = 12½" sandy, buff fabric + buff slip; white + grey grits - few only surviving; medium + small.

DOINV

- used by EB but may include Bone (4)

Colbridge [AA⁴xxvi p. 179 no. 17; 5.896 17; 174K] sandy, greyish cream fabric;
stamped a little diagonally; flange only. BF. 38


B

Melandra Castle [Derby A. + NS. J. LXIX p. 25, fig. V., no. 65; 10K] fragment of
hooked rim in sandy, grey fabric with orangey surface on top, buff to cream
below, possibly a slip. Stamp slightly diagonal. B.F. 34.

Chester [Stone Room. 3K; Hayter no. 2; CAS xxvi p. 33.] hole worn in base, otherwise
whole; sandy, pinkish cream fabric; sparse, medium light brown + brown grit;
+ 1 huge grit. DOINV || EECIT found patch in inside (sketch in book).

Chester [19K. William Coll. 223; CAS xxvi p. 33 no. 3] creamy orange fabric; sandy.

N.B. Chester [Arch. J. XXXV p. 293] W.T. Watkin saw 'DOINV on lip of an olla'.



6. Chester Museum.

from

1

D01NVS

5K

Piddington [16b archive. F 332 L20 cc/32 (N) Pid H/F q1] L-facing

Buff-cream

Deep cream, with slightly pinkish cast throughout to surface skin
probably a self-coloured slip. Inclusions: frequent, tiny
quartz, some flint?, rare opaque black + red-brown. This
is the fine end of Vernalium fabric. The surface is smooth
+ the fabric really cannot be regarded as granular.

Intumation: all worn away except for c. ½ inch below
bead where some concentric scoring also survives; mostly
flint, some quartz, rare opaque red-brown + black material.
Dr. 4 3. Die 3 grit smaller, tiny + few medium

Gadebridge Park, Hemel Hempstead, Herts. [479] 5.K] Sandy greyish cream fabric
with brownish slips; fabric contains some (brown) grit; most of interior grit worn
away; white grey + red-brown sunning near rim. Both stamps survive A.
Doncaster [DT/O.U. X] 79.K] Flange incomplete; coarsish sandy cream
fabric with pink core in flange; reddish buff slip. Stamp somewhat smeared. B
white + grey interior grit

Godmanchester [9.K PL 524:12 M. Green] sandy buff fabric; opaque
white + grey grit. D

Cirencester [c. 2231; 6K] flange only; sandy, buff fabric; patchy purple
and orange-brown surface; B.F. 38?; sketch.

Cirencester [c. 2219; 8K] sandy, buff fabric; little, light, orange-brown
grit; shape fairly like Leicester 26K.

Venlamium [58 BIV 28G; 147K] flange fragment dirty, brownish
dark grey fabric + surface; underneath strongly brown.

Venlamium [P.C. V. Theatre, unpublished 1934, 106.2; 29K] yellowish
buff; d = 12 $\frac{3}{4}$ ins.

Venlamium [Arch. 90, 1944, p. 124 f. 15, no. 6] M deposit
containing "early 71" — mid-Ant. pottery but mostly Hadrianic;
p. 114

POINVS 4 (fusible) Venetian region.

Estree [15/17 High St., HAT 69 (7/3) 4K] FF burnt. greyish-
cream fabric; abundant ill-s., quartz, rare red-brown & ^{black in char} ~~grey~~
Castleford [10.65 8 CAS 8 PS 10 L 618 joining and fragment 67K
Heavily burnt on inside. Borders only. D 34. Greyish-cream
fabric packed with well-sorted qtz, cream-buff sl. p.

DO INVS

Worcester [137.1968 ~~146~~ 154K] Sandy, brownish cream fabric with
tiny grits in it; buff slip; flint grit! (Silver Street) A

Wroxeter [WB 83 + 157K] flange fragment. sandy overcream
burnt. N [stamp slightly diagonal; abundant quartz inclusions
not very well sorted.


Baldock, Herts. [174 . V. Rigby 1971] In pit group 1971. Stamped each
side. NK D

Baldock [JF/GK 341 ; 8K] flange fragment burnt & discoloured. D.

Chester [Foregate St., no. 46-50, 1961. In Excav. at 46-50 Foregate
St, Chester, 1961 by J.B. Whitwell & S.H. McNamee in C.A.S. L

p. 17 fig. 12 no. 68 cf p. 18 no 68.

B.



Chesley

68

DODINS

Die C

Inside St. Paul's Cathedral [64307 illustration no. 15.

522K] L. facing. Spout does not survive. Heavily worn and slightly singed. Flange ^{no scoring} smooth excepts ~~surrounding~~ it, no scoring on flange.

Interration: very few cpts survive quartz, flint + r-brown. The grit never came up in the bottom of head fabric cream; surface slip cream froed in part orange-brown. Dia. 37cm; 65%

Inclusions: mostly quartz, a little o/brown, black + grey.

L.F.C. ? extra.
Research Papers of the Surrey Arch. Soc. No. 5. Excavations in Southwark K.M.K.
1959 [seen at Durham 1963; 22K]. fig. 14, on p. 48, no. 6; desc. also p. 48.
Southwark [Institute of Arch., 38; S.P. 5.9a; 55/16208; C 52/6:M53]

sandy buff fabric with pink core;

Brockley Hill [1951 o/s unpublished; IK Hendon M.] flange only;
worn and not well impressed; sandy, pinkish buff fabric; D = > 11 in.
London, Bank of England, King's Arms Yard, [Guildhall M. 269K]; E.R.
4-7.8] l. facing; sandy, greyish fabric some pink core; B.H./R
fabric; one or two grey grits.

Southwark [seen at Durham 1963; 22K] S.P. 58c. C XXII 52/1.

sandy, greyish cream fabric with pink core & cream slip; grit-mixed
at top - flint, grey & white. D = 16". (? is this part of vessel at
Institute).

DONVS (C)

Southwark [St. Thomas St. 74 M58] 253 J. Bird. 1975.

Dennis 1978, 291-422 Pt II of Southwark Excavations

DOINVSCK (probably) POSSIBLY Top border
?? Probably for REFCIT' borders only
Nelson Place, Bath [NPL 89 94 (26) 9K] FF. Granular greyish

cream fabric with thick orange core; abundant quartz
rare red-brown, rarer black. No tituration survives. Dr. c. 33cm^s Drc?

Beau St, Bath [BEST 89 140; (18) IV / 139 10K] r. facing

(18) (20+21) joining IV/139 joins IV/140 and IV/140.

3 joining sherds from a worn mortarium. Buff-cream
fabric with thick pink core. Fired to 0/6 near sport.

Abundant quartz inclusions, rare v/6, grey rare black. Some
v/6 length. Tituration included flint and quartz.
Dr. c. 32. It might be the IV in name stamp C

Venlamium [22^yK; 5^y. III. 23/2] flange fragment; sandy greyish cream fabric with brownish slip. A

The Grapes, Borough High St., London [Cuming Museum. 59/20/5
on pot; (4 in catalogue). r-facing; slightly sandy cream
fabric; flint grit.] NVSF 3K A

Alcester [Mahany 65. H II 39, 22K] Sandy, greyish cream
fabric; flange fragment; ^{depressed} ~~depressed~~ beneath stamp. A.

Depression underneath flange below stamp. Very fine concentric
ridges on single flange - perhaps a cloth mark.

Brockley Hill [S.A. Castle. West Kith Ditch F. A

DOINVS

die 4 (D)

Gorhambury [GOR 73 ④ 51 32]. 16k] I. facing, complete spont.

Micaceous, brownish cream fabric with thick pinkish core, granular texture, but fairly small quartz inclusions, sparse orange-brown and black fragments. No trituration grit survives. Dr. c. 31 cms. die

Ware, Herts [ATH 76 G2 ④ 227]. 9k] IRS, heavily burnt to grey throughout fabric. Granular texture, frequent inclusions of fairly fine grained quartz, occasional red-brown fragments (2mm). Trituration grit not surviving, but a few flint and quartz fragments on flange.

die 4

DONVS.

- uncertain - could well be ANBINSUS (H)
Berridge & Gray, figs.

(1)

Leicester [3274/87; 27K, 1887; Berridge & Gray] sandy buff fabric; light brown and
black grit. N.B. like 26K. DONV in fabric like Wren. W.P.C. 143

Alchester [Oxon. A.J. IX p. 132, fig. 9, no. 10] fragmentary.

Melandra Castle [Derby A. & N.S.S. xxix, p. 25, fig. v, notes; 10K] fragment of hooked rim in
sandy grey fabric with orangy surface on top, buff to cream below; possibly a slip; stamp
slightly diagonal. B.F. 34

A

Buxton M. [no prov. but bad erosion of piece suggests local; 12K] coarse, v. dark grey (nodular
burnt) fabric & inner surface but changing to dirty buff cream on outer surface & on
part of flange, sandy, small grit, colour indistinguishable; B.F. 34 r. facing -

B

DOINVS

(2)

Vernamium [f. Arch. 90 p. 24
A.C. Vernamium Theatre unpublished] 1934, 106: 2; 29K];
yellowish buff; d = 12³/₄". Drawing not copied.

Cochester M [f. 7, p. 241 no. 8; 16K; no no.]; flaked + worn; sandy fabric;
orange before to cream buff; some small black grit survive at bottom of b, worn away below.
Humbleden Villa [Arch. v. 71 p. 88 no. 1];

High Cross [2 xxviii no 47 from G.W. 1955] ? stamp not read exactly

Vernamium [Arch. 90, 1944, p. 124 A 15, no 6.]



DONVS

DONVI

(6)

D

Leicester [Fenners] ^{date} c/1953/155 26K] sandy buff fabric; large, sparse, white,
brown and black grit. D = 10". [Mus. no. 11.1L 1953]

Dartford M. [165] provenance not known. S.S.] light buff fabric; small, mixed,
flint-like grit, not much, some on rim; surface sandy coloured.

Hambleden Villa, Bucks. [Arch. 71, p. 188, fig. 19 no. 11, upside down; 7K Aylesbury M]
V ditch; flange only; slightly sandy orangey buff with drab surface to grey.

Cotteridge [unpublished. US. 71; 38.5K] sandy, buff reddish surface underflange

Kunderton, Middlewich [7K Middlewich M. Assigned only] sandy, Brockley Hill
Type, buff fabric; with red-brown surface; flange fragment. ??

Wroxeter [M150; 127K. Assigned to Down] slightly sandy fabric; soft; flange
fragment.

DORSET

(3)

Venulanium [Mus. - misread as IVNIOF no. no quoted by K. E.H.; 27K] white fabric,
fine black grit. Stamp repeated, separated by scored lines across flange. B
Chester [Hart's 2, Crown Room] DORSET SANDY STATE BUR. white, almost
v. h.

B

Ribchester [no 2 Site Museum] hard pinkish core with whitish buff surface;
a little tile in fabric. Fragment of hooked rim. c.w. 38. B
black grit




B

Wroxeter [c.w. W.p.C 14.3] hard pink fabric with buff slip. Fragment of heavy
hook rim. W. 38. 221K

B

Venulanium [S.S.F. 5.6 Cw(23)] coarse sandy, brownish red fabric with
buff=patchy surface - grey in bands (? wh eve covered by next mortar in
stack in kiln) grit in fabric. A little white grit with scoring stamp faint-as Chester 6K

၁၃၀၈ (၇၇) - ၁၂



DOINVS

DOINVS. (2) 2

Easton Grey, Wiltshire [VCH Wiltshire p 68
RS xxvi p 205]

Bedford

~~1956 C17 VII 1334, 04 in B1~~ 1957 2830 m

~~1956 C17 VIII 21/30~~ ?


Slack [YAS Part 10th Udderstryd Museum p 70 no 6] sandy buff, fusing with brownish buff A surface; fragmentary stamp on broken flange similar to Ver. 1956 C10(23)

DOINGS

Chichester [Shippams site WSH.F04 3254 context 18K]

r. facing 3.22 g; heavily worn. DP 450. 7%. A sherd
in context 2061 n from same vessel 2.84 gm. 9% l shard.
Greyish-white fabric perhaps with slightly darker slip.
Inclusions: frequent, packed, smallish, rounded,
transparent quartz, some ill-sorted red-brown +
irregular black. Interactions: flint + quartz + some black.

* The sherd in 2061 has a modern excavation break.
? it might originally be part of the stamped sherds



EECIT of DOLN vs die B

Newport Pagnell, Bucks [Renny Lodge Hospital site
now housing; Almost complete in autumn c AD 90 -
125 put on FLICKR by Wessex Archaeology

Leicester, Redcross Street [A316.1962.234 + 236 MQ 233.239K]
greyish-

R facing, CRS joining another CRS + FF. Granular, buff cream fabric, frequent inclusions of fairly ^{well-sorted} / small quartz grains occasional red-brown fragments. Trituration grit flint with some quartz, fired to darker buff colour at surface.

Morn. Dr. ¹⁹⁹ cm. Concentric scoring ^{traces of} in side only, die I

Caerleon Museum Sardens 83.232 ③ David Zawki 196K

Flange fragment. End of C and bottom of FFCIT stamp. Non-al granular greyish-cream fabric packed with qtz. Surface or slip fired to buff a upper part of flange. End of stamp not imp. PTO ref.

J. David Zienkiewicz, 'Pottery from excavations on the
site of the Roman legionary Museum, Caerleon 1983-5
in J. of Roman Pottery Studies Vol 5, 1992, p81-109

p. 92 no. 8 but the drawing for it is numbered 6
Not 8 on fig. 3.
— See Bontanica XXIV (1993) 27-140.

D01NVS

Colchester [S12. P3342 Die 1. BKc V267 greyish
white, pink core, slightly burnt. Thought to be overstamped
but not visible on rubbing.] A

DO INVS

(2)

Venlamium [59 L. IV. 5A] /₁; 27 (K) flange fragment; greyish buff fabric, sandy, with brownish pink core; cream to buff surface; some tiny glittering gritty particles showing on surface.

Chelmsford [Information W. J. Rodwell.. 8/3/1970] " cream fabric with thick pinkish core. Y + A sent. B

Rochester [1 CP/1 15] ECIT (ReB) Cream fabric with pink core. 6K

Bearshanger, near Worcester. P. Woods. 7/6/72. Rubbing. B.

Lancaster [Inf. P. V. Webster LC 73 ¹⁵³ T12 12 19K] Greyish cream B.

Manchester [15K /25] 72 T 209 + no. 251. Deep flange A.

DOINVS B. +

p3

Staines [47] BSS ~~Pit~~ 5K] Granular greyish cream
fabric; flint grit & red-brown; internal scoring to top of
bead. looks fairly early. Counter stamp. SK

(244) joins (248).

Dover [DV-2683 1K CLBR] Flange fragment.

Granular red-brown fabric tempered with quartz, flint
& red-brown particles. D

Doncaster [99K DE H (PM ⑤) 15-9-76 120 104] Die B.

Cirencester [M850 CIR 75; Q I 128 55K] Granular greyish
cream with gls. temper. frequent stp. Flange fragment B

FECIT // FECIT.

(3)

Not by
Vernamium but deposited late 1885

Vernamium [58 A VI (23) 154 K] stamped each side of spout; sandy fabric;
cream fabric with very thick pink core, almost to surface; internal scoring; much flint,
white + grey grit; cream slip; D = 12 ins. B

Vernamium [1958 B II 166 K Flavia 32 F 110 A D] stamped each side of spout; sandy cream fabric, with
pink core in parts; ~~top~~ stamped diagonal. Hole of urnarium (at Institute).

Richborough [V S. of Sect. 19; 3rd layer XVII; 103; site Mus. 116 K]
slightly sandy, cream fabric; 1 or 2 brownish white, grey +
white, ? flint, grits on top of flange; flange only; ~~only enough~~
for one stamp to survive. See DOINUS B.

Brockley Hill [B II 70 T 2 (F P) 108 K] See DOINUS.


Kirkham [Information J. Marshall, 22 Myrtle Drive, Kirkham; 1K] r. facing;
large portion of m. in sandy cream B.H/R fabric with some red-brown specks
in it; grit worn and originally abundant - black, and grey mostly very
small and neatly dispersed; D = 12½". B

Banting [C x xii K i P.I.T. 10 . S. S. F] r. facing; only slightly
sandy, cream fabric; inside & inner half of flange same
color but outside & outside half of flange orangy
brown - brown in patches; grits few - medium & small grey
probably flint. e. D = 13½" D. c. 36 cvis.

Caerleon [56.214.B.P.5; 114K] flange fragment: sandy cream fabric;
1 greyish flat grit embedded; cream slip. B

DOINVS (C) || IDE

Norton [in a burial 1967 January. Found Mauby] This does not seem to have been intact in burial as the fractures are old but bolt stamps survive even though all the adjoining parts do not + there is no doubt that bolt are from the same pot. Doinus v. faceted. Sandy greyish cream; slightly more buff in parts. Surface outside bright and also on inside slightly; fine, grey, white grit; very moderate amount on pieces. D = 12 $\frac{1}{2}$. A piece is much browned on inner surface & for $\frac{2}{3}$ of body. A This is only known example of name-stamp.



8K. Norton (Hutton II)

intrig.

bowl.




Norton (Hutton II)

Attributed to DOINVS = JE OJT II DANTLVC

Old Penith [131-177. 7826406. 7K] Flange fragment.

Fairly certainly the T of Fecit stamp to Doimus B. Granular
greyish cream fabric packed with w'reg. sized, whitish quartz.



POINVS

Pd. 2 Ph 4

Unpublished D

Barton St, Manchester [3] Cxt 554. 21K] 8 joining sherds
L. facing. Heavily worn. VRW fabric cream slip. Δ
Diam. Fragmentary stamp showing V.L.
11

DOLNVS

heisterk, Causeway have [AI. 1991. 17722. 1. 3549 Mot.]

L-facing. Heavily worn - all grit worn through. Dr. 36cm.

Greyish cream fabric, packed with well-sorted quartz; v. little else
v. rare siderite; perhaps v. v. rare black.

B ch.

York [SM13 1989. 21 2153] 121K r. Facing. Dr. 33

Granular greyish-cream. Inclusions: packed quartz, rare
orange-brown and rare dark brown. Intrusion: flint, rare black opal.

Heavily worn; burnt in part of flange. Traces of calc. staining
(inside), rim smooth. Context residual

B

Middlewich [so 1 trigetage floor 13K] Diam 32cm 11% spot had
flaked off but doesn't join, VRW.

A

DOINVS

Chester, [Inner King Road 1970 S.F./16, from 64K] P. Carrington.
Foregate St/Grosvenor Park Rd.

Enfield, Lincoln Rd [10K A3 F12] ^{Probably DOINVS} granular dark
cream fabric with pale grey core; grey + white flint grit.
North Church (Cow Roast sp 957101) 5K C.R.74/11 ⑨ 21F
L 4) Flange frequent in granular buff fabric, friable. D
slip fired to orange buff in places.

herester 1/220 A 78. 1975. 2328-2326 facing Granular cream fabric,
~~about 10%~~ ^V ⑥ ^{From red-brown flint} good amount quartz tempering; quartz, white + red-brown
trituration grit; cream - buff slip. 78 1975 V 175 ¹⁹⁷⁸ △
burnt on some sherd + in base (not joined), gritting mainly to 3cm.
below head than sporadic

181K (2) Spout shallow; side wide. Flange not scored. Dr. 30cm.
Teniers. Interventio ~~gut~~ fairly small. Inside scored in lower half only

DONVS


C

Hucclecote, Glos [later Prehistoric & R-B Barialand Settlement at H, Gloucestershire, Alan Thomas, Neil Holbrook & Clifford Bateman, Fig 1b, no. 30. Bristol & Gloucestershire Arch'l Report no. 2, To accompany vol 121 of Trans. of B & G. A. S. 2003] r-facing.

p. 43, no. 30. Flange from a whiteware material (VER WH) with a worn potter's stamp close to the spout area. Retrograde FECITE. Fill 3335 of ditch 2365, Period 4.3 SF 103.

Not seen

Period 4.3 is ② - ④ so residual .



Dominus C

York Minster [YM US/159 82K] Coarse, sl. brownish fabric with
brownish orange slips Phillips and Heywood 1995, 319, fig 129, 91
~~*Enfield, Lincoln Rd.~~ [A2 F2 9K] Attib. Dominus C counterstamp
granular cream fabric with darker surfaces

DOINVS The Ufac stamp ~~contains~~ The name
is
~~The counterstamp is also used on both sides.~~ C (2)
Stack [1968 P III ③] 138 Drab cream fabric, packed in moderately sorted
quartz, ranging from ^{and black} 2055 gm. 100% abraded like whole outside
with brownish cream slip; stamps ~~very~~ worn. Whole but pr.
central hole; titration grit worn almost away, white, red-brown
grey; some in fabric too. D = 11 $\frac{3}{4}$ " Slip mostly gone ^{D r. over} 310 mm of S.A.
Margidunum [M68PL 32K] r-facing. Sandy cream fabric with
pink core; buff slip; grit worn away but fair one or two red-
brown.

Vindolanda (SF 9217) 0 C

D01NVS C.

(1)

London [St. Olives Jewry; Guildhall M.262K] flange fragment; sandy
greyish cream fabric; worn; stamp. worn. Rubbing not found

Cripplegate East, London [Mus. Acc. 2, Site W0097 Context 152
415K] L-facing IRS. Drab greyish fabric with dark
discoloured slip. Packed with tiny almost entirely quartz
with very rare black + red-brown material. ^{Towards} inner end orange
but not V fire. No induration survives. Counterstamp C

Doinus

Southwark

Montague Close) [MC 73 T9/5 F5 6K Cuming M.] Two joining pieces + one from other side of spout - both stamps in bad state due to some abrasive process which has removed the slip entirely along the top of the flange. Can be attributed with fair certainty to Doinus die D. Brownish buff granular fabric w/ brown (unusual) slips. Fabric heavily tempered with quartz grit. Most of tempering grit is flint, grey + white.

D

Southwark, 175-7 Borough High St H.T. [8⑦ no. 5. 42K] granular, greyish-cream fabric packed w/ quartz, some pink in core; flint temper. Dr. 42²ms?

D

DOLNVS

London, Cheapside [CDP04 Access 6824] Context 835 850K]

L-facing. 300gms IRS. Greyish-cream fabric, packed with transparent qtz with rare red-brown + black inclusions.


Inclusions: quartz and flint + red-brown + black.

Flange probably smooth. Concentric scoring: i. 9 below bottom of bead, and grit; smooth above. Lowest third worn smooth.

London, Cheapside [CDP04 Access 686] Context 1776 die B

849K] L-facing 155gms Diameter 320mm 12% Burnt
on the interior. Concentric scoring below plain band,
cream fabric, inclusions: packed with transparent quartz, some
red-brown + black.

A



DONUS

(3)

A

B.D.E. only?

London [1937.249; Guildhall M; 30K] smooth surface; slightly sandy, dark grey fabric, burnt I think; pale greyish patches on surface; low 2 grey grits, very sparse; DONUS rim, very deep hook on 34 with broad up to flange; D = c. 9½ ins.

Check sometime Pub. C. Dep. E7E546
or extra E7E552-

London, Miles Lane [April 1926. Guildhall M; 6K; ?? same vessel as 215K] sandy, whitish grey fabric; surface burnt in parts; internal scoring; a little white & grey grits survives to b.b. D = slightly more than 11 ins.

London, Steelyard [R.XI.646; Guildhall M; 169K] L-facing; sandy, greyish cream fabric; few, gritty, r/b grit surviving; nearest 6.1 K but 169K more angular. c. 80 +

656 a second label. Probably wrong.

Museum of Practical Geology.

Dominus A in London S 17 consistently early,

DOINRS

London, Bon Bells House (BBB05 Context 2239 Acc
(1286) Open Area 2 Period 3 840K) Flange fragment
VRW 65gms. A d4

London, Cheapside, EOP04 Access (832) Context 365, 848K
r. facing 525gms. D. under 34cm. 18%. Fabric: greyish-
cream with cream slip. Inclusions: packed with tiny
small transparent quartz with rare red-brown & black
occasional large red-brown. Interraction: flint and quartz
trace red-brown. Heavily worn. No concentric scoring.
wide heavy spout - not too typical early Flavian or thin
early Q D

DOWM

1928. 141

(4)

hondor [May 1928; Guildhall, 14.1; G.H.; 204K] r. facing; slightly sandy,
grey core to pinkish buff; Type 2IK or near 42K but end of flange
thickens & juts inward. Type as *Bucius*.

^{B.D.F.}
hondor [1937.437 Guildhall M; 111K] l. facing; very faint stamp;
sandy, pinky-buff fabric; surface orange, blackened in parts;
1 or 2 grey grits. Sketch. After ^{G.H.} c AD 95

hondor, 99, Cheapside [April 1927/1927.29; 112K] L facing; sandy,
orangey buff fabric, blackened on surface, orangey underneath
& in parts on top. Approx. 6K. c AD 85 —

hondor [M.A. 2545 Guildhall 110K] r. facing; slightly sandy, buff fabric with
a few w/b. grits mix; 1 or 2 grey grits near bottom; like 6K but not bulbous at end of flange.
no rubbing

- DNNI ? DORNVS (4)
- London [1937.100 Guildhall M. 83K] L. facing; faint; no rubbing; sandy, cream-buff fabric, burnt black or grey in places, small, white, grey grit to b.b. Near 61K DORN's but smaller.
B.F. London [1937.73 Guildhall M. 59K] sandy, whitish grey fabric with drab surface; orange-buff in parts; a few grey grits; B.F. 38 with end of flange like a 34; no rubbing.
- London [1937.75^A Guildhall M. 60K] fabric as 59K; medium to small, vlb., black, grey grit, very sparse, perhaps worn away, b.bread; B.F. 38; not a part of 59K. no rubbing.
- B.F. London [1937.75 Guildhall M. 61K] fabric as 59K; tanish (small, v.sparse, white, grey, vlb, grit to c. 1/4 in. b.b.b. ? no rubbing. Δ) = 60K

DONVS

London [322K 91+ 56] flange fragment likely like early.
cream slips on cream fabric.

London Walbrook [740/11 r. facing] granular greyish cream
fabric with pink core. A

Southwark [93-5 Borough High St. B.S. 113 J. Burd 1975] D_A

London, Billingsgate Lorry Park in earth moved to Dartford. Guy de la
Bedoyere BAR Part. Ser. 154 (1986) p. fig. no. 1. A
Surface blackened; fabric greyish-cream. Die A

London, Billingsgate Lorry Park in earth moved to Dartford See above
Not published. pinkish cream. Dr. c. 32 cms. A Die D.

^{BSE}
london [1937.2.58; Guildhall M; 229K] r. facing; greyish cream fabric,
 pink in core; slightly diagonal; small, white + black grit right
 up to bead; flange + bead only. Sketch. B

london, t.Bank [1939.176. Guildhall M 223K] l. facing; sandy,
 grey fabric; fabric hard and thin nish but typical flange of this
 die; surface buff in parts but mostly black or grey. Early.
^{cheek - w. jn. 215K}

london [1930.242. Guildhall M. 62K] Miles Lane 1926; no rubbing
 die with narrow O; sandy, whitish grey fabric; orange ^{early} buff in parts,
 smallish grey grit to c. 1/2 b. b; fabric similar to other DOINUS. △

london, Mincing Lane Sewer; [Guildhall M. 270K; no. no. on box] cream
 fabric; few, brown and grey grit. B.F. 38; counterstamp. [?jars 264K] B

DOINVS

B(4)

Temple Site, Walbrook.

hondon [Guildhall M. 18,811; 125K] L. facing; slightly sandy, grey cream

fabric; black in parts, ~~surface~~ grey-cream surface with a few blackened
parts; few, small + medium, black t/r/b. grits; BF. 34. B

^{B.R.E} hondon [1937.254; Guildhall M.; 124K] sandy, grey fabric, blackened near
surface in parts with tiny, gritty, black fragments in fabric; medium to tiny,
grey + black t/r/b. grits. B

¹⁹²⁶ hondon, Miles Lane, [June 1926; 51; Guildhall M.; 215K] grey-cream
fabric with buff surface; grit mostly gone, few, small, grey + black
grit; BF. 58 - rather deep. B

^{B.R.E} hondon [1937.82 Guildhall M. 201K] sandy, greyish cream; buff to drab cream surface
black, grey, r/b. grits; Type as 61K, big hook; much worn. B

DOLINUS

Attrib.

Hondon Bond [LG] of 69 Area K EH 5K Cumming M] Granular
 greyish cream fabric w/ pale buff ~~are~~ slip & ranging
 in colour from cream to deep orange-buff. NVS. Has to
 be DOLINUS or ALB DOLINUS - forme more likely on rubbing form
 flange only.

Montague Close [MC 73 T 9/5 FS 6K Cumming M] granular
 brownish fabric, slip fired & black worn; few flat grit.
 Section incomplete. D

Montague Close

Hondon [TRIANGLE 9K 1430] tracing - greyish cream
 SK in book

POINVS

Highgate Wood [HW 74 T 2 L 2 474] 14K Flange fragment. Dirty ^DA
brownish-brt. fabric with black or grey surface (? burning);

Abundant inclusions mostly quartz v. rare black ironstg.

Highgate Wood [HW 68 T 27 L 2 505] 2K F.F. Weathered fragment
stamp damaged. Fabric rather soft due to conditions. Greyish
cream fabric. Abundant inclusions: mostly quartz. Dr. 35 ^DC

Hoyds Registry, London [FCC95 Acc no. 920 Context 1023 handuse -
external dump. Open area 13. Pd. 3(100-150) Fab VRW] ⁴⁹⁰K

45g. Incomplete rim-section in greyish-cream fabric with pink
core; probably a self-coloured slip. Inclusions frequent and not very well
-sorted, quartz with rare r-b and opaque black material. Not tnturated
Right-facing counterstamp C

DOINVS D

(F)

Ditchley [Oxon. 1 p. 54; Watts Wells Villa 1935; 1936.414]; Fishamble M.
71K] L-facing; sandy, buff fabric with buff slip; some, brown & grey
grits survive.

London [Mercers' Hall 286K G.H.] L-facing; inside half burnt grey,
red outside half; sandy; cracking in parts; large to small
flint grit to b. Finger marks from inside to outside of flange
for key ~~or~~ of spout. Identification for border only - probable
but not certain.

London, Walbrook [209/43 K.G.H.] Flange broken. Very coarse, sandy
greyish cream fabric with blackened slip from burning; used small
white, grey & red from ? flint grit; coarse concentric scoring. ? Die A.
? B.F. 34.

london [CRS. R. London p. 89; M 2829; CIL VII, 1334, no. 74; British Mus. 64K]

sandy, very dark grey fabric, black in parts; sparsely, grey, medium grit to
bead. D = 12½. B

london [M 2830; CRS. R. London p. 89; British Mus. 72K] L. facing; sandy
greyish white fabric with drab buff surface; most of grit worn away but a
few, black, whitish grit to near b. b. D = 14½ ins. B

london [Public Cleaning Depot; no. no. Guildhall M. 263K] sandyish cream
fabric with cream slips. B

london, Mincing Lane Sewer [no. no. Guildhall M. 264K] sandy cream B-
fabric with buff slip; B.F. 38. ? joints FECIT 270K

DOINVS

4668 artist

P 264

Regis House, London [KWS 94 Can 822 (519) Huntac 471K] w.

facing 110g Dr. 2.4 cms 18% Green fabric but fired
to dark brown except for skin at surface; cream
~~to pink~~ ^{thing in body} layer in flange, P-6 [Munsell 2.5YR 6/4 'light
reddish brown'] cream slip. Very thin ^{P TO} _{9.56} d.4

Regis House, London [KWS 94 Can 2181 (1877) 472K] Burnt

to black and grey throughout. 150g Dr 3.1 cms 10%
Inclusions worn away except for 1 clear flint.

Inclusions: packed with quartz, rare red-brown.
looks as if had cream slip.

d.4

471K. Packed with tiny small quartz inclusions and rare
large red-brown ones. Tiny to small flint & quartz inclusions.
1 large red-brown.


472K

DO: NVS
No 1, Poultry, London [ONE 94 Context 8531 Mus Acc. No 5502 440K]
C. facing very heavily burnt and worn 220 g. Dv. 29 cms.
all over.
13%. Original color probably buff-cream. Typical Ver fabric.
Abundant, fairly well-sorted qtz, rare red-brown opaque. Surface
smooth for Ver. Interventions: flint and quartz. D
London, Cheapside [CDP04 Access <78> Context 430 joining
access <842> in Context 430, 847 K] worn well in lower half.
Sits starts about 2 cm below b. of bead. Fabric: greyish-cream
with definite looking brownish/buff 'slip' inclusions: packed
with transparent quartz, few red-brown & rare black.
Interventions: flint + quartz + rare red-brown + black
90 gms and 240 gms. Diameter 390 mm 10% D

Do Inns? Uncert.

Northgate kiln, hondas [MRG95 Context A (790) Acc(811) 559K]

FF Overfired/burnt to grey throughout with discoloured slip
Inclusions: r frequent, in od well-sorted quartz. 35g




(could be Donist but not certain)

DOINNS?

Northgate Kilns phandans [MRG95 Con A[74] Acc 810 558K]

2 joining sherds, 155 g. Diam 370 mm 6% Buff cream
at surface only, otherwise deep pink. Inclusions: packed
with moderately well-sorted, ^{rare opaque black} quartz, ^{to red-} orange/-brown matt
slip. No tubular spit survives but 2 flints on underside
of flange + 1 blackish (?char) There is a little circular impression
impression at bead level. ? fossil



DOLNVS

AB v/s

Southwark [SIB Borough High St. v/s 26.8.77] LL 8K AB v/s.

Ver. region fabric. Die B - o squashed. Burnt △

DOWNI

DOINWS

(3)

Arch. S. xxxv, p. 293 fed. ware - re.
[31-78; 28K NMW (old find unpublished)] reddish orange core
clay, dark mortar 20-30.
to cream buff; sandy fabric; flange only. Found 1847-8 in Excav. by A.D. Bevington
Brecon [p. 247, no. 10 + p. 214, fig. 94, C.4.; 55K NMW] 1 stamp each
side; sandy buff fabric; low 2 v/b. + dark grits; B.F. 38; D=12ins.
Caersws [NHW.] rubbing sent by G. Boan 1965.

DOLIN VS
(Wales)

D


Caerleon [31:56:237 : 125K] L.facing. Granular, v. pale,³

brownish fabric packed with quartz. Heavily worn. Dv.³²~~31~~
plint, r/bd quite in place but mostly worn away. Buff-brn slip

Loughor [57/142 ⁴⁵⁷ archive 8K] FF. Circular, greyish brown
fabric, packed with quartz, well-sorted, sub-rounded. Buff-
brown slip: but if so only on top of flange, not underneath. D

POINVS

Carmarthen [CCS 18 399 3/940 1978 (Sl d.no. 864) 25V] FF greyish-
cream or rather buff. Abundant quartz (tiny - small), few r/b some large,
rare black. Smoother than the common fabric. This is the finer of the 2
main fabrics. self-coloured. stamp poorly impressed. D.v. = 31 cm.



Loudon Hill [Hunterian M. 86K] no no on it; flange fragment; sandy;
greyish cream fabric; A

Newstead [not published; no. no.; NMA. 134K] sandy, light brown surface; A

Newstead [not published; 1491.A; FRA; NMA. 151K] r. facing; restored whole;
grit worn away; could belong with flange fragment.

DOINNS.

(3) DCI V, C 2

Brockley Hill [LMAS 1956 vol 19, pt. 1, p 72 + figs. 2+3 no M.16] (4 exx) 9 cm

pinky buff; 2 others off white. 3 on profile shown, one on lighter flange.



Chester [Haytor H; ex Chas. Tower, Box 432 no. 161K] buff fabric, pinkish buff core; sparse white and brown grit. Stamp on 31/2

Castleshaw [Interior Report facing p. 27] Clearly Die C in photograph.

Wroxeter [Site Museum. 38 K, M76(?)] buff fabric with darker buff slip; possibly burnt on parts of surface - orangebrown. Broken stamp near spout. Some c. is on a C. 1.

Dalswinton II [Dumfries & Galloway N.H. and A.S. Trans., xxxiv, p. 21]

sandy yellowish buff fabric; sparse white and grey grit. Found immediately on intercalum of second fort, in burnt area.



DONVS 1973 Brockley Hill.

215K

Brockley Hill [BH 73 T.C. MS I. h M] r. fac. ing. Granular brownish buff

pale

fabric with thick greyish core; much grey + white & 6% feldspar tiny
to smallish + few red-brown grits, all concentrated in lower half of
vessel with only few pieces higher up. Reminiscent of 150 K BH but broader
at end of flange. Counterstamp showing like 31 K Chester. C

Brockley Hill [BH 73 T.C. MS 30 216K L.M.] flange only,
fired throughout a dark flesh grey containing many white
flecks. Counterstamp. Like Highgate Wood 68/57. C

Brockley Hill [BH 73 T.C. MS 34 217K LM] flange only,
in granular greyish buff fabric with orange buff slip. D

Brockley Hill MS 39. No Highgate Wood 68/57.

DOINVS


D

Brockley Hill House [Oxon Unit BHNOO Context 70; prn: 797
362 K] Flange fragment 75g c 300 mm. 7% Eroded

surface. Fingers depressions underneath stamp fabric soft,
packed with quartz inclusions with rare black and red-brown.

Brockley Hill House [Oxon Unit BHNOO Context 166 prn 1313
363 K]

L-facing. Slightly singed. late(?) w early(?) spout
fabric as above but not eroded. 145g c 310 mm). am 11% D



Doinus D.

Brockley Hill [B+74 T.C. 286K] Brownish buff fabric with pink

cove; ship - fused to drab grey. MS 34 D

* Brockley Hill [B+74 T.C. MS 5 337K] frag. of flage overfused
to dark grey. Attrib. to Doinus D. - frag. only of border.

* Brockley Hill [B+74 T.C. 338K] flge frag. MS 3. Greyish
fabric; pinkish buff ship. Attributed to Doinus D. Frag.

Brockley Hill [B+74 T.C. 351 K] flge frag. overfused
throughout to grey. A

Brockley Hill [BH 71. 46 Ti② 133K] L.-facung. Granular cream fabric with dark vesicles; abundant grey + white flint grit; Finger depressions across rim for keeping on extra clay for support.

Poorly made, some slight (not undisputable) water cracking). A
Brockley Hill [BH 71 K.F. 40. Ti34K] Very brownish cream sandy fabric clearly slightly discolored by heat; tiny transparent sandy particles in fabric; grey + white flint grit. small. A 2 different materials.

Brockley Hill [MSS BH 72 CTi② 212K] frag. Die D.
brownish cream with grey core.

DORNS

ZBH / H.W.

Brockley Hill [Kiln Site Layer ① S. A. Castle] H

A

Brockley Hill [BN 70 T2 TP 102K] Very sandy cream fabric with pink
core + buff slip; flint white + grey grit + red/brown grit. Counterstamp B.

B

Highgate Wood [BN 68 57.12A] flange. Sandy greyish cream with
inclusions + pale buff slip. (flint; + b. grey)

C

D01NRS

1971 March 29 differ

B

Brockley Hill [B471. K.F.2. 135K] L. facing; granular cream

fabric + slips; grey ^{tiny} spot. A few very insignificant cracks;
white + grey + black flint grits, tiny; not abundant probably unsorted.

Brockley Hill [B471. K.F. 11. 136K] Sandy, cream on inside
surface; slightly ^{brownish} ~~pinkish~~ top of flange, pinkish brown everywhere
else to outside, & underside of flange; abundant, tiny + small
grey + white flint + black red-brown. (see 129K)

Brockley Hill [B471. S.T.P. 49 137K] Range flay. Different vessel.
granular cream fabric + slip.

Brockley Hill [B471. K.F. 32 129K] counterstamp Sandy cream fabric with pink core;
abundant tiny grey + white flint grit + red-brown. Could just belong to 136K but not certain.

4 BH + (1)

DC 11

Brockley Hill [TLMAS (1956) 19 pt. i, p. 72 + fig. 2+3, M. 1b; Harrow 4K] 1 stamp each side of
spout; creamy fabric; large to tiny, flint, grey, black + white grit; D = 12½%; thin Rept. faint.

Brockley Hill [1953/4 Excav. TLMAS (1956) 19 pt. i, p. 72 + fig. 3, M. 1b; Harrow 6K] flange
fragment; cream fabric; few, small, flint grits in back; pale buff surface.

Brockley Hill [1953/4 Excav. TLMAS (1956) 19, pt. i, p. 72 + fig. 3, M. 1b; Harrow 7K] flange
& head fragment; different vessel; pink fabric; a little wear apparent.

Brockley Hill [1953/4 Excav. TLMAS (1956) 19, pt. i, p. 72 + fig. 3, M. 1b; D. 3; Harrow
34K] fragmentary; sandy, orangy pink fabric; 1 or 2, grey, black grits.

Vernacularium [Thurnham from B. Barr. 205K] inner flange
fragment. sl. sandy & brownish buff fabric & slip; Die C.

Brockley Hill [W.M.A.S. XI, iii p. 270, 14 on fig. 6, & p. 271; 46; 24K] 1 stamp

each side of spout; sandy, slightly brownish, buff fabric with cream-buff surface; grey, black, flinty grits, and a few r/b, BF 58;

Brockley Hill [1952Exc; See T.M.A.S.(1954) XI, iii, p. 271, no. 14; 48] 25K] die as 24K; no rubbing; soft, slightly sandy, slightly pinkish cream; has been rubbed smooth and stamp worn.

Brockley Hill [1952Exc; See T.M.A.S.(1954) XI, iii p. 271, no. 14. 47; 26K] no rubbing or Δ.

r. facing; sandy fabric; pinky core to cream-buff. in DD - - - o

Brockley Hill [1952Exc; See T.M.A.S.(1954) XI, iii, p. 271, no. 14 66] 32K] r. facing; no rubbing; sandy, buff cream; dark, drab buff surface to drab brown; tiny grey grit

DOINVS (1971) 25 numbered all (3) PTO D

Brockley Hill [71.W.P. 33 138K] Very large rim in sandy
brownish cream fabric containing much fine grit + brownish slip;
tiny white + grey flint a piece △

Brockley Hill [BH 71. K.F. 94. 139K] L-facing. Sandy brownish
cream with pinker core + brownish cream slip somewhat discoloured.
joining fragments. 1 faint crack; grey, white + black flint
grit. unred △

Brockley Hill [BH 71. K.F. 3. 140K] L-facing. Fired to pinkish
brown throughout (brownish pink rather); colour abnormal: grey
patch at end of spout. Sandy; few flint grits.

30.1.72 S.A. Castle

Serial numbers.

16.2.72 38

At least ~~29~~ vessels stamped with Downing D & 8?

"Only 2 mortaria with both stamps, all the rest from different vessels"

ל 143 K - could be same but for public so different.
簡單，簡單的東西就是 public (public) private (private) public private
簡單 public private public private public private public private
簡單 public private public private public private public private
簡單 public private public private public private public private
簡單 public private public private public private public private
簡單 public private public private public private public private

(1)

(3) סֵבֶת אֲמַנְדָּה וְעַמְלָה זָמָן דָּבָר וְעַמְלָה DONVS. 1961

Brockley Hill [BH 71. K.F. 27. 141K] 2 pieces joining. Brownish cream skin; brownish pink apart from that; Sandy; surface darkened to dark grey in parts, brownish grey others; grey, & white flint grit; a few brown. worn.

Brockley Hill [BH 71. K.F. 7. 142K] Very close to 140K but if part of it then stamps are not symmetrically placed. Sandy pinkish brown fabric containing tiny grits. Surface worn.

Brockley Hill [BH 71. K.F. 1. 143K] Lacing. Sandy, slightly brownish cream fabric with brownish orange slips; greyish white flint grit, brown. Flange heavily overpinned = grey
Read as originally

Brockley Hill [BH 71 K.F. 19. 151K] flange fragment; drab mottled brown fabric with very thick orange-brown core.

Brockley Hill [BH B. S. 41 152K] flange fragment; granular brickish pink fabric.

Brockley Hill [BH 71. B.S. 43 153K] flange fragment; granular bright terracotta colour.

Brockley Hill [BH 71 K.F. 23 154K] Coarse cream fabric with buff slip. fragmentary.

Brockley Hill [5x BH 71. T.C. 155K] flange fragment. Coarsish cream fabric with brownish cream slip.

DO INVS

1973

Brockley Hill [BH 73 TC MS42 262K] L. fac. frag.

granular brownish buff fabric with orange tinge in shgs. like 31K Chester D

Brockley Hill* [BH 73 TC MS39 218K] frag. cream with orange pink
core. Probably DO INVS D. but not certain.

1973 Probably from at least 4 vessels taking into consideration
dies & rim-forms.

Brockley Hill [BH 71 S.T.P. 52.161K] Attributed. Flange fragment.

Granular fabric overfired throughout to dark bluish grey.

Brockley Hill [BH 71 K.F. 13 162K] Flange fragment. Granular, pale drab brown fabric with traces of more orangy slip.

Brockley Hill [BH 71 K.F. 20 163K] Deeply overfired to drab, dark grey with brownish tinge on flange. Attributed.

Brockley Hill [BH 71 T.I. ② 164K] Flange fragment. Granular cream fabric.

Brockley Hill [BH 71 K.F. 156is 165K] Flange fragment. (facing; greater) cream fabric with reddish brown slip.

Brockley Hill [B#71 K.F. 9. 156K] Flange broken. Sandy cream fabric

with dark grey in part of flange; grey + white flint grit; a little transparent; appears to be unused but not absolutely certain.

Brockley Hill [B#71 K.F. 8. 157K] Flange fragment. Attributed.

Creamy brown fabric containing flint + red-brown grit in it.

Brockley Hill [B#71 T1 (Q) 47 158K] Flange broken. Granular pinkish brown - probably somewhat over-fired.

Brockley Hill [B#71 K.F. 12. 159K] Attributed. Flange broken. Granular

pale, terra brownish terracotta colour. White + grey flint grit; + red-brown

Brockley Hill [B#71 K.F. 6 160K] Flange broken. Heavily over-fired to near very dark drab grey with some reddish brown on outside; wh., grey flint grit.

Brockley Hill [BH 71 K.F. 16. 166K] Cocoa coloured brown granular
fabric discoloured to blackish in parts.

Brockley Hill [BH 71 K.F. 1⁽⁶⁶⁾ 167K] Much overfired to various shades
from ochre colour to dark bluish grey; grey + white flint grit in surface
inside reddish brown.

Brockley Hill [BH 71 K.F. 10. 168K] Flange fragment. Granular cream
fabric with pinkish slip.

Brockley Hill [BH 71 KFW 44 169K] Flange only; granular greyish
cream fabric with buff slip, more orangey in parts. Attributed like
138K

Brockley Hill [BH 71 B.S. 42. 170K] Flange only. Sandy brownish
cream fabric. C. facing; orangey brown slip.

Brockley Hill [BH 71 T1 (1) 35; 147K] flange broken. Brownish cream fabric with pink core; one white flint grit.

Brockley Hill [BH 71. W.P. 34 148K] Upper surface cream in part + meant to be this colour; rest is brownish bright orange. One slight crack in flange. grey + white + black flint grit; red-brown.

Brockley Hill [BH 71 K.F. 4 + 15 joining. 149K] L-facing Overpried to almost chocolate brown with pink core + darker brown under flange; grey, white + black flint grit; red-brown grit - curved.

Brockley Hill [BH 71 G.P. 31 150K] Surfaces very brownish cream with pink core to rear surfaces; slip turned brown; unturned white, grey + blackish flint grit;

DORNS 1971

(4)

D.

Brockley Hill [BH 71. K.F. 14. 171K] flange only; sandy creamy brown fabric with pinkish-orange core; brownish slip; white flint grit; 1 red-brown grit.

Brockley Hill [BH 71. K.F. 17. 172K] flange only; brownish sandy fabric with slightly redder slip.

Brockley Hill [BH 71. K.F. 18. 173K] flange only. Granular terra cotta coloured fabric

Brockley Hill [BH 71. K.F. 26. 174K] 2 joining fragments. Sandy drab brownish cream fabric with pink core, burnt to blackish grey on top of flange; whitish grey flint grit. Form as 146K

DONVS

Brockley Hill [BH 74; T.C. MS 10 289K] flange fragment in orangy
fabric more cream-coloured near surface, burnt throughout
at the end of piece.

Brockley Hill [BH 74; T.C. MS 6 288K] fragment burnt throughout
to blackish grey.

Brockley Hill [BH 74; T.C. MS 7 287K] flange fragment burnt
throughout to dark grey.

Brockley Hill [BH 74. T.C. MS 14. 285K] flange over-fired brown
+ grey.

Brockley Hill [BH 74. T.C. MS. 16 284K] flange in greyish cream.)

FAVSTI
DOMITIAES
VGILLAES

FANSTVS, DOMITIA LVCILLA
Italy,

Sea Mills [F1338; Bristol M. IK] stamp each side of spout; daub
texture; creamy pink fabric with thick pink core; tiny grit,
some shiny, throughout body; extremely heavy.

DOMITIUS (?) cf. DOUNUS (MIOC) (Corseval)


Domi Caesleou (Arch. I. XXXV, 273f) "Red ware"

DORTA - see DOCCIVS¹ [misreading by B²]

London (G.H.) 1909 1932.182. 73K

~~DRICCUS~~
Inveresk [FV 98 Final civilian occup". 30NK] Scotland,
r-facing.

56g. Diam. c. 28 cms. (4%) light brown fabric (Munsell
5YR 7/6 'reddish-yellow'), fired to buff-cream at
surface and ash of this colour. Fired to orangey
colour underneath flange. Abundant, mostly
well-sorted quartz inclusions, with very rare grey,
probably flint. No truncation survives



DRICCIUS?
Compare DRICCIUS & Reading.

HILL 6115 L1, T10 R13

Venlatinium [1932 ~~24~~ + 83K] yellow fabric; white grit (fine
rubbing) d = 10 1/4 ins.; hard buff fabric; internal scoring; medium
& small, grey & brown, white grit.

Venlatinium [1957. T VI ②0 82K] sl. sandy, pink core changing
to cream near surfaces; surface batt; appears to be a slip as it
covers some grit; rough internal scoring; abundant, white, v/b;
grit b. of b. D = 13 3/4 ins. A. vol i.

Venlatinium [54 Z I ②6. 255K] flange fragment; sandy,
creamy buff fabric w/ cream slip.

NSUPIO

Ventilamium + 1932 [34] PC
83K

BRICKS

Southwark [St. Thomas St. 15 (21) 205] J. Bird 1975.

△

Southwark [44-48 Borough High St. Inf. J. Bird rubbing.
28V] Granular cream fabric. occ. - i. r. facing;

DRICCIUS

Venlaminium [Blue House Lane, Insula 27] buff. no rubbing or drawing.

Venlaminium [55 A XXII 7; 189K] sandy, buff fabric with dark grey core, & slip discoloured to dark bluish grey; few grey & whitish grts on fragment.

Venlaminium [57 T. X. ⑫/2. 250K] l-facing. Sandy, greyish cream fabric with pink core. Buff slip burnt grey in parts, (over-fired) .. D= 11"

Folly Lane, St. Albans [A/91c BRV 16] enclosure ditch 250-300 8K] r.facing. Flange and sport. D. 28 (16%) Granular greyish-cream perhaps with self-coloured slip. Inclusions: abundant, sub-rounded quartz (trans. + whitish), v. var.

orange-brown. Has typical early 2 flange like
Solenites on Wall

DRICCIUS

Provenance unknown; but probably Braughing area [Gerald
Henderson Collection. Hertford Mus. Diameter 13". Buff fabric;
sparse grey grit.

Provenance unknown; but probably Braughing area [do]
do Buff fabric; grit whitish but sparse. Dv. II".

DRICCIUS — Very unlikely now in London ^{unidentified}
Lydney, hondon, Wallbrook [W/F 705/9 K. G.H.] border frag. d. stamp. likely to be
Dricius. Sandy, greyish ^{cream} white fabric with darker slips; a little grey
flint grit abundant.

D RICCIUS

出土於 Venlaw
T.L. 0613

Adrian Hawcroft

[Sent by Michael Freeman, 126, Brampton Rd.;

St. Albans, Herts. 17th August 1971.] B. 1. ④ Sandy pinkish cream fabric with traces buff slip; one dark joining fragments in burnt after fracture; some flint grey & white; and some red-brown limestone grit survives.

) 19 CI 22


1A. 21

A

Venlawnium [Rubbing sent VR by AN (DW 72 A + B. Book) - extra-mural. Stamped twice each side vessel. Sandy greyish fabric with pinkish core & flint grit - grey & white mostly.

Whelk shell

⑦ 18



DRICCIVS

7190157

Doncaster [DJ (BW. 98K)] Granular, ^{partly} creamy brown grit abundant
quartz. Heavily worn; traces of black, white, red-brown grit on surface
but almost all gone in wear. Dr. = c. 31 cms. △

S.G.F.D.B

Venlamium [195^y S.S.F. V.X (12), 93K] stamped each side of spout; rather sandy, pale buff fabric, darker surface near spout; grit worn away save one grey & red-brown grit. Form 253K

Stanton-how, Bucks. [M.U. Jones; SHB 58 II 73] slightly sandy, pale buff fabric, outside surface orangy buff; grit mostly worn away save a few medium and small, grey and white grits; fragmentary stamp on each side of spout.

Venlamium [5^y V X (12) /, 253.K] sandy brownish cream fabric; cream slip, probably; 1 grey flint grit. Facing Jones 93K

Venlamium [5^y V X (12) /, 254K] retacing. Sandy cream fabric with thick pink core; cream slip; 1 rib grit in fabric.

break

wip side
down

Q

93 K Ventanilla, Ucayali.
[1957. Vx (12)]

DCCIVS

Venutarium [1931 ⑥4 V.A. K. p.51. 3. 70K Tracing of P.C.'s rubbing];
yellowish buff, mixed grit. $d = 11\frac{1}{2}$; sandy; grey core; stem, white, brown, grey
London [G.H. 1937, 262

^{PSL}
London [1937. 262 Guildhall M.; 77K] sandy, pink fabric changing to dirty
cream near surfaces; buff-tinted surface; a very few, white + grey grits
survive. Near 61K in shape. ⑧.

Provenance w/o Khopri - Cutaway of
~~Rewtellae~~ [label probably belongs to this; Humboldt Pit with pottery in British Mus.

[1935, 10-22, 1; C.E.C. Hawkes, British M. 38K] $\frac{3}{4}$ of mortar; 1 stamp each
side; hole worn in bottom; slightly sandy, reddish pink fabric changing to dark
grey near inside surface; outside surface probably brownish buff; few survive of white,
black, grey grit; well-worn; backed cream slip) $D = 15\frac{3}{4}$ or $16^{\prime \prime}$.



Vernacularium. 1931(64) V.A.K. 70K

P.C.

S C I D R I C

Veniamin [1931, VER. A.B. House 49, 4. 1651, YIK]; sandy, pinkish
fabric; large & medium, brown, black, grey grit.

Veniamin [no K. no. cf.] D R I C . 122 K



Ventamium A.B. House.
49-4-1651 1931 P.C.TIK

DRICCIUS

Radlett [1959 Venlcam M.8Kn.s.] r.-facing; fired to cream at one end and brick red at other; waster cracking in side; hardly any grit in upper half; moderate amount, largely to very small, grey + black (flint) + red-brown grit.

Radlett [1959 Venlcam M.9Kn.s.] cream very v. near surface + surface may be fabric or slip with pinkish buff fabric with containing thick light blue grey core; hard; no grit in fragment.

Radlett [1959 Venlcam M.10Kn.s.] fabric as 9K; very few flint grits in fragment.

Radlett [1959 Venlcam M.11Kn.s.] fabric similar but greyish tinge in surface part inside; waster cracking in inside surface and under flange probably occurred during firing; moderate, grey, white + red-brown, medium + small widely dispersed grit to b.b. r.-facing.

~~Aldershot~~ Elstree [LMAS 1956, 19, pt i, p. 72 ref to it; Harrow 12K]

large, flange + spout fragment; cream buff, hard, v. v. slightly sandy fabric; Brockley Hill type; 1 red-brown grit in fabric.

Radlett [? kiln-site under bungalow! 1959;] l. facing; friable; tendency to lamination; surface slip grey no doubt discoloured; buff, slightly sandy fabric with thick grey core; no grit on fragment.

Radlett [1959 Verulamium 11.6 K n.s.] l. facing; pink buff, sandy fabric with grey core + discoloured grey slip; a few flint grits, medium, grey + black.

Radlett [1959 Verulam 19.7 K n.s.] l. facing; fabric + slip as b.K; 3 (flint) + r/b. grits on fragment; some waster cracking on outside and sign of warping.

BRICCIUS The fabric needs to be checked & it is not published as described in cards.

Radlett [1959 Vennam M. 12 Kus.] fabric similar; slip rather grey.

Radlett [1959 Vennam M. 13 Kus.] waster proper in colour at least - very dark grey throughout, sandy fabric; some grey & white grit;

Radlett [1959 Vennam M. 14 Kus.] r. facing; thin light grey layer then rather thicker orangy buff containing grey core; sandy fabric.


Radlett [1959 Vennam M. 15 Kus.] l. facing; probably Briccius; border only & damaged; sandy, reddish pink fabric slip gone; cracking on surface - whole piece eroded by exposure;

Radlett Check were - possible. Border only not entered

PROCEWS

Northgate Kiln, London [MRG95 Context A[1105] Acc 541] 5746K


?? L.fac. 155g Diam 29 ?8% Could be unused. Buff - brown
orange - buff
fabric with thick ~~poorly~~ well-defined grey core. Inclusions:
brown version; Frequent, transp. quartz with ^{occ. l. tan} orange red -
brown
Intrusive grit: flat with cracked surface, bubbly? black hardened
stalg., red-brown? chert, rare quartz. Slip orange-brown on
outside, brownish on inside appears to be intact.



DRCCIVS
No. 1 Poultry, London [ONE 94 Context 12465; Acc no 6438 (458R)]

240gms Diam 38 12% stamped across flange.


Heavy accretions overall of sherd. Pale pinkish brown fabric with pale grey core. Packed with inclusions only clearly visible at x20, quartz, mod sat, rare obs. Cannot tell if slip. Trituration grit not visible ∵ of accretion but included quartz. Very probably Return -



DRICC IV.S

London, Graham St G.H.M.05 [Access (578) Context 1395

845K] 638g. Diameter 330m 15% greyish-cream
fabric with slip, ^{purple}fixed to orange/brown outside +
under flange and chocolate brown on top of flange
+ inside. Heavily worn in lower half. Inclusions:
packed, tiny to small qtz, ^{+ some}red-brown + black. Fine end of
RW. Inclusions: feld and quartz + rare red-
brown 95.



DRICCIUS See Hornbeam Arch. Austin 1973 vol 2, No. 4

Brockley Hill [207K. BH 72 CTI] (3) MS 10 2 pieces joining
fine textured orange fabric with thick bluish grey core;
cream slips; white + dark l.-facing.

Brockley Hill [BH 72 CTI] (2) M.12 208K] Similar in fabric
+ cracking to 202K but probably not part of it. 2 joining
pieces.

Brockley Hill [BH 72 CTI] (3) MS 14 209K] ? l.-facing (orange-
brown fabric with drab core; contains white fragments.) sandy

Brockley Hill [BH 72 CTI] (3) MS 15 210K] flange fragment
in sandy orange-brown fabric

BRECCIAS 1972 Total 11 or 12 vessels (Castle)

1972 Kitchen apparatus produced unstamped m. in Breccias forms.

Brockley Hill [203K BH 72 CTI (3) MS7] L-facing: pinkish
possibly under-fired.

cream sandy fabric; contains red-brown + white grit in fabric

Brockley Hill [BH 72 CTI K2 Pedestal MS6. 204K]

fused to blackened brownish marks on surface; white +
black grits. L-facing. very hard.

Brockley Hill [BH 72 CTI (3) MS8. 205K] stamped each side
of spout. Cracked faintly all over; white + grey +
red-brown grits. Brownish cream fabric.

Brockley Hill [BH 72 CTI (3) MS10 206K] Fine orange-
fabric with thick bluish grey core + clean slip; white
+ dark grey grit. Warped.

DRICCIUS 1972 Total S A Castle says 11 or 12 different vessels
(14 different stamps). London Archaeology F 1973
Vol 2, no 4

Brockley Hill 97K Area adjacent to Brockley Hill House. Flange
fragment in unusual fabric; soft deep reddish brown,
fine-texture, with remain of cream slip.

 sent 1969
found 1966.

Brockley Hill [CTI ③ BH 72 MS 11. 199K] r.facing, orange brown fabric
with grey core; sandy fabric.

Brockley Hill [BH 72 CTI ③ MS 9. 200K] r.facing. hard, orange-
brown fabric with thick grey core; surface grey.

Brockley Hill [BH 72 CTI ③ MS 13 + CTI ② MS 12 +
BH 72 CTI ⑤ 202K] ^{Lip area} stamps on both sides but not joined.
orange-brown heavily cracked faintly all over; with
red-brown + white + translucent (few).

DRICCIUS

Brockley Hill [MAS 19 pt.i, figs. 2+3, M.13; 54 C 3 13] Harrow 9K] drab

creamy brown core changing to orange fairly near surface; cream or buff
slip burnt black in places = a little bit stuck on above stamp; very
smooth and fine-grained not like Brockley Hill fabric; ? mottled

Brockley Hill [T.L.MAS 19 pt.i, figs. 2+3; M.13; 54 C 3. D 3; Harrow 10K] soft,
tile red fabric with drab grey core; fine; no grit on fragment; pale
buff slip; very similar shape to 9K; worn; not like Brockley Hill fabric;
In "black under-colbles." Δ 22.

Brockley Hill [T.L.MAS 19 pt.i, figs. 2+3; M.13; Harrow 11K] r. facing; slightly
sandy; flange + spout only; buff fabric with orangy pink surface in
parts.

DRICCIUS

Brockley Hill [BH 74 T.C. MS 31 293K] l.-facing: greyish

cream fabric with thick brownish core; grey + black flint.

Brockley Hill [BH 74 T.C. MS 32 294K] r.-facing. weathered
no rubbing - greyish cream fabric, discoloured slip.

Brockley Hill [BH 72 CT(3) MS 16 211K] flange fragment

in sandy orange-brown fabric with cracking

Brockley Hill [BH 72 Site C 353K] Distorted bead, broken
in one part. Very hard, orange-brown, fine fabric with
grey core & thick cream slip.

D·RVLV | c o M R

under CONR.

NANI

Birrens (F.P. 194)

Leicester

DVBITATVS (Dubetans) Symonds and Wade

Colchester [P4452 X419 T2 150 S39] no rubbing

See Combs; heics;

DVBETAVS

Symonds and Wade

Colchester [P3320 BKC E130 Tz152 S40] L-facing

Colchester [P5639 x 396 ⁴⁴⁸ Tz78 S41] L-facing. Fine
brownish-cream with pinker core; hardly any
tempering.

Colchester [P5640 BKC Ni Tz169 S42]

DUBITATVS

✓ Δ 258
389.

Mucking, Essex [299 x 627 ① M; 302 M x 628 ②] L-facing. D = 15°

L-facing; hard, peachy brownish fabric; red-brown, white & few
transparent colourless tints variation grit. Cat no 5492
level 2 in Ditch feature

B

A

DUBETANS

S. Shields [P325 101 5573 26K] fragmentary. Must be
Dubetans. Green fabric with v. thick pink core. Fine-textured
rare grit & v. lib. inclusions. Quartz, flint & red-brown
trituration grit. Only border & third of panel survives.
Billingford, Norfolk Site 7206 1K] Rubbing sent by D.
Gurney.

DUBETRUS

5.6 M. 9K Drab greenish-cream
Cobridge [AV63, M504A. 41915] Paste yellowish-brown fabric

[Munsell 10YR 8/4], with a slightly powdery feel to the surface.
inclusions,
Slightly micaceous fabric with moderate fairly ill-sorted, sub-
rounded translucent \rightarrow opaque quartz, ^{? flint} red-brown and black
fragments. Trituration grit included translucent quartz,
opaque white quartz or limestone. IRS. : \approx DR. 31 cms.

Rim v. close to drawn one no 19 in Cobridge m. stamps. Could be
same pot. Bishop & Dore 1988, 265, no. 127 probably different -
need rubbing (facing SYP SS9/S6/6).

DVBETAVS *zf.* DVBITATVS

COLCHESTER

Colchester [395.29; 209K] cream fabric; some medium to largish red,
white, grey grits. A Plange. A

Colchester [Kilm. II 2/89; 215K.] cream fabric; stamp faint A Flange A

Colchester [Kilm. III 2/91; 234K.] slightly greyish cream; 2 stamps close
together; no grit visible. Read as DVBETAVS by K.F.H.S.K. Plange A

Colchester [c33 cws 35; 211K] cream buff fabric, few small to largish, A
white, red-brown, black grits to w.r. b.b. L-facing. Type as 213K. Die a Flange

Colchester [c 33 cws 45; 212K] drab buff fabric; few, median black grits.
L-facing; worn, broken stamp. Type similar to 209K. Die A. Flange. A

Colchester (33 cws 36; 213K) pale pinky buff; cream at surfaces; small to largish, white,
red-brown, grey to b.b. D = c12 ins. L-facing. Stamp flaked + worn. Die A⁴ Flange A

DVSE TANS


COLCHESTER

Venulamium [Arch. 90, 1944 p. 121 f. 19 & pl. 24, 7]; 104 K no rubbing residual?


~~Corbridge PAA⁴ XVI p. 180-19~~; pipeclay fabric with sharply broken white + grey grit.

Great Chesterford [Cambridge Mus. 12]; dirty yellowish pipe-clay; much flint grit. Braybrooke loam.

Cannons Mill, Bishops Stratford [J. W. Elcock, 42, Thorley Hill, Bishops Stratford, Herts] Plange.




Vertebrinum
Arch. 90 p. 114, 7



JVBETRUS

Heybridge, Elm Farm Project [14 EF 94] 7390 ft mid-late 3
9K L facing. 2 joining sherd + 1 extra not joining.
155(2), 195(3)g. Diam. 29cm 18%. Self-coloured,
fine textured cream fabric. Inclusions: ill-sorted
moderate, quartz, flint, opaque orange-brown and black.
Intervarian: none survives.



DUBITATUS

COLCHESTER.

✓ ^{own coll.}

London, Wood St. [CRS] M.R. London p.89; C.I.L. VII, 133.4, no. 27; Coll.

Ant. i, 149 + pl. 2; British M. 20K] r. facing; twice together; fine cream fabric; smallish, medium, fairly good amount, white, black, grey grit on fragment. Good c. facies Plange.

Mucking, S. Essex. [ink w. Bodwell] die ~~not Bodwell~~.

M.R. Hull notes a stamp of DUBITATUS from 13A and 13B (Kilns); DK, which stamp

Colbridge [AA⁴ XXVI p. 180, no. 19; S 59 + S 66. 19] 2 pieces. 1 stamp each side of
spout. 175K] Drab cream fabric; small to largish, prolific, grey & black,
whitish grit to $\Delta \frac{3}{4}$ b. b. b. D = c. 13 ins.

Colbridge [AV 63; seen at Dunham 1963, 9K] fine yellowish cream
fabric; white & flint grit - frequent. Site XI N.W. northern half
disturbed; contained stone tumble; immediately below topsoil].
See other card for 1987 description. M 504 A

DUBITATUS cf. DVBETAVS

COLCHESTER.

Colchester [kilo: 210K.] ✓ 2 stamps close together; l.facing; drab buff fabric, no grit survives. Type similar to 195K. Flange. B

Colchester [Kiln 3; z/96; 2.23K] cream fabric with pinky core; few, smallish white grit near b.b. D = prob c. 1411. Type nr. 207 but flange not as long vertically (BAN)

Flange. B

Colchester [Union Hospital 1930, 432K] cream-buff fabric; flint(s) & white pebbly grits. r.facing. F. Flange.

Prittlewell, Essex [Romano Saxon Cemetery, 14K; Southend Mus. Tp. 66/1] hard, cream fabric with pinkish core, large to smallish black, white, v/b, grey grits. l.facing, and sign of stamp on other side of spout. Flange. B

DUBITATUS

210K Colchester

DVBETANS cf. DV BETATUS

COLCHESTER.

Colchester [Kilm. cws 2188; 214K] cream fabric, much largish, white, black, red-brown, grey grits, straggles to head bottom. Type as 64K. Inside pulled about by grit. Stamp very faint. Die A

Flange. A

Colchester [C33 cws(14); 216K] cream fabric; broken flange; stamp faint but fairly certainly die A. Type 209K; no grit visible.

Flange. A

Colchester M [310.97; 419K] pink core to buff, cream-buff surface; small to medium white, black, grey grits to c $\frac{1}{4}$ in b.b.b. Type 66K. Flange
Colbridge

DVRB see BRVCNS

Rochester (Staffs - N. Staffs F.C. XLIX (1914-18) p. 104)

DUTIO — see AVITOR

AVITOR cf. DUTIO & ANTONIUS.

~~Stack (p.10, no 2 - AVITOR)~~

p.10, no 2 - AVITOR

AV. is not recordable on anyth. eq.

E.B. reads AVITOR or DUTIO.

