


G

G.

MORTARS.

Gaius	Geref (:GERMANVS B.)	
G. <u>Atilius</u> Primus	Germanus.	
G. <u>Atilius</u> Gratus	Gescod.	
G. <u>Atilius</u> Sabinus	Gracilis.	
G. <u>Atilius</u> Marinus	Græcus	
G. C. <u>Satto</u>	Gratianus or Gratianus	
Geminus	M.O. Greicus.	
Genialis		
Gentilis		
Ger or Gel.		



G. ATISIUS GRATVS

See ATISIUS GRATVS, C

~~CENTUS~~

~~CENTUS~~' *Vendomia* (P. S. XXI, p 279?)

' See Cattus
Mannus.

G ATISIUS SABINVS

See ATISIUS SABINVS G.

GERFE

(1) ~~GERFE~~ (GERFE (well)) Hambledon valley, Rucks (Arch. 71 p 188)

'cf. GER.

G. ATTIVS MARINVS

See ATTIVS MARINVS

DCO VF

G. C. SATTO - See S for SATTO.

~~ELSV~~

~~ON~~

INCOMPLETE

Wroxeter [no mark J. Houghton 1978 24.1. 174K] Picked up
on surface of fort. Stamped diagonally. Hardish Orange-
brown fabric with blue-grey core to near to surface; red-
brown & quartz-like grit



GEK Samian & Attic potters known called GELLIUS


Caisfor by Norwich [b'7K, R9, D19; 238 Nor. Arch. xxvi, part II, p. 211, R9]

cream fabric and surface; huge and medium grit, sporadic but good amount, nearly up to top. Pit 7.

Caistor by Norwich [Norf. Arch. xxvi part ii. p211, R.8. Pit 30.

Fabric as above.


Baylham House, Coddington, Suffolk [8K. N. Loughlin BJ / F. 9
BJ / BM (12) + BJ / F. 29 BJ / HP 77 Six pieces
making 3/4 of the upper part of vessel] Dr 26⁵ cms. Fine,
sl. sandy, soft, ~~600~~ creamy brown fabric wth pink core wth some
fine flint, qtz & red-brown tempering; has had large, coarse
interior grit, mostly ~~mostly~~ ^{materially} ~~now all~~ fallen out except
^{to} 3 lumps. A



4.7 kg Castorite

After 95+ are two v/b surfaces. Sl. abrasive to touch (but not sharply like wood sand).

Chester [Love St., Box 10; 34K], hard red-brown fabric with ^{purple} ~~greenish~~ core, —
filled inside; small brown + black grit, medium + small, not a
vast amount; fabric very heavy + after it was broken a greenish
glaze on part of it; shoot very shallow. This material is
either over-fired or has been subjected to very ~~very~~ considerably
heat; there is grit in the fabric. Surface of pot has been smoothed
after breaking; stamp diagonal; vessel very poorly
finished off.



GEMIN.

houdon, Old Change [1928.185 Guildhall M.119K] slightly sandy; deep brick red core to very near surface, then dark grey, almost black; buff slip blackened in parts; medium, moderate amount black, r/b grits to b.b but mostly in bottom. D=14 ins. r.facing.

Description (1972) Brick-like fabric; black skin $1\frac{1}{2}$ mm thick rest brick red + texture + discoloured buff slip; red-brown + black grit; 1 or 2 white; stamp right facing diagonal.
? comparable to fabric seen from Highgate Wood A.

GEMINVS

(i) ~~Kondor (G.H. 1928, p. 1)~~)

? Mansion House 1873 (Roman Antiquities recently discovered
on site of National Safe Deposit Company)

GEMI·OF
(? moriar)
Premises 1873 J. H. Pulerton & T. E. Price
Chester?

Leics. VCH I, 203. Theirs. Arch. Soc. VI, 96 (read
CENNIF) dull drab ware 15½" diam; stamp repeated twice

GT 1928.12.5

GEMINVS

Probably Oxford.

NEWKNORR, Oxon SU 1172 L759 8/11; Chas. Mowg. Yellish-textured cream

fabric with thick brownish pink core to rear surface. Smooth cream surface.

M. 40. Stamped twice close together w. facing. Ashmolean M

Gloucester, Berkeley Street [77/69. 90 XV ④. ~~1024~~ 33k.]

damaged FF. Flaked surface. complete stamp not impressed in one attempt; stamp fragmentary, stamped twice close slightly with grey core; (circular wheller than Veragan) together. Brownish-cream fabric, almost a granular texture, frequent inclusions of fairly well-sorted, sub-rounded pinkish quartz, sparse tiny black and red-brown fragments. Tribulation not surviving but a few quartz grits on upper surface of flange, translucent white and brownish with opaque brownish. Orange-brown slip surviving in places, gives a ^{surprisingly} smooth surface.




GENI [P]

?Colchester

- potus LWC 73 Δ 3709. P 3315 Tz 81

Colchester [LWC 71 B575 Δ 1212 610K] v.v. (stamp)

Fine-textured ochreous brown fabric with fine quartz + red-brown
inclusions. Perhaps had very little or no tempering but possibly
1 or 2 flint, quartz + calcareous. Dr. 33.50 50-80? Δ



GENIALIS

Sent by Phil Mills die 4

Wood St., Norton (by Merton) [5-08-15 (206) 23K]

3 joining body & base sherd plus one rim shard, not joining (190 gms + 65 gms). Diam. c 300 mm 6%
Diam of base 110 mm 40% Hard, compact, orange-
brown fabric with cream slip. Inclusions fairly
frequent and ill-sorted: mostly quartz (transparent),
with red-brown ~~for~~ & black indusions and possibly other
rocks. Mortarium unusual because it apparently
never had any trituration grit. The Slip is intact
under base intact except for some off an external P-
angle between side & base & possibly never used, but a

surface smoothed throughout on inside. Has some blackness + greying on surface probably due to stacking conditions in kiln. Die 4

GENITALS. See Heron-Grove '70 for similar fabric types.

Norton, Mallow [New Youth Club 1967. at 2' in Manhole Trench.]

flange fragment. Fairly coarse orange-brown fabric with cream slip. Some cracking just showing under flange. 9K D

Slack [TG. Manby, died unknown because never seen] D

"

"

Scarborough Museum. [No provenance. 1090. 38] L. facing; worn. pale orange-brown fabric with thin cream slip; orange-red showing through; grit gone except near brad; white fired-brown.

D



Genitalis
Narva

GENITALIS

Brough-on-Humber [P.C. + T. Romans, Excavations at the Roman Tonnacat]

Brough, E. Yorkshire 1936 Frig. 14, no. 100; Hull M. 5K] Read as
S.IVIAF. Under stone bottoming of Turf rampart + tree dated D
c. 80-110 A.D.; hard, brownish-red fabric with thin grey core + cream
slip. 1 brown + 1 red haematite-like grit; D. between 12 + 13".

Mallon 1949-52. WF.10K Flange + bead fragment. Hard dark red
fabric with blackish interior + buff slip. Probably L. facing D.

York, Minster [YM PK 69/164. 86K] Rather coarse brown-orange
fabric with cream slip coloured to orange on parts of flange.
Fabric tempered with quartz grit. No whit. grit survives. D. c.
L. facing.

GENITALIS Rush et al. 2000, p 187, no 27, not illustrated.

Castleford [no. 507] CAS 80 S. 10 L 058 (128) 59K] C-facing. IRS

Fairly fine-textured orange-brown fabric with drab core. Inclusions: moderate to fairly frequent, small rounded-sized, mainly ^{transparent} quartz, some ^{not evenly dispersed} red-brown. Intervening grit: included quartz, dark red sluggy material (not hard), pale brown sandstone (clusters of quartz grains); mixed not kaolin which was prominent: thin cocaine slip! Fabric more ^{inclusions} granular than Aldborough VA 10K type and colour slightly different - Heavily worn. Distribution suggest York as possible source.

D

Dies B, C, D can be attributed to poster

L. S. Edmunds (waster?)

Are they same poster as A

SENIALIS

Hayton, Humberside [Bridge Farm Service Branches to Barn
conversion JPG 8.⁷ HK] 210gms Dr 300m 8% 2
joining sherds in fabric identical to 3K Hayton.
All differentiation lost has fallen out except for one
large calcareous fragment. Again overfired but
saleable. No certain signs of wear; Slip intact
under base.

Δ(S) D

GENIAHIS

Elsham [TA] 03 G(32) found while ploughing.

Frederick, Mr. Steptoe; Sorellington, Hines. [D. Patch Lincoln M.] hard, smooth orange-buff fabric

with grey core and drab grey surface tinged with orange in places,
and stained red-brown in patches; grey & black grit to bottom of head. C

Wester M. [Highcross St. 1884. L. 102] stamped twice, once ^{once} ^{New die}, on each side

of spout; buff (slip); large, white & brown grit; no ribbing. C. 12" H. E.

Grantham M. 2K (98); assigned to GENIAHIS; fragment of border; coarse, sandy,
orange-buff fabric with orange-red surface. c. $\frac{2}{3}$ size sketch. P T O) on st

Brougham Humber [S. Wacher. BRO 58; A I 91] rather drab, buff core changing

imperceptibly to pinkish orange/^{green}, with cream slip; worn inside; very
moderate amount of largish sandstone and v. few whitish & ? brown grit to
c. 1 $\frac{1}{4}$ " b.b.b. D = 12 ins. D

Gonitham - Too fragmentary to assign

GENITALIS

Water Newton [from F. Dakin. In possession of D.G. Cotton, 63-65 Oundle Rd
Peterborough]

Brownish buff fabric with grey core; slip is pale buff; grit white;
+ ? ironstone, few + large + 1 large ? ironstone grit in
fabric; l-facing.

R.F.
Rochester (S.C. Critchlow Oldfields Secondary Boys School, Uttoxeter
6 Kgs flange fragment. Hard cream fabric with cream-
buff slip.

d.C

GENITALIS

Caistor [Norfolk Arch. xxvi, Part II, p 212 no 18; D'30, 236, 44K];

creamy fabric, medium and large, white, black, grey grit. As drawn but bead not as high as drawn.

A X
Caistor [Norfolk. Arch. xxvi, Part II, p 212 no 19, D 16, 231, 52K]

like above but bottom of flange cuts about back to body at top of bead is lower than flange. Fabric as last.

A X
Hunstanton. Kiln II [2: 954, 35 K. Norwich Mus. F. C. Denton] soft, buff fabric, with grey core, no grit on fragment. Probably GENITALIS.

GENALS-F

Caistor Hull 50 3030

GENIALIS

Gantlet to Asselby (Ganteady)
Gas line. Peter Didsbury 2012

Parish of Warren Hill Spring (Plot 123 on GAA 05) 22001

NGR: SE 8876 3450 Very hard, red-brown fabric with greenish-grey core; traces of cream slip. Inclusions: fairly frequent, mostly quartz with some black material; rare red-brown material. Intercalation grit: quartz, dark red-brown sandstone, black, quartz sandstone, pale sandstone well-mixed. Some concentric scoring inside from c 1cm below bottom of bead - 2 or 3 down to the break. Broken too high to know wear. 75g. incomplete rim-section △ D

Gaistorby-Norwich [N & N Arch. XXVI-Part II, 1936 p 212 nos 18719 + R 18719] (4) +


creamclay and surface.

Slack [Huddersfield Museum p 70 no 7 + f 44, 31 f 44 b. 7], [brownish pink clay] orange buff fabric with darker surface; largish red + white grit; very worn both stamps broken. D.

Wilderspool [May p 64 + War M 138. 01 (5K)] creamy fabric with fine sandy particles in it; rough + coarsely finished on outside; multicoloured grit to c. 1 in from rim. F

Cambondig [Bateman Coll "no 9K"] large hook rim. red brown fabric with thin grey core, cream slip. like York. H. w. one at C. is good. (h.)

Leicester [Kenyon p 217 nos 81 f. 58 nos] hard, yellowish buff ware, pinkish fracture, with smoothed surface; ZOK C



GENIALIS

Leicester [Kenyon p217 no 8] hook rim fragment; hard, smooth light buff.


Y3K. Not published.

Yorkshire Museum [14K] ^{plain} ^{fine reddish particles in fabric} hard sandy orange-brown; little white & black grit. Definitely ~~o~~ b. ^{dk} with grey core; no slip or seal covered. P63, no 100 D.

Brough ^{irregular} [no 100 + p63 fig 11 no 100] ^{thin, grey-brown} ^{(Understone Bettomia) greyish} ^{grey, gritty; a little slip remaining; coarse mixed grit} Many

Gaerlun [Arch Camb lxxxix. p 39 no 38 + p 79, no 12] p. 79, 12 T

~~Dra. Samian in base layer, in all 1 Savian; bkt plain seems includes 1 piece wh. can hardly be earlier than Hadrian and a little Hadrianic. Coarse pottery, H. w. not 1 ft. in height. Large coarse amphora fragments, the bases in stone & fl.~~



border
wrong

border
wrong

Out-

14 K. Yorkshire Mus.
Refer again for details.

17

14-15

~~GENITALS~~ Just above site in debris of 'temporary' fort near gateway
scarcely any other pottery found. This is only piece useful for dating.
~~Whitby Museum~~

lease Rigg, East Yorks; [Hawes, now Scarborough M=1958] hard, grey

fabric changing to orangy buff near the inner surface; and covered
with a discoloured slip probably intended to be buff; much red
sandstone, and some hard white grits. See Water's Causeway. D

Ambleside [Unpublished, Lomitt library] flange fragment; cream ^{sandy, greyish} fragment fabric. F.

Caerhun [26/III/2 Arch Camb. XXXIX pt. I, p. 22, fig. 26, no. 38 and

fig. 37, no. 12 on p. 79] drawing upside down; so ft, cream fabric;

brown, black and grey; largest to small grits to b. b. C


Bainbridge [B63. D.T. ⑬;] ^{stamp worn and broken CER} slightly sandy, cream fabric with a little
red-brown grit in fabric; tertiating grit mostly gone; only 1 whitish C
grit & one dark brown grit; probably a cream yellowish cream slip, mostly gone. C

GENIALIS

Trans. Thoroton Soc. of Notts LXXIII (1969) fig. 12, no 7, p 35, no. 5.

Margidunum [stamped twice each side of spout. M. Todd 1969.] Pale buff, with traces of reddish brown slips on flange. Interruption
guts are mainly pieces of white flint; a few are grey or
brown. Not seen. Complete vessel. Details sent by M. Todd. F

Doncaster [PT/E.T. ~~30~~ 76K] Hard creamy white, fine-textured fabric but
fairly heavily gritted; fine white, brownish grit in fabric; 1 brown interruption E
grit survives.



GENIALIS

High Cross [62, Greenfield 1955] stamped twice fairly close together. Orange fabric

with rather paler cream varying to grey core with slip, apparently grey but possibly due to
burning. Rather sparse, medium-small sized grit dark brown (ironstone) + mostly white
(quartz?). G

Wilderspool [May 56K p. 64 misread EVIAIF; pl. 14 '13] stamped 3 times close together;
smooth, soft, cream fabric with drab surface, more buff under flange,? burnt,
a few grey + brown grits.

? PTO ^{Someas Derbyshire} ^I several one
Mehandra Castle? H.A.L.F. now missing. Derby A.J.L.XIX 25 (1906)? F

Templeborough fac. p 90 pl. IV no 3 Manchester Mus.



Melandra Castle - listed twice published in 2
different places.


UNCERTAIN.

Wexler [K⁶²
M.I.S. 11, 93 no 584 p. 61] type-34. Sandy, yellow brown, surface brownish
orange slip; flange fragment.

Worcester [W.P. F. & b. 1892 site south of Baths, G.W.] hard brownish pink with grey core
buff slip: Some grits in the fabric white fired but none of interior grit on this
fragment. End of stamp seems complete (C) but stamp broken. (CATS)
Stamped diagonally.

Venularium [ex ss F. 1956. (III 10)], stamped diagonally, fragment of flange
in orange-brown fabric with slightly pinker slip; a few odd small grits
of flint underneath. In P. Socin b. 1956. 3. 1.

Melanocnemis. [p. 90 & Pl. V no 3] Derbyshire Arch. & N. H. Journal XXIX (1907)
Conway Bird 1905 Same one



? GEMMAE
(High Cross Type)

DIE ?

GENITALIS

source needs checking

Rochester [8087 in 1595 book] IRS. Very hard, brownish-buff fabric
with grey core; ^{some} quartz and red-brown inclusions; quartz, red-brown
& black? iron rich tintation. Buff-brown slip. Internal dr. \leq 22cm. G
Esmonde Cleary and Ferris 1996, p 68 1595 Not illustrated
note cont'd date

GENIALIS

Northwich [In same box as 49 which is Pastle. No number noted. 50K]

Worn. Upper $\frac{3}{4}$ complete. Dr. 28.75. Cream fabric, fairly fine textured; little quartz + less v/b temper; slightly abrasive surface. Seems mid land. r. facing stamp probably repeated 2/3 times but ruined by smearing or smoothing. small, mostly qtz & some v/b temper. Δ 6


GENITALIS

Widderpool [84K 66/E6/12/134] v-facing 38 twin, fine cream fabric
containing much fine red-brown + grey grit; buff slips; abundant small
white, grey + red-brown grit to b. translucent pinkish: G

GENIPHIS

Roseler [R.00-5003] 80K r.t.l. facing 1183g Dr. 37cm.
34% Hard, cream ^{slightly micaceous} slips with cream slip. Inclusions:
moderate, quartz, orange-brown and rare black, all ill-sorted.
Intrusion: quartz, transparent & pinkish, black (? slag) &
^{rare} tabular
pinkish sandstone, (mostly quartz). Joins 5006 (216g)
IRS.

E



GENITALIS

Newellie.

St. Edmunds

Caistor-by-Norwich [Via P. Carrington. Mr. J. Shaw,
35, Little Moss, Scholar Green, Stoke-on-Trent]
found by his daughter, Jane Shaw. In the embankment up to the
walls of Caistor St. Edmunds. Sketch in helter. A warped
waster; cement from walls adhering. Overfired to grey with
greenish cream surface; some tempering; quartz flint & occasional
dark sluggy grit & opaque white either limestone or chalk.

Dr. 24 to 26 cms.

R.




GENIALIS

Hayton, Humberside [Bridge Farm 2000.21b (JPG 6) WT(water)

Trench) ^{73K} 47m. 155 gms. Dr. 330 mm s 13%^{ext not very good} Very hard orange brown fabric with ~~v. thick~~, well-defined grey core Munsell 2.5YR 4/0 with an almost bluish tinge; cream slip so thin it barely masks the o/brown surface. Oxidation possibly post firing - see repeat. Inclusions: moderate to fairly frequent, tiny to small quarry, with rare orange-brown sandstone, calcareous and black material. One hard greyish white titration grit survives. Almost certainly overfired, but probably perfectly saleable. Stain v slightly diagonal.

GER - of SER.



C. SITAISFCIV C. virginalis according

Wroxeter [M 110: II f. 3 no 57 ap 61] Type 34 grey brown; small white grit.

GERI [

: GERMANUS - Castle area

Gld Penith [131-130-7710230 5K] Hard, fine textured,
red-brown fabric with a moderate amount of fine quartz & red-brown tempering.
Very well-finished off; much very fine tituration grit, quartz,
(white & transparent), small flakes of gold mica. Moulded on the
outside. (Feldspar a 1701.273?)



0V

6v


GERMANVS I

Hus Acc

London (Guildhall Amphitheatre GYE 92) (80) Context 11516
510K) r. facing and diagonal. Pd II (1140-1230);

1.525kg Diam 270mm. 100% This material has
been stamped only once. Spout looks Flavian.

Cream fabric with Inclusions: frequent transparent quartz
tiny to small, nor well sorted, rare red-brown. Interruption:
relatively free of grit for 20mm; below that tiny to
medium with ~~few~~^{some} large flint, transp. quartz. Some
vestigial conc. scoring below c. 30mm. ~~Heavily~~^{well-}
worn and hole c. 30mm across worn through base
ie centre presumably fell out. Height. Fine VRW (5)



Colchester M [1558.31. CEMR 1931-2 p34; 276K] pinkish buff, burnt black

throughout in parts; some whitish + red grits with stragglers to bead.

Pewterers Hall, Hume St.

London [1936.19.7; Guildhall M. 247K] r-facing; hard, cream-buff fabric


with buff surface, dark grey in parts; much, white, grey, black grit;
stamp slightly diagonal. D = 9½ - 10 ins. △

^{BSE} London [1937.74. Guildhall M. 80K] r-facing; sandy, cream-buff

fabric with drab to brown surface; ?burnt; flange and spots only.

^{Flavian Vienna} London [CRS. not in R. London; 19; British Mus. 66K] slightly sandy, pale
buff fabric with buff surface; smallish, red, white, grey grits to c. 3/4 b.b.b.

London, Southwark [At offices of B. & Cowage, Southwark Bridge Rd; Arch. xxiii p. 322] r-facing
cream fabric; grey flint grit to near bead.



27604 Colchester M..

Hambleden Villa, Bucks [Arch. 71, p. 188, fig. 19 no. 5; 6K Aylesbury M.]

"E. of Tuning Fork"; sandy fabric with greyish buff core changing to bright, rather "vulgar" shade of orange, but most of top surface and under side of flange burnt to a purplish grey; prolific, small to medium, red-brown, grey, white, black grits to top of head; 1 or 2 stragglers on top. D = 10^y 2 ins.

Hassocks [SAC, Ixvi p. 48, 71; 5K Newco Mus.] slightly sandy greyish cream fabric; much of grit worn away; rest, large to medium, orange-brown, red-brown, black, grey grit to b. b. D = 10^y 2 ins.

A

Cambridge [NE 60; Seen at Durham 15K] flange fragment; burnt grey throughout.

B

London [> 302K GH] sandy cream fabric with yellowish
brown slip; red-brown, white & grey grit; fragment,
Southwark [199, Borough High St., B. xix (27)] flange fragment.
24K. burnt. Pinkish granular fabric. Sketch.


Chester [Amphitheatre 1964-Tr. 1W. Pit at base of seating bank.

Bag [179] 57K] Sent by Hugh Thompson. Sandy, cream
fabric with thick pink core; grit in fabric; mixed smaller
to tiny white, r/bt grey grits. Section incomplete.

GERMANVS

Elginhaugh [58] EH86 AB 920 AC 6237 12K] FF

Burnt probably after fracture. cream fabric with
S-c slips. Inclusions: frequent; VRW almost entirely
quartz, rare black opaque & rare orange brown.



Cameron [EX 233; NMA. 47K] r. facing; slightly sandy, cream fabric;
abundant, white, grey, black, brown grit to lo. D = 9½ ins.

GERMANIUS Q

Annetwell St., Carlisle [CAR 89 ANN D] (318) serial no. 826 140K.

Jones [CAR 89 ANN D] (216) serial no. 524. Base/side frag. not joining

do. (227) Serial no. 555 Frange' frag. not joining. do (216) serial no.

526 140K] Ltr. fac. Very hard, greyish-cream fabric.

Moderate, ill-sorted quartz, sparse red-brown inclusions. Could have had a s-edimented slip. Very heavily worn throughout and all Trituration grit worn away except for certain odd ones (^{mostly} near top) including haematite, pale red-brown and pinkish quartz. slightly vitreous.

Surface Resembles South Carlton fairly closely. Dr. 40 cens. Burnt before fracture: 28% of frange/spt. but Germanius is harder & finer textured.

GEMANVS 2

E, Middlewood, Lincs.

A

slip, adust (the cat was at), from which out

hucculae [D. Shott, 17k] found near Fife in the early

Oaten Hall Farm [OHE 73 (2011). It's likely to be 1. Farington, Farington
stamp, IRS. Greyish - cream feathers, reddish to brownish red, some
winded gulls, sometimes pink, sparse brownish - black iron
fragments after staining the surrounding clay. Little
fragments of it survive, some trace of quartz and red
trinitite, glass, some trace of quartz and red
sandstone, traces of pinkish - brown silt.


Staircase, villa, N. also to .

Lancaster



GIBRILLUS DIP. C. 90 MIL YRS? See FECL T

Wroxeter [from G.W. Wpt. 64] very hard, fine, micaceous buff-brown
smooth / soft creamy fabric with brownish
medium sandstone
buff slip; bluish ~~stone~~ grit nearly up to band. Fabric like E. Midlands.
③ but this piece probably earlier. 136 K. sand L - framing.
Inclusions: fairly sparse quartz, red-b. naturalite + black.
Munsell 10 YR 8/2 Dr. 28 cm



out

Worcester

WPF-6544

17

Giomilus.

Wroxeter [62] No. no. 169K] L-facing Dr. 28 cm micaceous fabric,
v. pale creamy brown v. fine-textured fabric V. y. little grit
in fabric; few grits on or in fabric, white opaque + quartz,
red-brown (? soft) Inclusions: few quartz + black red-brown ss.
Munsell 7.5YR 7/2 approx ④ J. Evans. 2 young fragments.

Attributed to Grimes - F-ECIT - borders.

GISSVS

London [St. Albans, Wood St. SA^{SA} 35f / 8-14 H. A London]

Granular pinkish brown fabric & darker slip. Flange only. A
Border'd F-ECIT.

London, St. Albans, Wood St. [SA 29] 9110 Stamped (F-ECIT || LALLANS

Hard orange fabric with thin grey core in ^{flange} parts; surface brown. A
W.F. Grimes excavation - small; type not yet identified.

FACT OF GISSUS

London [12842 M. 10K Merseyside Lough by M.] r.facing.
Granular, creamy buff fabric with pinkish core; grey,
black, white & red-brown grit - mostly flint.

FECIT attributed to VII L

BROCKLEY HILL?

London [M2824, CRS Coll. 1856. British M] r. facing 114 K. hard, very slightly sandy, pink fabric, inside half dark grey; pinkish buff surface (? slip); few, black & grey grits. Probably the

FCC (i) ^(ref) referred to in Coombe, Arch S, 1787, p. 130 & in CIL VII, 1334, 78a (Cohen misread as T1DEF).

London [Site of Old Custom House c. 200 yds west of Tower L. Sent Tim Tatton-Brown. Ft 329K. f57] (880 > Cat 73 x ⑥). L-facing. Warmer orange brown fabric perhaps slightly burnt, with drab brown surface. Well-impressed finger impression where rim has been held under stamp.

GISSVS

Staines [CAD 77 A 20 (28) 33K]

Staines [CAD 77 A 20 (43) 34K] fl. fac. granular ^{pale brownish} opaque
~~cream~~ fabric with buff - ^{brown} slip, tempered with much quartz & ^{some} ~~more~~ large opaque. Dv. ??? 30cm. no body ~~flange~~ v. brown. Join CAD 77 A 45 (44) flange fragment. sumire.

Staines [CAD 77 A 58 (27) + (64) joining. Worn. 36K
fl. facing. granular cream fabric; dark cream to buff slip
discoloured to grey on flange; flint grit.

GSSVS

Ware [A H 79G 103C-200/1 12K] Just CR too small for Dr. ? 30-34
Almost greyish. Frequent tiny inclusions quartz. May have
a buff slip. No temperation survives. Burnt.

GISSVS Sometimes 2 or 3 p. & will have only BROCKLEY HILL?
sometimes with counterstamp only.

Venutarium [1933 v. A. 33 35] III 2. 6p. 117 4B. 99K. Dr. 15 1/4". Buff
fabric. Stamps smudged; put on when clay was wet.

Venutarium [59. BJ 31/2 259K] flange fragment. sandy, reddish brown
fabric with traces of slip, discoloured.

Brentford, Middlesex [P. 191 Heyton Collection. Previously in Brentford Library
& probably from Brentford. Now in London Museum 17K] Stamped each side
of spout; almost whole. Worn; sandy Bt/R fabric; slips discoloured to
very dark grey; large to smallish, few, white, grey & black grits to near
bead. Second century section. Worn heavily; hole in lower part. Stamped
with the name only on each side.

GISSVS

Baldock [Tx/AA 13K] flange fragment. Probably the bottom of
the 2 ss. Border can be attributed to GISSVS.

London [Old Custom House site c. 200 yards west of the Tower of L.]

Sent by T. Tatton-Brown 15 <880> CVS 73 X ⑥ - 2 frags. Felt
only l.-facing. granular orange-brown fabric (perhaps slightly
burnt) with drab brown surface. Good finger print.

Tawester, Wood Burste Farm [no. no. Peterwoods] Granular brownish
fabric; haematite grit + grey flint; slightly burnt, + well-worn. A
l.-facing

Brangford [BR 72 AQO 27 T. Potter 8K] Flange frag; burnt +
over-fired, granular fabric.

GISSVS

Brockley Hill [B.H.71. E.P. 29 122K] r.facing. Granular drab
greyish brown fabric with slightly more orangey brown near surface
& -slips fixed to muddy brownish grey; abundant grey &
white flint-like flint grit.

Brockley Hill [B.H.72 BT1 ① MSI 185K] Granular, pale brownish
cream fabric. Grey & white flint grit & red-brown (few) r.facing.
GISS[ret.]

Brockley Hill [B.H.74 TC .MS36 342K] greyish white fabric.
burnt to top & cracks throughout. flange only.

GISSVS

Brockley Hill [107] Hendon 71K] L. facing; fired brown buff, purplish
buff and black; 2 greyish + 1 pinkish grit. Sketch.

Brockley Hill [1968 Stephen A. Castle, 31 Micklefield Way, Boreham-
wood, Herts. Flange fragment. B.I.t. 6.8. S. Bulldozer spoil-
heap. Softish, yet sandy cream fabric with pink core with
fine ^{extreme} grit in fabric; there is a pink area on surface under flange
- perhaps surface burning. (A in Castle's list) 47K



77K Brockley Hill

FECIT attributed to VILL

BROCKLEY HILL

Brockley Hill [BH 68 Kiln O. K. in Castle's list. 78K] L-facing. Sandy,
greyish cream fabric with buff slip. Flange only. D. in a road 13".

Brockley Hill [Kiln O.D. 79K] Soft bright orangy fabric - abnormally
bright containing some fine grit; sandy texture; 1 white-grey flint
grit. Stamp very much damaged but certain of attribution, the
wavy border survives at inside & the F is clear but neither come out on a
rubbing clearly. Surface on top is paler where it survives.

Brockley Hill [KD O.C. 80K] r.facing. Several fragments quirig,
about $\frac{1}{3}$ of vessel. Stamps in three pieces. Sandy, brownish
fabric, ~~soft~~ friable; slip brownish; very moderate grit - grey to white flint
& red-brown (hard). Is either worn in lower half or grit has come out. Crack under flange.
^{FECIT} ~~orange~~ sandy.

8000' Brockley Hill. A further stamp ~~is~~ also reading FECIT + from the same die was found later + is from the same mortarium for which all of the rim is now preserved; so that the mortarium is stamped FECIT only on each side of spout.

FECIT ♂ G. I. SSVS

Brockley Hill 1973

Brockley Hill [BH 73 TC. MS 45. 255K] broken flange. Over-fired to blackish grey, parts brownish.

G. IV S ?

[1963 Origin probably northern].

Corbridge [S.344; EA.13; 114K] r. facing; gritty buff fabric with grey core in
parts; medium to large, grey and black grnts. Similar to 72K.

GLN

Bayham Mill [Ipswich M; B.M. 52. G/c. In topsoil; Ipswich School Excavations,
fine slightly yellowish cream

J. Young] smooth buff fabric; no grits; external diameter 11 ins.

* Bayham Mill [Ipswich M.c. I above Pit V; ditto.] could be part of same vessel
smooth buff fabric; large rough flint(?) grit; some rubbed out,

* Sent on for examination; East Anglian form & fabric; fabric has
similarly with Colchester fabric; has been held under flange while
stamped.



Ipswich Mass. Bayham Mill

GRACILIS at Catterick only

Assigned

N.R. Gracilis

~~Ilkley [Ilkley Museum 6K]~~ ll. facing; v. v. soft cream fabric with pinkish core;
uncertain reading
much grey, f. whitish, flintlike, small & few medium grits to b.b.; stamp almost
abraded away - border is clearest but may be assigned with certainty.

~~Catterick~~ ⁽⁴⁹⁾ [59+ 12K] r. facing; flange & spout fragment; surface much
worn; slightly sandy, cream fabric with cream slip; 1 or 2 grey, flint grits
on and under flange; stamp worn and broken; may be assigned with fair certainty.

~~Ilkley - attributed stamp v. faint. l.facing. 16K Old find. Fine, yellowish
cream with slightly pinker core; internal scoring; flint grit. BF14/18
not GRACILIS~~

GRACILIS

FOUND IN LONDON

hondar [R.XI.617 Guildhall M. 102K] r. facing; 1 stamp only on this
mortar; smooth, greyish cream fabric; some, large to small, black
& grey grits near bead, rest worn away; very evident marks of
grinding on surface. Bead not cut away to separate.

hondar [1937.88 Guildhall M 33K; G.H.C p.102 (3316) no.617 misread
as C.RACIVS F] L. facing; smooth, drab cream fabric; small to
mediumish, grey & black grits; b.b. internal scoring; no mudding
B.F. 14, Rahere St., Goswell Rd.

GRACILIS ha v'ss D'Ucqure - L. 1811 1814; GRACILIS

Ridgeway [in p. 252 (3)iii] identical with (i) and possibly from same mortar; sparse white grit.

~~Kenton [Ges. 1937 88. Cat. no. 61^(33/6) p. 102 misreads as CRACIUS F]~~

~~Aldborough [Information B²; RAS. 1938 exch.]; sleeper beam trench underlying 3rd C. Rampart banking; associated with Samian A.D. 65-90.
Chester [Museum. In built-up material dating up to Hadrian. Newgate site]. Buff fabric.~~

~~Chester [Mus. 26 K. Lovest. 1939, Box II] cream fabric + slip with cream pink core, internal lining, white, grey grit; a little on rim.~~

<<<<

RACILIS

<<<<<

Chester (1)

no. 26



(ii) Margidunum

GRAELHS

Richborough [IV, p. 251, 1(B). 3Y; 51K] L. facing; smooth, fine, cream fabric; internal scoring; medium greyish + white to b.b. and some in flange. D = c. 14 ins. B.F. 14.

Richborough [IV, p. 251, 1(B). 38; 52K] West gate, S. of Road. L. facing. fabric as 51K. Near BF. 14.

Richborough [IV, p. 251, 1(B); 45; 53K] outside west wall, filling of inner ditch. r. facing. different vessel I think. Near BF. 18. Fabric as 51K.

Aldborough [A 3631; 1938 excavations; sleepers in trench underlying 3rd century rampart backing associated with Samian AD 65-70; K. A. Steer; B²] r. facing; fine, smooth, cream fabric; tint grit near bead, worn away lower down; stamp faint. BF. 14/18

GRACILIS

la Ville d'Uggate - L. Coutil 1897 (GRACILIS) DK ruelliana

GRACILIS

Richborough [iii, p. 164 no. 1(A); M 18; 3K] Outside wall of fort, Trench 2;
almost whole; 1 stamp only on mortarium; r. facing; creamy pink, signs of
cream slip; worn inside, very little grit, smallish, white, red, brown, black,
by far the most of it on top of flange. D = $13\frac{1}{2}$. BF. 18.

Richborough [ii, p. 95, 1(A); M 13 1924/5; 12K] soft, smooth, pinky cream,
with cream surface; internal scoring; medium, largish to med tiny black,
grey, white and few r. (b.) grits to b. b.; rather faint, A gone; BF. 14/18
L. facing; unstratified.

Richborough [i, p. 84, 1; 3M; 15K] L. facing; hard, smooth, slightly
pinkish cream with a few grits in it; smallish, greyish and black
(flint) grits and a flange; internal scoring.

GRACILIS

Richborough [V. N. S] sect. 19; 2nd. layer 98; Site Mus. 96K] r. facing;
fine, very slightly pinkish cream fabric with drab cream surface;
medium to tiny, flint grit; internal scoring; ? aslip; fragmentary
flange. B.F. 14/18.

Richborough [V; 94; N. S] Sect. 19; W. extension, top layer; Site
Mus. 105K] l. facing; smooth, fine, hard, pink fabric changing
to cream very near to surface; cream slip; internal scoring;
good amount, flint, grey grit to b.-b. △

Canterbury [Archaeologia 43, p. 163; present whereabouts not known]
read as "IRACILIS." - Canterbury list for museum for
details.

GRACILIS ~~thin walled~~ thin wobbly handle. + Chichester

(76)

Chichester CH 80 CM 83 [220] 9k] l.facing die 2

Cream fabric with brownish core, ^{inclusions of} black slag fragments are common, quartz moderate and red brown fragments sparse. Trituration grit not surviving, but quartz fragments (1mm.) are added to the upper rim surface. Dr. 33 cm.
Worn. concentric scoring inside or top of flange.

2

9K Chichester

CH/80/CM B (83)

1220



1. facing

GRATINVS
Wilcote [1994.103. M 12, 7K] IRS · 25 g. Fine-textured creamy
white fabric with moderate + quartz inclusions (ill-sorted &


^{totally frequent}
almost all transparent and tiny to small); few, random blackish inclusions. No insulation grit survives. Die 1.

Wilcote [1994.103. M 15 8K] L facing 140 g. Diam. 28^{20%}
Hard, fine-textured, cream fabric with self-coloured slip
moderate to fairly frequent, random and ill-sorted,
transparent quartz and a few pinkish, rare ? quartz
sandstone, large; few blackish to dark red ? slag, rare
orange-brown inclusions. Only 3 insulation grits found on
fragment - blackish. Body sherd not joining with red brown/blackish grit! Die 1.

Heldon Bande (SF 30894) Anterior dorsal margin of Mandibular
a bandage over River Finke. A stamp posted on
bandaged with dark brown slip. Information from U.S.A.
January 31, 1969. See also. As
bandage, flannel, thunbleaside (286 DR 71 FB (with strap) + 242 DR 69 P
of flannel dark fabric with woollen padding, ill-suited, quarrel
+ head-burn in climbing. Influenza: dull, brown. Suffering
slightly swollen because quit in place. Dv. 31. S.

286

of clay back back fringe - well use in place. To the
in widely cut contour - read made by fold in face

Tredon Br. - Very hard, almost ~~pale~~^{buff-} brown fabric
with moderate, random greyish then black? slag inclusions
Interruption grit: only 1 or 2 surviving - greyish vesicular
?? slag. The interruption seems to have been to outline
the stamps in dark brown slips - May have been
among stamps as decorative motive 
round flange.  Dr. 36 cms.

4K May 1996, fig. 20.28, no. 1374 and p 573 side 1, not
carefully stratified.

SEXTINUS

o/s

Dragonby [270] D.R. 70.G.2 10K Hard, cream fabric. Moderate,
tiny quartz + larger red-brown + blackish inclusions.

Intersiotn included dark brown, angular material.

Dr. 27. Die II. May 1996, fig 20.28, no 1370 S.A.

Stonea, Cambs. ST 82 AEQ 376 HK

Worn. Fine textured, cream fabric. Inclusions: moderate,
quartz + fewer red-brown, opaque. No intersiotn grits seen.
Dr = 36 mm irregular. Judged from inside Die I.

FRATI AVVS

between Newark and Wirksworth

DE 3002

A4.6 road widening scheme 2009 Cotswold Archaeology

Margidurum [HGM09 303691 6K] 65g. Hard cream.

Smoothed on inside surface and in part of fabric below
surface. Inclusions: moderate, tiny to small, quartz, ^{cream-} 7%, fine
red-brown, rare black. Buff slip. No tnaturation survives

GRATINVS

135-165.

Corbridge [found 1951; unpublished. 65K] hard, cream fabric with buff surface; ? slip; some, large to medium, blackish grit. D = 14 ins. A

Corbridge [no. S.no. 21; Pit 404; T.B.; 47; 2.3.39 unpublished 349K] creamy buff fabric with a smooth surface, slip?; black grit.

Corbridge [no. S.no. ②1) 350K unpublished] a flake of whitish fabric.

Corbridge [②1) S318; 1906 T.K.; 352K; AA^yxxvi p.181 no.21] L. facing; white fabric; a little brown grit.

?

GRATINUS

Castile [81 Castle St. B(418) 2171 116K] Hard cream with some
quartz, transparent & pinkish to och. dark inclusions; 1: grey titration
grit survivor.

Die 1

York [1981.7 32909 / 13919] GG 28 127K] IRS. Hard cream
fabric with darker cream slip. Inclusions: fairly frequent, smallish,
some orange-brown, some dark sluggy. Titration: none
on fragment. Context Period does not fit exactly.

Die 1

York [1989.21 2219 SM 16 128K] Hard, fine-textured cream
fabric. Inclusions: moderate, transparent and pinkish quartz. No
titration on fragment. Context AD 150 + No rubbing?
I do not appear to have a rubbing of this stamp. Die 7

TVATTARQVSS. See GRATINVS

Ribchester [D 19b] coarse, white fabric; medium brown grit

177.1955

High Cross [Leicester Mus. S4K; 1956⁵⁰] very faint, slightly sandy; cream fabric; very sparse, medium large, white + brown grit.



D 19b. Rochester 71.

GRATINVS

Manetter [1958 G 2/b ⑯^K] flange fragment only; dark cream with some tiny grit in it; buff slip; found on kiln-site but not necessarily a kiln-product; spectrographic analysis compares well with Manetter-Hartshill [Mrs. Moreton] orangy fabric; flange fragment.

Grandford, near Hartshill, [G.G.-L.H.2] fine, hard, cream fabric; brown largish to small; 2 white grts on fragment. TL/393.997.

Mandeville [1963; ~~1962~~ T 2 ⑯^S] Birmingham (?) softish cream fabric with orange-brown tituration grits, largish to small sized; D=12". L-facing (#5K)


GRATINVS

HADMSA 99 (710) (58) near (68)

Haddon, Cambs (just west of Peterborough South interchange on the A1/A605 junction. Earlier finds are published in French 1994,
"The Archaeology along the A605 Elton - Haddalby pass,"
Cambs. Monograph Cambridgeshire County Collection.

TK Flange frequent. 10gms Hard, fine-textured cream fabric
with fairly frequent, transparent & pink/brown quartz ^{inclusions}. Tiny to medium
sized. No slip.

A d. 1.



GRATIN VS

York, Minster [87 K. YM 71 PG US/21; PK 69/166; PK 69/167; PK 69/168]

All join. v. facing. About $\frac{1}{4}$ quarter of vessel. quartz, red-brown
+ grey ~~for~~^{buff} grit; fine-textured [cream fabric containing fine
grit, buff slip. Tempering quite heavy + does not suffer from
softness that some gratins in Montana have. Dr. = 28 cens. Die 9
Fold Hills, Edingley,^{Note} [R. C. Alvey, Dept. of Archaeology, The University,
Nottingham. NG7 2RD] provenance not supplied but I suppose to be Notts.
Hard creamy white, fine-textured; occasional rounded quartz pebbles
+ rose quartz; occasional ill-sorted opaque v/b inclusions. Incomplete
rim section. Marked G H 3

Die i

University of Nottingham museum.

GRATINVS

Widenspool [May p.64 "PATINS"; 347'98; May Coll" 224'98; 59K r. facing];
very faint stamp; soft, slightly sandy cream fabric; moderate, brown, white,
grey grits to top of b; buff slip, burnt drab on top.

Templeborough [p.120, no.5; 1916-17 May; 5K] grey core to pale buff fabric; small
grits in fabric; largeish to small, whitish, black, r/b. to c. 1" below top of b., stragglers
above; dark buff slip; slightly diagonal; D = 8 ins; probably l.-facing

Tripartium [SF 227 Sc 629] 16K] D = c 12½." Very hard cream fabric,
self coloured; red-brown grnt.

Kelsey Bridge, Sibsey nr. Boston copy of drawing sent
by N. Moore, Lincoln Miss.



Restored 59 Wilderway Rd Leicester JW

GRATINVS

+ Strongground S. Counts.

Horsley Toll [v. Whittlesey] [Standen 1956:] ^{smooth} deep buff biscuit coloured fabric (1' slip) on inside
and fringe. The outer ½ of fabric & outside surface are a slightly purplish grey no doubt
due to conditions of firing. Prolific hard angular but worn smooth grit becoming sparse
up to rim - mostly black with reddish brown ^{flint} _(larger pieces) sentive or plain black. Lettering not legible.
Rite meter, L. 11.5 cm. C. 2.1 + C. 11.2. xiii

Rite meter, L. 11.5 cm. C. 2.1 + C. 11.2. xiii

Whitley [unpublished.] Museum 3K] creamy white with pinkish tinge, softish red brown grit A

Counts:

March [Stag's Holt Farm 1K Wisbech Mus. 2 v. 30; W. Watney] cream fabric with pale
creamish buff slip; a few small black grits on fragment up to c. ¼ below bead. A



GRATINUS

+

Leicester [A78 1975 V 55] stamp painted over
 + probably on letter spines only highlight letters with borders
 with red-brown paint. Fairly hard buff-cream fabric;
^{fairly frequent}
~~moderate~~ inclusions of quartz ^(green & pinkish) and ^{fewer} red-brown fragments.
 Trituration grit ^{1w2} [red-brown fragments] ^{green - possibly sand} darker ^{cream} slip
 on surface. Dr. 29cm.

Die 1

Leicester [A77 1975 I 409] joining A77 1975 5478 F68, 574
 fairly frequent ^{5475 F65} 580 . 216 k] I. facing. Hard, ~~buff~~-
 cream fabric, few inclusions of quartz and red-brown
 fragments. Trituration grit: ^{predominantly} red-brown fragments with ^{rare} ~~sand~~
^{possibly} quartz; ~~shorter~~ buff-brown slip. Dr. 32 cm. Heavily worn
 Spout type 4A/3E

GRATINUS

No. 21 in archive


handdrawnable

Rossington Bridge [Seen in Yorkshire Mus. 48K] IRS. Fine-textured, hard cream fabric with some quartz & occasional red-brown inclusions; red-brown & quartz intercalation with occasional sandstone. Die 1. Worn. Appears to have been returned to Doncaster. ^{front has} crown.

Rossington Bridge [PS no. 1. layer 5A 85 there is no. number. This and the above are from a pot now restored]. All of vessel except for a hole in centre. Dr. c. 27.5cm. wM Baulk 12, layer ^{5A} die 1. Stamped twice, once on each side. no 85 in archive 34K A

GRATINVS

* no information about provenance Rossington Bridge
according to verbal
Yorkshire Mus. [MSK] white fabric; angular brown and white grit. (intervener A)
Cambridge [1951 cor/14] yellowish-buff ware, brown grit. A
Rossington Bridge, Doncaster, [P.S. no. I] ^{restored} a base of peat. 34K. Dr 11 1/2 A.
Cantey. RAN 11 - assigned to GRATINUS by B²]



25

Gratinus : - - - - - wanted. ? reading. Die 8

Hartshill [See's Granite Quarry; Mrs. Moreton] flange fragment
cream fabric with slip, now drab colored;

break.



Hastell (Moreton)

See TUTTAR GV

GRATINVS

Leicester [Kenyon p.78 no 3 + f. 48 no 3]; drab buff ware. NOT SO CT.


P2ANAI (?? Antivs. C. P. G. D.) MISREAD B,

Leicester [Kenyon p.217 no 9 a + f. 58 no 9 a] hard, smooth, dirty white with medium to small black grit.


Leicester [Kenyon p. 217 no 9 + f. 58 no 9 b]

Leicester [Kenyon p.217 no 9 + f. 58 no 9 c];

York M [CIL VII 1331.52 "amphora" 40K.] ; hard cream fabric; black grit to bead, I guess. A




(1) 9a.



(1) 9b.



(1) 9c.



Yorkshire Arms. N.Y.K.

GRATINVS or GRATIANVS

F 15₂ + G₂ 140-1801

2

? Midland

Cotbridge (5318) fairly hard smooth fabric

GRATIN!

Monk's Road 15K.
Lincoln (Museum A.J. xxiv, 136); hard, cream fabric with buff slip(?); small black
(?flint) grit upto c.³/4 below head; black staining on part of inside. A

Wilderhope (Warrington K6'02+K) ^{soft}; creamy buff fabric with fine ^{black} brown/red particles;
fine grit nearly upto rim; rather sparse. See book no. 151K. A

Blairstead (FRA 4578; B. 266 of 35 in 9),

Kingscliffe (Dowsett) no. 44/49/49 T/DMW

Peterborough Mus.; creamy fabric; blue/brown grit; larger to small, not very
much on fragment; some on top of rim & outside strays. D = 13 1/2 ins. A



GRATINVS

Leicester [LP 223-8; c 334/6; Jewry Wall; London Institute] hard, buff fabric
with brown & purplish grey patchy slip; small & medium, black grit. Sheld.
Leicester [E/1967/46.185.1966.86.125 K]
~~Leicester~~

Leicester [21A 302 (971 161K)] very hard, creamy buff
fabric w/t slightly darker ³⁷buff slip; pale greyish core;
quite heavily tempered w/t quartz (mostly), dark
grey Fred-brown grit; no fint " grit or fragment;
section incomplete

GRATINVS

Ribchester [RB89 loc. 19 5701 54K] Dr. 32 cms. Several
fragments, making up 3 major shards which do not join
but are clearly from same pot. L. facing assumed.
Powdery surface. Cream fabric. Inclusions: moderate,
rounded, ill-sorted ^{random}, mostly quartz trans. & pinkish; rare
opaque orange-brown and black - black ^{sometimes} ~~very~~ streaky.
Interruption: frequent, both tiny to large angular,
orange-brown entirely and softish. Well-worn. Die 3

RR88a 19
SILK FIBROBLASTS purified



n-1

B


GRATINVS

Ribblesdale Mill

Ribchester [RM 90 1067 133 55K] v-facing Eight

joining fragments. Heavily burnt & well worn. Dr.

30-5cms. softish cream fabric. Powdery. Inclusions:
fairly frequent, mostly small to tiny transparent &
pinkish sub-rounded quartz + ^{some} red-brown + v. rare
black but all cut some random, large whitish quartz
and softish orange-brown (nail scrape). Interraction: mostly
worn away but the 1½ - 2" band below head
has only softish orange-brown - probably throughout.



GRATINVS

Market Overton/Thistleton area. [Oakham Museum J. Barber] creamy white fabric; very worn, no grit visible. Very faint stamp.

A

Margidunum [Ans. xxiv p. 55 + fig. 4 p. 56, no. 34; Not. Un. Mus. SK 33630, Ditch 14] stamped on both sides of spout; white fabric; red-brown, medium to large grit, fairly sparse.

Thistleton [E. Greenfield, M. 51/Baq 687 | Ref. TH2 4607] flange fragment; white pipeclay, hard, fine-textured greyish-cream fabric, possibly with cream slip.

Margidunum [Ans. xxiv p. 55 no. 35 + fig. 4, 35] not seen.

High Cross [HC. 401. 1?31] flange fragment. Fine creamy white fabric, with red/brown sandy inclusions.




Globe 11

Wroxeter [Rowley Ho. E14 K22] greyish cream fabric with cream slip; a few brown grits; flange fragments.

Wroxeter [Rowley Ho. E14, Pit, fig 40 p281 nos. 23K] grey, pinkish buff fabric, hard & smooth; prolific medium black grit up to head. 2 stamps, lead side of spout, of which only 1 fully survives.

Wall [E.Swanfield W.L. 968-M.21. 23K] slightly softish, fine cream fabric + slip; largest to small red angular grit, good amount; perhaps tile. $D = 12\frac{1}{2}$ "

Wroxeter. [WB 63 +; 1964; 139K site H.] : RS. Very moderate, gritty, orangy, blc ^{only} vesicular, large cream (grog) inclusions. Fine-t. cream + slightly angled.



GRATINVS

Gloucester, Berkeley Street [77/69. 149] XL 19. 489. 32 k]

CRS with joining IRS. Cream fabric with pinkish core,
moderate inclusions of .. pink quartz (upto 0.5mm.) and
red-brown fragments (upto 2mm.) Trituration grit hard blackish
red re-fired pottery fragments, few grits, very worn.

York, Tanner Row, [1984.32 2202 II. 99k] I. facing fragmentary
stamp. Micaceous, brownish fabric with pink core, fired to a
darker colour at the surface, possibly discoloured (waterlogged
deposit) brown areas may be discoloration or burning. Moderate
inclusions of quartz and red-brown fragments. Trituration grit quartz
and pale brown fragments. Worn. Dr. c. 31cm. Joining body sherd. die 7

Drab greenish fabric with brownish core - very odd.
but surface discolored. Source not entirely certain
but should be M/H

GRATINVS

WaterNewton [Kate's Cabin Farm Site no. 3; E Greenfield; M 70;
CH 5175]; hard, cream fabric with pale buff slip; brown
glaze; very little.

~~WaterNewton~~

Castor [B.R.H. 1961. CAS. 61.4.] Peterboro Hard, creamy white fabric
tempered with fine grit, & cream slip. D = 13°

Maxey, Combs [IK F 326 M 10654 Francis Ryer; Welland Valley]
Small ^{broad flange} fragment; cream fabric. Burnt.

Brought-on-Noe [104] B.V.84 ADW, 91K] I.R.S. Cream fabric, quartz
inclusions, black one and red clay frags.

GRATINVS

+

Leicester [A77-1975-5468] I (362) F43 271K] IRS. Hard, cream
fabric; fairly frequent inclusions: small/tiny mostly quartz (mostly
transp., some pinkish), rare red-brown opaque, rarer black. Buff
almost orange slip. Intercalation: blackish. Die 7.

7

Leicester [A165-1994 (26) Syston 'Pontylwe' 342K] Lfac.
Dr 38cm. Fine-textured cream fabric. Inclusions:
moderate +; ill-sorted, mostly quartz, rare black
red-brown. Buff. About 1 black intercalation grit
May have had a buff slip.

5

FRATINVS

Shiptonthorpe, N. Humberside [produced by J. Evans April 1995]

1394/1986 [5^a78 ST 86 + 1K] Dr 29 cms. Cream fabric, slightly more pinkish near surface. Inclusions: moderate to fairly frequent; ill-sorted, mostly quartz with some orange-brown opaque black. May have had a self-coloured slip. Incarnation: no certain identification on piece but such bits as visible include quartz & red-brown s.s. - just possibly in fabric.

Walt Museum [Grav 6 K Wallside] slightly pinkish cream fabric with creamier surface. Prolific medium and large bright red grit $5\frac{1}{4}$ to $6\frac{1}{2}$ mm.
Templeborough (fig 26, no 5);

East Stoke ^{Notts} [A. Oswald. Trans. Thoroton Soc. v. 2 (1938) p. 13 (fig. p. 8 no 4); whitish-grey with small pieces of grey grit. Diameter $9\frac{3}{4}$ "
Leicester [Kayan, p. 165 no 8 + f. 44 no 4]; orange buff fabric.

Templeborough (= fig 21, no 5)

JP



3

RATIN

E. Stake

GRA

II Templeton



GRATINVS R + A joined.

DIE 7

Hartshill [60 + 340] (19) Flange fragment. Softish creamy
white fabric.

Diet

Foothill 60

~~001/340~~

(19)

FRATINS

Found between Wansford and Wates Newton L1091 [

Peterborough Mus.] Cream fabric. Inclusions: moderate
D frequent quartz with some black iron slag Δ
Rosester [ROP '95 5003 71K] IRS likely to be L. facing
- pleat in clay. Hard, cream, fine-textured matrix,
self-coloured or sc. slip. Inclusions: ~~moderate to fairly~~
frequent, ill-sorted, transparent and pinkish quartz,
~~grey~~, ^{orange} brown and black \downarrow at X20. No
fertilization grit survives

d. 9

Holmes Crain Warehouse site.

Lincoln [HG 72. HL] Mo. I. ^{52K} Hard, cream fabric + cream slip; no grit
on piece. △

Lincoln: [P 71. G \rightarrow] Small find no. Mo. I. 53K] Hard, cream fabric
containing fine grit; drab cream slip; different vessel from 52K. △
flange stained with reddish brown substance.

Lincoln [56K J. Wagner, L. N. C. I. ⁷³ (11.8) - 1345] Hard, cream fabric
quartz, red-brown, black ^{A.37} tempered with much fine grit; brown + red grit. Orange buff slip.

Rochester [int. M. Brasington 1.7.85 RO 85 1003 30K] L. fac.

Hard, cream fabric with some quartz + v/f inclusions; 1 red-brown
intercalation grit survives. Dr. 27cm. Appear to have cream slip. Die 1. △
Esmonde Cleary and Ferris 1996, 70, no. 31, fig. 31, no. 31

GRATINVS

Bnq in quenied by Mr. Honda. [Merseyside County M. 17K
12848¹ Mayer Coll.] white pipeclay.

Tewisham ^{village} (civil) a site in Hinton Fields - the name of the fields on the
farm) flange fragment. HFT v(B). white, fine fabric. ?cameos

Walton-le-dale [WD 82 1312(186).8k] r. facing. die 5 or
may differ. Cream fabric (no Munsell equivalent) with pinkish
^{moderate amount, small} core; inclusions sub-rounded, ill-sorted ^{transp. & pinkish} quartz and red
clay pellets. Trituration grit iron slag + brown sandstone.

Dn. c. 27.

GRATINUS

Scotland.

Burrens [1966 519 + 600] joining. Hunterian M.] creamy white fabric containing much fine grit; red-brown medium & tiny tituration grit. D = 1/4". d.i. 1

Capepuck [FR. 585. NMA 166K] cream fabric with red grit d.i. A

Bearsdene (New Kilpatrick) Hard, fine white fabric tempered with much ^{quartzocal v/g} dark red-brown tituration grit; darker cream slip. NK 73 FF ~~29K~~ D. Preys. 25K Dv. c 34. 312 d.i. A

Bearsdene NK 76 DT W32 298 27K r. facing. Fabric 1. Dv. 35

Bearsdene 303 NK 75 Bl 26K Fabric 1. c 34 different, worn

ni. bond 298 27K 7K vessels
(knots on base) ① NK 73 AJ from Scotland to the Smiths (prob. probably) also contains

Macdonald p. 456.

Balmuildy [pl. xi. B.6, + p. 78; (243); F. 1922.314; Hunterian M. 10K] very

worn; fine, creamy white fabric; black grit; Type 5 Balmuildy d.l.

Newstead [FR. 1462 VII. 15.56; NMA. 97K] cream fabric with pink core to
near surface. A d.l. A

Newstead [FRA. 1454; VII. 15.48; NMA. 101K; p. 266, fig. 35, no. 2] soft, cream
fabric with drab cream surface; no grit survives; flange and head;
shape as 97K. d.l.

Newstead [p. 266, fig. 35, no. 10; FRA. 1461; VII. 15.55; NMA. 117K] hard,
cream fabric; medium - large, blue black grit; l. facing d.l.

Bitrens [PSAS LXIX, p. 331, fig. 34, no. 4; FR. 101; NMA. 157K] almost complete; cream
fabric; with red-brown & dark grit with brown centres; 1 stamp each side d.l.

GRATINUS


Kirkintilloch [F. 1953. 385. Hunterian]

GREECS

Kingstholm stamp: JRECVS Inf. J. Timby Wom.

A fine-textured, cream fabric; cream at the surface, but ~~almost~~ pale pinkish-brown (Munsell 7.5YR 7/4) ^{almost} throughout.

Few inclusions visible (x10 magnification) some feldspar, quartz and black fragments. See Exeter repn'l. Identified as Central France by J. Timby



GRATVS, C ATISIVS

See ATISIVS GRATVS ,C

MACN

(W) MACN Hambledon Valley; Bucks. (Arch. 71, p188)

~~ADA~~ See ~~HDA~~ HDA See ADA

C. Herne

CDP 903

Bayham House, p. d) Cadebyham, Suffolk [Garden of Bayham
House. R. Storer. Information from J. Plouviez 12K]

3 joining sherd^s of ~~no rim~~ rim. rubbing & drawing seen.
—No other details. (Seen at Carlisle 1999) Dr ? 43 cm. 7%
Fine-textured, dark cream fabric, very moderate, tiny
inclusions of quartz, rare flint and orange-brown
material. No tintivation survives.

Stoke Ash, Suff 1K [SAS019 1308 L 6 3] flange fragment,
seen at Chichester July 2009 BGRP. Hard, ^{dark} cream fabric.
Fine textured and self coloured. Inclusions few grey,
probably flint. Flange fragment.
(Second stamp not brought).

CALTERM E or F ? Triangular stop in 613K.

P5018 [15] Tz61 S23

Colchester [LWC 71 C223 A 1930 613K] Different vessel

from 612K. (Both have enough 8 point for certainty). L-facing.
Fabric as 612K and temper - only 2 or 3 grits survive including
quartz. Dr. very approx 36 cm. Stamped twice together. P5018

C. HERMÉ

— ask C. Gowing

Stibbing? [M. J. Camper Coll., Snape, Suff.] v. Rodwell. no. 38

in coll. fragment. krta. Camper says Stibbing W. R
suggests W. Notley as possible.

Kelvedon [spout with both stamps; sent by W. Rodwell]

M. J. Camper Coll., Snape, Suff. no. 41.

Colchester* [BM 1357K] rimming fine, yellowish cream;
flint grit. Marked 'col'. Big projecting spout.
close sketch in book. CRS. Unregistered. remainder.

Scole, Norfolk [IK 1007 scl 36] flange fragment in fine,
yellowish cream fabric

C. HERMERY

Colchester M. [no. no. 394 K.] cream fabric with sl. pinkish tinge; small whitish grit. D = c. $14\frac{1}{2}$ in. B.F. 34. r. facing.

Colchester M [no. no. 393 K] cream fabric with sl. pinkish tinge; small whitish grit. D = c. $14\frac{1}{2}$ in. l. facing. B.F. 34 but not same vessel as above.

Colchester M [391.97; 289K] slightly sandy, cream with very few greyish(?) grits to near top of head; heavy; D = $13\frac{1}{2}$ -14 ins. Nearest B.F. 34 but broad on level with flange, + scarcely distinguished, flange under T-splay, out a little at end.

Colchester M [310.97; May 6; 315K] cream fabric; some, medium + smallish, black, white, grey grits to c. $1\frac{1}{4}$ in. b. b. b.

Colchester. [Hospital 337.57; 345K] hard, smooth, cream fabric; some white, + grey, black grits; heavily scored inside with wear. 1 stamp each side of spout.

CH ERME

393 K Holchester M. b. facing east.

All of Hermes leaves (5)
are big hooks

C. HERMES or C. HERM F

Colchester [Union Hospital 612K] hard, smooth, cream fabric, sparse, whitish
grit, only 1 or 2 pieces; D = 14-14½ ins. Br.F. 38; L: facing, no rubbing.
^{As others.}

Colchester? [British Mus. no provenance but Col on in faint ink; c'es.
unregistered; 11K] L: facing; fine, cream fabric; very few blackish
or grey grits; two pieces joining 11K + 22K.

Colchester [LWC 71 C223 A 1930 612K] r. facing. burnt.

Fine-textured, smooth, cream with a little temper, mostly
quartz, occ. red-brown & ? flint. Dr. c 32-33.
Interruption - 1 quartz + 1 ? flint survive. P 5027

H 390+

UNCERTAIN.

St Edmunds

Caster [Unpublished. D 2. 32K] buff core changing to creamy surface;
flange only but one white grit on flange.

Needham [Nor. & N. Arch. S. xxvi, pt II, fig 7 no 8.
Empo. 15. 942, 79K. Norwich Museum.] large + medium,
moderate, white, grey, black flint(?) to bead; 82.930 pencilled
on pot. D 212 ins.

Bayham House, Coddington [Finders R. Storer. 13K] seen (Infor.
from J. Plowsey). Diam 260mm (inside 190mm) buff -
cream fabric few visible inclusions; mixed flint & grit
(not weathered grit). [Seen at Carlisle 1999] Dr 27cms. 10%

Fine-textured, deep cream fabric; few v. tiny inclusions quartz
& red-brown traver larger red-brown inclusions! Intercalation: flint & grit



Neadkaw N 15.442 79 K X Caistor D. 21, 32 K. Unpubd.

O H
A IV

No bar: A

Spoon normal type - handle, 996

Grandford, March [1959; Trench A, L 4; TL 997393]; information

E. Standen] r.facing; brownish orange brown fabric with few v. fine white gritty fragments in it; surface more pinky; no clear signs of slip; no tituration grit on fragment. D = 9 ins.

Flaggrass, s. March [T. Poller 1956] r.facing; fine textured, orange-brown fabric with pale purplish pink surface, perhaps a slip; much small grit to c. 1/2 b.b.b. opaque grey and translucent brown and pinkish grit. D = c. 9 inches; cream colouring can be discerned in places where the purplish pink is worn off. Stamp complete; 'H' not 'F' in stamp; spoon normal. (?) type + well-formed

TL 434 985



v. Facing

Grandford, March,
Th 997393

HOIVIA? or HORVIA

Incomplete.

Godmanchester [7K PL515.23] Salmon pink fabric with cream slip;
tempered with sandy transparent material + red-brown, & black tiny
particles; white, dark brown, grey red-brown trituration glt. L-facing

OF O-H-1A-IV- HO/VIN

Illiterate.

Flaggrass Nr. March [Potter 1961] r. facing. Found 1956.

pale

fine-textured orange-brown fabric with purplish pink surface -
perhaps a slip; much small grit to c. 1/2 b.b.b. opaque grey
brown & translucent pinkish grit. D = c. 9 ins; cream
colouring can be discerned in places through the purplish
pink. Stamp complete; 'H' not 'F' in stamp; spout mud @ type.
Flaggrass Greek well-formed.

Grandford, March TB 997393; r. facing.

Pottery on other card comes where.



Flagg 10.53 "facing
in Ranch
1956.

