



Leicester [A112 1991 (373) 295K] FF Cream fabric. Inclusions:

frequent, ill-sorted quartz (trans. & pinkish), orange-brown, rare black. More grit than is usual at M-H but would not necessarily be impossible in early second-century. Border unusual. Dr. ? 30  
Manchester seems less likely than LC, but not impossible

break




height 295K A112. 1991 (373)

IANVARIUS ?

? Little Chester

Little Chester [DLC 80 LRD.] Hard, Fairly fine-textured, cream fabric with a good amount of fine, transparent, <sup>quartz</sup> red-brown inclusions; ~~an~~ occasional large dark brown inclusion possibly iron-rich; texture consists of flint, transparent/translucent quartz and dark red-brown grit. Dr. 36 cms. Probably right facing. Very occasional calcareous grit. Midlands.



IANVS

READING UNCERTAIN

IAK

— See SARKVS

Bureau [p106 PSAS 1896 no3]

~~Chertiston or Water Newton~~

~~vclt H., 238~~

~~DEVAI wh. with buff slip~~

~~Stamp also found in London C VII, 1334 24~~

~~at iron-working sites in Sussex~~

~~gfe ii, 173~~

1B150

Lincoln [Technical College Kiln 1936, 6K] pinky buff fabric becoming creamy near surfaces with brownish buff slip; no grit on fragment but pinky fragments in fabric. A

Lincoln, Monks Road [16K] stamped each side of large spout, coarse greyish cream fabric with creamy buff slip; much white (pebbly texture), red-brown, brown + grey grit; large and smallish up to bottom of bead  $D=11"$ . Section varies in different parts;

'Plug' out of middle of base. A  
<sup>?? 1B150</sup> Lincoln, <sup>29K</sup> Cottesford Place [C.P. <sup>FP 5618</sup> A10.6] <sup>P/124</sup> flange fragment stamped; assigned with certainty to 1B150; fine, greyish cream fabric; few v/b. <sup>+ quartz</sup> grits in fabric; smoothed surface; flange only. <sup>upper border OK</sup> <sup>rest difficult.</sup> A


Newlead (NMA) (Xi packed away in cellar; found 1965). Hard, white fabric  
containing very, very tiny red-brown grains in it. Slightly sandy fabric.  
= FRA 3094 A

Watercrock [Kendal Mus. 20K] flange incomplete; cream fabric  
quartz & ss tinted with grit. A

Watercrock [W80.1.1980 Pipeline watching brief 21K] IRS. A  
softish cream fabric, some blackish; v/b & transparent inclusions;  
tintation, quartz & v/b grits surface; stamp in good conditions.  
There are traces of another stamp above this, and not part  
of the normal stamp; reading uncertain but  $\overline{E} \overline{C} \overline{I}$   
retrograde might be the most likely reading followed  
by D C R. L. two r.

11312 01115

Restored stamp



Probably retrograde  
stamp.

B150

Carlisle, Blackhairs Street [ 332 CAR 78BLA D ] + join

[ 331 ( D ) + . 87K ] Different vessel, less micaceous <sup>than 5K</sup>  
Slightly granular & greyish cream fabric with gl<sub>3</sub> &  
v/b tempering. (quite a lot of v/b). Pale buff slip-  
traces under flange. Quartz, v/brown + black (? iron slag?)  
Dr. = c 32cm. r. facing.

A

## Notes

Littleborough, times [h.59KL] 5K l. facing. Very greyish cream fabric containing some tortuaria grit; slip, brown on bead & top of flange;

not noticeable elsewhere. large unusual spout. Aa  
Carlisle [CAR 78 BL a D 42 (<sup>86k</sup> ~~no no~~) + 52 + 56 + 57 + 53 + 55 + 54 + 67

Three quarters of rim & a <sup>fair</sup> large portion of lower part including the base. Heavily worn & heavily burnt probably after partial fracture. l. facing. Slightly sandy drab cream fabric with micaceous, with red-brown & <sup>fine</sup> <sub>h</sub>quartz. A tempering <sup>also</sup> of red-brown <sup>in</sup> req. sized & irreg. distrib. Traces of a buff-brown slip. Grit worn away entirely at bottom but much at top - qtz (trans. & white); red-brown & blackish. Dr. 28.5

1B150

Arch. 416A likely to be C. fac but not certain;

Piercebridge [TF 74 54C (374). 13k] <sup>difficult</sup> Burnt.: ~~colour of fabric~~

not-obvious, inclusions quartz. <sup>well-</sup>Worn, no trituration grit survives.  
Dl. 29 cms. Fine textured, micaceous, cream fabric, A  
darkened ~~in parts~~ by burning. Inclusions: sparse quartz  
and small red-brown fragments.

1B150

SE 88780852

Scunthorpe [SCAE Cont ext 686 2K] 90gms Diam c 260mm

25% Two flange fragments, not joining; quite fine-textured, micaceous, cream fawn; self-coloured.

Inclusions: moderate, ill-sorted, transparent quartz and red-brown material, rare black material. No titration pit sunsets. Heavily burst.

B150

Walsend [WSP 58.2 no SF context 5523 loc 8 early C3 + 51K]

FF, Hard, ~~orange~~<sup>buff</sup>-brown fabric [Munsell 5YR 7/8 'reddish-yellow']

Inclusions: moderate, very ill-sorted quartz, red-brown and black? slag but on a background of frequent minute inclusions barely visible at x20. Slip may have been brown (1 place at edge brown) but largely discoloured to a whitish-grey. A


Templeborough [W. V. Wade 1948. 12K] white fabric; broken rim  
fragment; end of stamp. A

Chester, Love St., [1939, Box 50, 35K] orange-brown fabric with  
cream slip; large + medium, white grit, v. v. rarely brown grit,  
this is from a different (? northern) area. hard, heavy fabric;  
grit plentiful but sporadically distributed. Typical of the grit in other  
mortars in Chester museum in same fabric; stamped twice together.  
End of spout broken off. (Indicates new manufacturing centre). B  
Probably a different potter.

Chester, Abbey Green [AG.75 IV (204) / 790] TR VI 95.67K]

flange frequent, slightly hml. Bright orange-brown fabric with pinker core [Munsell 2.5YR 5/8 with 10R 6/6 core]; traces of cream slip survive. Dv. uncertain. s

Inclusions: moderate, ill-sorted, trans. + transl. quartz, with rare black. Possibly from same die as 35K Love St, Chvr. certainly by same potter. B



IBR VSA

London (C VII 138.) Callender p. 142, 729.

He thought it a mountain stamp.

PRIAMVS

CONTINENTAL SITES.

~~Prattwell, Essex (JRS XII, 261. Southend Museum)~~

~~Vienne (CIL XII 5685, <sup>(b)</sup>33) 15K Vienne~~

~~Ste Colombe (CIL XII 5685, <sup>(a)</sup>33).~~

~~(fuit apud Chavassienam iam in huiusmodi mus.~~

~~Vienne [fuit apud Chaverthodum tam in museo; do. (a)]~~

ICOTAGVS

Southwell, Notts. (Ian Rowlandson POSM 12 (484))

IK


70gms diam 290µm s 7% L. facing. Fabric: hard white  
with traces of what might be brownish-cream slip. Inclusions:  
moderate, mostly small. but not well sorted, mostly transp.  
quartz with rare red-brown & black material; very rare  
larger red-brown & black material. Δ γ d, & 5? MH.  
Inclusions: few, up to c 8mm b. bead. red-brown sandstone  
& black rock

ICOTASGUS ~~probably not certain.~~

~~SFR~~ ~~?~~ ~~die G~~ ~~probably not certain~~

Tripointum <sup>SFR</sup> Die E 23K or similar die. Fine cream fabric tempered with fine grit; wh., brown + grey (blk); r. facing D=c 8" v-small. A quartz (straps on flange); 2 white inside.

Tiddington [TW T74 No. 73.18k] die G. Hard cream fabric, very sparse quartz inclusions and black fragments. Trituration quartz, <sup>or some quartz (quite a lot)</sup> red-brown sandstone? and dark grey slag? probably r. facing. - fired to orange-brown colour in places.



ICOTASGVS

Tharpe Malsor, Northants (Info. Rob Perrin)

Die


Hard, cream fabric. Inclusions: moderate plus, ill-sorted, transparent and pinkish quartz, a little red-brown material, opaque cream (rare), rare black

Inclusions: moderate, scattered, mixed, quartz, orange-brown (s/s?), pale brown, black. (Typical earth <sup>gilt</sup> suite)

r. facing 4 sherds, 3 join. Dr. 320 2.5% + 2% <sup>not</sup> joining  
The die has slipped over the O ~~to~~ 335 gms. 4 joining

~~Rediff - or - Soar, Notts. [RS.00 (25) illust 17~~ I.C.T.A. S.G.M.S

Does need carefully  
assessing. could be  
Does 5 of 8 probably 1 die?  
new die { 110 heaviest  
          { 111       "  
          {       Rocester



Modern Churchyard (~~Ashbourne Rd - take extra note of book~~)  
 Rochester [New Churchyard site; 1959. Information R. S. Hughes, Derby M. 3K]

hard, cream fabric with buff slip, drab or flang; inside worn, much  
 length to tiny gits to b.b; white, black, brown; r. facing. d. 9  
 few drops of 'glaze' of some kind on one corner of stamp. Δ

Rochester [found & kept by a workman; information J. E. Pritchlow  
 21 Oct. 60. Rubbings sent.] 4K. acquired from workman, <sup>? new die</sup> ✓

Wall [WL/OB/4 - J. Gould 1962] stamped twice close together;  
 die as ROCHESTER 2K. hard, cream fabric; one dk. brown gits.

Cirencester [die 63W III (42) <sup>M211</sup> 25K] r. facing. hard, cream fabric with cream  
 slip; <sup>blackish</sup> dk. brown angular medium sized <sup>with a line</sup> gits to b.b. flang broken. Dr. 22

ICOTASQUS

F 943

Roxeter, Northfield [RON 01 8230] 96K L. facing.

270gms. Diam. 320mms 21% Fabric 12mlth post AD

140 inclusions gnt. Hard, smooth, fine-textured  
cream fabric; self-coloured. Inclusions <sup>very</sup> moderate, ill-  
sorted, quartz, red-brown + rare black. Inclusions  
few or sherd (broken high), all blackish. Spant is Type 4  
rather than a Type 3. Looks late in his production die 6 4 (5)

ICOTASGUS

Ribchester [77 AB 31 40K] <sup>than Ribchester vitellis</sup> f-facing. Fine creamy white fabric; noticeably less tempering but some qtz, red-brown to grey; cream slip. Trituration grit; qtz, v/b & grey. Δ

Ratcliffe-on-Soar, Notts. [R.H: 63-193 3K] r-facing. Hard, creamy-white fabric with pinkish core and buff slip and some quartz temper. Messy impression - die uncertain A

Walton-le-Dale [WD 81 168 16K] <sup>(66)</sup> stamp in two fragments; CRS + FF. r-facing <sup>WD 81 436. die 5</sup>  
<sup>brownish-yellow</sup> yellowish-brown fabric (10YR 8/6), hard, inclusions <sup>fair amount</sup> sub-angular, ill-sorted <sup>smallish</sup>  
 incl. pinkish, transp., white  
 qtz, red-brown, hard, haematite? re-fired pottery? fragments upto 2mm  
 and black one fragment. Trituration grit quartz and <sup>v/b & blkish (? iron)</sup> re-fired pottery.  
 (Fabric 32) Dr. approx 34. Stamped twice close together.

Dragonby (278) DR 70 ARJ 1K] (facing. worn; and burst after fracture. Dr. 28. Hard, fine-textured, drab cream (Munsell 10YR 8/3), ill-sorted, fairly large, moderate, quartz, red-brown & rare black inclusions. Interstratification: mixed, random, medium to largish, some smallerish, quartz, red-brown with rare black. Surface yellowish. u/s ? Before AD 130/135  $\Delta$  DIE 5

Dragonby (334) DR 71 ALK 2K] stamped each side. Dr. 24cm somewhat over-fired. Very hard, sandwich fabric; cream buff & pale grey. <sup>Interstratification quartz</sup> Moderate & fairly frequent, probably mostly quartz but fair amount of red-brown & black (? re-fired pottery). S  $\Delta$  ? in deposit 140 - 200/225 Die 5

May 1996

Fig 20.28, no 1373 and p 573 . Site 1, lower topsoil <sup>e/s</sup> 1K

between F1478 and F1550 . Diameter 310 mm . 7%

May 1996, Fig 20.28 no 1375 and p 573 Site 1, FT16,  
part of western road ditch . Diameter 280 mm 7% 2K

60.59

Lincoln [Leicester Mus. 48K. ~~151-151~~; E 223] hard; buff fabric; orange-

buff surface.

Templeborough [YAS. xxxv p. 96; T/ci. 29. ix. 38. S.E. Sheffield Rd. 1938] 1K.]

(facing; misread as <sup>E.B.</sup> como; thin grey core to pale slightly pinkish buff; surface on top and inside, very pale, drab brown - ? slip - but not this on outside; good amount, largish to small, black, grey, red-brown grit to c.  $\frac{3}{4}$  b. b. b.; stragglers above; tiny grits, blk & white mostly, in fabric; compact fabric; stamp a bit worn. RTO

High Cross [Chance find during Rd. works. J. Pickering<sup>1958</sup>] cream ware;

High Cross [Chance find during Road Works. J. Pickering 1958; rubbings: sketches & descriptions by G.W.] pinkish cream fabric; pink, white & red grits.

Templeboro' 35 Yorkshire Arch J. XXXV (1943)  
'Roman Yorkshire in 1939' Ed. by Mary Kilson

Clark p. 79-98, p. 96

(Misread by E B Burley because Dorothy Greene penciled  
over the rubbing which she sent him)

Cardwnock [CW<sup>2</sup> XLVII fig. 14 no. 5; Tullie House 49K] l. facing; pale buff

gilty fabric with buff slip; abundant, medium, grey, white + black grit to near b. b. s. R. ①; "within s. rampart, on subsoil"

Cardwnock [CW<sup>2</sup> XLVII fig. 14 no. 5 + p. 20 no. 5 Tullie Ho. 50K] r. facing, different vessel but of similar type; similar fabric and grit; N. R. ① — North Rampart.

Yorkshire Museum [10K] white pipeclay + white slip + on inside; medium black + brown grit from c. 1/2" line.

? See opening for details  
Rossington Bridge [Doncaster M. ~~68K~~ 674] well-worn stamp very poor impression. fine cream fabric; slip pinkish buff; few brown grits. E

Wildespool [Aug 7/49; 614; Box 200 Crowson & Mas] l. facing; cream fabric; stamp faint.

ICOTASGUS

WR III 2 sent by M. Darling Dr. 28.

Wrangle, nr. Boston [NGR 434 528] information Harry Healey. PTO

small excavation by local group in area of salt making biquetage.

R-13 pot generally early. Rubbing sent.

Winterton [DW / CT no 54; MW / NP no. 56; RW / BJ <sup>2 sherds not jg</sup> no. 57 7K] Die 5

(No. 56 smashed by pick into 11 young sherds + 1 not joining with old break.) Nos 54, 56 + 57 do not join but are clearly same vessel. No 54 discoloured to grey in fire.

Fabric descriptive from rest. Varies from <sup>hard</sup> cream to brownish-cream in parts of body. Inclusions: moderate quartz random with occasional hard blackish sometimes in cavity stained orange-brown rare opaque cream. Dr 35cms. Texture: all blackish with  $\frac{1}{2}$  rare gtz. <sup>? cream strip</sup>

Wrausle [see over card] Hard, fine, textured cream fabric.

Inclusions: moderate, small to tiny quartz, some red-brown, rare opaque white - all tiny...? cream slip. Inclusion: quartz and red-brown survive - <sup>very little</sup> ~~not a lot~~ but presumably mixed.

Dies of ICOTASSUS



4

ICOTASCUS

[B<sub>2</sub> d.g. 2 140-180  
Rim W. 110. with pale buff cone

Shenstone Reading Rpt. as 'COLVS'  
Shenstone Field 11.10.13 K.

Shenstone [Burm. AS. LXIII, Pl. VII no 3 on rim 7]; smooth hard pale grey fabric

Δ. c.W. 102.

Diameter 1 1/2" drab buff slip, badly finished on inside of head; large few small, red <sup>angular grit</sup>

Ambleside [W. p. 46 ff. 22 no 30 + p 55]; hard buff clay, grey cone; mixed grit some in rim 8" diam. Atwell library.

Wilderspool [Warr. Mus. 416'13; [12K]; May plat] creamy cone, buff surface, red and white grit rising occasionally to c 1/2" of rim.

Chesters [245 2/3 162]

~~Old Kilpatrick~~ [XVIII = Burm. read on XIX, 20] <sup>B. n.</sup> ? said to be MASC-VLVS.

Shenstone [Wall. S. Museum, BAS. LXIII Pl VII, <sup>18K</sup> no 9] 109' 4. No 2 holes.



Shenstone 3

(1/2)




7

Shenstone (4)



Ambleside


(1/2)



Wam KIG'IS [28]

ICOTASGVS

Deansgate vices, Manchester [inf. Rich. Clark fig 9, M6,  
Cxt 1B unpublished. 32K



100 TASEVS (One of 10K; 16; 59K + 60K in CIL unidentified  
separately; rest no provenance)



Yorkshire Museum [16K] hard creamy white; creamy buff slip; little  
medium brown & white grit.

Balmuccia [Pl. x. l. m. + p. 78] G. T. 13 plate 52; 6K] = A

Yorkshire Museum [59K] cream overfired fabric, slip purple to buff, abundant  
white and some brown grit.

Yorkshire Museum [60K] hard brown fabric with grey core, overfired, patchy brown  
and grey surface; small black grit.

Rocester, Staffs. [Oldfields Secondary Boys' School, Uttoxeter, S.C.]  
Critchlow's "uniform" from B.W.] 1K ~~1K~~ facing ✓ stet  
This is a fourth maximum. d.s.?



Rocester [OPR 96 6025 7AK] L. facing IRS worn.  
whole d side + half d) base survives. Fine-textured,  
hard cream fabric with darker cream slip ~~was~~  
~~inside~~. Inclusions: tiny and small, not well sorted but  
not bad; mostly transparent + pinkish quartz, opaque  
orange-brown, rare black; ~~moderate to~~ fairly frequent  
(x20). Interstratification, frequent up to c 2 cms below bead.  
medium to small sized with few larger ones; quartz, orange-  
brown (includes ss?), quartz sandstone, black, some showing  
red where worn. Probably means not later than 150. 5<sup>th</sup>

Margidunum [35K. M.6.8.R.T. M. Todd] r. facing. Nearest to die E  
 but does not fit it. Fine parallel smoothing marks, ? cloth going  
 round rim. Hard cream fabric, pink core; contains dark & white  
 grit; white; pale brown; red-brown & grey trituration grit; median  
 & small. r. facing.

Uk [67; AT 2] 5 pieces not all joining. 4K] r. facing. stamp print. Cream  
 fabric with ~~2 thick pink & grey~~ core; not as hard as it might be. Grit has rather  
 coarse appearance, - much rather clumped together. Large to small  
 red-brown, mostly, but fair amount of white quartz-like & grey grit.  
 & little finely ground grit in fabric & a surface. Largest outside. D =  $e 8\%$   
 not assessed V/S 29cms.?? E??

ICOTASGUS

King & Turkensite  
Middlewich Community Dig [Nob5 (arch) ~~125~~ 88 Tr 12

1216 Context 16W L facing. 369g Dr. 290m

23% Fine-texture, wear fabric with thin pink core, and perhaps with self-colored slip; slightly powdery surface.  
Inclusions: moderate to FF, tiny to small, mostly transparent quartz with some opaque, orange-brown and a little black material; rare larger quartz and orange-brown ss. Inclusions include well-mixed, medium to small sized quartz, orange-brown ss & black rock. Some wear.

Further details R (earrings & other stamps) Ruth Ham die 5

ICOTASGUS

The Links, Godmanchester. [P9098 1003] (43) 22K] l. facing.

Diam 29 cm. 20.5% g. l. facing. Die treated white being applied. Pinkish cream fabric. Cream at surface but pinkish throughout inside. Surface has quite a lot of grit on it, more <sup>frequent</sup> than inclusions - was it sprinkled on top? Inclusions: moderate plus, random and ill-sorted, quartz, o/b and opaque white (some <sup>composed of</sup> grains of quartzose). Surface grit fairly frequent, orange-brown sandstone, quartz & rare black - less on outside of body than on rim & inside. Intuition: 1 quartz & 1 o/b ss survive. Probably die 9.

Broughton Lodge, Willoughby-on-the-Wolds, Notts DIE 6

[51] Bh 66 AC ? , 2k ] R. facing. Hard, brownish-cream fabric with pale grey core (nr. spout) few tiny inclusions, quartz and black iron slag fragments. No trituration grit survivor. Dr. c. 28 cms. Spout type 4.

Rocester [RO 87 II 100 joining RO 87 III 1458 51K] L. fac. Fairly hard, cream fabric with thick brownish-pink core some quartz & occasional red-brown inclusions; red brown & blackish trituration grits. Die: 8 P. 70, Esmonde Cleary & Ferris not listed.

Rocester [RO 87 IV 1477 52K] probably r. fac. Fabric as above

N.B. ? Not Die 5 Dr. c. 28 cms Die 8. Possibly same mortarium as probably above  
 p. 69, no. 29, fig. 31 Esmonde Cleary and Ferris 1998

Tallington, hines [Peacock, Tal '57. B. D.] l. facing; soft, fine cream fabric; cream slip; good amount, large to smallish, black, grey, v/b, grey grit getting sparser to c.  $\frac{3}{4}$  b. b. b. D = 12 ins; slightly sandy to touch.

Rocester [Graveyard; found by Mr. L. v. Clarke, 79 Lyon Terrace, Rocester; see letter R. Hughes, Derby Mus;] <sup>2K</sup> buff fabric, surface rather yellowish; 1 stamp each side of spout showing G. clearly; largish to small, sandstone, greyish, white, black, dark reddish brown; good amount probably but thinning to c.  $\frac{1}{2}$  b. b. b. D = distance to c. 11 ins. d. 8

Stanton how, Bucks [Newport, <sup>ignell</sup> H. V. Jones. S. B. 59 Su. Bagill] flange fragment; compact, white fabric; a few grey grits & 1 large brown grit in body of fabric.

Cardinal  
128+

They thought Period II was 16.  
In Axial joints but not medial ones. — Yab,  
Ankle joints, Temples of but not in  
Radial fork. AD. 150-160

ICOTASGUS

+ #4/4 joining.

Wilderspool [82K 66/H4/③] r-facing fine-textured creamy buff fabric

with greyish cream core, contains much fine grit red-brown + grey; buff strips; dark grey, red-brown + white medium to small grit. E 100/124

Manchester [CA9. 3K] fragment 1909. 119/22

Manchester [over tail of East Rampart 1968] Hard cream fabric. 24K. Range not complete. D

Wilderspool [r

Whitaker [7K Building sent no. no. Phase II. V. R. 10/11] E

Lincoln [54K A I (143) (1522) Hard cream fabric, tempered with much 95% red-brown

fine grit; ~~brown to~~ b grit. Orange buff strips. LIN 73. CI (143)

1345 A I (143) (1522) Dr = c 28 cm.

ICOT ASCVS

South Stauropond

Harsey Toll [Standen] hard, white fabric, burnt to grey on parts of surface. Neither end completely impressed; flange fragment.

Leicester [88'860 36K Friars' lane 1<sup>2</sup>] hard buff pinkish cream; red, white, brown, grey, medium sized gut.


Warrington M [1188.1 r. facing. no prov. but probably Wilder post, probably W.R.R. p. 64; 55K] soft cream fabric; a little pinkish gut in fabric; surface burnt a little drab. Type similar to 12K but different size; broken, surface gone in places.

Maudresseden Found inside Maudresseden - in well  
Mancetter [23K Birn. Mus. A. Oswald] Well at Mancetter. hard, cream, smooth fabric with buff surfaces; possibly 2 stamps, 1 broken. The second stamp is from die 10 of SIMILIS 1.

1082a Antinous Judd notes.



1082a  
1082b



1082a  
1082b

← In well at Mardrossen  
Oswald (Adrian) Town of  
Birmingham & Works  
Arch. Soc

Heicester [Vauxhall St. 116. 1962/13; 112K] stamped twice together on each side of spout. cream fabric with buff slip; medium and small, white, grey and red-brown grit.

Ambleside [CW<sup>+</sup> XV, p. 56, fig. 26 + p. 55, no. 1 + p. 46, no. 30 read as COTASO. Atmitt Library 12K] orange-brown fabric, thick grey core and outer surface grey over large part; small part of upper surface of flange, also grey; medium, white, red-brown, grey + dark brown grit. D = 11"

Manduesdum [1964. Peter Ford <sup>48K</sup>] Fine pinkish fabric with cream core; white + orange-brown grit; some grit in fabric. Die as Rochester 2K. ○

ICOTASGVS (At York - wh. + brown gut)

Wroster [unpublished; M62; 55K] pink-white fabric with hard buff core;

umber surface; black and v/b. and white gut; Site V with A.S. of Domitian.

Leicester [Jewry Wall, in box (labelled S.W. Bldgs. II 104K)] hard, cream fabric; buff slip; brown, grey + black gut; (not published).

Leicester [H.M. Sale; "The Furlongs" (Hiscock's Field), strip nearest Watling Street; Dec. 1961] rather worn; fine cream fabric, probably buff slip; eroded surface find (handweaved).

Leicester [110K; 116-1962 | 48. Silver St] vessel complete. L-facing rubbed; red-brown, white, black or dark brown gut abundant.

Leicester [111K; 116-1962 | 287. Technical School corner facing Newark] Complete. cream; buff slip; grey, wh. + brown gut.

Mandussedum [W. ① 1. 1. 1964] stamped twice close together; hard, cream fabric containing tiny particles; darker slip. C

Mandussedum [W. ① 1. 15. 1964] fabric and slip as above. C

Mandussedum [W. ④ 1. 42. 1964] softish, off-white fabric with darker slip.

Mandussedum [W. ① 2. 101. 1964] fired to greyish colour; slip gone dirty greenish brown; tiny particles in fabric. G

Mandussedum [W. ③ 9. 181] r-facing. Stamp faintly impressed. C

softish cream fabric containing tiny grit; pale buff slip; dark brown grit. Δ

Mandussedum [MAN 64. B. ① I. 56K] l-facing. In flange, fabric cream with pink core; cream slip; burnt; surface of flange + interior break blackened; brown grit + much tiny grit in fabric. C. Mahany. C

Mandnessedum [64. A I (52) 54K] Edge of stamp, die A. Hard, <sup>A</sup>creamy buff fabric, pinker in core in body; buff slip; brown grits, small. D = 1 1/2"

Mandnessedum [64. A I (51) 58K] Probably ICOTASGUS, die C. Grits half pinkish, inner half cream; surfaces are an; has cream slip; contain a v. little grit; grey, brown, colourless medium + smallish trileteation C

Mandnessedum [Broadclose. S.W. Side 1961] 69K Birmingham M. Brownish cream; stamp. very ~~was~~ eroded; traces of discoloured slip. ~~#~~ Almost certainly ICOTASGUS. ?C

ICOTASGUS

MHI


Reporter Megan Stakley

heicester, Blackfriars [No. 9 in my Report. WAA 14;

BFL A Context 791 ~~WAA~~ 344-K] 155 gms

Diameter 240 mm 23% r. facing. Hard, ~~fine~~  
fine-textured, dark cream fabric with moderate,  
tiny to small, quartz & red-brown inclusions. Very  
<sup>hard</sup> modified for ICOTASGUS. Interstratification  
consists of mixture of quartz, red-brown &  
black material. A band of burning around  
sherd in one area, probably post fracture. A  
Poorly & partially impressed stamp

die 713



Not identified

Leicester, Causeway lane [A1.1991.17723-1 <sup>MO4</sup> <sup>?1207ASG.V3</sup> (3792) MO4 ]

r-facing border only. Hard cream fabric. Inclusions: moderate, mostly tiny quartz; sparse larger o-brown. Possibly v sparse opaque black. Intonation: hard black on fragment. Spout Type 3E

Pr. 27cms.

3/27/72  
iclasgan Die 7  
Muddy NOT  
Gorman

AI 1991 37 92  
1772 2.

KOTASQUS

date = 2/28/88

Mancetta, [Surface find, Broadclose north-east corner]. Drab cream fabric

with slip lined grey. Tony Sumpter 7OK

Attributed to Icotasgus

Heracles (Blue Boar Lane B XIV 2. 1958). Two pieces joined.

? Die G. Stamp broken & smeared over part of flange.

Overpoured to grey throughout most of body but a skin of brownish buff at outside surface on underside. Dr. 29 gms. white, blackish  $\text{qtz}$  inclusions & quartz, blackish unevenly distributed interstices.

heicester [A77.1975.5492 T F110 (766) / 792) 226K] Flange fragment.

Hard cream fabric with thick pink core. Inclusions: ill-sorted, slightly more than moderate, red-brown, quartz + opaque white clay - in order of frequency. Different pot from rest. Dr. 29cms. E

heicester [A77.1975.5474 T F44 (718) / 732) 263K] L. facing. <sup>Spout type 2</sup>

Smooth - slightly micaceous, pinkish cream fabric with v. moderate inclusions, few quartz, trans. + pinkish, + red-brown material. Inclusion: red-brown, <sup>most</sup> few quartz, few black vesicular (? slag). Worn. Dr. 24cms. Burnt. Die 2

heicester [A77.1975.5466 T F33 (692) / 733) joining ditto. 5467

(734) 264K] r. facing. Dr. 36cms. Hard cream fabric; <sup>Die 1</sup> inclusions, moderate +; red-brown (large) + quartz (small). Inclusion: PTO

red-brown certainly wasted it but 2 quartz. Well worn. Bunt.

one stamp each side

✓  
Leicester [A78 1975] <sup>2329</sup> <sup>130</sup> V (13) 231k] R. and L. facing stamps,

1 body shard missing.

Hard,

almost complete restored vessel. Cream fabric, with <sup>thick</sup> slightly pinkish core; moderate <sup>+</sup> inclusions, fairly ill-sorted quartz and red-brown fragments, <sup>v.v.</sup> sparse white <sup>✓✓✓</sup> fragments.

and pale brown sandstone

Trituration grit - opaque quartz and red-brown <sup>well-mixed</sup> fragments.

fired to a darker colour in places on the surface.


Dr. 22cms. Some use. Spout type 2. die E

KOITASGUS

✓  
Leicester [A39.1988] <sup>5251 X</sup> (970) F183 265K] L + r. facing. Dr. 22.5cm.

Burnt probably after fracture. Hard <sup>sl. wicaceous</sup> cream fabric, inclusions:  
moderate + red-brown, quartz + rare grey. Intertaxation grit: v.  
little survives brown, quartz + black. Worn. Flange no spot + spot  
darker colour. Spout type 3? / face

Leicester [A39.1988] <sup>+</sup> (1012) F232 6133 joining A39.1988.8493  
(476) F70 266K] r. facing. Very well worn. Dr. 22cm. 2  
pieces joining. Very poor impression of stamp. Hard cream.  
Inclusions: moderate, quartz, red-brown + black. Intertaxation: 1 quartz,  
1 blackish + 1 v. brown survive. Spout type 2



ICOTASGVS

Leicester [Causewayhane, AI.1991.0304 17702 M12 <sup>Die 5</sup> K] Lt r. fac

Dr. 22.5 cms. Hard cream fabric might have self-coloured slip;  
inclusions: moderate, orange-brown with few greyish + rare black.  
Intuition: mixed, quartz, sandstone, dark-blackish sandstone  
with reddish parts; smooth red-brown, pale ? ss, rare white. Spout 3? G

Leicester, Causewayhane [AI.1991.3930] 17729.1 ARGA 3 M12?

]L. facing: Hard, deep cream fabric; inclusions fairly frequent  
transparent + pinkish quartz, + red-brown (opaque), rare larger r/b  
+ v. rare white. Dr. 30 cms. Spout Type 2. Die 5

Leicester [L.P. 265. 14 C II 168(2)] 160K Jenny Wall Flange fragment  
in hard cream fabric; a little fine tempering & darker slip. D

Leicester [295 1973<sup>#</sup> (41) 167K] hard, cream fabric; moderate  
tempering of qtz & red-brown; cream buff slip; quartz & v/b  
& 1 or 2 dark grey trituration grit up to bead. Sk D

Leicester [323<sup>500</sup> A 77. 1975. 176K] a little overfired. V<sub>h</sub> hard, brownish  
buff fabric with pale grey core; <sup>5485-6</sup> grey chunk-like, <sup>451</sup> sandstone, <sup>78</sup> quartz & opaque  
white <sup>(? clay pellets)</sup> grit in fabric; <sup>trituration grit</sup> grey chunk-like, <sup>black</sup> sandstone, <sup>vesicular</sup> quartz & opaque  
hard pale grey trituration grit; surface grey in patches

Dr. = c. 30cms. ? a sc slip. Surface colour varies from the almost brown  
with patches or areas of grey due to overfiring. Well-worn. r. facing. Δ  
# 295 1973 = Accession no. Spout type 6A S


ICOTASGVUS

Icotasgus

Attribution probable or possible - DO NOT COUNT as

Biachester [77.121 BIN A785 D. 12k] die 7? Cream fabric, moderate inclusions quartz and sparse orange-brown and black fragments. No trituration grit survives. Dr. 30 cms. FF. Distal bead.

Leicester [A77. 1975 <sup>5501</sup> I (92) <sup>F154</sup> 196 222k] R facing. Hard, fine, buff-cream fabric, few inclusions of quartz, and sparse red-brown fragments. Trituration grit mainly quartz with some red-brown fragments, darker buff surface, either a slip or firing effect. Dr. <sup>31</sup>/~~32~~ cms. some burning. die E 3 joining sherds. Rather bowl shaped. Well-worn in lower half. 3 part type 2 Face of spout projects at top



York <sup>58K</sup> May p 44 <sup>Tray A of section</sup> not known wh. he refers to] whitish fabric, sandy surface, no  
grit left. As 59K 7.

Leicester [14K; 76'889; High Street] hard, white fabric; sparse white and brown grit.

Leicester [St. Margarets Work; 28. 1919/3; 59K] not seen; in D.G's list.

Corbridge (2) [SAT XXVI p 181 no 23] unusually hard, smooth blue-grey fabric  
with white slip.

North Collingham [Notts 1850 in Warr. Museum 320'02]; 2 stamps, one  
each side of spout, rather vesicular sandy fabric of creamy colour.  
Very large, and small grit, black and white, much pitted.

Rough Castle [p. 52] [1121V 5] 6r

'CIL VII, 1334, 23a). ref. to COL V 2 C1 at York. This one not separately identified.  
(Mus. L. 308).

ICOTASC

(H) 7 Warr. M. Found N. Collingham, Notts  
310°02. 1850 (K.32)

ICOTASC

(K.32)

York CIL VII 1331. (amphora) 57a + b

(a) COSVA K321

(b) ICOSV K312

CIL VII 1334, 23 a 308 COLV2C1

Aldbrough [OS 450/L M122 85K MON] hard, fine-textured, creamy white fabric with cream slip.

Maxey [MAX 64 A.P. X] Hard cream fabric [19 pieces] <sup>quantity inclusions red and white</sup> [19 pieces] <sup>and white</sup> discoloured, probably by burning.  $D = \frac{19}{7 \frac{1}{2}}$  Form unusual. **D**

Litchester [Brassington <sup>the</sup> 1967 The Flats 11K.] Hard <sup>greyish</sup> cream fabric;

dark ~~brown~~ <sup>granular surface</sup> & white grit in the fabric; only one tinturation grit (dark) on fragment. Discoloured slip. Could not say if made at L. but not impossible.

Leicester [Leic. 1965 II 40] (23) <sup>in it</sup> 12.6 K stamped twice close together. Hard cream fabric with brown & grey grits [ & buff slip, fired grey in parts.

High Cross [H.C. 399. M89] v. facing. Hard slightly yellowish cream, fine-textured with grey core; brown & white <sup>dark</sup> inclusions; overfired 15 dk grey in parts on surface. grey, red-brown & brown & white grits. **D**

ICOTASGUS Date 130-50 <sup>optimum date</sup>

5486  $\pm$  u/s  $\frac{293}{293}$

and others.

hercester [(293) A 77, 1975, 177K] different vessel from 176K  
but similar fabric; l.  $\frac{1}{2}$  facing. PTD  $\Delta$  Dr. 28cms. Ds

Park Street, Gloucester. [C.H.A.T. 2/84 (155) (186) 28k] Die C. l. facing.  
Hard, cream fabric, sparse inclusions quartz and red-brown  
fragments. No trituration grt survives. Fragmentary.

Castleford [(560) CAS 80 S10 L119  $\Delta$  (307) 38k] l. facing <sup>IRS</sup> die E. Hard,  
cream fabric, with (pale - orange) core, <sup>pink</sup> moderate inclusions, haematite  
stained quartz and occasional red-brown <sup>trace black</sup> fragments (upto 3mm) <sup>richly</sup>.

Trituration grt quartz, some black and red-brown slag? fragmentary  
stamp fragmentary. Most inclusions smaller. B3.2 fabric? with  
B3.1 trituration grt. Surface is darker cream but same colour as

weathered  
break so its not all that clear if it has a slip. (721) T. Sanypter  
is also L. facies of so they are different parts.

Leicester 177K Very hard, fabric identical with 176K. 3sc slip. Mixed  
trilobation gut: r-brown, light brown ss, quartz, grey ? sandstone.

Leicester <sup>HR of Eng. Mus.</sup> [164-1969. I 56 s A/A 150K] Fine + <sup>hardly any temp.</sup> Hard cream fabric fired grey in

parts; orange slip also grey in parts. L. face. - Dr. 30 cms. burnt

Ancaster [AT 70 CP.] r. facing. Fine slightly pinkish cream fabric containing  
 smallish brown grit; <sup>dark</sup> grey; white + brown grit.

Horncastle [Henry Hurst Tr. 6 (7-9). lines.] Fine, hard cream

with some quartz, chert & red-brown tempering mostly fine; red-brown +

<sup>25 mm diameter?</sup> pale brown & quartz fragmentation on piece; r. facing. Dr. = c. 32 cms. D

Long Bennington [(96) LB 77 00 3K] l. facing die 1. Cream fabric,

hard; inclusions quartz and sparse red clay frags. No grit

survives. Cream slip.

ICOTASQU:

Drc 250mm. 5%

Margidunum [A46 Newark to Widmerpool road  
widening scheme 2009 - Cotswold Arch. IK] Die 7  
r. facing. M9M 09 303678 DE 3002. Some singing.  
40g Fine-textured, cream discoloured by smoke perhaps  
rather than burning. Inclusions; moderate, ill-sorted,  
quartz, red-brown & rare black material (later 2 tiny & small)  
but occasional large grits. Tituration: up to the bead  
small with occasional larger on sherd (near top). Quartz  
with some red-brown. Probably had a self-coloured slip,  
but there is some orange-brown slip which covered more  
than the stamp. Reminiscent of *Mencius* obs at  
Bearsden.

Castlegary. [1882 NMA. 27K] l. facing. hard, fine, cream fabric with drab  
 cream surface; sparse grit on fragment; black, brown, + grey, near 22K.  
Newstead [FR 7; CIL VII, 1334, 236; Wilsons Preh. Annals. p. 403; NMA 152K]  
 l. facing; softish, fine, cream fabric; abundant, black + brown grit to c.  
 1/4 b. b. b.; some black with brown centres. D. 6

Balmuildy [pl. xl. B. 14 + p. 78; F. 1922-309; 6K Hunterian M.] L. facing; fine, creamy white fabric; flange bead; few black ~~flat~~ gits in fabric + stamp. --  
Rough Lattle [p. 52 <sup>Buchanan 1905</sup> ICOTASQVS; Macdonald p. 456; F.R. 337; NMA 6K] fine, pinky cream fabric, surface drab grey; some r/b; grey, black gits survive quartz.

Ardoch [F.Q. 65; NMA. 24K] L. facing; hard, greyish cream fabric; parts of flange grey; 1 black git on one <sup>flat</sup> fragment; much black with red centres, white + grey, hard gits to c. 1/2 b. b. b. D = 12 1/2; no us on second piece with clearer stamp; pieces do not join but as certain as can be in circumstances.

Corbridge [(23) 74 7/4; 67K. see AA<sup>4</sup> xxvi p. 181 no. 23] flange fragment; compact

cream fabric; softish; buff surface? slip.

Corbridge [8351; 51; 253K; see AA<sup>4</sup> xxvi p. 181 no. 23] slightly sandy, orangy-buff fabric; no grit left.

Corbridge [AA<sup>4</sup> xxvi, p. 181, no. 23; S163; North Area 1911; 354K] burnt; original, orangy buff(?) fabric; hard, smooth; 1 black grit + 1 on rim.

Corbridge [see AA<sup>4</sup> xxvi, p. 181, no. 23; no. S. no. 231; 355K] yellowish buff fabric with orange brown core + surface; no grit.

Clesters [2452/3762; 29K] r. facing; hard, cream fabric; medium, white, red, & brown <sup>trituration</sup> / grit.

~~Albion G. ATLAS MARINUS (C) ? ? ?~~  
IHEMITVOBON

Answering  
Sushf. coli.

Little cluster [21K Flato. ] flange fragment. Fine cream fabric

with v. fine grit in it; only covered stamp survives; surface curiously pitted.

Brayford Wharf East, Lincoln [LIBE 15, Allen Arch Ltd  
(2047) DO] 34.5 gms Diam 290mm. 19/0 - L facing.  
Fine-textured, white, self-coloured. Inclusions;  
most only visible at x20. Quartz & red-brown;  
intergranular grit; the visible grits are blackish & show  
red centre when worn; red-brown sandstone, rare  
quartz, rarer quartz sandstone. stamps partially  
impressed.

HEMITUBON

Market Cruton / Thistleton area [Oakham M; J. Barber?;

unstratified], creamy white fabric; 'pebble' grit; 1 stamp.

Wall [W/OK / 4 S. Gould 1962] flange fragment; fine, cream fabric.

Toad's Hole Piece, <sup>in formation M. Hodder.</sup> north of hichfield (SK 115113).

A drawing in D. Woodhouse, A Short Account of the Ancient and Modern State of the City & Close of hichfield (

Lichfield 1819) p. 5 "a mortarium fragment found in

T. H. Piece (SK 115113), north of hichfield, in 1819, at a

depth of 1.2 m. below the surface, in peaty soil, amongst roots & branches & associated with Roman pottery & a

(17) halberd.

HEMITUBON  
between Newark & Widmerpool DE 2073

A46 road widening scheme 2009. (Cotswold Arch) at  
Saxondale, Notts [SAX 09 273039 IK] 2 joining  
sherds. 90g. Dt, 280 mm 10% Surface appears to be  
reduced with some of cream slip showing as slip. l-  
facing. <sup>Brownish</sup> Cream fabric. Inclusions: moderate to  
fairly frequent, mostly barely visible at x20. Quartz  
red-brown & black, rare larger grits. 4 black  
grits or fragments any inside; Fabric brown fa H-H,

HEMITVOBON Probably worked at Han - Hartshill at some time but  
some (Address. one piece) look like Ver. mounts or Heme Valley - form texture of  
grit.)

Tiddington [TD81 (181/19)  
TD81 (151/40) No. 1101. 4K] 4 pieces (facing brown <sup>brass</sup> heavily)

Hard, greyish-white fabric with fine quartz & v. occ! dk grey-black  
inclusions; blackish tetratation. Worn <sup>brass</sup> v. c 33cus

Aldborough [OS 45 1964 Found on desk in York Museum July 1985 60K]

Fine-textured, cream fabric with a little quartz, red-brown & occasional  
black inclusions; hard; tetratation <sup>brass</sup> dark brown, red-brown & occasional  
quartz; well-mixed. Worn. Dr. 28cus. Both stamps. A.  
Surface slightly darker cream.

# IMMITUOBON

check in volume

heicester [Jewry Wall, fig. 58, no. 10; 109K] not seen. The stamp

drawn in the report shows a different part of the name from 24K. There is a Burley  $\Delta$  on loose sheets

heicester [Jewry Wall, p. 218, no. 10 + fig. 58, no. 10; 80K; h.p. 248.8] fragmentary stamp from West Block; mentioned but not drawn in Report.

heicester [Jewry Wall + ; 24K] hard, cream fabric and buff slip; black, <sup>white</sup> & brown gut; reminiscent of ICOTASGUS + looks certainly Midland.

heicester [heicester M. M. 8.] 133K no 7

MEMITVORSON


Mandruessedum [1964 W①, 17] flange fragment. Cream fabric containing fine gritty particles; stamp faint. In topsoil above SARREIVS / IVNIUS kiln.

heicester [145. 1966.10.129 K] stamp broken. Some of grit worn away. Rather coarse, cream fabric with buff slip.

1 dark grit and one brown on edge

Burton by Lincoln <sup>n. of Lincoln</sup> [info. Andrew White 19. 4.1979] rubbing

returned; no description sent



Corbridge [AA<sup>4</sup> xxvi, p. 182, no. 24; 24; 185K] L facings; smooth, compact, cream fabric; with a few black or red grits.

Corbridge [AA<sup>4</sup> xxvi, p. 182, no. 24; S 165; 24; 318K] yellowish white fabric with more buff core; smooth surface; no grit left.

Corbridge [AA<sup>4</sup> xxvi, p. 182, no. 24; S 81; XI W; 24; 319K] white fabric; a little red brown grit. NB. 1 more found than in Report.

Corbridge seen 1963. 398K no 7

MEMITVOBON probably has both mixed STAMPS FROM SCOTLAND.  
p. 529 fig 94, 6 and later trituration gut types

Mumvills [~~K. Steer 1958~~; NMA. 12K] cream buff fabric with some mixed  
gilt in fabric; abundant, grey, brown, blue-black, few white, small to  
large to c. lin. b. b. strays above; buff slip; D = c. 10 ins.

Mumvills. [~~K. Steer 1958~~; NMA 13K] mt. facing; almost whole; 1 stamp  
each side; fine, cream fabric; abundant, medium to large, black,  
orange, black with red in centre, grey, white + few red gits to c. lin. b.  
b. b.; strays to b; 1 or 2 gits on head + flange; some gilt worn away  
near bottom.

Camelon [unregistered; NMA. 57K] <sup>P. 10</sup> l. facing; soft, cream fabric;  
buff cream slip; medium sized, brown, black, grey gilt to c. 1/4 b. b. b.

Check which side stamp is on - of stamp on CAM 76  
also l. facing & from same die (not the normal one). 10

Newstead [p. 266, fig. 35, no. 19; FRA 1471; VII. 15. 64; NMA 122K]

white fabric with drab surface (? slip); medium + large, brown and black gnt. A "MILM"

Newstead [p. 266, fig. 35, no. 24; FRA 1430; NMA 153K] v. facing.

soft, cream fabric; quite worn; much gnt, black, <sup>grey</sup> brown, white gnt but some worn away.

Ardoch [F. 66; NMA 21K] v. facing; soft, fine, cream fabric; brown + black gnt; v. v. faint; <sup>checked</sup> ~~signed~~ to IMEMTUOBON.

Bearsden (3-19) ~~NK 74 AG~~ ~~(F. 29K)~~

# HEMITVOBON

Bearsden [319] NK 74 AG. 29k] l. facing Cream fabric, quartz

inclusions, fairly well-sorted grains, red clay pellets, sparse  
black ore fragments, slightly micaceous. Trituration <sup>mostly</sup> with  
~~red brown~~ pottery frags. and quartz. <sup>rare</sup> <sup>quartz ss.</sup> Red-brown slip.

~~Maneater on the site~~ large patches of <sup>thin, normal</sup> orange-brown  
slip survive, mostly on upper surface of ~~large~~ but smaller  
patches elsewhere. Appears to be <sup>normal</sup> a slip.  
Is there a possibility that he moved


(319) Nr 74 AG

break

beansden 1 fac. 29k

IN. SECUNDVS, P.

C. Herr

A single, thin, dark diagonal line is drawn across the page, starting from the lower-left quadrant and extending towards the upper-right quadrant. It passes through the middle of the page, roughly parallel to the top and bottom lines of the ruled area.

INGENVVS ~ INGENVS

HEVINGHAM ?

Nordelph, nr. Denver, Norfolk [Wilsbeck Mus. 5K. Borchfield Farm 29:XI:1949]

dark grey core with some white grit in it, changing to buff near surfaces;  
moderate, medium-sized white and black grit, some missing.

Heringham [Kiln V, Stokehole; Norwich M. 2K] L-facing; very drab, darkish buff,  
very, very friable; much large + medium grey grit to b.b; badly impressed.  
J.R.S. L (1960), p. 228  
Same shape as 3K.

Heringham [Kiln V, Stokehole; Norwich M. 3K] r-facing; very drab, greyish cream  
fabric; large + medium, grey + brown, angular, hard grit to b.b; quite  
a lot. Boro J.R.S.

Heringham [Kiln II 21.954, F.O. Benton. Norwich M. 55K] soft, buff fabric.  
with grey core; no grit on fragment; very worn but most likely to be INGENV [

INCEND out.

Denver (Nördelphi)  
Norfolk.

7 5/15

INVOKANDVS Check if he normally put slip above girt.  
15 - Normal practice!

Camelon [unregistered; NMA 53K] 30ft, pink fabric with cream slip; 1 grey girt  
survives. *Linken*

Newstead [p. 266, fig. 35, no. 14; FRA 1465; VII. 15. 59; NMA 115K] coarse sandy  
red fabric but burnt grey; no girt left.

Inveresk [FR. 167; NMA 161K] red-brown fabric with cream slip.

Inveresk [FR. 415; NMA 162K] red-brown, slightly sandy fabric; small +  
medium, white + brown girt. PPCM

Inveresk/Husselburgh [M 5 3-zone 4 Rytters Shields 4.3 NK]

L. facing. Diameter 280mm. 17% g. Hard, orange-  
brown fabric with thick cream slip which was applied

PSAS. 35, 380-417. (1901)

PSAS  
Herd. 35 329-417.

Trans. Striding. N. H. & Arch. Soc

24 pp. - 1902.

~~1400-1901~~ p 393

on top of the tinteration grit. Much less  
clay added to form spout so no real distortion  
of profile.

Inclusions: fairly frequent, ill-sorted; mostly  
tiny to small quartz (rounded, transparent)  
with rare black material; a few,  
largish and random vesicular  
blackish grits; Tinteration grit, put in  
place before slip was applied; quartz  
purplish-brown, grey rock, brown sandstone,  
black rock & probably others. (S)  
No indication of wear on sherd.

10C

? Doc 1 or MOE.

Lancaster (2 eggs. L & Ch. XXIV, 1907, p. 54); no. 7. Found at  
the Stoney Institute. Not seen at Museum.

10VIN Compare IOARV[S] - Caerwent.

~~Green~~<sup>Ush</sup> (Arch J. XXXV, 293.04) "Red war"

IRICCO

---

See ERICCOF + DIRICCVS

IRNI

London G.H. 1937.60 [E.B.'s reading for IANVS; SANIASON]



C. ITAL SEC V [

Wroxeter [iii, f. 3 nos 7 + p. 61, 4K] drab to orange pink varying; signs of burning  
black underneath and on parts of flange; slip burnt + lost colour; small white grit  
up to bead, rather sparse; stamp diagonal; slightly sandy. r. facing.  
Description 1963 - Burnt; orange-brown fabric with fine grit in it; slip  
discoloured by burning; medium + small, white, black + brown grit; N.B.  
similarity of style of ~~pan~~ fabric to CAMULACUS. D = 12". A.

STATSEK

W. W. W. W.

2

IVCUNDUS

? VERECUNDUS

? reading

IBAA 4, p 267, cil VII, 1334, no 29  
Maresfield (Suss. A.G. II, 1849, p. 173 — IVCUN)

(4) Richborough (IV, p. 449, 25) <sup>of Newborough at p 26-5</sup> Wh. fabric — Verecundus

T. IV. AF.

Le Pont-Rouge à Baulou, Pas-de-Calais. See Continental Cards


† Offprint.

11kley [Part 40 vol. xxviii p 258, f. 40 no. 11. + p. 264 no. 3]. 1K. Pinkish buff  
 fabric; small white and grey grit, mostly scoured out. Stamped outside only.  
 Burrows in horsdale <sup>houses</sup> [W<sup>2</sup>. 211 p. 94 f. 6 no. 2 + p 93] yellowish white slightly,  
 sandy fabric with traces of white grit both on interior and rim; In  
 J. P. G.'s store at Newcastle 17K; (2) Gp: 12. '1953; sketch; l. facing.  
 (Otherwise known as Overborough.)

~~\* Probably  
 Manchester [City Art Gallery 7K] 14/18 1909-1912  
 1909. 371/6 refacing cream fabric. see over.~~



IK Ikley.



Barrow in Lonsdale

TRIV. AF See?

Manchester [City Art Gallery, 1909. 371/6] v. facing A 14/18  
in fine cream fabric with very difficult stamp. FK  
not published.

Fishbourne, Sussex. [FB 67 348 (15) 1185] 2K r. facing at right angles to spout 7mm.  
from outer edge <sup>clearly</sup> tucked under beading of spout though broken here. The  
stamp is almost complete. Clay tempered with fine grey + some v-b. grit + white  
grit, probably mostly quartz. Cream fabric with pale apricot coloured  
core throughout. If any slip it is self-coloured; Heavily burnt.  
Bulmer-Fox 50. Period: Occupation layer, pre A.D. 75

Fishbourne, Sussex (FB64/189 (17) 941) IK. v. facing at right angles to flange  
 and v. close indeed to spout which was perhaps v. narrow ~~in order~~ a stamp  
 could not have been placed here - 10 mm. from flattened part. Flange  
 fragmentary. Fabric has been tempered by addition of grit - much translucent  
 pinkish <sup>red.</sup> brown, some white - likely to be mostly quartz. The tempering makes  
 the fabric slightly sandy to the touch but it is basically fairly fine-  
 textured; cream with a pink, almost pale brown core obviously  
 thicker near spout & perhaps disappearing further round. Bundle  
 - Fox 50.

Richborough [IV p. 249, no. 22; 34 read as CIVILIS; 18K] r. facing; Pit 86

filled c. AD. 90 according to B.F. Fine, smooth, soft, pinkish cream-buff fabric; internal scoring; much, medium to tiny, black, grey, whitish to b; stamp v. faint but border there. Probably B.F. 14/18.

Corbridge [unpublished. 5317; 105K] r. facing; compact, cream fabric; internal scoring; 1 or 2 small, greyish grits survive; some grit on flange; scoring on flange. D = approx. 16 ins. B.F. 14; not deeply impressed.

York, Davy Hall [Gulley 1958 G. Willmot] r. facing; burnt grey overall surfaces & fractures; slight pink core in part of flange; fine, compact fabric; abundant, small, white, grey & brown grit to b; spout badly finished off under flange; internal scoring; no grit on rim. In Flavian deposit.

C. IVL [ius] PRI [VATVS]

Richborough [V. 50] Sect. 19, S. of Red layer 95; site Mus. 119K].


r. facing; appears to have been only one stamp; fine, smoothed, hard pink fabric changing to buff very v. near surface but a change in fabric, not a slip; fair amount of grey, whitish, brown (few) grits to b. b.

G. IVKIVS PRI

Not certain

Attributed.

Chichester [CH/77/CS x 93. 13k] 1-facing. Spout with CRS  
and fragmentary stamp. Fine brownish-cream fabric, <sup>with thick pink</sup> core,  
moderate tiny inclusions of quartz with sparse red-brown  
black and flint fragments. Trituration grit included flint  
and quartz.



Cirencester [1897; Ashmolean ] l. facing; large 14/18; fine cream fabric; internal scoring; much black + grey grit; very worn stamp & damaged by scored lines.

Sea Mills [4K.


r. facing. ~~for~~ certain.

C. IVLIVS PAISCVS

NOYON

ROUEN

NOYON (OISE)




G. IVVS PRISCUS

See C. IVL  
7. CIVILIS

Carlisle Millenium Excavations [CAR 98 (337) 253K]

r. facing one side slightly obscured by clay added  
to form spout. 870gm. Diam. 330mm 44% Hard,  
fine-textured, pale brown fabric fired to cream at  
surface. Probably self-coloured. Inclusions:  
~~found~~ moderate tiny to small, quartz, red-brown and  
black. Inclusion pit: flint and quartz combined  
with concentric scoring. 6 sherds breaks modern,  
but 2 sherds are base and do not join rest.  
Well worn in base.



IVLIVRIS

See VLIVRIS + notes

IVNIVS? I

London (Bow Bells House BBB05 Context 1370 Acc <1285>

L-facing. Building 12 Period 3, 832K) 95gms.  
Reduced throughout, otherwise VRW.

Cont # 61

Stone [ST & 2 AAV (895) (containing STR 2 AAV 244) cont.]

15K] (ctr. facing. About 1/2 of min surviving. D. 35

Worn. Buff color surviving around spot but almost all

A fabric is pink (not the red-brown that Machiguan uses)

Abundant, facing well sorted quartz inclusions. Mat

A texture that has been worn away but some that

of quartz survive. Photograph

Fibrous [FE 98 611.4 18K] possibly rite but by no means

contains. Diam 2.80 mm. 15% Cream fabric with brownish-

pink (Munsell 5R 7/4 pink) core with surface skin. Inclusions:

frequent, moderately well-sorted overall with very rare orange-brown & black material. No intrication survives; possible slight traces of cream slip. Singed before fracture.

UNIVS 1

Brockley Hill House [exam Unit - B&N 00 Context 152 prn 1136/1138

364 K.] prn 1136 has 2 left-facing stamps impressed close together; prn 1138 has a fragmentary r. facing stamp. 1055 gw Diam 4.40mm. 26% Abundant, moderately well-sorted, vase orange-brown and black. Nearest to granular end of VRW. Tint gnt. mainly flat with rare qtz. little in upper part of vessel. Slightly yellowish-cream fabric and surface. <sup>fine grey calc</sup> Fabric split into 2 layers (split going up behind head)

Brockley Hill House [ditto 152 context prn 1139/365K].  
A very similar material in every way, differing slightly in section but it could be part of 364 K - the 2nd stamp.

Radlett [9K; 173; 56.1.37] sandy, greyish fabric with buff surface  
(?lip) discoloured slightly grey in parts; few medium white + black (flint)  
gits; most gone.

Brockley Hill [L.M.A.S. XI, pt.ii p. 181, fig. 4, M4 + p. 183; B.A.G. A10; 3K]

sandy, pinkish, pale buff fabric; 1 grey git; D = c. 12 ins. or more.

Venhamium [1958; B.II (28E); 142K] varies between dark grey and  
muddy brown fabric + surface; white, flint-like git. D = 15½ - 16 in. <sup>Δ</sup>

Brockley Hill [B.H. 74 T.C. MS 28 345K] Overturned to very dark  
grey throughout except for little bit underneath surface which  
is orange-brown. Fragmentary.

IVNIVS I

Radlet.

London [Mincinghane Sewer; Guildhall M. 261K] <sup>2</sup>/<sub>3</sub> facing; sandy, greyish

cream fabric; some, greyish + black, medium grits to c. 1 1/4" b.b.b.

Braughing [Inf. C. Partridge B 71 B 26 + B 71 B 21] " Hard,  
granular brownish-buff fabric; small, pinkish brown grey &  
white tinted grits". Stamps deeply impressed.

Fine end of Ver.


? (fac.

Ware, Herts [AH 79 G.114.D 205/4 ~~2710~~ 6k] CRS, burnt and

surface flaked off, leaving incomplete stamp. Granular, greyish-cream fabric, abundant inclusions of quartz, one large fragment (c. 5mm.) hard pale grey, <sup>but fractures also grey so becoming</sup> hackly fracture possibly unmixed clay pellet? No trituration grit survives, surface may have had a slip, now discoloured to pale grey. Dr. c. 28 cms.

Brockley Hill [information for Guy de la Bedoyère: 17/11/88

Sandy, cream white. Drawing of find spot in letter.



IVNIVS

44

Southwell, Notts [SCS x 12 (911) Lau Rowlandson, 2013]

r. facing + pt of l facing. 875g Diam 49% + 4%  
Three joining sherds and ~~one~~ non-joining sherd.  
Hard, cream with some grey in parts of core; self-distorted  
slip. Inclusions moderate, random, small to medium-sized  
quartz, black & orange-brown material: Intertal  
grit: abundant, thinning towards the top, mainly black  
some with red centres, occasional brown and quartz,  
Well-worn, wear also visible on underside of base.

die 12 d. 5 Δ

IVNIUS

Dragoaby, Humber [91] <sup>v/s.</sup> DR 65. A0 6K] <sup>S</sup> tint. Very hard,  
 cream fabric, moderate, smallish, quartz, red-brown, rare black  
 inclusions. - No inclusions survives. Dr. 29 <sup>1598</sup> Surface is a  
 certainly darker than fabric. probably not published. Die  
 Stonea [FB 55] 1981 5K] likely to be left f. but not certain. Hard  
 fine-textured, cream fabric. Inclusions: very moderate, sporadic  
 tiny quartz with few <sup>large</sup> red-brown & black. ~~None~~. No inclusions survives  
 except c. 2 dk brown & 1 qtz. Fired to buff on pat. of flange  
 but either s-coloured or a self-coloured slip. Dr. 31 <sup>Die</sup> 5

in unidentified envelope

Bainbridge [184.60 or 69. Grd Find.] ~~stump worn & damaged, white, cream,~~

~~fine fabric; a little red-brown grit in fabric, no tintation grit on fragment.~~

York, Blossom St [H. 28; 70K] l. facing, hard, white fabric and cream p slip; dark brown grit.

Lillechester <sup>Flats</sup> ~~Downing House - Lashed Find~~ M. Brassington ~~43K~~ [hard, F fine cream fabric, tempered with fine grit; cream slip oversails some of grit; dark brown or grey medium to small grit; slightly grey patch on rim surface.

Granular surface; probably normal H. 07 product. 23K I

Margidunum [33K. Unstratified, found during roadworks. M. Todd] "Cream, faintly pinkish in fracture." not sent K.

Corbridge [AA<sup>4</sup> ~~xxv~~ p. 182, no. 25; s. 354; 125; 190K] (facing;  
cream on outside half of fabric, pink on inside half; grit worn away  
except one r/b. F

Bainbridge [B.68. A.T. (13)] flake from flange; of cream fabric with  
discoloured grey patch on surface of fracture. E

Berwell [AA<sup>4</sup> V fig. 5, no. 2 on waftain & fig. 8, no. 1] No information  
of find-spot or dating evidence. NS.

Mandresdun [1963 information K Durham] 47K

Gloucester [IR 64 J. III (22); 28K] Fine, cream fabric but discoloured  
grey in upper half. Fragment of flange & bead. M.259. G

piece ?

Thistleton, [THV XXXI M.54. 1k] Hard cream fabric,

occasional inclusions of quartz and tiny orange-brown fragments with rare tiny black fragments. Trituration grit black iron slag; pinkish-brown slip. Dr. c. 39cms.

Sidbury, Worcs. [WS 76 1429 (P26) (30). 1k.] Cream fabric with

thick pinkish core; few inclusions of quartz and red-brown fragments. Trituration grit red-brown fragments and quartz. Dr. 25cms.

Deanway, Worcester [HxM 3899 17007 4k] flange fragment. Die 5

Cream fabric with some greenish stains in fabric: Red-brown quartz inclusions. Die 5. Fired to darker cream at surface. Sl. micaceous.

Downway  
exact  
angle -  
uncertain



Castleford [No. 40 + probably no. 83] Dr. 31 cm  
 28K Phase III GSTT F170. <sup>(28)</sup> Unlikely to be as  
 early as the AD 100-140 date for Phase III. A <sup>very</sup> well-worn  
 mortarium in fine cream fabric with red-brown <sup>interstitial</sup>  
 spt. Moderate, random, ill-sorted quartz & red-brown inclusions. A  
 Banerse, N. Yorks. [46-1819 <sup>(213)</sup> <sup>(215)</sup> <sup>(221)</sup> | 1819 <sup>(209)</sup> <sup>(210)</sup> / 2061 <sup>(228)</sup> : 15K  
 46-2061 <sup>(227)</sup> | 2061 <sup>(226)</sup> | 1819 <sup>(224)</sup> are the same pot but do not  
 join. r. facing but spt not sunning. Dr. 39 cm, B ant in lower half <sup>and a few other parts</sup>  
 heavily worn. Spt type H. Basically fine-textured <sup>with greyish</sup>  
 cream with pink in parts but not a pink core; moderate inclusions, very <sup>die 4</sup>  
 ill-sorted & some large; some quartz ~~and~~ but not dark brown, probably  
 iron slag. Different vessel from 16K but very similar. <sup>Park brown slip</sup>  
<sup>over stamps only.</sup>



0

28K Castleford GSTT 74

DIES OF JUNIUS



160K WroK eka

J

~~Wroxeter~~ <sup>F17</sup> [1915 ff. no 44] Type 18

IVN12?

Wroxeter [Arch. 88, 1938; Prob. ably: a number of reference to GB-3

Maycetter, [Burm. - A. S. [?], 1925 p. 184 pl. XXVII] on Wrox 1938: "precisely same characteristics as Wrox 1912 p. 27 no 25." <sup>? same IVN12?</sup>

Ebdwester, [KA's information from B<sub>2</sub>]; biscuit-buff fabric the opposite; gilt, red, medium-small at times covered by the heavy white slip.

Benwell [AA<sup>4</sup> 14, p. 62 p. 22 & p. 67 no. 1] unstratified. IVN =

Check tree of the  
results etc.

WVWZ

1. WROX 3001 44

heicester [Causeway Lane Area A1. 1991: 17726.1 (3879) AREA 3. M19

] r. facing. Burnt before fracture. Hard cream fabric;  
 inclusions, fairly frequent: quartz, few orange-brown. Dr. 39cms. <sup>Die 12</sup>  
 Tinturation: 2 black

heicester [A78. 1975. 2318 V F30 (112)/177] 285K] 3 fragments joining <sup>and 1 in fragment 2359 (104)</sup>

burnt before fracture inside. Cream fabric; inclusions, moderate.  
 quartz + v/b, ill-sorted, mostly small, sporadic red-brown (larger).  
 Tinturation: probably blackish but too discoloured by burning. <sup>Die 9</sup> <sup>Dr. 29cms</sup> <sup>Dr. 54cms</sup>

heicester [A40. 1988. 3265 (322) 286K] l. facing. Hard, cream fabric.

Inclusion: moderate +, quartz, red-brown, rare black. Ill-sorted but v. small.  
 Buff-brown slip. Tinturation: blackish. Spont type 6A. Dr. 29cms.

INVS

Lincoln, The lawn [L87 235 84K] 2 joining sherds.


Dr. 36-37 cms. Hard, fine-textured cream fabric. S-c.

Inclusions: moderate +, tiny but not well-sorted, mostly transparent pinkish quartz, rare orange-brown to rare black. <sup>trace opaque white</sup> Inclusion: all surrounding is dark red-b. + dark brown or black.

Die 2

Lincoln, Hungate [1214 H85 87K] 1 RS Two stamps impressed side by side, one ~~is~~ slightly above the other. Hard, fine textured cream fabric. SC.

Inclusions: moderate +; tiny to small orange-brown quartz, v. rare black; quartz. Inclusion: black to 1 quartz Die 1



IVNIVS Excavations at Brayford Pool, Lincoln  
Lincoln Access

Lincoln [LBNX 10 2010.94 (43? context) 100K]

r-facing Diameter 300 mm 14% 160g. Hard,  
pinkish fabric fired to cream at surface. Inclusions:  
moderate to fair frequent, trans & pinkish quartz, some  
red-brown, few black. All ill-sorted but tiny to smallish.

Inturation: black with occasional red perhaps, WORN

May have had a self-coloured slip

Pre-construct Arch. Lincoln (consulted by I. Rowlandson) die 2  
29/2

VNIUS vs check that VNIUS Die A KILN at Hartshill 1963.  
Presumably under MINOMIUS is entered on 1 unit in ends

Hartshill [Kiln 1963 (34)] 4K; softish, cream fabric; perhaps buff slip;  
abundant, medium + small red grit, stamped each side; Die 10" A

Hartshill [do. 5K] Hard, creamy white fabric; small + smallest,  
moderate amount grit; ? buff slip. D = 12". Horizontal striations  
in stamp and blocking of N probably due to poor cutting in wood.  
Borders are impressed clearly + deeply + it is clear that the  
vertical bars are not continued beyond the I. A A

Hartshill [do. 6K] hard, creamy buff with buff slip; very little  
brown or dk. brown grit; D = 14". Note where panel making ends  
above letters - this is clear. Presumably ends in same place below  
lettering; see 5K. A A

Hatshill [Kiln (34) 1963; 13K] hard, cream fabric containing some fine grit; some smallish, angular grit inside. D = 12" A A  
 Note blocking of V as well as N.


Hatshill [Kiln (34) 1963; 14K] l. facing; cream fabric with buff slip; a very few white grits; medium + small sized, brown turturation grit in fair amount. D = 12" A A

Hatshill [Kiln (34) 1963. 15K] flange frequent; stamped twice nearly together; both broken; hard, cream fabric with darker surface. tiny grit in fabric - brown; end of border of stamp not impressed; no horizontal markings. A B

Hatshill [Kiln 34 1963. 16K] creamy, hard fabric with tiny grit in it; stamp not well impressed; horizontal striations & blockages in some letters. The stamp is retrograde and there are no bars in the border in  $\frac{2}{3}$  of it. A 

Hatshill [Kiln 34 1963. 17K] Hard, cream fabric with some tiny grit in it; darker slip; a few trituration grits. A 

Hatshill [Kiln 34 1963. not numbered] flange fragment; very faintly surviving stamp; probably die C but not certainly identifiable.

Hatshill [do. 9K] flange + bead fragment. no A or 7 IVN [A  break.]

Hatshill [do. 10K] ?] NIV [weak. flge. fragment. no A or 7 A

Hartbill [Kiln (34) 1963] 7K. Hard; cream fabric; one or two grit in fabric; only few. Note top tail of N trails up to border.  $\Delta$  A

Hartbill [do. 8K] 1-facing; hard, cream fabric with buff slip. Abundant brown and black grit; mostly small + smaller with one or two larger pieces. D = 11". Waste cracking on flange near spout.  $\Delta$  A

Hartbill [do. 11K] impression faint; cream fabric; tiny grit in fabric - red-brown.  $\Delta$  A

Hartbill [do. 12K] cream fabric with buff slip; fair amount of medium and small-sized, dark brown grit; Fabric has some fine grit in it and one or two larger ones. D = 15".  $\Delta$  A

IVNIVS II + p. 184 no. 1.

~~NE of this with Report - The description of this face is badly wrong.~~

Manetter [Birm. A.S. 1928, III, pl. xxvii, no. 1; 4K Birm. Mus.] 206.56 + 210.56

adjoining; smooth, soft, cream fabric; burnt dark grey in part inside surface and part of fabric; no grit survives; stamped along the near vertical side. **R**


Wroeter [See Mus. 66K; M4; 1912 fig. 16, no. 25 + p. 68] stamped along; ~~soft~~ ~~fine~~

pinkish cream fabric with <sup>+ slip</sup> buff surface; thin spindly letters; moderate amount, <sup>1 white grit.</sup> medium, <sup>dark brown</sup> ~~black~~ reddish brown (grits to head; many missing, worn. <sup>M</sup> Ex with H.

Wall [Tamworth Castle; Rubbing + A.G.W.] cream fabric; black + dark brown grits. **E**

Little Chester [G.W. 1960] hard, white fabric; black grit. **D**

Derbyshire Archaeological Journal LXXXI (1961) Fig. 10, no. 16.  
+



4K Hanceller

Derby Race Course  
 Little Chester [DRC 79 BM with stamp. 4 other pages not joining. D

DRC 79 BM; BR; EM;] ~~DRC 83 20 NS 54K~~ Fine-textured,  
 creamy white fabric with hardly any inclusions; 1 black ink  
 tribulation grit.

Derby Race Course  
 Little Chester [DRC 78 AF 55K] Fine, cream fabric with red-brown  
 tribulation. Discoloured? by burning. IRS. A

IVNIVS ~~1911~~

Little Chester [~~190~~<sup>15K</sup> Denwent House.] flange fragment. Greyish cream with much grit in it over red-brown. Drab yellow slip showing yellow only on top of flange. (Wall section) ~~1911~~ F

Chester [190 59K. Amphitheatre] Stamped three times together. Fine hard creamy white fabric with darker slip; no grit on piece. F

~~Derby Racecourse~~  
Little Chester [Derby M. 33K J. Doat] Hard cream, flange incomplete. (35) DRC 74 ① no. 387. D

~~Derby Racecourse~~  
Little Chester [ " " 34K " " ] / 101 DRC 74 VI

F4-1 Hard cream fabric containing some ~~dark~~ fine grit; dark brown with grit no 388 I

NNIVS

The Parks, Godmanchester [P90 98] [1003] (42) 21K] likely to be L fac.

Diam. 29cms. 13.5% g. Hard white fabric, fine-textured fabric. Inclusions; relatively few, random, ill-sorted but mostly tiny, quartz, o/b and rare black. No tinturation survive, could have had a S-c slip - surface drier or could be weathering.

King Hall, Warks SP444735 [LH 98 11.67/1 M.22. Wg 1018

2K] stamp at end of sherd. assumed to be facing. 260g. 31cms. 2.2% v. Hard, buff-cream fabric with <sup>thick</sup> ~~pa~~ pale grey core: Inclusions: moderate, ill-sorted and random black? slag with rare quartz. Tinturation gilt: few survive, mixture of blackish & red-brown. Butt slip. Sent by J. Evans Die 4

LVNIVS

Cambs. N. Sawtry (E. H. d. land)

Tot Hill East [THE A1(m) 96 M12 (5078) 2K] L. facing

retro.  
Die 5

diam. 24 cms. Stamp - background of, very smeary -  
to do with either what die was made of or how it was impressed.

Hard, fine textured, clean fabric, S.C. Inclusions: moderate,  
mostly fairly small quartz, red-brown and blackish material

with few large fragments of same material including 1  
large pale brown? sandstone. Intercut: hard  
mostly dark red-brown, odd one black. probably re-fired

pottery. This die as always shows curious striations,  
letters not completely cut and there is a rough unfinished

background: either perhaps wood rather than way impressed since  
all stamps from this die show same features.

IUNIUS ?

moderate, random, ill-sorted quartz + red-brown inclusions

Die Q.

little Chester [31K. LC 165. C. Green] <sup>Bag 11</sup> Hard, fine cream fabric; <sup>creamslip</sup> Dr. 30 dms.

<sup>most</sup> Boron, <sup>some</sup> red-b. & white gut. <sup>3 or 4 quartz inclusions - rare</sup> Close to die F but not exact. A

Crantham Mus [3K] white, slightly sandy fabric with buff slip; red-brown + brown gut. Q

Ravenglass [5K, <sup>R.V.</sup> 76A T. Potter.] Fine wh. creamy white fabric tempered with fine v/b & grey & quartz (trans). gut. Hardly any tr<sup>ns</sup>. gut on fragment, but includes 1 qtz & 1 grey gut. Q

Ribchester [43K 78. BBL 1] two joining fragments with a graffito V I R I N I (Verini) cut after firing on outside below M flange. flange incomplete; fine cream fabric with a little fine red-brown <sup>intentional</sup> gut. quartz + red-brown tempering. Warm

IUNIVS

WALES

Carmarthen [CM 80 93 3/34/89 22K] likely to be l. fac  
but cannot be certain. Dr. 27 cm fine-textured, slightly drab  
cream; a few inclusions: qtz with rare native  
iron oxides. 1 or 2 red-brown tintation spots. Die 12.

IVNIVS

A 20 1983 SP 32 699521 K Scott P. Booth

Atherstone, Hartshill [43/1956  $\frac{6}{06}$ ; 3K Warwick Mus. previously at Altesbury]

cream-buff fabric with greyish buff slip; fair amount of medium to small white, red, black grits - sparser towards top of mortar; <sup>Dist. 5.</sup> E stained inside, a purkish brown & on parts of top of flange. stamp faint Grantham Mus. [no. 3K.]; white, sl. sandy, fabric with buff slip, red-b

Fb:grit

Templeborough [10K May, pl. xxxviii no. 19] 1877-8 found s.

cobnaded of granaries, whole; stamped twice on each side of spot; probably pale buff fabric, - slip; prolific (flint), black, white, black with red dentures, smallish; well worn at bottom, thinning to nr. b.b, horizontal marks in stamp;  $D = 13\frac{3}{4}$ "

F



3 Kr. Aberrington, Hart Hill

IVNI/ J. IVNIVS.  
(Hemmelford Hotel)

circle - see sketch of a jar

Yorkshire Museum [2h] hard pipelay; red grit to about  $\frac{1}{2}$  below rim. Cream



slip on interior face for  $\frac{1}{2}$ " ending definite line above grit. Exh.

Thornton - 6 - Moor. 1969 [Mrs. Hausard] Lincs. - Hard cream fabric containing  
some v. fine grit; cream slip. D = c. 10". Private possession

Lincs. Hist. Arch vol 1, no 5, 1970, Arch. Notes 1969

Mrs C. M. Wilson p 9. TF05829611 AD 160-190 suggested.

In Lincs. M. K 7H Fig 11, no. 3.



Leicester [137-1968 ss T (25) (42) ~~24K~~ <sup>159K</sup>] Dr. 30 or more. Fine-textured,

creamy white fabric; moderate amount quartz, fewer black and r/b inclusions. Trituration probably not surviving; greyish-buff upper surface.

Corbridge [H063, LK63, KW63, M504. 1K] <sup>(sample only at Durham 1963)</sup> ~~Slightly~~ burnt to gray in places on surface, ∴ fabric looks greyish-cream; fine-textured, few tiny translucent quartz grains with some yellowish iron-stained fragments. <sup>A few sl. vacuola black & r/b</sup> ~~No~~ trituration grit survives, heavily worn. Dr. 32 cms. See other entry NOTE D1E 14

Wasperton [WN83 F1511 3030 (518) Incomplete rim-section BK] hard cream fabric; qtz & r/b inclusions.

# FELICIDI

(1) FELICIDI F Benwell A.A. <sup>4</sup> IV p. 167 fig 6 B No. 1.

(Shape as Potross Burn (C9W 2 X I fig IV 2

Ambleside 2, (<sup>1152 XV f 26-1 f 22, 21</sup> C M. S. 20, 21, 22) Chester, ( )

Cambridge 6, (S 93, 94, 107, 153, VS 5, 132) S. Shields. (AA<sup>2</sup> X p 274, 24.)

Rein. W. 54 = some like Austinia  
- - - - - CUDIE.

IVNIVS LOCCIVS, see with LOCCIVS.

IVNIVS


Deansgate vicus, Manchester [in Rich Clark, fig 9, M7

31K context 1B.



look in Barton St.

Die



JUNIUS

✓  
 heicester [Great Holmes St A 77. 1975. 172K] v. facing v. slightly  
 I (251) 5500 +  
 micaceous cream fabric; self-colored; <sup>moderate +</sup> temping of quartz <sup>v. b</sup> ss; blk  
 lamination <sup>gut:</sup> ~~pink~~ red-brown + ~~sandstone~~ <sup>dark brown v. rare quartz</sup> grey gut. Dies  
 Dr. c. 30 cms. Worn. Δ 7 E

✓  
 heicester [A389 V (10) F38 / 1077 170K] Dr. 28 cms.  
 V (10) <sup>almost orange</sup> cream fabric, brown pink core with grey <sup>mushroom</sup> in inner core;  
 v. unusual fabric for M-H but likely to be from there.  
 no gut on fabric but temping v. mod, small-sized quartz  
 + few v-blk <sup>rare blk</sup> two joining sherds. Lamination: blackish, vesicular A on sherd. Δ

✓  
 heicester [77 1975 (145) 187K] Hange frag. note mark VN. Cream with con-buff dip  
 possibly slightly burnt <sup>v/s</sup> . qtz + vlb temping. stamped twice close together. A  
 JUNIUS 246K

Same die as Hemmingsford  
Atberst

Northampton Mus. [no provenance but probably Tynwell - Thropston area S.K. Charlton

64<sup>1</sup>] buff fabric, no slip, sandy, small + medium black, brown, white grit K

~~Rochester (Denstone College 436] hard cream fabric with slightly~~  
~~darker slip, few brown grits, stamp slightly impressed +~~  
~~incomplete.~~ ~~as Hemmingsford - Extra~~

Margidunum [Notts. U. 33449; 3K] s. outer ditch 5; hard,

white fabric; large + medium brown, red-brown + white grit. Extra

IV [die as Kbechester. Different find spot from no. 39 in Report so cannot  
be stamp referred to as no. 39 ~~to~~ K

Old Penith [CW<sup>2</sup> xxxvi p. 135 fig. 3] not seen.

N.S.




Northampton Mus. SK 1  
? Twywill - Turpston area

Ancaster Sand Pits, [coll<sup>n</sup>. D. Manning, Lincoln M. 18K] buff cream fabric with buff slip; brownish, medium-sized, sparse grit upto and on inside of bead. J

Atherstone, Hartshill. [13/1956  $\frac{7}{0}$  6; 2K Warwick Mas. previously at Aylesbury]; cream fabric; medium, tile-like grit, rather sporadic to c.  $1\frac{1}{4}$ " b. b. J

Shenstone [Wall site Museum 12K] cream, fine, slightly sandy fabric, with buff slip, tiny black specks on surface. ~~ratio~~ J

Mancetter [10K Birm. Mus. A. Oswald's ex<sup>n</sup>. u/s] r. facing compact, cream fabric with cream-buff slip face; much r/b, grey, <sup>one or two white</sup> black grit [to c.  $\frac{3}{4}$ " b. b. b.], a few stragglers to bead. D = 10 ins; medium to small grit. J



Ancașlor Sand Pits. (Lincoln M) 18K 1/2

Brough-on-Noe [<sup>5K</sup> (119) BR 83 C1] l. facing, die 9. Cream fabric, coarse texture, micaceous, inclusions quartz, red clay pellets. Red-brown slag? trituration does not survive.

Walton-le-Dale [(123) (119) WD 81 043] [13K] Flange fragment. Die 13 Cream fabric (no Munsell equivalent), sparse inclusions quartz and angular pottery fragments upto 2mm. No trituration grit survives.

Caldecotte, Milton Keynes [no. 182 79 M18 (112) 3K] <sup>1RS.</sup> cream fabric; hard; inclusions: small quartz grains; rare v. (b) blackish (ill-sorted); Die 10.

Bainesse [1819 (220) | 622 (88) 16K] 1819 (216) in same pot not joining.

~~1819 (215)~~; 1819 (212); 1819 218; 1819 (219) probably this pot rather than 15K. Burnt in same way as 15K. Heavily worn. r-facing 2 stamps impressed together and covered with dark brown paint.

Similar run; probably came to Bainesse in same batch. Fabric identical with 15K. Intertwining gilt on both matrices almost all hard, black and angular with very occasional grey and occasional black with red centre. Dr. J. G. C.

IUNUS

Forden Saev [F9 87 T (A5) R0 10 Drg. 70 2K] <sup>perhaps 5</sup> 4 joining  
sherds of a burnt mortar. Soft, cream, fine-textured, some  
small quartz & occasional darker inclusions. Abundant  
interstitial grit; mostly angular blackish but occasional  
quartz. Dr. 28. Two fine lines incised a top of 'shoulder' of  
flange. Die T

Iunius

✓  
heicester [A77.1975.5464 I 284 F22, 287K] <sup>l-facing</sup> Same pot as


A77.1975.5513 I v/s 287<sup>A</sup>K] Hard, cream <sup>abund.</sup> inclusions:

quartz, red-brown, rare black, moderate +, ill-sorted but small <sup>-tingy</sup>  
rare larger v-brown. Burnt inside. Might have a slightly darker  
cream <sup>sup</sup> ~~abund.~~ Dv. 26cm. Spout type <sup>early</sup> 6A. Interivation grit:

blackish with v.v. rare quartz. Worn

Probably same pot as heicester A77.1975.5513 I v/s 287<sup>A</sup>K.

Flange frequent. Very heavily burnt and part which is cream  
has drab off-white surface. Probably Die 10



Tripontium [SF 419 [900] + 21K] Hard, creamy white fabric with slightly darker slip, fabric contains some grit, probably not much. ~~Dark grey~~ <sup>Hand to grey</sup> red-brown grit. D = c 13" A

Tripontium [SF 900 + SF 420. 22K] Hard, fine textured creamy white fabric with self coloured slip fixed to buff on flange. Abundant tiny & largeish red-brown grit; 2 white, a very few dark grey but neither grey nor white grits make any real impression. D = c 11 1/4" J.

Tripontium (Sc [955] | 24K) Fragmentary if not from same vessel as 22K weathered, cream fabric, 1 red-brown grit. Identification with Junius (J) virtually certain. J.

## IVNIVS

D=28cm

Wall [W 8/6/2] Hard fine cream fabric with tiny red-brown + gray inclusions.

<sup>darker</sup> slip; hard angular grey + red-brown (white quartz) smallish + medium to 6.6 F  $\Delta$

Wroster [1971 J. Haughton. 160K] Hard fine-textured cream fabric with

darker slip. Dark brown tinturation grit

J  $\Delta$ 

Manchester [4K City Art Gallery no. 41] flange of small metanite

1909-119/22

Rochester [R0 86 i 1119; 50K] Internal Dr. 21 cm. IRS. Hard, cream

fabric; a few quartz inclusions; probably has a slightly darker cream slip;

Black tinturation grit - 1 quartz. Esmond Cleary + Ferns Die 4  $\Delta$

p. 70, Not illustrated.

Margidunum [A.J. xxiv p. 58, no. 44 + fig. 5 no. 44; H 123, 1'; 15K]

stamped twice together; stamps show horizontal <sup>weaves</sup> / grain marks as if of a wooden die; hard, fine, cream fabric with deep buff slip; fair amount largest & small, black or v. dark brown grit + one red-brown one; one or two grits appear vesicular. D = 14" A

Margidunum [A.J. xxiv p. 55, no. 39 + Fig. 5 no. 39; (D 114, 2 1/2')

not seen]; probably same die as Old Penwith, ~~the latter~~ ~~as~~ ~~Atterstone~~ ~~H~~;  
"cream ware; black grit" N.S.

Margidunum [A.J. xxiv p. 58, no. 43 + fig. 5, no. 43; H 117, 1 1/2';

not seen] "cream ware; sparse, brown grit" ~~the latter~~ ~~as~~ ~~Atterstone~~ ~~H~~ A

High Cross + [Sent by H. Cameron June 1974] Hard cream fabric with

dker slip, r. Brown grit

Wroxeter [171K F.P. N. trench, in silt of outer small ditch]

hard, fine-textured, cream fabric; hard dark grits, one with red core. D = 28cms. J. Houghton sent 1977

Wroxeter [172K Wv. F.P. 7 (3)] D = 28cms. Fine, hard cream fabric; red-brown grit. J. Houghton sent 1977

K

IVNIVS

NOT CERTAIN.

Heronbridge [B<sub>2</sub>assigns to IVNIVS; ?] MINONBEWS CASER, P. ~~XIVS~~ P. 48] no. found 9/57

M/c (?) Same die as Heronbridge of date (?) L + CAS XVII P. facing p. 170,  
no H1 (upside die).

Check

IVNVS cf. also IVNIV (Yellowish lines) ? same As Hemingford Abbott  
bowties with V upside down in retrograde stamp.

A

Hemingford Abbott [Hunts. J. Liversedge] hard smooth dirty white fabric  
with cream slip. Interior broken but large and small grits (flint) inside fabric.

Wroster [Site Museum unpublished 37K] hard buff fabric changing to  
creamier colour; buff slip; with a few pieces of small black grit on fragment  
surviving. Stamp broken.

Mauncetter [Broadblose (2 words); Collection of H. M. Sale. 15 Feb. 1961] 40K  
r. facing; softish cream fabric.

Dimmocks Cote <sup>Wicken, Cambs</sup> [214974 E. C.M. of Archaeology & Anthropology] hard,  
cream fabric with cream slip; 1 dark brown grit + one or two a  
flange; stamp poorly impressed. Sheet 135; ~~5~~ 2/721 for  
Dimmock's Cote. TL 5437 22: Die 5



Hemmingford Abbell.

78

Coleshill, Warks. [950] 4K] L. facing. Die C

Winterton [Archive no 79 XW/TB. 18K] Three stamps impressed close together and covered with red-brown paint. 2 different dies used 2 and 11. Dr ~~5~~ 57cms. Hard creamy white.

Inclusions: moderate to FF transparent and pinkish quartz few opaque o/b; rare black. Mostly tiny to small + few mediumish.


Tubulation: black, small to medium. 1 qtz on sherd. Dies 2 + 11

Winterton [Archive no 202 VW/FE 21K] Very edge d stampie border

CANNOT BE ASSUMED TO BE IUNIUS but thought to be Die 2.

Dr. 35cms. <sup>Hard white fabric.</sup> Inclusions: mod to FF - small + tiny quartz, some red-brown, + blackish. Tubulation: blackish.

Wroreter [WB (47) 17 212K] r. facing Dv = 26cms. Very hard fired,  
 perhaps slightly reducing atmosphere. Deep cream, approaching  
 ochre <sup>in parts</sup> (7.5 YR 8/4), slightly variations in t. slow. Inclusions:  
 moderate, ill-sorted, black vesicular, quartz, red-brown  
 natural iron compounds (None common). <sup>TRITURATION:</sup> Abundant, black,  
 vesicular with, occasionally a red-brown centre; v. rare brown  
 ? sandstone + quartz grit. Brownish-buff surface fired to  
 grey in <sup>end of spall brown off</sup> spot area on outside + on top of flange. Die II  
 Wroreter [WB (47) <sup>(75) J. EVANS</sup> 15 213K] flake giving bead + pit of flange inside  
 Fine-t. cream fabric. Inclusions: v. moderate quartz, o-b. (natural);  
 rare black. No trituration survives. Different vessel from other WBones.  
 213K NOT drawable but compared to rest of 12  
 beads



angle unetaie  
213K

IVNIVS

~~Corbridge 2/55~~

UNIV, IVNIVZ

Cl. 1.1a [c. 400]  
range 10-204]

Leicester [Kenyon p. 219 f. 58 no. 11] hard, dirty-white ware with under slip on the rim. Part of stamp IVNIVS.

⌈

Stoucester [Eng. A. Vol. LXVII p. 376 f. 142] <sup>no. 2</sup> no. 7513; dirty white fabric like pipeclay but rim and interior covered with light buff wash, medium fine black grit

Brough under Stainmore [19/8] [H. Tribbins B2 North + Scotland folders] - Information

from S. B2. Rubbed + drawn 1963; J. P. G. + D. C.

⌋

B2 G2 - Soft buff fabric, with buff slip, friable. W.S. 8 of the bar at end



Cambridge (1/4)



Leicester 11

Wroxeter [1913, fig. 17 no. 44, + p. 46.; M 92; 11.7K] hard white fabric; smooth surface; black grit. #

Heicester [316/1953/E] Heicester 11. 122K. Hard white fabric; flange

Fragment; very well impressed stamp. Inclusions: quartz, natural v. l. iron & some black with larger rounded rare red-brown, qtz + blk. Dr. = 38. d. 20

Wroxeter [WB (62) I. Site. 138K] Hard, cream fabric. Moderate to fairly frequent inclusions: moderate, ill-sorted mostly quartz including

Wroxeter [WB (47) 17] Hard creamy white fabric with grit used in it -

pinkish, fewer opaque v. b. pieces. 2 large pieces included; a very few red-brown grits. Die 20. 150K

~~Not drawn because flange incomplete.~~ (94) J. Evans IRS d. 20

Heicester [LP 212.2.2d 142K] fragmentary. Hard cream with reddish buff slip. B




(69) J. Evans

Wroxeter [WB (63) 4] 2 pieces not joining, assumed to be from same pot. 215K] L + r. Dr. 29<sup>5</sup>cms. Worn. Cream fabric, fine texture. Inclusions: sparse to moderate, quartz, red-b. natural iron, rare black. Titration: few survive, red-brown. Die 20

Wroxeter [WB (63) 4] <sup>from 138K</sup> 216K different vessel] FF. Dr. 44 Hard, fine t cream fabric. Inclusions: sparse to moderate, as above. Material is similar to WB (62) <sup>(138K)</sup> but may not be same vessel. But I have counted it finally as same vessel. d 20

Inclusions: ill-sorted, mostly quartz including pinkish, opaque black + red-brown, some of these + black large up to  $\leq 4$  mm



Beaumont Free, Lincoln [<sup>4Ka</sup>BF 2/9] greyish buff fabric with tiny specks of gnt in it, cream. G-

towards surfaces; slip creamy buff; worn angular medium red file-like gnt prolific in lower part, hardly any in c. 1/4 ins. below bottom of bead. 2 stamps close together.

Leicester [8K; 10295] hard, white fabric; large brown and black (? flint) gnt. found Blackfriars, Leicester; stamped twice together. Die as above G-

Margidunum [Ants. xxi. v. 1. p. 56 fig. 4. no. 28 misread] as SVB.

1/2 Pa 2 This will be "Blossom St." in "North Elder". NOT seen.

Leicester [Nov. 1959; All Saints Rd., 61K] stamped twice together. A  
cream fabric with buff slip.




LVNIVS

Lincoln, Spring Hill, Michaelgate [SPM 83 (161) 88K]

r. facing. Modern break. D r. 27cms. Hard, fine-text.

Inclusions: moderate +, small + tiny quartz,  
transparent + pinkish, rare orange-brown + black.

Intercalation: worn away, few red-brown. Die 15



RANAI = IUNIVS

5m N of Kirkby Stephen

Brough. under. Stainmore [BVS + 72 XIII ; 96] unstratified Hard, cream

fabric. Parallel marks all over of flange going along  $\equiv$ .

· fabric marks for smoothing - inside, as well

Little Chester [L c 165 28K c Green] hard cream fabric R

with orange buff slip. Dr. = 28 cm. micaceous, cream fabric, moderate + inclusions of quartz, red-brown and blackish fragments. Trituration grit red-brown re-fired pottery fragments. Dr. 30 cm. Fabric slightly granular to touch but inclusions responsible for small

Leicester [A77: 1975: I] (76) - (194) - 213K] - R. facing cream fabric, moderate + inclusions of quartz, red-brown and blackish fragments. Trituration grit red-brown re-fired pottery fragments. Dr. 30 cm. Fabric slightly granular to touch but inclusions responsible for small

Little Chester M. Brassington rubbing on Christmas Card 1988 57K

RANA I = IVN IFS N

Causton [18 Doncaster 30K] cream fabric with grey core; flange fragment.

Heicester [Jewry Wall, fig. 48 no. 3, p. 180 + p. 218; L 185/7 (A); 255.6 (A)] misread GRATINVS.

Wroxeter [1912 fig. 16, no. 28 p. 68, misread] VNVO; M. 46 Site Museum 106K] hard, slightly yellowish white, smooth fabric; no grit.

Wroxeter [1914, fig. 3, no. 53 + p. 60] on Type 102; not found.

Mancetter [A. Oswald BM/1; Birmingham M. 22K] in top clay of bank behind wall; dated 2nd-3rd c. deposit; l. facing, compact, cream, smooth fabric; 1 black grit.

Templeborough [May pl. xxxviii + p. 121, no. 9; RAMOTV suggested by May - or overbaked 'waster'; Rotherham M. 15K] rim warped; hard, smooth, fine, orange buff fabric with grey core; small black grits in fabric; surface grey and brownish buff; fair amount, large to medium, white, black (some with red centres); l. facing. ??? Rossington Park

Ebchester [Old Felling Mill; Dept. 8] Arch., Durham; K D 8; unstratified] white pipeclay; small brown and red-brown grit.

Binchester [BIN MS; Durham DE 4] hard, white fabric w/ yellow-cream surface. - removed.

Pattenick [1959. MIX ③; J. Washer. 23K] l. facing; hard, fine-textured cream fabric with tiny, grey & brown guls in it; much, largish to small black (some with red/brown centres) grit, with 1 or 2 white grits to c. 3/4

b. b. b. probably a cream buff slip. <sup>Pr. 345 Spot 4/6</sup> <sup>As 1/2 tray etc. 11/1K</sup>  
Doncaster [DM/BS ⑤. 86K] r. facing <sup>Site DM. Site Engineers Test Trench No 1. W. Ranon Ditch. 1969.</sup> hard, fine-textured, cream fabric

with self-colored slip; hard dark grey grit & 1 large white one. flange broken worn

~~JK~~

Extra.

H

N

~~Castlecary [unregistered; NMA 29K] flange broken; hard, creamy white fabric; 1 large, black grit on flange. sheet 1.~~

~~Catterick Village [North side; found Croft Andrew; 1.7.K] B<sub>3</sub> 5x; two fragments with stamps; <sup>4 frags altogether</sup> from same vessel almost certainly but not joining; hard, t-t.; few small <sup>fragments</sup> inclusions; <sup>burnt slightly</sup> cream fabric with slight greyish tinge in parts; red-brown grit and <sup>quartz</sup> grey grit survive; D = 12 1/2; Midland fabric. Sol river 32 cms.~~

~~Colbridge [Seen at Durham 1963; 1963 1.K; LK63/HO63/KW63 - 5 fragments] <sup>see other entry</sup> fine, cream fabric with grey core in flange; brown grit.~~

~~HO - Site XLIV, Trench II, Clearing; burnt level + clay on flags outside.~~

~~N of circular structure - KW Site XLIV Trench II [N. Extension] t.~~


~~LK. Site XLIV Trench II N. Extension Burnt wattle + daub immediately under top soil.~~

Baginton nr. Coventry (Hall Grounds B. A. Stanley] fine, smooth, creamy fabric with grey core in places; prolific black & greyish brown flint of varied size to about an in below bead. Some of black flints have a reddish brown centre like those of GRATINUS. D

Gloucester <sup>4K; St. Aldgate's in King's Square, 1934</sup> [B & G. A. T. vol. LXVII p. 76-7 f. 1 & 2 no 2, no 7513]; dirty white fabric like pipeclay but rim and interior covered with light buff wash; medium fine black grit; l. facing, smooth; probably ironstone; horizontal marks in die. Die 5 E

Corbridge [unpublished. US. 64; 103K] broken and worn; two stamps close together; compact, cream fabric with slight pink tinge. 1 or 2 r/b. grits; <sup>in: tab.</sup> Die B.

~~Baginton [B. Hall Pit, Coventry Mus, 9 [information B. Stanley] rather soft, white fabric; no grits visible. Die as SUSPECT see rim - tab~~



MUG

229. Baginton (Stanley) 7 1/7



(2) nos. GLOUCESTER.



no 1.

Gloucester.

Chester [Odeon, Northgate St., 1936; Box 32; 15K] yellowish buff fabric; no  
gint left. A

Corbridge [AA<sup>+</sup> xxvi p. 182 no. 25; 251; 83K] l. facing; hard, pale buff  
fabric with darker buff slip; largish to small, few, r/b, black gints to  
c. 1 1/2 ins. nr. b. b. b; D = c. 11 1/2 ins. A

Corbridge [AA<sup>+</sup> xxvi p. 182 no. 25; 25; 189K; 25; S. 5 xIE] greyish cream  
fabric and surface; largish to medium, r/b, gints to c. 1 in. b. b. b. Type A  
exactly 25 in Rept. but does not fit exactly! Stamp badly impressed.

Gloucester, 110 Bellows written on vessel; Jn. Bellows, Eastgate, Gloucester; 5K] A  
v. slightly pinkish cream fabric, compact; surface drab or pale buff-cream; r/b;  
dark brown, angular, hard; med. + small to nr. b. b. b; worn away below c. 1 in. b. b. b. D = 12 ins.

IV IVS

Cherter 15K 5 7

Heicester [A.475.1979 (14) (36) 206K] Dr. 49 mob. 2 joining sherds; stamped.

twice close together; for Mancetter a lot of tempering mostly whitish quartz, occasional black (? iron rich) + white inclusions + looks like some grey; one ~~black~~ trite grit; Dr. <sup>49</sup>/~~5~~ cms Prob. l. fac. D.2 B.

Heicester [907.1978 I (163) 210K] Dr. 30 cms. l. facing. 2 jig pieces.

1/2 spt. only plan drawn; bed does not go through but (3) tails at spt. Fine t., creamy white fabric; smallish amount temper - qtz, o/b, grey + some ill-sorted soft white lumps (large). v. little tinturation - v/b, greyish + 1 qtz. K

Margidunum [A. J. xxiv p. 55 no. 28; H. 59 1 1/2 (the illustration on Fig. 4 no. 28 is of 14K) interpreted wrongly as 'SUB'; 13K] stamp blurred & smeared; hard, cream, fine fabric with cream slip; largish to small, brown + dark brown grit; D = c. 13". D

Margidunum [A. J. xxiv p. 55 no. 28 - mentioned. H. 29 1 1/4; + illustrated Fig. 4, no. 28; misinterpreted as 'SUB'; 14K] rippling; fine, cream fabric + buff slip; red-brown + dark brown, medium & small grit; v. tiny, near transparent grits, visible only on very close examination. D

Margidunum [A. J. xxiv p. 58, no. 50 + fig. 6 no. 50 misread 'VAN'; 16K] fine, cream fabric + darker slip; black grit + 1? brown; stamps poorly impressed; possibly wooden die D

Water Newton [Kate's Pabin Farm site no. 3; e. Greenfield; CH. 1350;

M 2 B;] hard cream fabric with buff slip; v. few grits  
or fragment - dark brown; stamp looks as if from a  
wooden die. A


Tripointum [Sc. P] S. 17K] Fine, creamy fabric, interior surface  
burnt; red-brown and brown medium-sized grit. D = 12" A

Alaster [65. D II (14). 34K] 5 joining pieces of stone. L facing.  
Cream fabric with thick grey core with cream slip; grey or dark  
brown grit. Slip grey in parts. D = 11 1/2 D

IVNIVS ? nearest to die <sup>21</sup><sub>440</sub> > 1

Walton. L. Dab. [WD96 Drq ~~639~~ 3080/8175 joining Drq 639  
1080. 66K] stamped along L-facing, 448g (Drq 440)

Dr. 18.5 cms, 50% Drq 639 82g. 14%. Fine-  
textured, cream fabric with very moderate, random, ill-sorted  
inclusions: quartz, slag? + orange-brown material. Self-coloured  
slip. Intonation - all blackish, few with red shading.  
Some wear. Die probably impressed twice, once above earlier  
stamp. The most straightforward reading in IVN[?]  
impressed upside down. Wall-sided



Bottom

Top ←

Walter-Dale



IVNIVS: attrib to d

J. Dool

Daby Race course

Kittle Chester

[D.R.C 74 VI (6) + (2) <sup>+83</sup> 88 37K]


stamped along r. facing

Fine-textured creamy white fabric, fairly hard black grit. Man-Hart.  
Stamp upside down.

Kenchester [9K. HWCM 119; ACST P 833] Fine cream fabric  
at surface but mostly a slightly pinkish cream tempered  
with red-brown, grey & quartz grit, red-brown tetration grit.  
l. facing. Almost certainly die K K



Walton Dale [WD96 Drg 521 909 7529 65K] 2 joining  
 sherds. 240g Diam 32 cms 6.5%. Hard, cream fabric  
 with buff-cream slip. Burnt on top of flange. Heavily worn.  
 Inclusions: moderate, ill-sorted, quartz (transp. & pinkish) and orange-  
 brown material. Intonation: all blackish, some with red shawny  
 in them; 1 quartz. Fine-textured d. 3  
Middlewich [38/39 Area of caldron hearth 12K] flange  
 frequent. Stamped twice close together with red-brown  
 paint (traces) on stamps. Hard, fine-textured cream  
 fabric. Inclusions: fairly frequent, ill-sorted, mostly  
 pinkish quartz, few red-brown.



IVNIUS

M on left

Dr. Large? 40/41

✓ ✓ + 5460  
Leicester [77.1975.I (336) 483 246k] IRS. V. Hard, cream

fabric, <sup>moderate</sup> ~~few~~ inclusions of quartz, <sup>some</sup> sparse red-brown and sparse  
 blackish slag fragments. Trituration grit. hard reddish-brown  
 fragments with <sup>rare</sup> ~~little~~ quartz; <sup>maybe a greenish slip</sup> surface discoloured <sup>mean highly fired</sup> ~~at the surface~~ <sup>probably die 1 ✓</sup>

JOINS 187K

Leicester [Causeway lane A1. 1991. 17706 (2133) MO 19?

] Flange + bead. Fairly fine-textured cream fabric;  
 self-coloured or sl. darker slip. Inclusions: moderate, quartz  
 opaque red-brown; ill-sorted.

Leicester 246k

77. 1975 I 336

483



Lynch Farm II near edge of Peterborough, Cambs 300 m

[L=2 72 C (3) / 245 2K] L. facing. 155g Diameter

12% Hard cream fabric, self coloured with self-coloured slip. Inclusions: moderate to fairly frequent, tiny to medium-sized, mainly rose quartz, some tiny to small-sized red-brown sandstone and very rare black material. Insufficient of the internal surface survives to show the tinturation grit. Underneath the flange has been smoothed so that barely any inclusions show in it while the <sup>1.4cm wide</sup> band below is uniformly pimply which may continue below the fracture (ie below the band)

A few large red-brown gnts on its flange (sandstone)  
are likely to be accidental strays from Intaraha  
process.


d. 1

△

IVNIUS 2

The Hive, Worcester [Context 6782 Recno IE 2318; Period <sup>4</sup>]


60 gms. Three flange fragments, tied joining,  
broken stamp die b [7K] Hard, green fabric, self-  
coloured slip. Inclusions moderate, rounded,  
quartz, not well-sorted, all tiny to small; rare  
tiny red-brown + black; very rare large black  
+ slag d red-brown. d/b



IVNINS

Mum. rills [1972-69-491 M19 <sup>3</sup> ~~AK~~] Flange frequent  
all surfaces including fractures covered with brown or  
buff which appears to be stained brown. Hard, fine-  
textured, ~~crystal~~<sup>buff</sup> fabric (MH). Inclusions: v. moderate,  
ill-sorted, red brown, <sup>with</sup> quartz, black material.  
3 zone rim, convex, thickish, big bottom bead. <sup>6</sup>/<sub>8</sub>

Castlecary [unregistered; NMA 29K] flange broken; hard, <sup>Die 14</sup> creamy  
 white fabric; 1 large, black gut survives on flange; sketch.  
Duntocher [DUN 77 DT. 175 Hunterian M.] Hard cream DIE 14  
 with frequent quartz & other inclusions. flange fragment; 3 impres<sup>ions</sup>  
 close together, one impression stamped over the other. Probably 4  
 4 impressions, two above two earlier ones.



Manduresedum [W ④ 2  $\triangle$  34] Hard, greyish cream fabric with slip discoloured to beige colour. D = 10 1/2". B A

Manduresedum [W ④ 2  $\triangle$  35] B

Manduresedum [W ④ 3  $\triangle$  53] Hard, cream fabric containing tiny particles; buff slip fixed darker; dark brown grit; red-brown. B A

Manduresedum [W ④ 2  $\triangle$  36] stamped twice close together. Hard, slightly greyish cream containing tiny particles; slip discoloured greyish pink; dark brown grit. D = c. 16". B A

Manduresedum [W ④ 3  $\triangle$  58] Die K.

NNIVS (DISP,

Mandressdam [W①,  $\triangle$ 121] 1964] fragment. (P.)

Manduessedum [w ① 9.  $\triangle 104$ ] Die B

Manduessedum [w ① 11.  $\triangle 135$ ] Die B

Manduessedum [w ① 11.  $\triangle 122$ ] Die C.

Manduessedum [ $\triangle 148$  w ① 24] Die C.

Manduessedum [w ① 4.  $\triangle 85$ ] Die H. Hard, cream fabric; drab slip; dark brown gut.

Manduessedum [w ① 9.  $\triangle 51$ ] Die I. Pink fabric; slip fixed grey.

Manduessedum [w ① 3.  $\triangle 15$ ] Die K.

Manduessedum [w ① 11.  $\triangle 126$ ] Die K.

Manduessedum [w ① 11.  $\triangle 182$ ] Die L flange frag. Greyish cream fabric. Slip(?) greyish.

NNIUS


Die

Dec 1984

Manduersedum [Carnal find. SP 327 359 6880 sent. P. Booth Jan.]

Manduersedum, [Broaddose 600K] stamped along. Dr. 43cms  
stamped upside down. Hard, cream fabric with slightly  
darker self-coloured slip fired to drab buff-cream.  
Inclusions: moderate, tiny and smallish rose quartz, transp.  
quartz, soft orange-brown, fewer black. In hands of  
finder ~~So Connell, Witherley Lodge, Watling Street, Witherley,~~  
~~ATHERSTONE, Warks CV9 1RD, 01827 712128~~ Die 11  
Ann Scott,

RANNI = IUNIVS N

Manduresedum [1964 W ① 11 ] flange fragment. softish cream fabric containing fine particles of grit.

Manduresedum [1964 W ① 12 ] flange fragment of different vessel. fine cream fabric containing tiny fragments. slightly micaceous.

NNIUS - dies uncertain or attrib. only.

Manduesredum [W ① 11 / 115] 1964] Hard, cream fabric containing tiny particles;  
drab cream slip; dark brown grit. Δ. Dies as Henningsford Abbott.

Manduesredum [W ① 9 / 50] 1964] Creamy white fabric containing tiny  
particles; pale buff slip. Δ.

Manduesredum [W ① 4 / 26] 1964] damp faint; cream fabric containing  
tiny particles; very slightly pinkish in core. Almost certainly die L. Δ

Manduesredum Kila-site [SP 325965 'C' K. Scott). Fine-textured,  
cream fabric with some mostly fine tempering, mostly quartz and  
a few grey & black grits, some ~~set~~ ~~than~~ quite large. Internal  
surface gone. Warrick Mus. marked ✓. A  
See Colin Baddley Folder for Ⓟ

Manduesedum [1964. w①4.  $\triangle$ 57] fragment (L)

Manduesedum [1964 w①4  $\triangle$ 56] " faint stamp. (L)

Manduesedum [1964 w①4  $\triangle$ 23] stamped along. Cream fabric containing (L)  
fine particles; tiny cracks in surface; dark brown grit; slip drab cream. D=7 $\frac{1}{2}$   $\Delta$

Manduesedum [1964 w①4  $\triangle$ 25] Cream fabric containing fine particles of grit; slip  
overfired to dirty brown. (L)  $\Delta$

Manduesedum [1964 w①11  $\triangle$ 133] Cream fabric containing fine particles of grit;  
pinkish tinge in core. (L)  $\Delta$

Manduesedum [1964 w①10  $\triangle$ 95] Cream fabric with fine particles of grit;  
dark brown grit. (M)  $\Delta$

IVNIUS HOCCIUS

(170-200)

Baunese [46 - 1491 - 187] 19K. (5 other sherds joining each

other but not stamped sherd (46 | 1491 (186) (185) (189) | 1491 (324)

46 682 (105). 21 sherd <sup>Flake</sup> 1491 (190) belonging but not joining  
body flake (188) could be put dm.] L-facing. Fine textured,

greyish-cream, dark grey in parts and pinkish in parts.  
may have had darker cream slip. Only 2 brown qtzs survive  
on main pieces. Dr. 34. Burnt and shattered - many

~~sherds~~ so that flakes have come off. ? heat & water? A

Alcester

~~1000105~~ IUNIUS LOCCIUS

+

Leicester [A39.1988.8494 (549) F94 249K] r. facing. Very hard cream fabric. Inclusions: fairly frequent, ill-sorted, mostly quartz (trans. + pinkish), some red-brown, rare black. Dr. 41 cms. Buff-cream slip. No lamination or sawing.

Rocaster [Ro. 50 [5027] 82K] stamped along. Unusually steep wall. (Hard), fine-textured cream fabric with cream slip. Inclusions: moderate tiny small quartz <sup>including pinkish quartz</sup> and <sup>some</sup> orange-brown, ~~and~~ orange-brown + one large dark red material. Lamination: red-brown with a few black. Htg. Dr. 27 cms 8%

1 of heic. stamps is from Phase 3 B mid E<sup>1</sup> A  
early ③

Corbridge [AA<sup>4</sup> xvii p. 182; no 27; S 123, ③ a/xi/47; 183K] l. facing; chalk-like

cream-white fabric, with good amount of angular red-brown grit (c.  $\frac{3}{4}$  in b. top of b. 1 stamp each side of spout. D=10ins, stamped along; 27 Di A.

Corbridge [AA<sup>4</sup> xvii p. 182; no 27; S. 359; ③ b/xi/47; 27; 184K] r. facing.

cream-white fabric with buff surface; no grit. grit survives. 27 Di A.

Amble side [not published, Amblett Library 9K] fine cream fabric type c

with buff slip; dark brown grit.

Mendensaker [1964 P Ford 51K]

Shenstone [B. in A. S. Tran. .xiii p. 28 pl. VIII b. 2. Foden (1<sup>h</sup>)]

softish cream fabric; brown grit; (s. xiii 2'-4" on piece).

IVNIUS KOCCIUS

Mandresseden [1964. P. Fork. 51K]. Sofa rubbering

Mandresseden [1964. w③ 2. 20] flange fraquet. Cream fabric, darker  
slip - grey in parts.

Leicester, Causeway lane [A1. 1991. 17718 (1198) M04] r. fac. slightly micaceous  
 2 pieces not joining. Dr. 29 cms. Heavily worn. Fine-textured cream fabric; inclusions: ill-sorted, transparent, white and brownish quartz, rare orange-brown (? siderite). Self-coloured slip perhaps. Red-brown & blackish tintation, very rare quartz. Spout type 4 check. Slightly shorter than Die 1.

Leicester, Causeway lane [A1. 1991. 17730.1 M04 3954]  
 l. fac. stamped along a wall-side. Softish creamy white fabric. Inclusions: very little <sup>mostly</sup> quartz. Tintation: mostly r/brown; 1 half black half r/b. Dr. 24 cms. Type 5 spout (as IUNIVS 322) but spout badly formed. (16) W (14) in Ref. File

Q. IVS. C100

Ribchester [no. 5, D. 19] hard, dirty white fabric with brownish buff  
slip; flange fragment.

in RIVSCICO out

Ribchester D. 1. 9. 5.

7 1/2

Q. IVS CRES ✓

cannot tell which side. <sup>opaque 1-6</sup> ? all haematite  
in archive (31) Archiv nos. 81-85 + 75

Winterton [XW | ACX \$15K] 3 joining sherds. Surface of stamp A

perhaps eroded; certainly poorly impressed. Vessel  
worn smooth & <sup>possibly</sup> probably had a hole in centre bottom.

Self-coloured, softish, powdery, micaceous. Fabric is  
pinkish at or near the surface but is clearly intended to  
be the colour of the 'core'. Cream (10YR 8/2); inclusions:

<sup>sporadic moderate</sup> mostly fine but with <sup>sporadic large</sup>  
<sup>some to moderate</sup> ill-sorted, <sup>or with haematite</sup> irregularly dispersed, mostly opaque  
red-brown (softish); darker brown streaky bits & dk brown lined cavities; pink & <sup>fragile</sup>

transparent quartz <sup>fragile</sup> shreds of mica. Inclusions gut: mostly  
cavities but soft, bright orange-brown; <sup>haematite</sup> quartz; purplish v-brown P10  
1? flint; white (opaque) calcareous. Only odd quartz survive. Dr. <sup>40</sup> 39cms

⑧④ archive xw/A-FV (\$) joining g xw/ARQ (\$) ⑧⑤ archive  
and ⑧③ archive xw/FQ (\$) and ⑦⑤ archive TW/W<sup>1</sup>R (\$) are  
probably all from the same material but do not join. The  
bead treatment varies in different parts of the vessel.  
9 sherds.



Same orange-brown ? ss, same quartz. Heavily worn. Bunt.  
1 + 6 inclusions 6 mm.

Q. IVS [TIVS] CRES [CENS]

Old Witheringham, Lincs [OW AV. 1965 5K. 1. Stead] Fine cream


fabric with some very finely broken red-brown + ? transparent grit in it.  
brownish buff slip; 1 large red-brown grit on flange. Flange only, Dc. 11's  
Leicester [144-1969-I (51) 106] flange fragment. Cream fabric with yellowish  
slip, burnt in part. 151K & abundant ill-sorted inclusions of qtz + s/b

Castleford [(691) CAS. 81 510 L388 1325] 46k <sup>Just complete</sup> Incomplete rim <sup>Dr. ? 31 cur</sup>

fragment, stamped twice close together. Cream fabric, <sup>some</sup> ill-sorted  
inclusions of quartz and red-brown fragments. No trituration  
grit survives. Fabric quite hard. Pale brown slip survives on underside.

Doncaster [B. 113] (8) DG/RW NO rubbing. <sup>and slightly burnt-</sup> fired to cream on  
upper surface.  
Confusion between 2 in publication NEED checking





Q. IVS. CRES

Lincoln, TF00197713 [Evaluation trenches, N-E quadrant  
of Lincoln py-pas, site code NEQ 04, prepared for Pre-  
Construct Archaeology. October 2004. M. Darling. 96K] A  
50g (sherd sent) Diameter 340mm. Self-coloured, cream to  
light brown micaceous fabric. fixed & vitreous at surface Inclusions: moderate to fairly  
frequent, ill-sorted: red iron ore, scatter of earthy  
white inclusions, sparse sub-rounded pinkish quartz,  
tiny opaque black. No lamination gut surviving. Well-  
worn. Two non-joining rim fragments, one with nearly  
complete impression, the other with just the first letter. P. 70  
0/s topsoil. Trenches 6 and 7.

Tut got transparent and pinkish quartz, & one black and  
r/b. You can say included pinkish quartz.

Q. IVS ~~20~~ ~ CRES

Lincoln, Flaxengate [F76 (BVA) 72K] An unusually thick  
and chunky rim. Surface <sup>slip</sup> discoloured to brownish-grey  
but a small area where it may be normal - buff-brown.  
Hard cream fabric. Inclusions: moderate +, tiny orange-  
brown, quartz, rare black ill-sated. Dr.  $\leq 34$  cms. 1 red-  
brown tintation just survives. Dating & Precious 2014, p 171, B  
no. 1490.


Q145 CRES

Buxton & Howard - Davis 2000 p. 195 no. 23

Ribchester [RB89 Context 1.02 SF 7034 58K] r. facing

Dr. 31 cms. Twenty three joining sherds forming at least  $\frac{2}{3}$  of the vessel. Very heavily worn. Burnt. Slightly brownish cream fabric, fine-textured inclusions at x20; moderate+, mostly quartz, some opaque red-brown; very rare black.

Interration: sunures only at top. largish to smallish, mixed quartz <sup>mostly</sup> clusters of quartz grains (s.s.); red-brown (?s.s) and orange brown. B



Q.115. ~~RES~~ ~~CO~~ ?

Phase 7 residual

Binchester [79.2 BIN A2575 33K] L-facing 4 pieces

joining. Dr. 37. Fairly fine-textured <sup>micaceous</sup> cream fabric with <sup>white</sup> <sup>sporadic</sup> fragments of orange-brown (? natural iron compounds) and quartz. Relatively moderate, ill-sorted inclusions, random. Slip discoloured near spout ~~from cream~~ briefly to orange-brown and then grey-surface with ~~grey~~ ~~textured~~ ~~tooth~~ in parts of this area. Outside similar but more orange-brown surviving.

Q. IVS. CRES

INSTINS

TRITURATION GRIT OF  
ALBOROUGH + DONCASTER  
MORTAR. A NEED LOOKING AT

Alborough [BK unpub.] soft white fabric, rather soft; buff slip; small white

and brown grits. Lines. 2nd. century - ~~perhaps mid or late Roman~~. A

Ribchester [1957 B.R.H.] hard, dirty white fabric with brownish buff slip;  
medium and small white and reddish-brown (? sandstone) grit up to rim &  
some sandstone in fabric. End not impressed. A

Doncaster [F/GATE 1966 (1). 69K] r. facing. Slightly sandy,  
greenish cream fabric containing very finely fragmented grit;  
traces of a peachy coloured slip on flange; fabric micaceous;  
grit worn away in bottom but abundant otherwise, largest  
to small brown (? ss.), ~~grey~~ white, and translucent grits D = c. 1/2"  
stamped twice close together. DEH/- A A

QIVSCBE

QIVSCBE

Ribchester 1957.

21

Q. IVS. CRES? Placed in Doncaster - ATTRIBUTED ONLY  
DG/PQ under the

Doncaster [F/Gate 1965 B 11 8 70K] flange fragment. Stamp

fragmentary and identification is not undoubtable but v.  
probable. Certainly from some sort of area. Greyish cream,  
slightly sandy, micaceous fabric with orangy cream slip  
on top of flange only. If it is this potter it is from the other  
die not as 69K. Bottom of S & part of c.

11 8 Total at least 2 vessels  
no rubbing for second piece. DG/RW

<sup>DG/PQ</sup>  
Published as Q. IVS CRES but not certain

Templeborough [not published; Rotherham 13K] flange only; softish cream fabric; small patches of orangey pale brown on top; 1 or 2 red gits in surface of fabric; 2 v/b; 1 grey.

Catterick <sup>Bypass</sup> [59; v/s; 22K <sup>495</sup> S. Wachar] flange fragment; drab, greyish buff fabric with buff slip; surface smoothed; appears to be from same die as above. p. 339

Old Wincingham  
Winter [68] ES/EC.103] r. facing. Very slightly sandy, cream fabric with traces of yellowish cream slip; some v. fine red/brown git in fabric. Ends of keying for sport visible - appear to be concave at right angles from across flange - outside ends only visible. 7K

Q. IVS CRK

Flint most common in tuteration in all <sup>Newton on Trent</sup> Newton pots (Maggi  
niglet).

Newton on Trent [pottery forwarded by M. Darling, not marked]

Kiln side. Stamped on each side. Three ~~un~~ stamped joining  
fragments (no. 25) <sup>some pot but do not</sup> <sup>(3K)</sup> <sup>under large stamp piece</sup> Dr. 3/4 cms. Waste cracks

in base & lower side. Darker than norm - i.e. grey wh surface  
but the fabric was <sup>intended to be greyish</sup> clear cream. Micaceous. Fair amount of  
ill-sorted quartz and occasional flint <sup>v. more brown ss</sup> inclusions. Self-coloured.

Tuteration: bottom and 1/4 upside, packed with grit; medium & small  
with occasional large: flint, quartz and occasional haematite  
and opaque black. Deep finger depression underneath flange  
where stamp is impressed & beginning of the one on other side.  
Nail marks under end of spat. Spout projects. PTO Δ

This could be part of same material as 3 joining fragments drawn as 3K, No join (no. 25 original drawings published).

1 of the 3 fragments is not overtired except at join - waste crack

in this piece. Probably not used.

break



TOP

to top

2K Newton on Trent CFC

2 drawings 2K & 3K

Turning on both fragments 2 & 3 is rounded.

Newton on Trent [postcard forwarded by M. Darling. not marked off]

Kiln. stamped each side. 3 pieces joining. <sup>secondary?</sup> Overfired to  
 grey. Micaceous. Moderate ill-sorted quartz  
 inclusions with some black <sup>all fairly small</sup>. Intertaxation concentrated in lower  
 half <sup>or 2/3 down</sup> quartz, hematite + flint. Dv. 30cms. No depression  
 under stamps. This is the published mortar analysis.



0.  
h.1


W. Newton as Trustee.

Q. IVS. CRES  
A single line stamp Die as Newton on Trent 2K

Doncaster [D.T./Q.J. (5) 212] 75.K] Flange fragment. Overpiled through lead

to blackish grey with thickish brownish pink. Vitrified on end of flange  
& underneath. Very hard. ~~Probably Canterbury/Ross in the box.~~  
~~but no certainty~~ not published

1007



End

W.V.  
1912

only a single  
line drawing

characteristic

15K Dou-cao-tu

CEW

CH 5 R

Newton upon Trent, hines N.B. TRITURIT AS S. Carlton hines.  
No 21 differs from rest.

1. No-21 original publication. My no. 6.D.v. 30.5. Drawn.

Definitely not stamped on left face side and probably not on r. side. Very heavy. More than  $\frac{1}{2}$  of top survives.

Overpiced to grey. Surface clearly intended to be greyish cream; has a completely black core in parts. Inclusions;

Very fine textured: even at X20 difficult to see the quartz, save red-brown fragments & rare black visible at X10. Inclusions

quite spread ALL OVER interior: quartz, flint (a lot) & probably other materials. This vessel could well have been used

then - the grits look as though some wear. But it is technically an overpiced ~~2~~ probably non-saleable vessel  
PTO

NEWTON ON TRENT, WILCS.

KILN

~~Fragments from no 21 (labelled no. 22) probably never stamped - if so only on one side. Also a flange fragment from a mortar (different from any other) and one spout fragment.~~


With no waste cracks in surviving parts. Micaceous.  
Almost certainly NEVER stamped.

No. 4. Flange fragment. Drawn. With deep, <sup>twice</sup> distal groove. Slightly greyish cream fabric. Moderate, ill-sorted quartz transparent + pinkish (rare); Very rare black + red-brown. Red brown definitely rarer than in S. Carlton specimen. <sup>Some buff-brown</sup> surface slip?

No. 5. Spout probably belonging to a separate m. from any other found. Greyish-cream; mod qtz + rare red-brown ~~inclusions~~ inclusions. Nearest to S. Carlton

Q IVS CRES

Sudbrooke (5m/7km NE of Lincoln village SUD05; (118)  
and (133) joining inf. M. Darling L. facing . B



See graffiti.

> IVSTVS SUPER

RIB II fascicle 6-7

Cursive graffiti cut before firing i.e. from  
a military kiln.

> IVSTI

SVPIRI

JRS XXXIV p. 91 no. 23,  
London Head St. (within area of Colonia).

# IVVENAHS

Canterbury [ss. Frene c. x c. i. 8] fragment of flange; slightly sandy fabric, with piece of chalk in it & frags. of shell; dark greenish grey core changing to pale orangy brown v. near surfaces; stamp in completely impressed. 46K

Richborough [i, p. 88, 6; M 5; 13K] flange only; stamp v. imperfectly and incompletely impressed; pinkish brown patches on surface, ? slip; sandy, drab cream core changing to orange and orange surface probably l. facing.

Worth, Kent [in group of pottery from site; found? 1958; British M. 128K] l. facing; flange & spout; <sup>brownish coarse fabric with dull creamy core</sup> somewhat coarse, creamy pink fabric.

Canterbury - seen at Institute 19.6.63 Jan.

IVENALIS some v. faint grooves at intervals on inside.

Canterbury [CBR IV 80/81 (538) 1527 - 1531 all joining

except for body sherd [1530 65K] l. facing Fabric as 64K

but slightly fewer inclusions (still fairly frequent. Worn.

few <sup>flint</sup> ~~quartz~~ inclusions <sup>CORE</sup> 5Y-6/2 (greenish-grey) survive. Cream slip, fairly thin. Worn.

Canterbury [CBR II 78 (225) 1458-1460 + (277) 1472 1475-1480

All sherds join. [66K] l + r. stamps <sup>7.5YR 7/4</sup> c. two-thirds of pot

w/ some base. Hard, fairly light brown fabric with fairly

frequent mostly quartz inclusions. Cream slip. Well-worn.

Some <sup>flint</sup> ~~quartz~~ inclusions <sup>+ red flint</sup> survive. Need a check on the nos.

for all these sherds re. the (277) 1472 1475-80

the pieces are packed together because they join.

IWENALIS

Boulogne [CIL xvii, 10006, 42]; definitely same pattern & must

certainly same die.

IWVE  
IWNALIS

The Hermitage, Box, Wilts. [Devizes Mus] Informat<sup>n</sup> J. Keally

Richborough [IV p. 244, no. 48(A); 66; 82k] stamped along handle;  
broad, smooth, handle, cleanly broken from surface of vessel; sandy,  
fabric; thin bluish grey core changing to cream buff then to reddish  
orange, surface also; unlike amphora fabric. P.E. 119; B.F. dates  
filling c. A.D. 90.

Dover Mus. [no provenance, probably local] orange-brown-red fabric; few, largish, mostly worn away, white, black, reddish grits to near b. b.; 1 stamp each side of sp.  
Lauterbury, 10, Castle St. [Jenkins, 1952/98/6; Pit 14; 10K] orange-buff fabric with reddish tinge near surfaces, dark reddish surface; had hole in bottom, smallish, white and red grits to near b. b.; grit worn away below c. 1 in.  $D = 9\frac{3}{4}$  in.

Canterbury, Burgate St. [At Butcher's house; 1945, no 3 Rept p 19 Fig 7 no 7; 19K 5805] Hard, pinkish buff fabric; <sup>with grey core.</sup> some black, brown, white, large & largish grit to c. 1 in. b. b. b. Mid. (2)

Canterbury [site unknown; At Butcher's house 20K]; sandy buff with greyish cream core to very near surface; a very few, black, orange-brown grits

30K granular <sup>pinkish</sup> core

Canterbury [CXX EXIII (5)] / sandy, orange-brown fabric with greyish core.

on rim fragment. ~~30K~~ 30K Flange fragment. Flint, transp. & pinkish quartz tempering. <sup>and black spots (quartz)</sup> Fabric 2F.

Canterbury [CXX EXIII 80 (819) 48K] r-facing. heavily worn; apparently self-colored orange-brown fabric with ~~very~~ thick <sup>brownish-grey</sup> ~~pink~~ core; heavily packed with <sup>mostly</sup> well-sorted inclusions, mostly quartz. <sup>Probably in pieces of flint.</sup> occasional chalk & occasional flk; only 1 or 2 ~~flint~~ (? flint) inclusions quite survive. Dr. 24 cms. Sample.

Cracked under flange

IVUENALIS ?

Canterbury [RL/P 77] 278 279 T. T - Brown. 40K  
 Mansell 2.5YR 6/8  
 v. facing. Very hard, granular ~~with~~ orange-brown fabric;  
 frequent, ~~isolated~~ fairly well-sorted inclusions, ~~with~~ <sup>washed (probably flint)</sup> quartz grit & L quartz <sup>with</sup> grit showing  
 on frequent. looks as though it ought to say Iuvenalis  
 but doesn't quite fit any rubbing, self-colored. Dr.

Canterbury [CBR II 78 (191)] 1461 64K L. facing. Basically fine-  
 textured, orange-brown fabric with fairly frequent (less than 40K + 48K)  
 ill-sorted, <sup>probably mostly</sup> quartz inclusions <sup>(flint possible rare)</sup> (have v. brown + black <sup>iron slag</sup> staining); one or two  
 qtz inclusions quite survive. cream slip. Dr. Locust. Thickest <sup>P</sup> drab  
 core Mansell 5YR 7/2 Pale, greenish-grey.

1  
Check form for *menalis*  
against poster like  
EXPIRED. Could be  
possibly be contaminated?

IVST I

6 [L] CALVINS > IVST

# BIRVCIVS or BRVCUS

- (1) <sup>B.R.V. (Pibon)</sup> Chester (Pibon) (31 MS, 29) Chesterton (AA<sup>4</sup> XV 236, fig 5, 56);  
Corbridge 2, ( ) Templeborough? ( )  
Wilderspool (May 1, 64) Wroxeter? (1912, 66, 2)

Rim Wrox 38, buff, sand clay. white opaque grit.  
EOM 100

Wanborough [970. M252 3K] Hard, orange-brown fabric with grey  
 core + ill-sorted quartz + v/b. inclusions; traces of creamy buff slip,  
 no int. survives; green & brown accretion under flange; stamped  
 at least 3 times together. A

Wanborough [M53 23K] stamped at least twice together. Two  
 joining pieces - bottom piece has graffiti on outside; slightly  
 burnt. V. slightly granular with many well-sorted tiny  
 quartz inclusions. Traces of cream slip. Intertwined: mostly  
 transparent quartz, with haematite, chalky material, iron-rich  
 material (black). A



3K



23K wandbrosch