

L

See Monocampus


L. FECIT

L SATTOS of SATTOS ~

A misreading somewhere probably

VIATOR.

67



~~LALLANS~~ HANDLE IS LALLAIVS

Richborough [V, 86 surface; s.w. Area; inside fort; site Museum. 109K]

r-facing; flange fragment; sandy, creamy buff fabric; very deeply impressed but not borders.

Offord [See A. Cant. xlii p. 167, ? #13; #21 on p. 8; Maidstone 3K] l-facing survives; vessel heavily restored; greyish fabric; only 1 or 2 gits survive; buff slip.

Offord [Arch. Cant. xlii p. 167 #12; Maidstone 11.8K] r-facing; sandy, greyish cream, buff slip, black + grey gits, fragment only.

Offord [Arch. Cant. xlii p. 167 but not published. Maidstone 11.9K; #15] fragment only; sandy, greyish cream fabric; black + grey gits.

see over


~~Check Offord ... ? - Located ... 2 or 3 - At least 2 vessels~~

One of the Offord LALLAIVS stamps has been used
in a restored vessel. The other 2 stamps could
possibly be from the same vessel on the other
side of the pont,

Wixoe, Suffolk ^{Extnd Arch. East.} [Alice Lyons Fig. 3.35, no. 112. 1K] L-facing ^{LALLALUS (BRH III)}

60g Diam (320mm 8% 1 rim sherd. Spout clay has come off. Variant of VRW. Buff brown fabric with slightly darker slip. Frequent, very ill-sorted, composed mostly of quartz, rare tiny red-brown material and black material. 2 flint inclusions still survive. There is some burning on the inside. Δ

Context 1244 in Pit 1245, Pit Group 7, Areal, Period 2. 2 sf 1892
^{Grid Ref}
NGR 570986.54, 24320.29



Wall Museum 2K. (from G.W.) hard, orange fabric; moderate, medium sized

red, white, black grit to head; worn away near bottom.

Brockley Hill [LMAS 1956 vol. 19 pt. 1, p. 77 fig 243] ^{M10} stamp impressed twice; cream surface, burnt grey.

Brockley Hill [LMAS 1956 vol. 19 pt. 1 p. 77 figs 243, M10] on lighter flange; creamy buff.

London, National Safe Deposit Co [G.H. RXV 384] burnt surface, buff core.

Walton-le-Dale [Pickering Ex. 1.] sandy, creamy buff fabric; flange fragment.



1937-77



Walton Le Dale Ex. 1.

74



Brockley Hill M. 60 (2)
1945-1956



M. 10a. (2)
Brockley Hill

LALLIUS

London, Bow Bells House (BBB05 Context 1202 Acc <834>

823K) L. facing 150 grams VRW, probably finer version with a curiously pinkish brown surface on upper surface ^{only} of flange, near spout. With end of spout. $\phi \Delta$


London, Cheapside, EDPO 46 Accession <847> Context 919; 852K

right facing. flange fragment, greyish-white fabric surface slip yellowish. Inclusions; packed with transp. quartz with few red-brown and rare black. Diameter 300mm
11% 85gms.

WALLATVS

No. 1 Ponting, London [ONE 94 Context 17903 Mus Acc. 4404 #41K]

r. facing IRS Very heavily worn. 218g. Slightly burnt.
Flange fairly smooth. Brownish fabric, brownish-cream slip.
Finer version. Abundant, mod. well-sorted quartz inclusions
& v rare opaque red-brown. Intercalation worn away except for
one or two, flint & quartz & rare red-brown. Slightly burnt



LALHANS

* ^{probably known} London [Sotheby's Sale, 19 July 1848; 48/8/3/59; M.2.828; 68; British Mus. 55K]

L-facing q., inside caked with some clayey stuff; very slightly sandy, cream fabric with orange buff surface, probably slip.

^{Worcester} Worcester [1912; Blacklayer Bx. No. 66 "light red" on card, ^{Worthing M.2K} 37/64] L-facing; slightly sandy, sl. orange buff fabric with orange core, most of grit gone, flint, black, white, grey, medium T largish, few to b. b.; middle of stamp ~~absolutely gone but probably LALHANS.~~

^{LMA 3} London [Plough Court, Lombard St; P. 232 ^{late 1st. Century} "Rubbish Pit"; ^{22 pt 1 (1968) p. 34 fig 3 no. 4, 9 p. 42 no. 4 reads as VIATA}]

Marsden [5W: 1K] creamy buff fabric; grey & white grit.

London, Addle St., Bag 56; Guildhall 24.9K] stamp each side of spout; whole except inside base; buff fabric & surface; grey, white & brown grit. 22253

LALLAYS. LALLAIVS

London [ER 735 Paternoster Row G.H. 281 K] no rubbing

sandy greyish buff fabric; flint grit.

Brockley Hill [Westkith Ditch - S. A. Castle]

London [Trans. London & Middx. Arch. Soc. 22, Pt I, (1968) fig. 3 on p. 34,

no. 4: ? = Royal Court, Lombard St.

London [ER 788 Paternoster Row 317KSH] no rubbing "A1"

London, St. Albans, Wood St [SA 29/9 +10 stamped FACIT LALLAIVS]

Hard orange fabric with thin grey core in flange & brown surface.

London [no. no. Guildhall M; 35K] r. facing; sandy, grey to greyish

buff fabric; grey surface in patches; orange-brown colour in other
gritty accretions; small to largish, white, black, grey grit to b. b.

B.F. 58 but end of flange more inturned; no rubbing as 27K.

^{B51E}
London [1937.5.4 Guildhall M. 27K] probably l. facing; sandy, heavy,
grey fabric, buff on parts of surface; medium to tiny, grey + black
grits to bead, worn away at bottom. D well over 14 ins. Approx. BF. 38.

London [1937.276 Guildhall M. 26K] l. facing; fairly smooth; slightly
sandy fabric, greyish core to buff, + buff surface; some, medium
+ small, grey + white grits near bead in a c. lin band; worn away
below + signs of burning below. D = 13 ins. BF. 58 but bead much lower than flange.


London [R. XI. 626 Guildhall M. 173K; St. Martin-le-Grand; May 1840];

sandy, buff to pink-buff near surface; prolific, large to medium, rb., white, grey grit to near bead. D = 10 in s. Misread VIALLA (written on pot) fragmentary; r. facing.

London [1934 44 Guildhall M. 37K] flange only; sandy, whitish grey fabric with grey surface, buff in parts; BF. 34/38; ~~no rubbing~~, die as 27K.

London [Sotterby's Sale, 19 July 1848; cat VII, 1334, no. 7; 82; 48/8/3/58; M 2827; British M. 102K] r. facing; slightly sandy, greyish cream; black, white, grey grit, sparse on frag., to bead. BF. 38.

Shepreth, Cambs [TL 3967 RONGM 1992. 21 1K Royston M] vessel
 complete except for c 3" of rim restored and 2-3 tiny body sherds.
 L+r both v. poorly impressed stamps. Well-worn.
 Greyish-cream fabric. Random, large to smallish
 inclusions of flint, quartz and rare red-brown
 Venetian region. Diam. 30 cms ^{+ early 2nd spf.} Early second c 4
 Diameter of base 11.5 cms.
 Bower Rd, Nr Ashford [inf: Paul Booth. Channel Tunnel
 Rail Link]



Walton-le-Dale [WD 81 519 (108). 1AK] Brownish-cream fabric (no

Munsell equivalent), granular texture; abundant inclusions angular, ill-sorted quartz, sparse red ^{-brown} ~~clay~~ ^{fragments.} ~~particles~~ and black ore fragments.

No biturbation grit survives. (Fabric 33) Dv. 32 cms.

Caldecotte, Milton Keynes, Bucks [144] 18 F1 F77 (1) 2K] r. facing; ^{IRS}


pale brownish fabric; granular; packed with inclusions: quartz, sparse red-brown fragments, black ore fragments, ? flint. ^{Toofang's} ^{draw IRS}
 Inturbation grit: mostly flint, some r/b + quartz. Heavily worn.

LALLAIVS

check later

Binchester [79.2 BIN A 2166 20K] Flange fragment.

burnt. ^{18/20} greyish-brown with abundant quartz.] 1 A [>>>



LALHANS

Brockley Hill [BH 74 T.C. MS 47 309K] r. facing

Cream fabric, pink (thick) core; buff slip.

Brockley Hill [BH 74 T.C. MS 41 308K] Cream fabric, pink
towards top of flange. buff slip.

Brockley Hill [BH 74 T.C. MS 44 306K] flange. Fired
w dark brown & grey ~~sur~~ blackish surface

Brockley Hill [BH 74 T.C. MS 50 307K] r. facing
fired throughout w dark brownish grey; grey-red surface
white & grey flint grit

Brockley Hill [BH 74 T.C. MS 38 305K] greyish cream, buff
in parts.

Brockley Hill [BH 74 T.C. MS 39 302K] flange in greyish cream

Brockley Hill [BH 74 T.C. MS 45 300K] flange in greyish cream

Brockley Hill [BH 74 T.C. MS 42 301K] Overfired throughout
 & dark grey l. facing.

Brockley Hill [BH 74 T.C. MS 42 311K] flange fired
 throughout to blackish grey

Brockley Hill [BH 74 T.C. MS 52/ 302K] l. facing greyish
 cream; slip dark slightly reddish brown

Brockley Hill [BH 74 T.C. MS 51 303K] r. facing
 greyish cream fabric: grey to black; small flint grit; few red-brown

LAWANS

Atlib

Brockley Hill [BH 73 TC. MS 9 248K] flange broken off. (fac.

border above? Greyish cream to brown streaky fabric with
brownish buff slip overfired to grey in parts & in parts of fabric;
grey, white & blk flint grit.

LAWLANS


1973 Brockley Hill.

Brockley Hill [BH 73 TC MS10] ^{228K} 2 pieces joining Overfired to

black + ^{dk} muddy redd brown throughout. few flint grit.

Brockley Hill [BH 73 TC MS16. 229K] l. facing flange to pt fragment; typical spout of Saturnian type + tiny rim too.

Brockley Hill [BH 73 TC MS6. 230K] Overfired throughout most of piece to black + dark brown. granular greyish cream in one part only. 1 flint grit.

Brockley Hill [BH 73 TC MS17 231K] l. facing. light brown granular fabric, darker in parts. granular. grey, white + blk flint grit; + 1 red-brown. $D = \frac{3 \text{ ics.}}{1}$
Spout shallow + depressed back in middle 

LANHAIN S BROCKLEY HILL 1973 AU 1973 big hooks except MS 16.

Brockley Hill [BH 73 TC MS 7 232K] flange fragment

in pale brownish cream fabric with orange buff slip. Deep finger depress^{ions}.

Brockley Hill [BH 73 TC MS 5 233K] v. facing. Large piece but flange broken. Overpiled to grey + v. dark reddish brown.

on surface purplish in parts. Fabric grey in part but mostly a dark reddish grey brown. Base hacked instead diagonal

Brockley Hill [BH 73 TC MS 4 234K] flange fragment in ^{cutting} granular cream fabric; sl. smoked upper surface.

Brockley Hill [BH 73 TC MS 3 235K] flange fragment with deep thumb depression under flange. Granular greyish cream

Brockley Hill [MS 65 277K] information S. Castle.

LAHANS 1974

Brockley Hill [BH74 T.C. MS40 297K] granular fabric

intended to be cream, fired to black in parts.

Brockley Hill [BH74 T.C. MS 53 310K] flange greyish cream
with brownish buff slip.

Brockley Hill [BH74 T.C. 298 K MS46.] flange fired
throughout to black.

Brockley Hill [BH74 T.C. MS 49 299K.] blue-grey
throughout.

Brockley Hill [BH74 T.C. MS 48 304K] cream fabric, pink
core; buff slip.

Brockley Hill [BH74 T.C. MS 37. 338K] attrib. but S. Castle partly certain
fragments. greyish cream

Brockley Hill [BH 73 TC MS 13 236K] intacing, flge broken. Overfired

to dk grey throughout; few flint grits.

Brockley Hill [BH 73 TC MS 11 237K] flge broken off. Overfired

throughout to blackish grey + orange brown; with fine white speckle in fabric; few flint grits.

NB None of the mortaria have grit near the top of the vessels.

Brockley Hill [BH 73 TC MS 8 259K] intacing pres. Overfired. Granular

fabric varying in colour from greyish cream to brown + black. G + w + few fl. flint grit thinning out a lot towards bead.

Brockley Hill [BH 73 TC MS 15 265K] flge fragment. Granular greyish cream with brownish streaks. but ship discoloured. L. facing.

Brockley Hill [B.70 T2 (4).101K] v. facing. Flange to spt fragment. Very sandy creamy buff fabric containing grey & red-brown inclusions (tiny & 1 large grey grit). Self coloured star as can be seen.

Brockley Hill [195K BH'66 m. T.C. M2] flange fragment; depression into flange - underneath stamp slightly diagonally greyish granular fabric with brownish slip.

Brockley Hill [Inf. Stephen Castle 27.11.1981] Found in flower beds near main entrance of Hospital in 1976. Now in M. of London. Creamy buff fabric 2VIA11 [. No rubbing

LALLANS

Brockley Hill [BH 1971. F. 116K] flange fragment; granular cream

fabric with slightly brownish cream slip.

Brockley Hill [BH. 1971. E. 117K] flange fragment. granular ^{greenish} cream fabric with darker cream slip.

Brockley Hill [BH. 1971 + D. 118K] flange ^{+ side} fragment burnt ^{dark blue grey} black through at fabric bottle. 2 frags. joining grey & white flint grit.

Brockley Hill [BH 1971 C. 119K] flange frag with bit of bead. In granular brownish cream fabric. Some transparent sandy fragments in fabric.

Brockley Hill [BH 71. KF. 39 175K] tiny fragment] 1/1 [not rubbed.

From Kiln furnace. Sandy cream fabric.

LALLANS

Brockley Hill [1971 BH 71. ST.P. 51 112K] Flange fragment; granular

cream fabric with dark slip.

Brockley Hill [1971. BH 71. J 113K] L. facing. fragmentary. Fairly certain really but only tiny bit of bottom border. Granular brownish cream fabric with greyer outside. Brownish cream slip on inside; grey white + blackish flint grit; some red-brown.

Brockley Hill [1971 4X BH 71 TC. 114K] Flange fragment; greyish cream fabric, surface a bit eroded.

Brockley Hill [1971. B. H. G. 115K] Flange broken. Granular fabric burnt to overfired to dark blue grey with a blackish patch.

Brockley Hill [L.M.A.S. XI, iii p. 270, no. 10⁺ p. 271; 52; 28K] sandy,

cream-buff fabric; fragment of flange; no A

Brockley Hill [L.M.A.S. 19, pt. i p. 71, M.10; Sull. 57; D.3 14; Harrow 19K]

stamped twice close together; sandy, cream surface save grey on top of flange; grey throughout in body; 1 or 2 black + grey, smallish grits.

Brockley Hill [L.M.A.S. 19 pt. i p. 71, M.10b; Sull. 53. D.3 (Black); Harrow 27K]

different vessel; flange fragment; cream fabric; ~~no~~ Δ

Brockley Hill [L.M.A.S. 19 pt. i p. 71 ^{M.3 - wrongly ascribed to MARUSGENS} ~~710 - See~~ but not published; Sull 57; D.3.

Black below cobble; Harrow 31K] L-facing, slightly sandy, greyish cream fabric with cream surface; flint, grey, white, blackish grit

Putney, London [IK Nicholas Farrant, 7 Coakcroft Road, S.W.15]

[116] BEM II 65 Y 4. Worn. l. facing granular, greyish cream fabric with quartz (opaque), grey (flint), r-b & transparent quartz tinturation grit. Wandsworth Historical Soc Δ

Brentford [22/62 74 c 72. SK] granular greenish cream with grey core, flint grit.

Staines [CAD 77 (18) Ror QBZ 44k] r. facing ^{worn} fragmentary slip.

Granular buff-cream fabric tempered with ~~opaque~~ quartz; vessel battered; red-brown chips. tinturation grit not really visible.

Ashted [David Bird

WALLIANS

Stchester, [May, pl. ^{p. 275} LXXXIII A, no. 3; 15 K.] slightly coarsish, grey-white fabric;
large to small, grey, r/b, black grit to head.

London, National safe Deposito. [R. XV. 384; Guildhall M; 213 K.] r. facing;
sandy fabric; reddish pink core to buff cream but surfaces blackened
all over; drab, red-buff showing through in places; no grit
survives; near 14 K.

London, Milk Street [1926.51, Guildhall M. 36 K.] sandy, pinky red
fabric, to pink surface with ? buff slip mostly worn off;
very v. few, r/b, white, grey grits, smallish; D = 1 3/8 in S; very
shallow & broad BF. 38.

LALLAINS

LALLAINS

(1r stamp + l. stamp)

greyish cream!

78108292

Aldborough [20K Unpub] sandy brown fabric; sparse, small white and brown grit; complete, except for hole ~~in~~^{not near} in base. Heavily worn. ^{? cream slip}

Wroxeter [M18, 49K. Unpublished] sandy buff fabric with darker buff slip; little grit originally, now missing. Broken flange. Stamp fragmentary. ^{Matches with}

Trinity Lane, ^{hard near} ^{Southwark} [Guildford Mus. Battenworth Collⁿ; Surrey Arch. Collⁿ 1, 1858, p. xxxii] sandy, grey-cream fabric, surface brown buff in parts; very little grit, probably mostly worn away, ? flint. D=13ms. 1 stamp each sided spot ^{as Walton-le-Dale.}

Worcester [GW.]

Bank of England [E. Birley]

? Segontin ~~at~~ Wroxeter [NMW] labels says Segontin but says ~~marked~~ ^{is} ~~sw.~~ ^{pit}, a Caerws provenance.

Heronbridge [CAS. Vol. 41 p. 33 f. 11 no. 75, p. 34.] Rim fragment in buff-brown fabric,
 moderately sandy texture. ? 100 - 130
90 -

Brookley Hill [MAS N^s Vol. XI part III p. 269, no. 10] sandy buff fabric.

~~Brookley Hill [MAS vol. 19 part 1, 1956 f. 2 no. 10 at f. 4, 110 A] cream surface
 burnt grey stamped tone.~~

~~Brookley Hill [MAS vol. 19 part 1, 1956 f. 2 no. 10 b & f. 3, 110 B p. 71] creamy
 buff fabric.~~

Templeborough [p. 121 no. 13 v. pl. xxviii] hard white clay. misread]

Walters M 282-7 / 2 & Cat. 101000 - 101000

KAWHAKIS.
AIVS

Kirkham, nr. Preston [S. Marshall, 22, Myrtle Drive, Kirkham; 1959; 2K]

r. facing; flange frequent; sandy, BH/R, buff fabric with thick
greyish cream fabric; may have brownish buff slip. greyish oatmeal
Great Weldon [G.W. 647] stamp broken; slightly sandy, typical BH/R
fabric; 1 greyish flint grit on flange; attribution certain; signs of burning
at one end.

Brixworth, Northants [P. J. Woods, 45, Stannard Way, Brixworth, Northants]

1967. r. facing. Sandy greyish cream fabric with a cream slip, fired
to buff on top of flange; most of grit worn away; remaining few
grey flint. $D \approx 17\frac{1}{2}$ finger print under flange ^{near} beneath stamp. Δ
bird's eye.
depression
sl. to as d. to q. on E face inside of base

Brixworth Excav^{ns} Vol. 1. The R-B Villa 1965-70

(Pt. 1. The Roman Course Pottery Decorated Samian ware). by P. J. Woods. Reprinted from Journal of the Northampton Museums & Art Gallery 432 & Fig 33, no. 243.

LALHANS (AINS)

Cambridge [no. 79. 4K.] sent M.R. Hull. A's sent.

Ewell, Surrey [T72 SMC 71 R.] sent. St. Mary's Churchyard.

Burton. ^{Herts.} Sandy greyish cream fabric with traces of buff slip A
St. Albans [SK/AF SF18 Δ 30IK] flange frag. in greyish
cream fabric.

Nazeingbury, Essex in the Parish of Nazeing. Rhona Huggins
Waltham Abbey Historical Society. 27, Grange Court,

Waltham Abbey, Essex. '75 v(7) flange fragment. Shallow-spout
cream fabric. Essex Arch. & History vol 10, 1978, Hitt, no 136 + P¹⁸⁰ Δ

North Church, Cow Roast GK CR 74 (598) 19L L9 C. facing -
other straps broken; worn granular, brownish cream fabric with bronze
slip; flut + red-brown sent.

WANKANS

Venlamium [58; BIT (32E) 153K] r. facing; sandy; pink core changing

to greyish cream; surface orangy, brownish to a slip; grey
+ r/b, flint, tiny to medium grit in band from c. 1/4 in b.l.b.
to c. 1 1/4"; worn away below. ^{SSR = 90-105} A Harris. & Harris in
Mumham from B. Barr.

Venlamium [Pit 2; XVII Ver. 61. 208K] r. facing; sandy, greyish
buff fabric; medium sized brown, grey + white grit -
worn away in lower half. D = 12"

Venlamium (SK/AP 18 Rubbings sent by V. Rigby)

LALLAIVS

occasionally stamped with GISSUS Stamp
on other side

Gorhambury [GOR 75 (546) 2018 (3) 9K] Flange fragment,
incomplete stamp. Pinkish-brown (5YR 7/6) fabric, granular
texture; frequent inclusions of quartz, sparse red-brown
fragments. No trituration grit survives.

Wroxeter [WB (33) (98) 138. 193K] Flange fragment. Granular,
~~drab cream~~ normal colour.
~~normal cream~~; abundant inclusions fairly well-sorted quartz,
sparse red-brown ^{natural iron Fe} fragments. No trituration grit survives.

Dr. c. 34 cm. Does not seem to be part of 205K or 248K.

Wroxeter [WB (30) (98) 138 205K] (facing) IR.S. Granular. P.T.O
Pale brown fabric, texture as above.
[with orangy brown surface. Trituration grit flint, quartz, black slag.
So far as one can tell, a different vessel. 2 joining sheds. Dr = 34 ±

LALLAUS

(April 1994) (125)

Wroxe [WB 90 164 on pot 79 100 on pot. Not part of 205K or +

248K] r-facing. Ochraceous but surface discoloured - greyish brown. Slip buff brown, worn away up to c. 1cm below top bead. Interactions all worn away. Inclusions: frequent quartz, mostly rounded + 1 size but some ill-sorted. Normal ver. range.

(125) J. Evans number

All 3 types of vessels are for different vessels.

LALLAGS


Silchester [p. 275, Pl. LXXXIII, no. 3].

London [G.H. 1937.77] Type 34; hard rough dirty cream; too small for grit.

Oxford [A. Cant. xlii p. 167, H. 12. Maidstone M] creamy buff fabric.

Oxford [A. Cant. xlii p. 167, H. 13.

Castor [Dunbrival pl. xlii, no. 6] "white stone ware".



Offord
(Maidstone Mus.)
H 12

$\frac{1}{1}$ 4

Art's $\frac{1}{1}$ 2. no. 6.

LEQVL VS

Caistor by Norwich [Norf. & N. A.S. xxvi pt ii p. 210, R3; D.11, 70K.] cream fabric
and surface; medium & small, white, grey, black (flint), fair amount.
Piercebridge [^{Archie} (461) HS 80/ER 80 4622 14K.] ~~Probably~~ l. facing;
badly eroded IRS. Yellowish-cream fabric, inclusions quartz,
red-brown and black fragments. No trituration grit survives.

IRS

Malton [LSM 69 101 12K] l. facing. Dr. 29cms.
Powdery, cream fabric. Inclusions: moderate not
well-sorted, ^{quartz} some tiny opaque black & rare opaque orange
-brown. Trituration: flint & quartz. No 6 lost to Paul



70 B Container by Norwich

Staxton - pottery Plain + Trojanian
Check whether Cambridge - straps part are used.

Malton [L.S.M. 69. 101. 13 K. L.P. Wenham 1969] (facing with complete
spout. Fine cream fabric heavily tempered with very fine flint & translucent
particles, making surface rough; grey & white flint grit. D = c. 12½ but
difficult. Twice entered

Corbridge [AA⁺xxvi p. 184, no. 28; S. 301; 1906 [28]; 356K] sandy, slightly yellowish, ^{clean} fabric; moderate amount ^{medium} white, grey (flint \approx) grit, including several pieces on head and in groove.

Corbridge [AA⁺xxvi p. 184, no. 28; S. 105; [28]; 357K] sandy, white fabric with sandy surface; large & medium, white + grey flint grit; a little grit on rim. Very similar to 356K but rim slightly flatter.

Staxton, Yorks. [YAJ¹⁹⁵⁷ pt. 154, vol. xxxix, p. 214 f. 12, no. 12; p. 215 + p. 222] M. 15; "dull buff" with slightly yellowish tones; fairly large, white, grey grits.

Malton [AN 3 L 8; Malton M. 3K]. flange frag + bit of spout; fine, brownish clean fabric; in box of samian marked T 37, r. facing

LESBIVS die. which site. Tregear a Nanstallon
Nanstallon die

Tregear, Cornwall [Bodmin M.] VCH. Cornwall p. 5 "probably came

from this site, fig. 4; stamped along; l. facing; slightly sandy,
cream fabric with brownish orange slip (but not sienna), the fabric
is pitted throughout with v. tiny black, white & grey & brown pits
but much more visible on inside than elsewhere; bead
turned out to form spout & ends just peter out; D. = 10 1/2";
die deeply impressed; letters quite clear but rather worn; 23 on
pot. [Arch. J. xlvii p. 232 ^{no. 3} L. Found with coins of Trajan & Vesp.
It. J. of Royal Institute of Cornwall 21890 P.S. A.L. 2uds. 5, 18/3,
p. 487 to check whether mentioned

(See Notebook.)

RESBIVS

Winchester [WP 67 ^{on pot.} 400] Phase 809 Trench 150 level ⁵³

also on pot 15D (53) Creamy brown (?beige) with 1 long streak of white in fabric & traces of another.

Inclusions: frequent, most quartz, mostly tiny to small, 1 or 2 larger; rare red-brown and black had projecting spout. Hit grit: mostly quartz, some opaque grey, rare opaque black and rare red-brown. Dr. c 30 13% Δ l. facing stamped along. 7K

LESBIUS

Colchester [P4121 1.81 A580 Tz 36 S14] stamped along Δ

Dr. 35 cm. Very hard, greyish-white fabric, self-coloured. Fairly frequent tiny quartz inclusions. Trituration; packed tiny quartz and occasional black.

Caistor by Norwich [unpublished D. 44; 40K] drab buff fabric; blackish gilt on
fragment.

Bullington [Site 7206 5K] retrograde. Mrs Hamell,
66, Elizabeth Rd., Tharpe St. Andrews, Norfolk. Information
P. Gurney.



LICINIUS

READING

Catalogue of Museum of London Antiquities. Collected by
Property of CRS. 1854.

POTTERS' MARKS

B2 5000-1000-1000

(1) Wroxeter (2, 3002 f. 3, 59) on Type 58; M118, 42K; slightly sandy creamy fabric with pale buff slip; rather sparse medium and large white, red-brown, and black grit.

LIVIVS

E. Anglian

Caistor by Norwich [D. Atkinson 1961; S. Gale] r. facing; drab
cream. Certainly East Anglian; no gilton fragment.

Diameter roughly 12"

L. ATISIVS SECUNDVS

See ATISIVS SECUNDVS

BRICIRO' (?)

- (1) South Carlton (A. 5 ⁴⁰⁰⁰ 10/44 p135); Balmuiry (pXL, 8); Newstead
fig 35 12 7/8); Rough Castle (Museum Edinburgh)
- (2) Colchester (Museum). EB says another poster.
- (3) Newstead (p. 265 f. 35, 13)

EW, XV 196
Endonwald, Southwell, (from Tmp mound)
Colbridge 2; Chesterholm,

'1st Letter may be B of BRIC. F Widspool; BRCO, sequantium.

L. CALVIVS > IVSTI

cf. CALVIVS > IVSTI, L.

BACAZ-F

~~Bvc(?)vs~~

- ~~(1) J. 2VJVB Springhead (Kent) (A J. /28 p341-2.~~
- ~~(2) BVCCVS(?) Stockstadt; Rottweil (Knoor)~~

LITVGENVS ~~1~~ 1

Chichester [300; 3K r. facing, fine, pale buff fabric;
pinkish core in flange. surface darker buff,
blackened a bit at the flange.

LITVGENVS | + 2 = LITUSEWVS 1

6872

London [1937-87 Guildhall M; 79K] In every way like Venetian fabric stamped diagonal; sandy, greyish

fabric with pink in core in places, and burnt black in parts; surface drab cream, blackened round bead; much of grit worn away in lower half; smallish to tiny, r/b, grey, black grit to top of bead. LITVENT 1

London [1937-62 Guildhall M. 185K] L. facing; ^{fine yellowish cream} smooth, cream fabric; grit gone

save lvs 2 grey & black, probably never much. like 102K GRACILIS. II

London, Southwark [CRS ^{LITVCENT I} p. 89 misread; M2781; Col Ant. i, pl. 50, p. 149;

British M. 108K] St. Thomas St., r. facing; greyish cream fabric, drabish cream fabric surface; grit worn away save lvs 2 red-brown grits.

BF-38. CIL VII, 1331, 6/6 ^{given on w. p. 114}

BM 28 Walters M 278 1-2 / CRS Cat. of Lond. A. p. 16 no. 42; CIL VII, 1334, 29; RTM 10006; W. + C. also no. 66 - LITVGINOS - vicky

LITUGENUS (Large die) ~~III~~ Litigonus ~~II~~ Venulamim - London
LITUGENUS I

Staines [CAD 77 L23 (119) 43K] l-facing. Letters very
sharply & deeply cut. burnt on inside. Granular greyish
cream fabric with good amount of quartz tempering.
Concentric scoring on flange inside at top, worn below,
but ^{2 or 3 frags. only frag.} none on flange. Very little lamination grit survives
mostly ^{q/2 with some e.} v/b + small. Fabric in every way similar to BH/R.
^{30 c.w.s. probably}

Joins flange fragment CAD 77 L23 (118). Dv. $\leq 3 \frac{1}{2}$ cm. S.
^{quartz} Inclusions not really well-sorted i.e. not as well sorted as can be.
^{opaque} Rare large red-brown inclusions.

LITURGICAL 2

STAMPS FROM SCOTLAND.

Trans Glasgow Arch Soc = NS . XIV (1956) p. 56 & Burley
Bochastle [T. Glasgow A.S., N.S. vol. XIV p. 55f; F. 1954. 38; Hunterian

M. 56K] l. facing; stamped twice, close together; buff fabric with thick
red-pink core; BF. 14/18. II

Camelon (5) CAM 76 UR Site A (259) 14K] l. facing, die D. Soft,
actually pale brown brownish-cream fabric (104R 7/6) with thick pink core, inclusions
of tiny quartz, red-brown and soft white chalk? fragments.
Trituration grit flint and quartz. Grit on flange beginning; inside surface UR in normal state. IRS. Inside first 4.5 cms has neither grit nor scoring - only beginning striations

LITVGENUS 2

Chepstow, Bridge St. Emergency work / ^{close to the Wye Bridge} reported to Monmouth Arch. Soc. There is no recorded R. site there. Details sent by David Zenkiewicz including rubbing.

Caerleon ?? (see ^{SW} Colch)

LITVGENUS 2

no there is a ~~condition~~ ~~same~~ ~~potter~~ called
LITVGENUS.

Richborough [ii, p. 96, 2(B); 9K] flange only of c. BF. 18. L-facing;

soft, cream fabric and surface. Illustrated. No A II

Richborough [i, p. 84, 2; 14K] L-facing; cream, hard, smooth fabric with
thin red-pink core; quite a lot, black, white, greyish, largish to
small grit to b. b. not no dating evidence A II

Richborough [iv p. 252 2(B); 86B; 64K] ^{Illustrated.} L-facing; very faint; A
drab cream fabric, soft, fine; tiny, whitish grit to b; c. BF. 14/18

Richborough [iv p. 252, 2(C); 69; 65K] L-facing; thick pink core
changing to cream-buff; BF. 14/18. Described as Flavian; residual B II

Richborough [v 92 Stray; Site Mus. 102K] L-facing; fine, rather yellowish cream,
smooth fabric; much, flint, white + grey, medium to tiny grit to b. b. A II

LITVGENVS ²¹ PTO

Return (Kwarcenka)

Fabric hard + smooth

Circester [CIR 74 H XVI M627 4.5K] l-facing. Spout + flange

Fragment. Exact form indeterminate. ^{quite hard for this sort of fabric}. Fairly frequent v. tiny quartz; ^{red brown} inclusions; random blackish ^{larger} inclusions. ^{possibly with pink in the core}. Spout looks like BF 14-18. ^{fine dark cream fabric}

Circester [CIR 74 MI (67) M 775.46K] l-facing. Fine, yellowish ^{opaque}

cream fabric with scoring inside; opaque quartz + blackish

+ ? flint

git. Dr. 30 cms. Powdery. Similar inclusions to above - ^{background inclusions} unobvious; random ^{opaque} larger black

Circester [CIR 72 A III (21) M 401.57K] l-facing. Yellowish-

cream fabric (10YR 8/4), fine texture, sparse inclusions of quartz

and red-brown fragments. Tituration git quartz and grey

flint.

72 A III 21 (368) LITVSE ? not seen
9! 151

LITVGENVS 2

Amiens (Somme) (Rev. Arch. du Picardie 2006 pt 1-2 p 7 ff)

LITVGEN/IVGIF. Cynot Probably 2 - see Cynilly
Chaidron

Vendevl-Caply (Orse)

LITVGENUS 2

Coldwater M. [508.57; 282K] in 2 pieces; core of flange & inside half of body pink; flange surfaces and outside half of body cream; moderate, medium & small black, white, red-brown grits to b. of b; possibly milling l-facing. D = $10\frac{3}{4}$ - $10\frac{1}{2}$ internally. Much grit on top of flange; huge flat rim. II


Silchester [May pl. lxxxiii A, no. 28 + p. 248; 34K] 1905. Pit 1. cream buff fabric; whole D = $13\frac{3}{10}$; much, small & medium, grey grit (flint like, some worn away) to bead, + on flange which is rilled; probably scored internally, BF 14/18 downcurved; l-facing; 1 stamp only on whole mortar. II

Richborough [V. Area XVIII; N. of Platform; pebble layer; 87 + 88; Silē M. 112K] l-facing; flange & bead only; fine, smooth, cream fabric; a few grits in fabric. B. F. 14/18 C II

LITVGENVS
I. FECT

282K Colchester M 15

Fishbourne, [67/3.49 ③ 11.88. 4K] L. facing. Clay has sandy particles in it but probably natural; very fine-textured, very slightly brownish cream (or buff-cream) with pink core in flange & bead area; a few grey flint grits or fragments which has only small triangle of inner surface; a few grits on top of flange, mostly flint. Stamp worn smooth. Small surface area of flange is pink at surface. B.F. 14/18. Almost impossible to draw correctly. A not reliable



Fishbourne [FB.64/203 (14) 949] 5K. l-facing. Fine-textured, very porous porous yellowish-cream fabric containing nothing more than sandy particles probably natural to the clay. Concentric internal scoring & grey probably all flint small to medium grit - mostly smallish. Some fallen out. Grit only survives in fair quantity below bead although not much sign of heavy wear. The flange only survives in part area & is here clear of grit but a bit flaked off at outer edge shows heavy deposit of flint grit underneath, also small hole in surface shows flint beneath. Evidence that surfaces were gritted before the spout & stamp were added. It would help to key the spout.

~~Chichester [300; 3K] f. facing; fine, pale buff fabric; pinkish core in
flange; surface darker buff, blackened a bit on flange.~~ I

Doncaster, High Street opp. Campbells 1960 [Doncaster M. 65K] l. facing;
fine, yellowish cream fabric; grey & white small grit to b. b.
- few survive; few on flange of fragment; stamp poorly
impressed, some slight damage; (fabric is distinctly yellowish
& different from that of PRASSO & LOSSA). II

Silchester [May Pl. LXXXIII A, no. 7 + p. 275; Reading M] 40K; Bushe-Fox 14/18;
fine buff fabric; flint grit. II

LITVGENVS 2

Gambier Farm Lodge, Gloucester [C.H.A.T. 9/83 W (28) 269 .27k] Die E

r. facing. Hard brownish-cream fabric with pinkish core,
inclusions tiny quartz, red-brown and black fragments
with rare chalk fragments. Titration grit fine (1mm) flint
and quartz. Worn. Concentric scoring. G. 238 curved.

LITVGENVS 2

No A3

Colchester [P5642 1.81 B1390 S1 (TZ) in Symonds + Wade p. 197] Die B
L. facing. Fig. 4.5, TZ 82.

Colchester [P3161 1.81 E494 S2 (TZ)] Die E L. facing. G. 238
Fig. 4.7, no. 101. Symonds + Wade.

Colchester [P5641 1.81 D280 S3 (TZ)] Die D L. facing G. 238
Fig. 4.5, no. 87


Chelmsford, [Rochford Road CH: D. 70; 104 X 34 E (7)] Fine-textured,
cream fabric perhaps with slightly brownish cream core; tempered with
very fine sandy & transparent & ? flint fragments; grit worn in
bottom of vessel; moderate amount elsewhere; grey & white flint mostly,
but occasional translucent pinkish grits. Dr. = 11 1/2" (occasional black
grit (? translucent). Perhaps made at Colchester. Very clear
lettering; stamped on each side of spout; spout not early looking.
? early second century.





no facing

LoBBGB-2T(2)S) - Really VIATOR


~~Cambridge [AA⁴ XXVI p. 182, no. 26, S 98; 115K] r facing; gritty buff fabric
with grey core in places; medium to large, grey grit; orange buff surface.
(Die as 365K Cambridge.)~~


Manduesedum [1964. w① 11 ] stamp painted dark brown; creamy white fabric, containing tiny particles of r/b grit; buff slip. DIE B1Δ

Manduesedum [1964. w① 9. ] section incomplete. Cream fabric, containing tiny particles of grit; brown grit. DIE ?

Manduesedum [1964 w① 4 ] cream fabric, buff slip. No rubbing. DIE ?

Manduesedum [1964. w② 1 ] section incomplete. Cream fabric; buff slip. DIE B1

Manduesedum [1964 w③ 10 ] Cream fabric containing tiny particles; buff slip; stamp faint. dubit! CHECK

Manduesedum [w③ 10 ] l-fang. Cream fabric; slip discoloured; dark grit; DIE ?

check

Thottleton, Rutland (Black Horse; sent Jan. 1964. 357 BH 1620 M. 16.]

Hard, pale buff fabric containing fragmented brown and whitish grits;
flange fragment. where is the rubbing,

Watercreek [1975 BCT + BBI 13 Stratified layer in the guard-chamber at the north gate. "fairly smooth cream fabric + has ^{only the stamp remaining} red-brown grits. Almost complete. no rubbing r. facing.

Potter, "Romans in North-West England" 254, no. 226 + fig. 106.

Ribchester Bathhouse [RIB 78. BH II. 211. 53K] r. facing; frag. stamp

hard, cream fabric with quite a lot of quartz inclusions; occasional black inclusions; 3 dk grey Intercalar grits: small bit ^{Dr.} c 40 cm.

DIE?

LOCCI PRO
✓ Recount^h c 158. Pre 140 ... or after 158

Bennell (Depth Arch., Durham, B'n l. 38 A1). L-facing. No

rubbing but stamp reads [LOCCI]. Seen BRH 1968. B1

Leicester [LP 31.9 135K] fragment. Hard cream fabric with slightly darker surface. not drawable. DIE?

Littlechester [Rubbing 1969. M. Brassington. 25K]. Derby

Racecourse. DIE B1

Lynch Farm² (Piton Longueville) S.P. wild LFC 72 Lc 2 (73) 1K]

fragment of ~~hard~~ cream fabric with brown surfaces. 1 white + grey ^{SE} ~~at~~ a head. (+) General area. 60g ↓ L-facing DIE B1

Hard, ~~virtually~~ ^{See} ~~pale brown~~ fabric with white core of no brown slip. Inclusions, moderate, tiny to medium-sized, mostly quartz

P TO

Some tiny red brown & rare black material. No inside surface survives, but two or three grits which have stayed onto the head are of hard black material.
Hard, white fabric, fused to buff colour near parts of the surface. The surface is pale brown. Pity broken at top inside because some indication that surface would be darker brown before break. This could link it with Sumilis 3K as an LNV product but too little evidence for certainty. Cannot be certain that surface brown is slip rather than it being fused with colour but as it is, it is a very unusual fabric surface for Mancetter II.

Balmuildy [Macdonald p. 456.
p. 78; pl. xl. nos. 9 & 10; Hunterian M. 1K; F. 1922. 304] ^{DIEBI} facing;

hard, buff fabric with slight pinkish tinge; ~~fine~~, few, black grits to b. b.

Balmuildy [p. 78; pl. xl. nos. 9 & 10; Hunterian M. 2K; F. 1922. 305] L. facing; flange fragment; fairly similar to no. 1K; hard, buff fabric, orange buff near surface; surface appears burnt to dark grey in parts. ^{DIEBI}

Balmuildy [p. 78, pl. xl. nos. 9 & 10; Hunterian M. 3K; F. 1922. 307] flange & bead; fine, smooth, creamy buff fabric; hole drilled in it; stamped twice ^{DIE?}

Balmuildy [p. 78, pl. xl. nos. 9 & 10; Hunterian M. 4K; F. 1922. 306] L. facing; stamped twice; smooth, fine, cream fabric with greenish grey surface; two black grits on fragment; very like no. 1K. ^{DIE A1}

Newstead [VII.15.76; FRA 1484; NMA.103K; p.266, Fig. 35, not published]

Flange broken; hard, smooth, fine, cream fabric with cream slip; brown
+ black grit. sketch. DIE B1

Burien [1962 (148) + (163) joining. Hunterian M] fine
cream fabric containing some v. fine grit. Softish. DIE ?

Strageath [80 E-II ① 9K] Flange fragment. Cream fabric. sketch.

Old Kilpatrick [Macdonald p. 456. DIE B1
p. 42, B7 + p. 42; F. 1928. 309; OK. 1900 XC; Hunterian M. 37K]

r. facing; hard, compact, cream fabric with drab cream slip; much, hard, dark brown grit; largish to medium; less neaver to b. b; stamp painted with with darkish brown (not red-brown) paint; very close to no. 1K

Bar Hill [Macdonald p. 456 DIE B1
F. 1936. 477; Hunterian M. 63K] fragment; fairly near 1K

Hunterian but broken & head gone; cream fabric with pale grey cone

Rough Castle [unregistered. NMA. 38K] flange fragment; hard, creamy white fabric. DIE ?

Mumills [Macdonald p. 456; p. 52 & ; 91.2; 1930. 217; NMA. 89K]

hard, white fabric with tiny grits in it; no internal grit; bead & flange only; cream slip?; dark number paint over stamp. Shrivich FRB 169 DIE B1

IUNIVS LOCCIVS/LOCCIVS PRO —

Hand,

Alabaster [G.V. (5) .65. 35K] / Fine-textured white fabric with cream

think quartz.

slip. ~~Poros~~ $\frac{1}{4}$ r/b. Burnt throughout in part, probably ^{before} ~~after~~ fracture.

~~0 = $\frac{1}{4}$ r/b~~
^{4/1000}

very moderate a few qtz and rare r/b inclusions DIE ?

LOCCIVS PROBL]

Wallend [Swan Hunter WSP603 9900 52K] assumed from
 position to be r-facing. ~~Wt~~ 210gm. Diam. 31cm 18%
 Very hard, cream fabric with s.c slip fired to ~~off~~ yellow cream
 only c 1st 2nd at bead covered. Inclusions: Inclusions: moderate
 tiny to small, ill-sorted mostly quartz (transp. + pinkish), red-brn
 opaque and rare black. Intertaxation: red-brn, mixed tiny
 to med, few up to bead. Some wear at bottom of sherd
 but slip not entirely worn through there.

WACCUS PRO

Healam Bridge [M109 Context 5028 6K] Flange fragment,

Hard, cream fabric with darker, ^{heavy in weight} cream slip. Inclusions:
~~fairly frequent~~
~~moderate~~, random, ill-sorted quartz probably mostly;
black; red-brown rare. Dr. 310 8.5% Top of [] [] []
~~fragments of ss in fabric & 2 cm long in fabric.~~

LOCCIVS PRO

✓
Aldbrough [PK in pub.] hard, orangy buff; no grit left. DIE ?

Sawtry, ^{Camples} Hunts [St. Ives Mus. AJ. xx, 506; 2026] light buff, almost white fabric with iron staining; red-brown + black grit; l. facing. DIE A1

✓
Kenchester [Jack, Woolhope Field Club Trans. 1912-3 p. 231 + pl. 38 no 2; JK, Hereford M.]; Rather coarse, pinkish cream fabric with tiny, brownish + black fragments in frag fabric; stamps only, painted r / brown. DIE ?

South Shields [AA² Z p. 274 no. 25] stamp now missing

✓
Binchester [Hoopell Collⁿ. E. B. rubbing with Parbridge Locc II. Arch. J. xxxv, p. 293/4 Locc I in spot of a mortar (Hoopell's Park). DIE ?

Binchester [... + ...] ... with ... Locc II

Handwritten text in a decorative, stylized font, possibly a name or title, enclosed in a dashed rectangular border. The text is mirrored across a central horizontal line.



Handwritten text in a decorative, stylized font, possibly a name or title, enclosed in a dashed rectangular border. The text is mirrored across a central horizontal line.



Handwritten text, possibly a signature or name, located at the bottom left of the page.

Handwritten text, possibly a signature or name, located at the bottom right of the page.

Q B 49+

Ribchester [RIB 77 BC ~~£3~~ 32K] presumed l. facing creamy white fabric with ^{a moderate amount of} light v/b tempering; creamy buff slip; dark brown (hard) interstitial grit. Well-worn. Dr. = 48.5 cm. DIE?

Ambleside [Now in Kendal Mus. 16K] Soft, fine-textured, orange-brown fabric with cream slip. Glaze frequent only. Willerspool thought to be most likely source. ^{Probably different clay??} MADE IN NORTHERN ENGLAND? DIE?

Chedworth, Glos. [R. Goodburn 1987 Sept.] ^{Q1} with red-brown ^{Q2} ^{and orange brown} ^{l. fac assumed.} ^{Worn: Dr. 34 cm.} ^{black with dark red centres, v. rare quartz.} ^{moderate, ill-s. inclusions: quartz}
 Paint over stamp. Fine-textured cream fabric. Moderate, ill-s. inclusions: quartz.

South Shields [Yue + Wear. Arbeia Roman Fort & Museum

SS. 70 AT + AC + AA Q1K.] L-facing. Heavily worn. Dr. 36 cm.
 (8 sheds) (1) (1 shed.) Hard, white cream (10YR 8/2) fairly fine

Textured; moderate, mostly small-sized & well dispersed, quartz, & opaque red-brown.
Tinturation: all hard red-brown, vari-sized; very heavily worn indeed.

(rare black inclusions; some dark brown streaks in fabric.)

S. Shields: Bidwell and Speak 1994 See report

LOCCIUS PRO

Alcester, Works [ALC 69 (86) S. Taylor, Bleachfield St. Baranix Firm

50K] Dr. 46/47. Stamped 3 times close together; hard, fine-textured creamy white with few tiny quartz + red-brown inclusions; Dark brown turturatum gut; some wear. DIE B1 Δ

keicester, Causeway Lane [A1.1991.1770 3 (498). M04 but no

turturatum surviving. K] Flange fragment. Cream fabric with slightly darker surface, probably a self-coloured slip. Inclusions: moderate, red-brown and quartz inclusions medium to small sized. Die not identifiable. DIE NOT IDENTIFIABLE

keicester [A77.1975.5513 I u/s (779) 276K] Flange fragment. Hard, cream fabric inclusions: moderate, ill-sorted, mostly quartz, rare red-brown. ? cream slip: slightly singed. B2

Shenstone [B.A.S. XIII p. 28, pl. VII b; no. 7; 33 + 5 (with stamp)]

joined. S. XV Oct. 1930 S] D=17" Cream fabric + slip; red-brown paint on stamp; brown and dark brown with red centres; 1 or 2 grey grits. A

Leicester [380.1957. Leicester M. 121K] Hard, white fabric; surface burnt inside; Hatshill-Mandueseden fabric + grit. Much dark brown, medium to small grit; r. facing.

DIE B1

Ambleside [not published. Armitth library 16K] flange fragment; buff


Ribchester [Information ^{burnt. fragment.} Felicity Pearce - no rubbing] 52/3 Hard cream fabric;

DIE ?

Wall [R/2 40K] tiny flange fragment in cream fabric. L without second bar.

DIE A1

LOCUS PRO

Osleshill [9K  +] r. facing. cream fabric with
black lamination. DIE B1

Winterton [RW | CH 19K] r. facing. burnt before and after fracture
as it survives. Grit worn away in bottom. Almost 1/2 surviving
Dr. 29cms. Creamy white fabric. Inclusions: moderate to
fairly frequent pinkish quartz small; few ill-sorted orange-
brown sometimes larger. Lamination grit: mostly red-brown,
New blackish 1? sandstone. Might have self coloured slip.

Chedworth [CH 87DW Room 5 channel L. In ? pit pre-dating
pier G.] probably l. facing Dr. 35cms. Hard creamy white
Inclusions: moderate to FF transparent and wavy pinkish quartz
rare opaque v/b + blk. Tiny to medium sized; lamination: black + red-brown
? wear and possible s.c. Red-b. paint on the stamp.

LOCC: PRO

62K
55K

Lincoln (East Bight. EB49 ⑪ v/s ⑫) [Flange broken. Fine creamy white fabric tempered with a little v/b + qty grit; buff-wear slip. Hard v/b. tubular in grit. Must have had two feet on L note in surface ~~concentration~~ has removed real foot. DIE B1

Carlisle [CAR 81 Cst. B ⑤32] P 2088 118K [retro: L. fac. fairly certain

fabric not noted.

Seen 6.2.1993.

Kinton Lindsey villa 2 [Fieldwalking site. Ben Whitwell 1K] hard (33.2) cream fabric; moderate, all sorted but rarely large inclusions; quartz, sometimes brown stained; opaque orange-brown; rare black material. No tubular survives. Dr. 32cms. Surface smooth. Probably S-C. without a slip.

Dragonby, Humberside [526] DR 71 AGL 5K] l. fac. Fine-textured,

cream fabric, with fairly frequent, ill-sorted, quartz inclusions,
pinkish ^{quartz} red-brown inclusions. Titration: included

dark brown titration qt. s. Dr. 26 No stratigraphy. Die 1 ^{P TO} Δ

York [1989.21. 2318; 2388; 2342 SM 25 122K] 14 sherds ^{not all} jg.

l. fac. Cream fabric. Inclusions: frequent, ill-sorted,
transparent + pinkish quartz, orange-brown ss., tawny black

? iron slag. Titration: red-brown material with few black
mixed in. Dr. 24 cms. well-worn. c. 1/2 d. inclusions Die 1

Spout Type 4a. 2388 in Context ^{AD} 160 + 2318 in context
AD 140 + + 2342 in Context dated AD 170 +

Not-published.

Bainesse [46-2067 (231) 17K] FF. Hard, fine-textured cream fabric with ~~pinkish~~^{buff} core; some quartz and red-brown inclusions looks like a buff slip. Dr. 150-165/170

Bainesse [46-1819 (217) 18K] FF. Fine-textured cream fabric with some tiny ^{white} quartz & crystalline pink quartz inclusions. Fabric is slightly different from 17K & its likely to be from a different vessel. Buff slip.

LOCCVS

B + C

B₂ G₂ 140-200 }
Midlands }

2

~~In Wall Museum. Not seen.~~

Sheenstone [Beim. AS. lxiii, Pl. VII no 8 on rim I] hard cream, brown grit. Diameter

15" ~~Fragment of 11. used at ... ? ... stamped twice together.~~

Tiddington [Sharnford Mus. 9K L. 1209. May p. 65 no 19] ; "hard, sandy, pipeclay", smooth, fair amount
hard black flint and few white or orange-brown grits, medium sized. ^{Fab 8 (PB) No 17} _{Toul. 7.9. A. 26.1}

Watercrock [B₂ C + W. XLV p. 161 f. 5. 181 V 1)) 0

Stanground, nr. Whittlesea [1956 Standen] greyish white fabric, coarse in texture with small particles of grit inside the fabric. Grit brown (iron stain) and white (? quartz) and widely dispersed on fragment.


[B₂ G₂ Fabric - cream with ... large sparse bright ... begins well below head; covered with white slip but some die

8




Shenstone

(1)



SHENSTONE.
(1/4)



Stanground, Leicestershire
(1/4)

? LOCCIVS ~~HELVIS~~ VIBO

? DIE 4

Mancetter-Hartshill. (2) W 71 (22) 58 [655] r. fac. CRS.

(1) W 71 (22) 76

FF.



break

① W71 (22) 76

DIE
4?




② W71 (22) 58 r. fac
DIE 4?

LOCUS VIBO

+

Heister [A78 . 1975 . 2332 ∇ v/s SA 277K] ? L. facing . IRS
sl. micaceous

hard, fine textured cream fabric. Inclusions: moderate, isolated
quartz, some black streaky/staining in fabric. Inturation:
mostly red-brown, some blackish. Dr. c 21 self-colored. Dr 20 ^{d. 4} _{ans.}



Little Chester [M. Brassington 24K. 1969. Rubbing sent.] Derby Racecourse.

Cirencester [CIR 61 ^{M112} ~~III~~ ① 31K] 3 stamps impressed close together on broken flange & bead frag. Hard almost pale brownish fabric tempered with grey to white grit; brownish pinkish slip. Unusual. Flange broken Dr. 23

Castleford [Phase III ^{no 39 /} SS XI 74. Probable date of Phase XI) 100-140, my number (27). 27K] 2 fragments from a mortarium in hard, cream fabric tempered with fine grit, and with a yellowish buff slip. Inclusions: fairly frequent, not well-sorted, a mostly quartz including pinkish quartz, some opaque red-brown rare black & perhaps rare sandstone. B3.1/2. Dr. ?36.

LOCCIVS ~~VI~~ VIBO ✓

Corbridge [AA⁴ XVI p. 182 no. 27; US. 24; ND/1914; ③ d./XII, 47; 27; 176K]

cream fabric with buff surface; large to smallish, red-brown, angular grit
to c. 1/2 in. b.b.b.

Berleswell [Corstopitum M. in 1964 VC]

Corbridge [Site M. VQ * . 402K] fragmentary: old find.

Hard, cream fabric.

York [BC/64 - P. Wenham MK] ^{NOT BLOSSOM ST} l. facing. Fine textured, creamy
white fabric with ^{buff} cream tinge; red-brown + dark brown or grey
grits some with red centres - large to medium; very finely broken
grit in fabric which is very slightly micaceous. D = c. 15"

Reportedly 3 different varieties York. Checked ✓ LOCCIVS VIBO

LOCCIVS ~~11-31~~ VIBO

✓
Heicester [A7. 1975. ⁵⁴⁸⁶ (352) 174K] ^{Probably r. facing.} Hard, cream fabric; ^{ill-sorted} ^{fairly frequent} tempering mostly quartz ^{v/s} some v/b + blackish. Probably self-colored but surface buff. Tituration: ^{Mixed;} ^{some} brown sandstone a ~~little~~ quartz, ^{d. 1-1} red-brown ~~some~~ blackish slaggy grit. Pr. 35 cm. Δ

~~Barnsley Park [BP 158 + 2K] (3135) Flange frag. creamy white fabric; stamped ~~with~~ brown paint on stamps. ^{probably} ^{character}~~

Colbridge [80 FX 227 77 in pencil 4 ^{+ black} 15K] v. hard, fine-text; creamy ~~white~~ fabric with fine quartz & ool v/b inclusions, sl. darker surface. Probably l. facing. Blackish tituration A 10YR 8/3 2 (white). Dr. 32 cm

LOCCIVS ?? N13 B₂ notes that some of the Locci's work
are in red fabric with white slip but linked by same die.

Corbridge [AA⁴ xxvi p. 182 no. 27; S. 29 ③ h/xii, 47; [27]; 177K] flange fragment.

compact cream-buff fabric and surface; horizontal grainy marks in stamp; Type as
176K so far as can be judged.

Corbridge [AA⁴ xxvi p. 182 no. 27; S. 3; ③ i/xii, 47; [27]; 178K] fragment of flange

very slightly sandy, drab, creamy buff fabric; shape apparently as 177K.

Corbridge [AA⁴ xxvi p. 182 no. 27; S. 4; ③ e/xii, 47; [27]; 179K] fabric as 177K

1 black grit in stamp.

Corbridge [AA⁴ xxvi p. 182, no. 27; ③ g/xii, 47; [27]; 180K] slightly sandy, cream
fabric with tiny bits of grit in it; few black grits. Type as 27C but smaller.

Corbridge [AA⁴ xxvi p. 182, no. 27; S. 320 ③ f/xii, 47; 181K; [27]] v. facing;
could be part of 179K but fabric heavier than ink; white fabric; many blk. grits, small to b.b. D = 11 in.

LOCCIVS

Corbridge [AA^{xvi} p. 182, no. 27; S 311, 27; 182K] r-facing; hard,

fairly smooth, cream fabric; Type as 27C. D = 9 3/4 ins.

Yorkshire Mus. [49K] white pipeclay; abundant angular red-brown & some brown ^{grey} white grits. no record of provenance

High Cross [Chance find in Road works. J. Pickering, 1958; sketch, rubbing, description. G.W.] "cream fabric; big black grits". ^{Disc on 1/2 in. dia.}

Margidunum [AS. xxiv p. 58, no. 45 & fig. 5, no. 45; 26K] l-facing.

hard, fine, cream fabric; drab cream slip; 1 dark brown grit

York, Blossom St. [M. 1/54; 64K] l-facing. Hard, cream fabric with buff slip;

surface discoloured by fire; abundant, red-brown & dark-brown, medium to small, trituration grit; D = 13".

KOCCUS VIBRUS
VIBO

Hartshill [VCH Works I p. 246 'VD10'] lost

Leicester [287.1975 I (128) 208K] r-facing; $\frac{1}{2}$ spt but end broken; hard,
fine-t., cream fabric with fair amount quartz, blk. + occasional r/b
inclusions; no trituration survives. Dr. 33cms. d. 2

York, Bedern [73.13.1706 (95~~4~~)] R. Perrin. IRS. Burnt. Paint
(tan-coloured) on top of stamp. hard cream fabric with r/b + a little
quartz inclusions; r/b trituration.

Tiddington [T179 no. 170 stamp no. 19] 2K. l-facing. Cream fabric
inclusions quartz, red and red-brown fragments. Trituration
quartz and dark grey and occasional red-brown fragments.
Dr. 25cms.

hester, Causewayhane [A1.1991.17716 (1088) M04]

r. fac assumed. Upper surface pitted + stamp damaged. Fine textured, cream fabric, slightly micaceous. Inclusions: moderate, quartz, rare black. Trituration: Blackish, rarely with red in them; ^{v.} rare quartz. Dr. 28cms. Die 5?

hester, Causewayhane [A1.1991.17728.1 (3908) M019.]

stamped twice close together. ? r. fac. Dr. 44cms. Very hard, pale brownish cream fabric with paler core. In body grey in core. Very hard fired. Inclusions: more than moderate tiny quartz, sparse larger quartz, red-brown + blackish. Sl. darker slip Black grit. (This is the newer fired type of fabric). Die 2

ASSIGNED. COCCUS VIBO

✓
Leicester [A14.1992 (324) 278K] L. facing. IRS. Die 2
Paint overstamp

Very hard, cream fabric. Inclusions: fairly frequent, mostly quartz
including pinkish. Rare red-brown & black. No inclusions survives

2781haverley A-14-1992

327#

1 jar
Banded



die 2
locus
Vibro
NOT
Ident.

LOCCIVS VIBLVS - LOCCIVS

BARNSEY PARK, ^{? why VISO}

~~YORK [BP (158) + 3135 185k] Flange fragment. Stamped~~

~~twice close together, ^{ochre} orange-brown slip just over the stamp.
Hard, cream fabric, moderate inclusions [fairly fine mostly
quartz, sparse blackish fragments. No trituration grit survives. Dv. ≈ 36~~

YORK [Rougier St (formerly Tanner Row) 1981. [1240] 101K] M/H.

YORK [As above 1981. [1205] 102K] M/H. Different vessel.


Barnsley Park [BP 158 + 3135, 2K] Flange fragment.

Stamped twice close together; ochre-brown slip just over stamps. Fine-textured, cream fabric, v. slightly powdery. moderate to fairly frequent inclusions, ill-sorted, tiny to small, mostly quartz, rare orange brown and black material.

Dr. \approx 36 cms.

Die 1

Ancaster [Z169 C 7K] Flange fragment. Hard, fine-textured cream fabric, self-coloured or s.c slip. Broken stamp. Inclusions: moderate, transparent quartz with grey quartz & flint & rare red-brown material.



R.V.(E) - Mid.
? LOCCIUS VIBIVS

25K

? DIE 5 LOCCIUS
VIBO

Ribchester [R70 367] flange fragment in pie cream fabric with tiny grit in it,
including fine transparent particles

Ribchester [RBG80 Context 019 GF. 3-37. 77K] FF.
hard cream fabric, may have had self-colored slip.
Inclusions: moderate, rounded, ~~the~~sonor well-sorted,
mostly quartz, rare natural orange compounds, rare red-
brown (1 large), rare tiny black. Dr. c. 27cms.



Ribchester 703(67)



hi
77K Ribchester RBG 80
019

Ardoch [AA⁺ XXVI p. 182, no. 27; NMA. 8K unregistered] flange broken; very creamy pink fabric with buff slip; moderate, largish to small, hard, red-brown grit; di

Inveresk [both stamps very fragmentary; NMA. FR 102; 165K] rivetted & burnt; hard, cream fabric; black grit with brown centres; medium to large; attribution fairly certain di

Camelon [CAM 75 AA (78) Site A Topsoil ^{27K} +] Soft, fine-textured cream fabric with few quartz inclusions; Tituration grit. includes v/b & blackish. Dr. 29cws. Die 2

LOCCIUS VIBIOSO

SCOTLAND

Carzield [Dumfriess M.] Brown paint on stamp. Die 2

NMA FR 728

~~Attributed to~~ [✓] Loccius Vibius.

LOCCIUS VIBO

B
LOCCIV (vet) · C
LOCCIVIBI (vet)

Ardoch [NMA no. no. B. AA⁴ xxvi p. 182 no 27];

Ardoch [NMA no. no. C. AA⁴ xxvi p. 182 no 27];

NOT seen

Corbridge [AA⁴ xxvi p. 182 no 27] ^{S 3, S 2 A, S 3 11, S 3 20, US 4} AA⁴ xv, 274-275 (fig 4 no 4) ^B hard cream ware
with dark specks in it

Corbridge [AA⁴ xxvi ^{US 24} p. 182 no 27] ^{C.}

Margidunum [AS 1944 fs. no 45]



1/11/01
1/11/01

27c. Corbridge (2)

AA^o 1001, 1112



1/11/01

27c. Corbridge

02



Margidunum ⁴⁵⁰
45 (1)

LOSS A (A Gallo-Belgic potter of this name) ^{Re. 15}
^{Circ. with}

Cirencester (CIR 61; K. I. 15); 11 pieces; 21K] L-facing; fine, cream

fabric; internal scoring; abundant small stray grey
(probably flint) grit; similar grit on flange, stamp worn.
D = 16mm; fabric very similar to that of FRASSO.

York [54K Yorkshire Mus.] fine, cream fabric + grey flint grit.

B-F 14/18. Surely the same potter but a different die.

CIL VII, 1331, 133

CI 18 61
KI 15
Young Press

Chandala




Jan

0

WSSA

Noyon (Dise.)




LOTTIUS

Cambridge [R.G.S. IV 11j 14K] stamped each side, ~~probably~~
letters in centre with unusually large herringbone borders
above & below. ^{Hand} Cream-buff fabric with light, muddy grey
core + ~~buff brown~~ slip. Coarsened by addition of much
quartz pebble + probably other material. Very worn. Dn. c. 27cm
Fabric likely to be upper Nene valley, Interpretation:
~~Some wear but not cold~~ E. Midlands Cambs?

?130-170

Buff-cream slip fired to almost orange-
brown on parts of the feet. Heavily worn (note to
Jerry March
Phil 2012)

0
L-4/1



LOTTINS?

Bourne, lines. [B.M.D 94 (56) joins B.M.D 94.206 (3 going fragments)]

Dr. 27 cms. Drab buff-cream, greyish in core. Inclusions:
fairly frequent but not as packed as they can be in Ver.
fabric. Ill-sorted, mostly ^{transparent} quartz, some opaque black? slag
rare orange-brown. Interstices: only are a few grains
siliceous - red-brown, grey ^{black} & white. Quite well worn.
Probably had a buff-cream slip which is worn away
1.5 cms below top of bead.

letter 28.11.94




Boume H A C
56 + 206

Duplicate entries

Bourne [sent by M. Darling. BMD 94 ¹(56) + 2³06 IK] 4 joining

sherds. Dr 27 cms 1 tiny sherd not joining. Drab creamy buff fabric with pale grey core. Inclusions: frequent not v. well sorted and not as packed as usual in Venetan fabric. By far most are quartz, but more black (opaque) than usual, rare orange-brown. There may be more black because of it being latic? Could have a buff slip. Intuition: only few fragments survive, included flint, ^{slip?} red-brown + black. Worn. Both stamps survive.



Q. LUCILIVS CRESCENS

Vindolamium [55 A.I. 7/8 241K] Fine-textured yellowish cream fabric
tempered with grit (white is noticeable) but some grey also; abundant medium
and small sized grit, grey, white, r/b; t.b. b. Probably iron pyrites
in fabric.

see Wilhelm Schulze, CIL XI, 3664

Zur Geschichte Lateinischer Eigennamen ¹⁹⁶⁶ 441-_{p. 442}. LUCILIVS likely.

0

941K Venlamin 55 A.I. 718

LV9VD


Brockley Hill [184K BH 72 BT1 (2a) M52] Flange fragment.

In grey cream granular fabric. Faint cracks. Diagonal stamps.

Castle 1973, London Arch 2, pl 2, p 36-39

LVGVD

Old Winterringham, Lincs [ES/H.G. 1964 3K] flange
fragment. stamp diagonal. right facing. Whole of
stamp should be impressed. Flange heavily quilted with
dark grey & white flint, and red-brown grit, & some
small transparent grits. Hard cream fabric with pinkish
core. The fabric would be fairly fine textured if it did not
contain large amount of tiny grit. Normal Ver. fabric. Δ



Diagonal
Old Wintourgham, Virginia.

LUGVD

Venclanium [no. no. D.110. P.C. 13K] gummy drab Fabric.

Exeter [MM 71 2DD L (44) A 1K.] Frange fragment burnt
black throughout. Stamped diagonally along the flange [V]
Die as above ^{p 195 Bidwell 19707 Pd (A) Construction $\leq 80-85$} + 69K London. fig 60, no 24 and p 198. Δ

Usk [see Catalogue Drawing no. 10638. 6 pieces ^{U74 LAJ 10/31}, 2 of them joining]

Granular, very thick blue-black core changing to pink near surface
which is creamy buff; packed with moderately well-sorted quartz
conc. scum on flange & inside; moderate wearaly. flint & quartz ^{intra}
stamped diagonally. Dr. 37cm 19K. Fortress 55-75

LVGD

Check ~~for A-B-C-D-E~~

Big 34 not head but in curved flange.

London, Cheapside, nr. G.P.O. [A.102.03 London Mus. 9K] stamped

diagonally each side; sandy buff fabric with pink core; cream dr buff slip; black, grey & brown grit; scoring on flange & on inside; heavy wear; D = c. 1.4"; BF. 24/38; no sign of F. BH/R → L

^{BE/E}
London [Guildhall M; 1937.112; 69K] sandy greyish white fabric; surface cream, red-buff to dark grey; scoring on flange & small & smallest white & grey grits on it; flange & bead only; stamped diagonally; r. facing. A) 65-95

London [City, Roodst.]; A. 227; Marsden Coln 8K; stamped diagonally; flange & bead. 309K

L.VGVD (or London, Chesapeake 9K Eon. II.)

TR 32458105

10-15 Queen St;

London (E.R. 642; from Roman Barrel Well, Alderman^{antony}
Context slightly ambiguous, but mid first
century.

House; 19th. Sept. 60 Pottery removed by workmen - Box 2

Guildhall M. 282 K] l-facing; diagonally stamped;
slightly sandy, creamy fabric; flint grit; tiny & ~~small~~
~~medium~~ small flint grit; slight scoring on flange;

London [St. Swithin's House D. 301K] r-facing diagonal.

Cream fabric, greyish cream slip. early. A

London [SHWD. Diagonal stamp. r-facing. 304K

G.H. Hard, coarsish cream fabric; grit on flange.

LVGVD.

keiserer [3279.1887, St. Martins. 40K] hard, sandy buff; sparse

black and white grit; internal scoring. Find out whether
across along, diagonal

LV9VDN
No 1, Poultry, London [ONE 94 Context 15508 Mus. Acc. no 4630-^{443K}]
stamped along
L-facing 730g. Dr. 36.5cm. 42% + 18.5%, not joining.
Several pieces all with modern breaks (42%); several other
joining sheets (18.5%) all with modern breaks. Greyish-cream
fabric and cream slip. Abundant, milky and transparent quartz
with rare opaque orange-brown inclusion. The inside is
too heavily worn up to 2cm below 6- σ /6 and stained ^{in part} with
? iron oxides. Interstition grit mostly flint with few quartz
grits. The flange has had concentric scoring and is covered
with mostly flint + some quartz grit. The stamp was
impressed before the grit was applied. Extra clay for slip
was applied after the getting of the whole rim.

LVGV DV - without any other stamp. Different

Dies on separate cards.

London [R. XI. 619; Guildhall M.; 196K] mortarium entire & only stamp

on it on l. side, stamped along; sandy, greyish fabric; internal
prolific v/b, white, grey, black, large to small gnt b.c. $\frac{1}{2}$ b.b.b.,
some also on flange; scoring on flange only; D = $14\frac{3}{10}$; BF 34

LVGV DV FACTVS

Counterstamp of RIPAVVS TIBER F.

MCV

London (BIM no. 14 CRS);

LVNAVCH 15?

see R P Wright - LVNARIS
file pers. comm.

Caistor St. Edmunds [unpublished. D47; 14K Norwich M.]


greyish-cream fabric, almost greenish, with a cream surface;
moderate, medium, black, red, grey, white gut to bottom
of bead with strays on bead.

Caistor St. Edmunds [information letter Tony Gregory 20.8.84]

Site 9791/C1. Field immediately east of the Roman town at
Caistor St. Edmunds in an area of 1-4th-century occupation.

Die as above. These 2 m. need checking
Gayton. (3743 SMR^{TF} 7360 1790 in side of field dyke
inf. M de Boorman. LVNAVCH retr.)

Kingshynn Mus. Reading indicates small die.



19K5 D#7 Carston 1/16

1

LVNAVCS?

Ellingham, Norfolk.

LVRIPRO CRESCES. L. LUVIUS PROCVLUS
CRESCENS.

Italy

Abano di rim.

Supposed to be from Italy (Cambridge Mus.); stamped on each side of spout; buff fabric.

Seen 1965 again B.R.H. — complete & unvarnished — except for small
plug out of base. Purchased 1891. ? Italy. Stamped each side
of spout. gilt mainly medium, pink tined, almost to head —
worn in lower part. Hole through rim opp. spout for suspension?
— worn on outer side of hole as if normally hung up by
something through it. See A. for new description of fabric.

VRI PRO
ESCES

VRI PPO

RESCES

Cambridge illus.
Provenance ? Italy

L. LURIVS PRISCVS

Italy

^{60k^u.}
London, Clements have [12 on label; CR S [p. 89; British M. 112 K] fine,
pale buff fabric but with some grit on it; abundant, black, ^{glassy} red-brown
grey, largish + medium grits to near b.b. CIL VII, 1331, 67.
gold mica.

LVA

5 K D23. thick, greyish buff, soft.
Laister-by-Norwich (Norfolk A. xxvi Pt. II 1936, p 211 no 11); cream fabric & light brown

surface; Pt II. v. 13 - D.A. - 100-150 A.D. mostly large black & white, grey grit


Laister-by-Norwich [Norfolk A. xxvi Pt. II 1936, p 211 cf. no 11] D 15, E. Trend.

NOT seen.

West Essex
Colchester M [Pat. fig 7, 10; 4155.21; 407K] Deep cream, fine-textured, pale, slightly pinkish, buff fabric,

buff surface; sporadic, large, knobby, to medium black, white, grey; clumps of grit to b; worn away in bottom; nr. B-F 34.

VCH Essex p. 159



Caster by Norwich.

R11
5.0
4/.



Caster 2.8 9.2

LV9V TASS9V S

(wallsend) · CARDS MISSING.

Bubbenhall, Warks [BB 93 102 / 1 IK] L + v. Dr. 26.5cm.
53% burnt. Heavily worn. 8 joining sherds. Fine-
textured, micaceous, cream fabric. Inclusions: moderate,
ill-sorted, ^{random} quartz (much of it pinkish) and 1 black. Orange-
brown interstratification grit. If there was any slip it was s.c.
grit worn away in bottom.

GATTIUS MARINUS

King Hall SP 464735, Waukesha [M22 L198 (1164) 2 shards

1139/9, 1 shard and 3 joined base shards

? same as Binm. A.S. 41

Alcester, Warwick, [E.S.W. 41d yard/bought in Hope-Masham Collection sold Sotheby's in 1948]

Tiddington [TW 179 No. 171. 11k] 2 pieces stamped - EPS 1. facing
 FF - r. facing. Dr. 31cms. Cream fabric, inclusions translucent pink
 quartz and red-brown fragments. Trituration grit red-brown
 re-fired pottery. Burnt. letters incredibly sharply cut & impressed.

P. H. P. Booth. Feb 8.

Wasperton [WN 83 P15.11 3209 2K] P. Booth incomplete in section
 hard creamy white fabric, qtz, v/b inclusions, occasional grey

INGVTAS

Alcastor (from Hildgaard). 7 X

VTASGVS

LVSVTASGVS

Walsend [WSP237 nosF context F11: 11 locS phase 3 46K]

assumed L facing. Stamp damaged by exfoliation - 522g.
Diam. 27cms. 42%. Anom monstancu with brown accretion
over whole of surface and over the fracture. Surface has
suffered some slight exfoliation but the fabric itself has been
hardened as though the piece has been soaked over a
period. Fabric very hard and yellowish-cream fine-textured.
Harder than one would expect + unusual colour for Man/Hart.
Inclusions: moderate, tiny quartz, orange-brown + rare blackish.
Inturation: frequent, well-sorted probably mostly red-brown but
some may have been discoloured to a blackish shade; extremely
rare quartz. JASGVS

LVGVTASGVS

Corbridge [unpublished; US 50; 391K] smeared stamp. white fabric with

rusty surface; midband, red grit + some brown.

Sketch.

Catterick [J. Wachter 1959; CAT. 59; H XI ①; 8K] hard, white fabric with

buff slip; flange + bead only.

Lisenester [CIR 61 + J. Wachter 19K] hard, cream fabric with

tiny red brown grit admixed; buff slip; smallish + medium
grit to c. $\frac{1}{4}$ bbb; some has gone - perhaps some flaking
of inside surface; l. facing; apparently a Warrickshire
product.