



Present hip is possibly a change from a gabled end

Collars have double cuts suggesting a change to the roof or reuse of the collar rafter truss.

Dragon ties are nailed on across tiebeam to wallplate on each side.

Post 170 x 170

Post 170 x 165

Standard type drop in door bar security mortises

Unusual direct drop into slot version for the lower bar

Brick plinth

This area of roof is plastered internally as the large overhang of the roof, supported on brackets, precludes from fitting boarding on outside

Area shows remains of dove boxes set between tiebeam and lower tie. Area has modern board infill. Along the lower tie are a series of large peg holes for supporting the base boarding of the boxes. At each end a timber survives to control the position of the base. Three board support pegs survive.

Tiebeam average 200 x 170

Post 170 x 160

Post 160 x 155

Brick plinth

Collar is bird's mouthed over purlins and hip rafters are partially housed over the purlins

Bottom of post swelled for leap boards but no board slot evidence as present doors cut further in removing any evidence

Brick plinth

Brick plinth

SCALE: 1:50.

Midstrey at south end, inside view from A towards F. Bay 1 1-2

Midstrey at north, inside view from A towards F. Bay 5 5-6